

**Part 1            General**

**1.1                REFERENCES**

- .1        Section 01 51 00 – Temporary Utilities Services
- .2        Section 01 52 00 – Construction Facilities
- .3        Section 01 74 21 – Management and Disposal construction waste / demolition

**1.2                INSTALLATION AND REMOVAL**

- .1        Provide temporary controls in order to execute Work expeditiously.
- .2        Remove from site all such work after use.

**1.3                PALISADES**

- .1        Erect a palisade temporary in order to close access to the site in compliance with the Safety Code for the construction work.

**1.4                GUARD RAILS AND BARRICADES**

- .1        Provide secure, rigid guard rails and barricades around deep excavations and all such works.
- .2        Provide as required by governing authorities.

**1.5                SHELTER AGAINST, NAVEL AND WEATHER CLOSURES**

- .1        Provide railings and rigid and security barriers and settle around deep excavations.
- .2        Supply and install these items as indicated.

**1.6                ACCESS TO SITE**

- .1        Provide and maintain access roads, sidewalk crossings, ramps and construction runways as may be required for access to Work.

**1.7                TRAFIC**

- .1        Hire competent signal flag operator and foresee any necessary traffic lights, fences, flares, and lights useful to complete the work while ensuring public security. This requirement applies during periods of recovery of the stone located in the area of Route 132 (Montée Laurencelle).

**1.8                ACCESS TO THE SITE**

- .1        The path designated by the Contractor for the execution of work is shown on the plan. The Contractor shall use the path from the road 132 that goes to the coast road. There is an existing barrier to entry where the Contractor shall monitor and keep it closed and locked when there is no road and outside working hours. The Contractor shall install signs of dimension 1200 x 2440 mm indicating "No Trespassing, construction.

- .2 The Contractor shall take the bridge Whalen special charges such as the mobilization of heavy equipment on flatbed truck. Thus, it will use the path of Cap Bon Ami in these cases alone.

## **1.9 ACCESS ROAD FOR EMERGENCY VEHICLES**

- .1 Provide access to the site for emergency vehicles and provide in this regard clearances sufficient height.

## **1.10 PROTECTION FOR OFF-SITE AND PUBLIC PROPERTY**

- .1 Protect surrounding private and public property from damage during performance of Work.
- .2 Be responsible for damage incurred.
- .3 Assume full responsibility for damage to the work due to a lack of protection or inadequate protection.

## **1.11 PROTECTION OF WORK FINISHES**

- .1 Provide protection for finished and partially finished element finishes and equipment during performance of Work.
- .2 Assume full responsibility for damage to articles due to a lack of protection or inadequate protection.

## **1.12 WASTE MANAGEMENT AND DISPOSAL**

- .1 Separate waste materials for reuse and recycling in accordance with Section 01 74 21 – Construction-Demolition Waste Management and Disposal.

## **Part 2 Products**

### **2.1 NOT USED**

- .1 Not Used.

## **Part 3 Execution**

### **3.1 NOT USED**

- .1 Not Used.

**END OF SECTION**