

Part 1 General

1.1 RELATED SECTIONS

- .1 Section 01 52 00 – Construction Facilities.
- .2 Section 01 56 00 – Temporary Barriers and Enclosures.
- .3 Section 01 74 21 – Construction/Demolition Waste Management.

1.2 INSTALLATION AND REMOVAL

- .1 Provide temporary utilities controls in order to execute work expeditiously.
- .2 Remove from site all such work after use.

1.3 WATER SUPPLY

- .1 Departmental Representative will not provide continuous supply of potable water for construction use.

1.4 TEMPORARY POWER AND LIGHT

- .1 Departmental Representative does not provide the temporary power supply for lighting and operation of power tools during construction. The Contractor shall make its own arrangements, either install an electric meter specific to their needs or make an agreement with the Parks Canada Agency.
- .2 Provide temporary lighting places throughout the duration of the work and ensure network maintenance.
- .3 Provide temporary lighting of the premises for the duration of the work and ensure network maintenance.
- .4 Electrical power and lighting systems installed under this Contract may be used for construction requirements only with prior approval of Departmental Representative provided that guarantees are not affected. Make good damage to electrical system caused by use under this Contract.

1.5 TELECOMMUNICATIONS

- .1 The Contractor shall provide temporary telecommunications facilities, including telephone, fax and Internet services, including lines for its own use and for use by the Departmental Representative and must ensure the connection of these facilities for major networks and bear the costs of these services.

1.6 FIRE PROTECTION

- .1 Provide and maintain temporary fire protection equipment during performance of Work required by insurance companies having jurisdiction and governing codes, regulations and bylaws.

- .2 Burning rubbish and construction waste materials is not permitted on site.

Part 2 Products

2.1 NOT USED

- .1 Not Used.

Part 3 Execution

3.1 NOT USED

- .1 Not Used.

END OF SECTION