

Question 1

Please provide the exact locations for each internal point repair in the contract (i.e. chainage (how far) from the start manhole).

Answer 1

PLR: S18X, Johnston Street. Trenchless point repair at 16.5m trim two connections and re-inspect full length of main prior to repair.

Question 2

What is the chainage of the external point repair and how long this repair is expected to be (i.e. from X meter to Y meters) ?

Answer 2

PLR: CB136X, Anderson Street, Repair joint displacement at catch basin interface with main pipe – 0.5m from start of survey at least 2m long.

Question 3

Part 2, section 2.4, p.10 of the ITT document: Could you please clarify item ‘(A) For the firm lump sum’, item ‘(B) For the unit prices set out below’ and item ‘(C) For the unit prices set out for identified repairs’?

Answer 3

Please disregard and do not fill out Item ‘(B) For the unit prices set out below’.

Item ‘(A) For the firm lump sum’ represents the total lump sum cost of the project as it is broken down in the Schedule – Labour, Material, plant and or equipment table.

Item ‘(C) For the unit prices set out for identified repairs’ represents the allowance, as requested by CMHC, for repairs that may be identified by the successful proponent during the course of the project.

Item “Total Tender Price” represents Item (A) + Item (C) + GST.