

Question 7

As we understand when the last contractor did the Flush & video program in 2005, he could not finish the whole job as there are no Inspection Chamber (I/C) or clean out (C/O) for some of those laterals, also there are few unknown pipe in the area. We may not be able to finish the whole job as well.

In the mean time, few of those laterals do not have any I/C or C/O and we need to use other CCTV equipment to do those cleaning inspection such as Launch Flushing & Launch Camera. The cost for that equipment will be different than the cost for a regular CCTV inspection Unit. Should we blend it together and use one figure or those will be treated as extra?

Answer 7

This flush and video program does not include service laterals. Only mainlines and catch-basin leads will be flushed and video inspected. As previously noted, some trapping hoods may require additional effort to remove. Assume all inspections / cleaning can be complete via access from a manhole, catch basin or clean out. Provide pricing for equipment appropriate for the above noted conditions.