PWGSC Ontario	SPECIFICATION	Section 00 00 00
Region Project	TITLE SHEET	Page 1
Number R.059392.001		2013-09-10

PROJECT TITLE WIKWEMIKONG, ONTARIO MANITOULIN ISLAND

OIL AND GAS WELL RE-ABANDONMENT

PROJECT NUMBER R.059392.001

PROJECT DATE 2013-09-10

PWGSC Ontario	List of Contents	Section 00 01 11
Region Project		Page 1
Number R.059392.001		2013-09-10

Section <u>Title</u>		Pages
Division 00 - Procuremen 00 00 00 SPECIFICATION	t and Contracting Requirements TITLE SHEET	1
Division 01 - General Reconstruction 01 - General Instruction 01 35 29 HEALTH AND SA 01 35 43 ENVIRONMENTAL	 UCTIONS FETY REQUIREMENTS	13 6 6
Division 33 - Utilities 33 29 00 OIL & GAS WEL	L ABANDONMENT	11
Appendices		
Appendix 1 Sit	e Location Plan	1
	l Location Plan & e Photographs	10
	hnical Memorandum m Golder Associates Ltd.	10

PWGSC Ontario	GENERAL INSTRUCTIONS	Section 01 11 01
Region Project		Page 1
Number R.059392.001		2013-09-10

PART 1 - GENERAL

1.1 WORK COVERED BY .1 CONTRACT DOCUMENTS

- Re-abandonment of two (2) old, unproductive, shallow oil wells (approx. 225 m deep) located on different properties on the Wikwemikong Unceded Indian Reserve #26 on Manitoulin Island in Ontario. Contractor must be licenced to perform the work.
- .2 Give priority to hiring local First Nation labour and equipment for any additional services.
- .3 Meeting the specifications and other provisions of Section 11 of the Ontario Provincial Standards Version 2, dated January 2002.

1.2 MINIMUM STANDARDS

- .1 Execute work to meet or exceed:
 - .1 National Building Code of Canada 2010, National Fire Code of Canada 2010, Ontario Building Code 2006 and any other code of provincial or local application, including all amendments up to project date, provided that in any case of conflict or discrepancy, the more stringent requirements shall apply.
 - .2 Rules and regulations of authorities having jurisdiction.
 - .3 Federal Fire Commissioner, No. 301, Standard for Construction Operations, and No. 302, Standard for Welding and Cutting, June 1982.
 - .4 Treasury Board of Canada Secretatiat, Fire Protection Standard, April 1, 2010.
 - .5 Observe and enforce construction safety measures required by National Building Code 2010, Part 8 Safety Measures at Construction and Demolition Sites, Occupational Health and Safety Act and Regulations for Construction Projects, Revised Statutes of Ontario 1990, Chapter 0.1 as amended, O. Reg. 213/91 as amended by O. Reg. 631/94, O. Reg. 143/99, O. Reg. 571/99, O. Reg. 145/00, O. Reg. 527/00, R.R.O. 1990, Reg. 834, O. Reg. 278/05 (Asbestos), Workplace Safety and Insurance Board and municipal statutes and authorities.
 - .6 Environmental Protection Act, O. Reg. 102/94 and O. Reg. 103/94.
 - .7 Indian Oil and Gas Act R.S.C. 1985 c. 1-7
 - .8 Oil, Gas, and Salt Resources Act, R.S.O. 2002.

PWGSC Ontario Region Project Number R.059392.001		GENERAL INSTRUCTIONS	Section 01 11 01 Page 2 2013-09-10
1.2 MINIMUM STANDARDS (Cont'd)	.1	(Cont'd) .9 Ont. Regulation 245/9 Drilling and Production	97, Exploration,
1.3 CONTRACT METHOD	.1	Construct Work under combi	ined price Contract.
1.4 COST BREAKDOWN	.1	Within 48 hours of notific of bid furnish a cost brea aggregating contract price	akdown by Section
	.2	Show separately cost of edexempt from Ontario Retail	l Sales Tax under your
	.3	Within 48 hours of accepta	ance of bid submit a
1.5 AUTHORITIES HAVING JURISDICTION	.1	The Federal Fire Commission authority having jurisdict with regards to fire standards	tion over this project
	.2	Be responsible for construted techniques, sequences and co-ordinating the various as directed by the Department	<pre>procedures and for parts of the Work, or</pre>
1.6 TAXES	.1	Pay applicable Federal, Pi Municipal taxes.	rovincial and
1.7 FEES, PERMITS, CERTIFICATES AND LETTERS	.1	Provide authorities having information requested.	g jurisdiction with
DETTERO	.2	Pay fees and obtain certification letters required.	ficates, permits and
	.3	Furnish certificates, perrrequested.	mits and letters when
1.8 EXAMINATION	.1	Examine existing condition conditions affecting work	

PWGSC Ontario		GENERAL INSTRUCTIONS	Section 01 11 01
Region Project			Page 3
Number R.059392.001			2013-09-10
1.9 PROJECT MEETINGS	.1	The Contractor's Site Super Safety Representative, and are required to attend a major start of plugging to discuss major subcontractors are approgress meetings, which we required basis, to discuss progress, any problems and problems. Progress meeting at the Project Site unless meet at another location.	d major subcontractors meeting prior to the uss the Decommissioning es. The Site fety Representative and also required to attend will be held on an as s field observations, d resolution of any gs will generally occur
1.10 DOCUMENTS	.1	Keep one copy of contract site.	documents on the
	. 2	Keep one copy of all releving licences and permits on situations or similar for Departmental Representativinspectors.	ite during plugging inspection by
1.11 ELECTRONIC SUBMITTALS	.1	Submit number of hard copitype and format of submitted electronic format as pdf for Departmental Representative	tal and also submit in files as directed by
1.12 CONTRACTOR'S AS-BUILT DRAWINGS AND SPECIFICATIONS	.1	As work progresses, neatly deviations from the Contraplan and specifications us on full size white prints	actor's decommissioning sing fine, red marker

.2 Neatly print lettering and numbers in size to match original. Lines may be drawn free-hand but shall be neat and accurate. Add at each title block note: "AS BUILT". Also circle on List of documents each title and number of document marked with "AS-BUILT" information. Circle on Table of Contents each document number and title of specification sections marked with "AS-BUILT" information.

Make the same changes on the electronic files.

.3 Departmental Representative will provide one electronic set of contract information and

PWGSC Ontario	GENERAL INSTRUCTIONS	Section 01 11 01
Region Project		Page 4
Number R.059392.001		2013-09-10

1.12 CONTRACTOR'S AS-BUILT DRAWINGS AND SPECIFICATIONS (Cont'd)

- .3 (Cont'd) specifications for inclusion with as-built drawing and specification purposes.
 - .1 Specifications are in NMSEdit Professional.
 - .2 Amendments and addenda are in MS Word.
- .4 Record following significant deviations including but not limited to:
 - .1 Depths of various horizons of well, casings existing, down hole equipment, existing plugs, etc.
 - .2 Horizontal and vertical location of underground utilities and appurtenances referenced to permanent surface improvement.
 - .3 Field changes of dimension as approved by Departamental Representative.
 - .4 Other significant deviations which are concealed in construction and can not be identified by visual inspection.
 - .5 Alternative materials and systems installed replacing original materials and systems.
- .5 Turn one set, paper copy and electronic copy, of AS-BUILT drawings and specifications over to Departmental Representative on completion of work.
- .6 If project is completed without significant deviations from Contract drawings and specifications submit to Departmental Representative one set of drawings and specifications marked "AS-BUILT".

1.13 SITE QUALITY CONTROL SUBMITTALS

- .1 Maintain to date accurate daily record of work and hours performed including the following information, which shall be approved daily by the Departmental Representative and submit weekly reports signed by Site Supervisor (by twelve noon on Monday) to the Departmental Representative:
 - .1 Names of personnel indicating activities performed by each person and number of hours worked per day.
 - .2 Types and quantities of equipment used.
 - .3 Progress made (e.g., depth reached, materials received and consumed).
 - .4 Equipment removed.
 - .5 Site restoration or remediation conducted.
 - .6 Any problems encountered.
 - .7 Solutions to problems encountered.

PWGSC Ontario Region Project Number R.059392.001		GENERAL INSTRUCTIONS	Section 01 11 01 Page 5 2013-09-10
1.14 CONSTRUCTION PHOTOGRAPHS	.1	Provide one set of photos for each well illustrating each sequence of operation conducted and of any well plugging problems.	
	. 2	Submit electronic and ha digital photography in jresolution.	
	.3	Identification: name and date of exposure indicat	
	. 4	Viewpoints and location determined by Department	
	.5	Frequency: as directed b Representative.	y Departmental
1.15 ADDITIONAL DRAWINGS	.1	Departmental Representat additional drawings to c	
	. 2	Such drawings become par Documents.	t of Contract
1.16 PROTECTION	.1	Protect existing trees a adjacent properties as m	
	. 2	Cut down only trees appr Departmental Representat to a forested area.	
	.3	Ensure that all Requirme complied with and that a precautions are taken to damage to trees and vege	<pre>ll reasonable prevent forest fires o</pre>
1.17 EXISTING SERVICES	.1	Obtain from local utility respective approval for utilities, and bear any other charges to said ut for any and all damage to services to the extent so the negligent acts or ommisconduct of the Contration its subcontractors or an employees, officers, dir representatives or other	any such changes to the applicable relocation of ilities. Be responsible of such utilities and uch damage is caused by issions or wilful ctor's staff or any of y of their respective ectors, agents,
	. 2	Establish location, prot existing utility lines.	ect and maintain

PWGSC Ontario Region Project Number R.059392.001		GENERAL INSTRUCTIONS	Section 01 11 01 Page 6 2013-09-10
1.17 EXISTING SERVICES (Cont'd)	.3	Establish location of over area of Well #2. Avoid intutilities during Work.	
	. 4	Maintain existing services	s in occupied areas.
1.18 TEMPORARY FACILITIES AND SERVICES	.1	Provide and maintain tempo services required to carry	=
	. 2	Provide portable sanitary	facilities.
	.3	Remove temporary facilities completion of work.	es and services on
1.19 METRIC SIZED MATERIALS	.1	SI metric units of measure exclusively on the drawing specifications for this pr	gs and in the
	.2	Claims for exemptions from products shall be in writing substantiated with support Promptly submit application Representative for consider Non-metric sized products Contractor's application has writing by the Departments	ing and fully tive documentation. on to Departmental eration and ruling. may not be used unless has been approved in
	.3	Difficulties caused by the planning and effort to obt sized products which are a Canadian market will not a sufficient reasons for classe provided.	tain modular metric available on the De considered
	. 4	Claims for additional cost specified modular metric sbe considered.	-
1.20 CUTTING AND REMEDIAL WORK	.1	Co-ordinate work to keep of work to a minimum.	cutting and remedial
	. 2	Make good surfaces exposed with material and finish tadjoining surfaces. Included sod as indicated.	to match existing

1.21 DECOMMISSIONING PLAN

- .1 Prepare and submit a Decommissioning Plan(s) (or Plan(s)), including a Site Preparation Plan and Access Drawing, based on the Project specific details to Departmental Representative and a copy to the Ministry of Natural Resources for review and comment/consultation prior to execution of any of the other Work.
- .2 The Decommissioning Plan shall include the sequence of events, proposed access to the Site, evaluation of the Site for spills and contamination, preparation of the Site for decommissioning operations, notification of the nature, timing and safety implications of the Project, securing the Site, plugging the Well(s) (as described below), removal of production and surface equipment, and restoration of the Site to original or comparable conditions.
- .3 A Band appointed First Nations Facilitator will arrange a site access agreement with the land owners for the contractor.
- .4 Abide by site access agreement and arrangements made by the First Nations Facilitator with the landowner. Coordinate well abandonment operations with the First Nations representative who will notify the landowner and facilitate the Contractor to access the site at no charge to the Contractor.
- .5 The Site Preparation Plan and Access Drawing shall show, the location of the Well, planned access route, fencing, signage, and any trees, buildings, roads, etc. in the vicinity of the Well and identify any anticipated environmental disturbance, and any mitigating measures.
- .6 The Site Preparation Plan and Access Drawing shall include all aspects as detailed in the Access Agreement as provided by the Departmental Representative.
- .7 The Site Preparation Plan shall include but not be limited to:
 - .1 A means for the control, diversion, and disposal (e.g. flaring) of gas escaping from the Well during all operations, including provisions for dealing with Sweet and Sour Gas.
 - .2 Personnel training, certification and procedures for monitoring, alarms, specialized breathing apparatus, public safety mitigation measures and emergency response.

PWGSC Ontario	GENERAL INSTRUCTIONS	Section 01 11 01
Region Project		Page 8
Number R.059392.001		2013-09-10

1.21 DECOMMISSIONING PLAN (Cont'd)

.7 (Cont'd)

- .3 A Spill Control Plan to handle the potential release of hydrocarbons and/or formation water from the Well.
- .4 Measures to maintain all necessary spill control equipment and supplies on Site, and be prepared to implement the proposed remedial actions of the Spill Control Plan.
- .5 The design and maintenance of the Project area to divert surface runoff from entering and collecting in the Project area. There shall be no discharge to any drain or waterway. Steel-lined pits or tanks shall be used rather than constructing a lined earthen pit.
- .8 In the event of additional spills by contractor, evaluate the additional spills and contamination by including a sample and analysis method to determine the extent and composition of surface contaminants.
- .9 Report to the Departmental Representative and send a copy of the decommissioning plan to the Ontario Ministry of Natural Resources (MNR) and obtain written approval from the Departamental Representative prior to making changes to the Decommissioning Plan as a result of conditions differing from those originally assessed as existing at the outset of the Project.
- .10 Provide certification by a professional engineer or other authority acceptable to the Departmental Representative and MNR that any rig used for plugging Wells is suitable mechanically, operationally and structurally for the task.
- .11 Submit the Decommissioning Plans for both of the wells to the Departamental Representative with a copy the MNR within twenty-one (21) Days from the date of award of contract. Failure to do so may result in termination of the Contract.

1.22 CO-ORDINATION .1 AND CO-OPERATION

- 11 There is a residence approximately 60 m away from the work area of the Well 2 site, and several hundred metres away from the Well 1B area.
- .2 Work area will not be occupied during execution of work.
- .3 A designated First Nation Facilitator will arrange for access to the site with the land

1.22 CO-ORDINATION .3 AND CO-OPERATION (Cont'd)

- (Cont'd) owners for all involved with the project. The Facilitator shall also assist in the coordination and cooperation of others who are to oversee the work for the Band, and report to the Band on the aspects of the work and with any other First Nations individuals. Facilitator's services will be supplied at no cost to the Contractor.
- .4 At the call of the Departmental Representative, assist the Departmental Representative in taking soil samples from the excavated areas.
- .5 Execute work with minimum disturbance to occupants, public and normal use of site.
- .6 Maintain access and exits.
- .7 Where security has been reduced by work of contract, provide temporary means to maintain security.
- .8 Establish necessary security and safety controls, including, but not limited to, fencing, warning signs, etc. Gate or barricade the access road to the Site during non-work periods to prevent unauthorized entry to work areas by any third parties, including without limitation, the Landowner or any of his/her invitees, workmen, employees or family, and to protect existing facilities and adjacent properties from damage. Prior to commencing any work, place in conspicuous locations, appropriate signage stating public access to the Site is prohibited and warning the public regarding the hazardous nature of the work on the Site.

1.23 SITE ACCESS .1

- .1 Do not enter unto the work site property until the First Nation Facilitator has authorized accessing the land.
- .2 Establish appropriate access to the Well along a route and in a manner that minimizes damage to the environment and disturbance to the local residents, and is acceptable to the Facilitator.
- .3 As directed by the Departmental Representative, abide by a recent Landowner's Access Agreement

1.23 SITE ACCESS .3 (Cont'd)

.3 (Cont'd)

with the landowner of the site to complete the site work.

- .1 If a copy of the Landowner's Access Agreement is required by the Ministry as part of the Decommissioning Plan, consult with the First Nation Facilitator and the Departmental Representative.
- .2 The Landowner's Access Agreement may include:
 - .1 Provisions whereby the Landowner agrees to the location, route, and scheduling, and other details of the Site access by the Contractor, and grants permission for the Contractor to enter his/her Lands to complete the Work;
 - .2 Provisions whereby the Landowner agrees that all tools, equipment, and materials found at the Well Site, belong solely to the Landowner but the Contractor shall remove and dispose of them with the Landowner's permission;
 - .3 Details of any disruption in land operations, impact on existing trees, crops, vegetation, etc.; the Contractor shall only remove these items as necessary to provide access or create a work area large enough for the Work to proceed;
 - .4 Details of remediation activities such as the removal of old Well equipment, removal and disposal of contaminated soil, and of restoration activities such as replacing removed soil, reseeding grassed areas, restoration of access roads;
 - .5 Details regarding any necessary relocation of tile drains, piping or any other subsurface utilities, or of overhead utilities as required for access;
 - .6 Indemnification, in favour of the Landowner, against any loss or damages due to negligence or wilful misconduct on the part of the Contractor.

1.24 ALTERATIONS TO .1 EXISTING SITE

Remove and recycle or dispose of: .1 Piping.

.2 Restore to original grades.

PWGSC Ontario Region Project Number R.059392.001		GENERAL INSTRUCTIONS	Section 01 11 01 Page 11 2013-09-10
1.25 INSPECTION AND TESTING	.1	When quality confirmation reveal that the final work requirements, pay for test required by Departmental R corrected work.	is not to contract s and inspections
	.2	Designated AANDC staff and the MNR may visit the Site activities to ensure that according to the Requireme those under the Oil, Gas a	during the plugging all work is done nts of Law, including
	.3	Departmental Representative confirmatory sampling of seduring the excavation of the at no cost to the Contract	oil contaminants he contaminated soil
1.26 SCHEDULING	.1	On award of contract submiconstruction schedule for anticipated progress stage completion. When schedule the Departmental Represent measures to complete work Do not change schedule wit Departmental Representativ	work, indicating s within time of has been reviewed by ative take necessary within scheduled time. hout notifying
	.2	Carry out work from 07:00 Sundays and Statutory Holi	
	.3	Carry out noise generating 18:00	work from 07:30 to
1.27 CLEANING	.1	Maintain Project areas in condition; free of waste m rubbish.	
	.2	Final cleaning: .1 Remove temporary prot .2 Broom clean paved ext clean other exterior surfa	erior surfaces, rake
1.28 CONSTRUCTION & DEMOLITION WASTE	.1	Submit proof that all wast of at a licensed land fill transfer site. A copy of t transfer site's license an that said landfill site wi must be supplied to Depart prior to removal of waste	site or waste he disposal/waste d a letter verifying ll accept the waste mental Representative

PWGSC Ontario	GENERAL INSTRUCTIONS	Section 01 11 01
Region Project		Page 12
Number R.059392.001		2013-09-10

1.29 DESIGNATED SUBSTANCES

. 1

Based on visual inspections, there are no "designated substances" as defined by the Occupational Health and Safety Act Revised Statutes of Ontario, 1990, Chapter 0.1 as amended, in the work area.

1.30 SPECIAL PROTECTION AND PRECAUTIONS

- .1 Comply with the requirements of the Workplace Hazardous Materials Information System (WHMIS) regarding use, handling, storage, and disposal of hazardous materials; and regarding labelling and the provision of material safety data sheets acceptable to HRSDC Labour Program.
- .2 When the use of explosives is necessary for the execution of the Project, receive written approval from the Departmental Representative, exercise the utmost care and diligence not to endanger life or property. Duly comply with all Requirements of Law regarding the use of explosives. Be responsible for any and all losses and damages to persons, including without limitation injuries and death, and property arising in connection with the use of explosives.

1.31 POLLUTION CONTROL

- .1 Spills of deleterious substances:
 - .1 Immediately contain, limit spread and clean up in accordance with provincial regulatory requirements.
 - .2 Report immediately to Ontario Spills Action Centre: 1-800-268-6060.
 - .3 Further information on dangerous goods emergency cleanup and precautions including a list of companies performing this work can be obtained from the Transport Canada 24-hour number (613) 996-6666 collect.
- .2 If the Work or any part thereof is carried out in or about any wetland or body of water, including without limitation any stream, river or lake, undertake and maintain at its own expense and at all times, take such measures (including such measures as may be directed by the Ministry of Natural resources and the Departmental Representative) as may be necessary to control and contain fill materials, soil erosion, sedimentation and other harmful wastes resulting from its operations that could result in harm to or pollution of such wetlands or bodies of water.

PWGSC Ontario		GENERAL INSTRUCTIONS	Section 01 11 01
Region Project			Page 13
Number R.059392.001			2013-09-10
1.31 POLLUTION CONTROL (Cont'd)	.3	Where an old oil or gas we within 100 m of a domestic samples of the water well others prior to plugging, afterwards, and again, threxpense of others. The puris to determine if the oil having any impact on the wabandonment operations com assess whether the problem alleviated as a result of operations.	c use water well, may be obtained by immediately see months later at the spose of the sampling or gas well was water well before the mmenced and, if so, to has been resolved or
1.32 OPSS AND OPSD	.1	OPSS Ontario Provincial St and OPSD Ontario Provincia quoted in these specificat online at http://www.raqsa techpubs/ops.nsf/OPSHomepa	al Standard Drawings zions are available a.mto.gov.on.ca/
PART 2 - PRODUCTS			
2.1 NOT USED	.1	Not used.	
PART 3 - EXECUTION			

3.1 NOT USED .1 Not used.

PART 1 - GENERAL

1.1 REFERENCES .1

- .1 National Fire Code 2010 (NFC):
 - .1 NFC 2010, Division B, Part 5 Hazardous Processes and Operations, subsection 5.6.1.3 Fire Safety Plan.
- .2 Province of Ontario:
 - .1 Occupational Health and Safety Act Revised Statutes of Ontario 1990, Chapter 0.1 as amended, and Regulations for Construction Projects, O. Reg. 213/91 as amended.
 - .2 O. Reg. 490/09, Designated Substances.
 - .3 Workplace Safety and Insurance Act, 1997.
 - .4 Municipal statutes and authorities.
- .3 Fire Commissioner of Canada (FCC):
 - .1 FC-301 Standard for Construction Operations, June 1982.
 - .2 FC-302 Standard for Welding and Cutting, June 1982.

Labour Program
Fire Protection Engineering Services
4900 Yonge Street 8th Floor
North York, Ontario M2N 6A8

and copies may be obtained from:

Human Resources and Social Development Canada Labour Program Fire Protection Engineering Services Ottawa, Ontario K1A 0J2

1.2 SUBMITTALS .1

- .1 Make submittals in accordance with Section 01 11 01.
- .2 Submit site-specific Health and Safety Plan: Within 7 days after date of Notice to Proceed and prior to commencement of Work. Health and Safety Plan must include:
 - .1 Results of site specific safety hazard assessment.
 - .2 Results of safety and health risk or hazard analysis for site tasks and operations found in work plan.
 - .3 Measures and controls to be implemented to address identified safety hazards and risks.
 - .4 Provide a Fire Safety Plan, specific to the work location.

PWGSC Ontario	HEALTH AND SAFETY	Section 01 35 29
Region Project	REQUIREMENTS	Page 2
Number R.059392.001		2013-09-10

1.2 SUBMITTALS (Cont'd)

- .2 (Cont'd)
 - .5 Contractor's and Sub-contractors' Safety Communication Plan.
 - .6 Contingency and Emergency Response Plan addressing standard operating procedures specific to the project site to be implemented during emergency situations.
- .3 Departmental Representative will review Contractor's site-specific Health and Safety Plan and provide comments to Contractor within 5 days after receipt of plan. Revise plan as appropriate and resubmit plan to Departmental Representative within 3 days after receipt of comments from Departmental Representative.
- .4 Departmental Representative's review of Contractor's final Health and Safety plan should not be construed as approval and does not reduce the Contractor's overall responsibility for construction Health and Safety.
- .5 Submit names of personnel and alternates responsible for site safety and health.
- .6 Submit records of Contractor's Health and Safety meetings when requested.
- .7 Submit 2 copies of Contractor's authorized representative's work site health and safety inspection reports to Departmental Representative, weekly.
- .8 Submit copies of orders, directions or reports issued by health and safety inspectors of the authorities having jurisdiction.
- .9 Submit copies of incident and accident reports.
- .10 Submit Material Safety Data Sheets (MSDS).
- .11 Submit Workplace Safety and Insurance Board (WSIB) Experience Rating Report.

1.3 FILING OF NOTICE

.1 File Notice of Project with Provincial authorities prior to commencement of Work.

1.4 WORK PERMITS .1

.1 Obtain any permits related to project prior to commencement of Work.

<u>.</u>			
PWGSC Ontario		HEALTH AND SAFETY	Section 01 35 29
Region Project		REQUIREMENTS	Page 3
Number R.059392.001			2013-09-10
1 F CARRON	1	Douglass with a secific sec	bad aggregations
1.5 SAFETY	.1	Perform site specific safe	ty nazard assessment
ASSESSMENT		related to project.	
1 C MEDETNICS	1		-1-1
1.6 MEETINGS	.1	Schedule and administer He	
		meeting with Departmental	Representative prior
		to commencement of Work.	
1.7 REGULATORY	.1	Comply with the Acts and r	ogulations of the
_ ,	• 1	Province of Ontario.	egulations of the
REQUIREMENTS		Province of Officatio.	
	. 2	Comply with appaified atom	danda and magnilations
	. 4	Comply with specified stand	
		to ensure safe operations	at site.
1.8 PROJECT/SITE	. 1	Work at site will involve	contact with:
CONDITIONS	• -	.1 Crude Oil.	College Wiell
CONDITIONS		.2 Sweet or Sour Gases.	
		. I Sweet of Sour Cases.	
1.9 GENERAL	.1	Develop written site-speci	fic Health and Safety
REQUIREMENTS		Plan based on hazard asses	
		beginning site Work and co	
		maintain, and enforce plan	
		demobilization from site.	
		must address project speci	-
	. 2	Departmental Representativ	e may respond in
		writing, where deficiencie	s or concerns are
		noted and may request re-s	ubmission with
		correction of deficiencies	or concerns either
		accepting or requesting im	provements.
	.3	Relief from or substitution	
		provision of minimum Healt	-
		specified herein or review	ed site-specific
		Health and Safety Plan sha	ll be submitted to
		Departmental Representativ	e in writing.
1 10 00000	-1		
1.10 COMPLIANCE	.1	Comply with Ontario Occupa	
REQUIREMENTS		Safety Act, R.S.O. 1990 Ch.	apter U.I, as amended.
1.11 RESPONSIBILITY	1	Be responsible for health	and safety of persons
T.TT KUDI ONDIDILITI	• -	on site, safety of propert	
		protection of persons adja	
		proceeding or persons adja	cerre do prec ana

PWGSC Ontario	HEALTH AND SAFETY	Section 01 35 29
Region Project	REQUIREMENTS	Page 4
Number R.059392.001		2013-09-10

1.11 RESPONSIBILITY .1 (Cont'd)

- (Cont'd)
 environment to extent that they may be affected
 by conduct of Work.
- .2 Comply with and enforce compliance by employees with safety requirements of Contract Documents, applicable federal, provincial, territorial and local statutes, regulations, and ordinances, and with site-specific Health and Safety Plan.
- .3 Where applicable the Contractor shall be designated "Constructor", as defined by Occupational Health and Safety Act for the Province of Ontario.

1.12 UNFORSEEN HAZARDS

- .1 Should any unforeseen or peculiar safety-related factor, hazard, or condition become evident during performance of Work, immediately stop work and advise Departmental Representative verbally and in writing.
- .2 Follow procedures in place for Employees Right to Refuse Work as specified in the Occupational Health and Safety Act for the Province of Ontario.

1.13 HEALTH AND SAFETY CO-ORDINATOR

- .1 Employ and assign to Work, competent and authorized representative as Health and Safety Co-ordinator. Health and Safety Co-ordinator must:
 - .1 Have site-related working experience specific to activities associated with the work of this project.
 - .2 Have working knowledge of occupational safety and health regulations.
 - .3 Be responsible for completing Contractor's Health and Safety Training Sessions and ensuring that personnel not successfully completing required training are not permitted to enter site to perform Work.
 - .4 Be responsible for implementing, enforcing daily and monitoring site-specific Contractor's Health and Safety Plan.
 - .5 Be on site during execution of Work.

PWGSC Ontario Region Project Number R.059392.001		HEALTH AND SAFETY REQUIREMENTS	Section 01 35 29 Page 5 2013-09-10
1.14 POSTING OF DOCUMENTS	.1	2013-09-10	
1.15 CORRECTION OF NON-COMPLIANCE	.1	Immediately address head non-compliance issues in having jurisdiction or Representative.	identified by authority
	. 2	Provide Departmental Rewritten report of action non-compliance of healtidentified.	on taken to correct
	.3	Departmental Representation non-compliance of health	ative may stop Work if th and safety regulations

1.16 BLASTING .1 Blasting or other use of explosives is not permitted.

is not corrected.

- 1.17 WORK STOPPAGE .1 Give precedence to safety and health of public and site personnel and protection of environment over cost and schedule considerations for Work.
 - .2 Assign responsibility and obligation to Health and Safety Coordinator to stop or start Work when, at Health and Safety Coordinator's discretion, it is necessary or advisable for

PWGSC Ontario		HEALTH AND SAFETY	Section 01 35 29
Region Project		REQUIREMENTS	Page 6
Number R.059392.001			2013-09-10
1.17 WORK STOPPAGE (Cont'd)	. 2	(Cont'd) reasons of health or safe	ty Departmental
(cone u)		Representative may also stafety considerations.	
PART 2 - PRODUCTS		-	
2.1 NOT USED	.1	Not used.	
PART 3 - EXECUTION			
2 1 NOT HATE	-1	27	
3.1 NOT USED	.1	Not used.	

PART 1 - GENERAL

1.1 DEFINITIONS .1

- Environmental Pollution and Damage: presence of chemical, physical, biological elements or agents which adversely affect human health and welfare; unfavourably alter ecological balances of importance to human life; affect other species of importance to humans; or degrade environment aesthetically, culturally and/or historically.
- .2 Environmental Protection: prevention/control of pollution and habitat or environment disruption during construction.

1.2 REFERENCES

- _ .1 Oil, Gas and Salt Resources of Ontario,
 Provicial Operating Standards Version 2 dated
 January, 2002.
 - .2 U.S. Environmental Protection Agency (EPA)/Office of Water
 - .1 EPA 832/R-92-005-92, Storm Water Management for Construction Activities, Chapter 3.
 - .2 EPA General Construction Permit (GCP) 2012.

1.3 ACTION AND INFORMATIONAL SUBMITTALS

.1 Submit in accordance with Section 01 33 00.

.2 Product Data:

- .1 Submit manufacturer's instructions, printed product literature and data sheets for plugging material and any other products to be used and include product characteristics, performance criteria, physical size, finish and limitations.
- .2 Submit 2 copies of WHMIS MSDS.
- .3 Before commencing construction activities or delivery of materials to site, submit Environmental Protection Plan for review and approval by Departmental Representative.
- .4 Environmental Protection Plan must include comprehensive overview of known or potential environmental issues to be addressed during construction.

PWGSC Ontario	ENVIRONMENTAL PROCEDURES	Section 01 35 43
Region Project		Page 2
Number R.059392.001		2013-09-10

1.3 ACTION AND INFORMATIONAL SUBMITTALS (Cont'd)

.5 Address topics at level of detail commensurate with environmental issue and required construction tasks.

.6 Include in Environmental Protection Plan:

- .1 Names of persons responsible for ensuring adherence to Environmental Protection Plan.
- .2 Names and qualifications of persons responsible for manifesting hazardous waste to be removed from site.
- .3 Names and qualifications of persons responsible for training site personnel.
- .4 Descriptions of environmental protection personnel training program.
- .5 Erosion and sediment control plan identifying type and location of erosion and sediment controls to be provided including monitoring and reporting requirements to assure that control measures are in compliance with erosion and sediment control plan, Federal, Provincial, and Municipal laws and regulations and EPA 832/R-92-005, Chapter 3.
- .6 Drawings indicating locations of proposed temporary excavations or embankments for haul roads, stream crossings, material storage areas, structures, sanitary facilities, and stockpiles of excess or spoil materials including methods to control runoff and to contain materials on site.
- .7 Traffic Control Plans including measures to reduce erosion of temporary roadbeds by construction traffic, especially during wet weather.
 - .1 Plans to include measures to minimize amount of material transported onto paved public roads by vehicles or runoff.
- .8 Work area plan showing proposed activity in each portion of area and identifying areas of limited use or non-use.
 - .1 Plan to include measures for marking limits of use areas and methods for protection of features to be preserved within authorized work areas.
- .9 Spill Control Plan to include procedures, instructions, and reports to be used in event of unforeseen spill of regulated substance.
- .10 Non-Hazardous solid waste disposal plan identifying methods and locations for solid waste disposal including clearing debris.
- .11 Air pollution control plan detailing provisions to assure that dust, debris, materials, and trash, are contained on project site.
- .12 Contaminant Prevention Plan identifying potentially hazardous substances to be used on

PWGSC Ontario Region Project Number R.059392.001		ENVIRONMENTAL PROCEDURES	Section 01 35 43 Page 3 2013-09-10
1.3 ACTION AND . INFORMATIONAL SUBMITTALS (Cont'd)	6	(Cont'd) .12 (Cont'd) job site; intended actions introduction of such mater or ground; and detailing prompliance with Federal, Municipal laws and regulate handling of these material .13 Waste Water Management methods and procedures for discharge of waste waters derived from construction concrete curing water, cleated watering of ground water disinfection water, hydros water used in flushing of .14 Historical, archaeological resources biological resources	rials into air, water, provisions for Provincial, and cions for storage and ls. Int Plan identifying management and or which are directly activities, such as ean-up water, e, well drillings, static test water, and lines. Ogical, cultural

1.4 FIRES

_ .1 Fires and burning of rubbish on site is not permitted.

and updated, as required.

that defines procedures for identifying and protecting historical, archaeological, cultural resources, biological resources and wetlands.

.15 Pesticide treatment plan to be included

1.5 DRAINAGE

- ______.1 Develop and submit erosion and Sediment Control Plan (ESC) identifying type and location of erosion and sediment controls provided. Plan to include monitoring and reporting requirements to assure that control measures are in compliance with erosion and sediment control plan, Federal, Provincial, and Municipal laws and regulations, EPA 832/R-92-005, Chapter 3 US EPA General Construction Permit.
 - .2 Storm Water Pollution Prevention Plan (SWPPP) to be substituted for erosion and sediment control plan.
 - .3 Provide temporary drainage and pumping required to keep excavations and site free from water.
 - .4 Ensure pumped water into waterways, sewer or drainage systems is free of suspended materials.
 - .5 Control disposal or runoff of water containing suspended materials or other harmful substances in accordance with local authority requirements.

PWGSC Ontario Region Project Number R.059392.001		ENVIRONMENTAL PROCEDURES Section 01 35 43 Page 4 2013-09-10
1.6 SITE CLEARING AND PLANT PROTECTION	.1	Protect trees and plants on site and adjacent properties as indicated.
	.2	Protect trees and shrubs adjacent to construction work, storage areas and trucking lanes.
	.3	Protect roots of designated trees to dripline during excavation and site grading to prevent disturbance or damage. 1 Avoid unnecessary traffic, dumping and storage of materials over root zones.
	. 4	Minimize stripping of topsoil and vegetation.
	.5	Restrict tree removal to areas designated by Departmental Representative.
1.7 WORK ADJACENT TO WATERWAYS	.1	Construction equipment to be operated on land only.
	.2	Waterways to be kept free of excavated fill, waste material and debris.
	.3	Design and construct temporary crossings to minimize erosion to waterways.
	. 4	Do not skid logs or construction materials across waterways.
	.5	Avoid indicated spawning beds when constructing temporary crossings of waterways.
	.6	Blasting is allowed only above water and 100 m minimum from indicated spawning beds.
1.8 POLLUTION CONTROL	.1	Maintain temporary erosion and pollution control features installed under this Contract.
	. 2	Control emissions from equipment and plant in accordance with local authorities' emission requirements.
	.3	Prevent sandblasting and other extraneous materials from contaminating air and waterways beyond application area. 1 Provide temporary enclosures where directed by Departmental Representative.

PWGSC Ontario Region Project Number R.059392.001		ENVIRONMENTAL PROCEDURES Section 01 35 43 Page 5 2013-09-10	
1.8 POLLUTION CONTROL (Cont'd)	. 4	Cover or wet down dry materials and rubbish to prevent blowing dust and debris. Provide dust control for temporary roads.	
1.9 HISTORICAL/ ARCHAEOLOGICAL CONTROL	.1	Assist in the preparation of a historical, archaeological, cultural resources, biological resources, and wetlands plan that defines procedures for identifying and protecting historical, archaeological, cultural resources, biological resources and wetlands known to be on project site: and identifies procedures to be followed if historical archaeological, cultural resources, biological resources and wetlands not previously known to be onsite or in area are discovered during construction.	
	. 2	Assistance in the Plan shall include, but not be limited to: employing methods to assure protection of known or discovered resources and identify lines of communication between Contractor personnel and Departmental Representative.	
1.10 NOTIFICATION	.1	Departmental Representative will notify Contractor in writing of observed noncompliance with Federal, Provincial or Municipal environmental laws or regulations, permits, and other elements of Contractor's Environmental Protection plan.	
	.2	Contractor: after receipt of such notice, inform Departmental Representative of proposed corrective action and take such action for approval by Departmental Representative. .1 Take action only after receipt of written approval by Departmental Representative.	
	.3	Departmental Representative will issue stop order of work until satisfactory corrective action has been taken.	
	. 4	No time extensions granted or equitable adjustments allowed to Contractor for such suspensions.	

PWGSC Ontario	ENVIRONMENTAL PROCEDURES	Section 01 35 43
Region Project		Page 6
Number R.059392.001		2013-09-10

PART 2 - PRODUCTS

2.1 NOT USED .1 Not Used.

PART 3 - EXECUTION

3.1 CLEANING .1 Progress Cleaning:

- .1 Leave Work area clean at end of each day.
- .2 Ensure public waterways, storm and sanitary sewers remain free of waste and volatile materials disposal.
- .3 Final Cleaning: upon completion remove surplus materials, rubbish, tools and equipment.
- .4 Waste Management: separate waste materials for reuse and recycling.
 - .1 Remove recycling containers and bins from site and dispose of materials at appropriate facility.

PART 1 - GENERAL

1.1 MEASUREMENT PROCEDURES

- .1 Measure for on-site Site Supervisor services by the hour.
- .2 Measure for on-site Rig Rate when actively used, including operating rig, and all necessary appurtances and crew to complete the work by the hour.
- .3 Measure for on-site Standby Time by the hour.
 .1 Refer to definition for description.
- .4 Measure Well Logs by each well.
- .5 Measure Cementing equipment by the hour.
 .1 Rates shall only be charged when equipment is on-site and actively used. No charges may be submitted for equipment which is on the Project Site but idle.
- .6 Measure the removal and disposal of non-hazardous Waste Fluid from inside of the piping and or well casing by the litre based on delivery receipts of fluid delivered to a licensed disposal facility.
- .7 Measure the removal and disposal of non-hazardous Waste Solids from inside the casing by the tonne based on delivery receipts of solids delivered to a licensed disposal facility.
 - .1 Waste material is assumed to be non-hazardous. Where hazardous material is anticipated, Rates will be requested on a Project-specific basis.
- .8 Measure the removal and disposal of non-hazardous Contaminated Soil from outside of the casing by the tonne based on delivery receipts of soil delivered to a licensed disposal facility.
 - .1 Contaminated Soil is assumed to be non-hazardous. Where hazardous material is anticipated, Rates will be requested on a Project-specific basis.
- .9 Measure the supply, placement and compaction of clean backfill to required grade by the tonne based on weigh bills of material delivered to the site.

PWGSC Ontario	OIL & GAS WELL	Section 33 29 00
Region Project	ABANDONMENT	Page 2
Number R.059392.001		2013-09-10

1.1 MEASUREMENT PROCEDURES (Cont'd)

- .10 Measure the supply and installation of a 100 mm layer of topsoil over the backfilled excavated areas and backfilling ruts of setup areas by the m^3 .
- .11 Measure grass seed and fertilizer raked into topsoiled excavation and set-up areas by the m².
- .12 All of the services of the designated First Nations Facilitator, including facilitating access to the sites, negotiating access agreements with property owners, dealing with the property owners issues, restoration requirements, Band inspectors, Band staff, and any First Nation issues, will be arranged by others at no cost to the Contractor.

1.2 DEFINITIONS

- .1 Annular space: space between well casing and borehole wall.
- .2 Aquifer: part of formation or group of formations that is water bearing.
- .3 Authority: means any government authority, agency, body or department, whether federal, provincial or municipal, having or claiming jurisdiction over the Contract; and "Authorities" mean all such authorities, agencies, bodies and departments.
- .4 Consolidated formation: a geologic formation of bedrock.
- .5 Day: means any working day, Monday to Sunday inclusive, excluding statutory and other holidays, namely: New Year's Day; Good Friday; Easter Monday; Victoria Day; Canada Day; Civic Holiday; Labour Day; Thanksgiving Day; Remembrance Day; Christmas Day; Boxing Day and any other day which the Ministry of Natural Resources and Federal Government has elected to be closed for business.
- .6 Decommissioning Plan or 'Plan': means the document developed by the Contractor to outline its method for the provision of the Work requirements.
- .7 Drawdown: difference in elevation, between static level and pumping level.
- .8 First Nations Facilitator: The Band will designate an official local First Nations Band

1.2 DEFINITIONS (Cont'd)

- .8 First Nations Facilitator:(Cont'd)
 member to act as the facilitator for the
 contractor and all involved with the project in
 all activities involving all other First Nations
 people at no cost to the Contractor. This
 includes negotiating, communicating, arranging
 access with property owners and advising the
 property owner of the construction schedule,
 construction work restoration and dealing with
 Band inspectors.
- .9 Incident: means an event such as a spill, discharge, emission, release or escape of a material, pollutant, contaminant, deleterious substance or dangerous good as defined in the legislation referenced in Section 01 11 01.
- .10 Industry Standards: include, but are not limited to:
 - .1 The provision of any and all labour, supplies, equipment and other goods or services that are necessary and can reasonably be understood or inferred to be included within the scope of the Contract or customarily furnished by Persons providing Deliverables of the type provided hereunder in similar situations in Ontario and;
 - .2 Adherence to commonly accepted norms of ethical business practices, which shall include establishing, and ensuring adherence to, precautions to prevent its employees or agents from providing or offering gifts or hospitality of greater than nominal value to any person acting on behalf of or employed by Her Majesty the Queen in right of Ontario or Canada.
- .11 IOGC: Indian Oil and Gas Canada.
- .12 Landowner or 'Owner': means the owner of the Lands on which the Well or Work is situated.
- .13 Landowner's Access Agreement: means the agreement created by the others granting permission to the Contractor and others to enter the property of the Landowner for the purpose of providing the Work for this specific Project.
- .14 MNR: Ministry of Natural Resources.
- .15 Potable water: water that is safe for human consumption.
- .16 Sour Gas: means natural gas containing chemical impurities, notably hydrogen sulphide (H2S) or

1.2 DEFINITIONS (Cont'd)

- .16 Sour Gas:(Cont'd) other sulphur compounds that make it extremely harmful to breathe even in small amounts.
- .17 Standby Time: means but
 - .1 Standby Time charges for the rig and crew will be allowed for delays incurred by Contractor in performing the work resulting from Departmental Representatives direction(s) to accommodate such events as Departmental Representative evaluations or consultations to resolve unforeseen complications.
 - .2 Standby Time does not include waiting time inherent in providing the work or due to equipment breakdowns, unavailability of personnel or other events within the reasonable control of the Contractor and does not include Force Majeure events.
 - .3 Where progress in clearing the Well bore, despite the best efforts of the Contractor, is slowed to less than 3 metres per hour, or if the Contractor requires special tools not reasonably contemplated at the outset of the work, the Contractor may discontinue work with the approval of the Departmental Representative. Perform the additional work to clean out or log the Well bore at the applicable Rates on a per hour basis.
 - .4 Charges for such additional work and Standby Time shall cease when instructed by the Departmental Representative to resume plugging and abandonment of the Well. The Departmental Representative shall, in their sole discretion, determine the nature and amount of any payments for such additional work and Standby Time.
- .18 Sweet Gas: means natural gas free of significant amounts of hydrogen sulphide (H2S) when produced.
- .19 Term: means the period of time from the effective commencement date up to and including the later of the original Contract completion date, and may vary, depending on:
 - .1 The expiry date of any extension to the Contract; or
 - .2 The expiry date of the last to expire term, including any extension thereof, of the Contract(s) between parties.
- .20 Unconsolidated formation: geologic formation of sand, gravel or other soil strata.

PWGSC Ontario	OIL & GAS WELL	Section 33 29 00
Region Project	ABANDONMENT	Page 5
Number R.059392.001		2013-09-10

1.2 DEFINITIONS (Cont'd)

- .21 Well: means the well as defined by the Oil, Gas and Salt Resources Act located on the Lands or Site as more particularly identified and described in Appendices 2 and 3.
- .22 Well datum: top of outer casing or similar fixed point of well head with elevation tied to geodetic or suitable local datum.

1.3 SUBMITTALS .1

- .1 In accordance with Section 01 11 01.
- .2 Prior to the award of this Contract, the Contractor must provide the Departmental Representative with a copy of the well contractor and technician licenses, as may also be required by the MNR.
- .3 Submit the Decommissioning Plan including the detailed procedures for the proper investigation of, and abandonment of, each well bore to ensure the isolation of each hydrocarbon bearing formation and the protection of any aquifers. The procedures must include provision of daily operations reports and other progress reports to IOGC during the abandonment operations (NOTE that these reports will come to IOGC's petroleum geologist).
- .4 Submit a written schedule to the Departmental Representative forty-eight (48) hours prior to the start of plugging or restoration operations.
- .5 Submit photos as per Section 01 11 01 Clause 1.14.
- .6 During the plugging activities, submit reports at least weekly, in writing, to the Departmental Representative as to the progress of the Project and up-to-date totals of payment items.
- .7 On completion of Work, submit to Departmental Representative:
 - .1 Copies of all Project documents.
 - .2 Copies of inspection reports.
 - .3 Waste disposal information including waste volumes, description/characterization, disposal location and receipt(s) for disposal fees.
- .8 Within twenty (20) days after the completion of the plugging operations and all Deliverables, prepare and submit a plugging report to the MNR and Departmental Representative, in accordance with the Provincial Standards. The MNR will then

PWGSC Ontario	OIL & GAS WELL	Section 33 29 00
Region Project	ABANDONMENT	Page 6
Number R.059392.001		2013-09-10

1.3 SUBMITTALS (Cont'd)

.8 (Cont'd)
issue a Certificate of Completion to the
contractor with a copy to the Departmental
Representative.

1.4 QUALIFICATIONS .1

. 2

1 Well decommissioning work shall be undertaken by a licensed oil and gas well drilling contractor.

While Work is in progress, have a Site

Supervisor on site who shall oversee the decommissioning operations, make Project decisions on behalf of the Contractor and communicate with the MNR.

.1 The Site Supervisor must be a member of the Project team, and must have the authority to make decisions and be able to communicate effectively after consultation with the Departmental Representative. The Departmental Representative must be able, at all times, to contact the Site Supervisor by means of cellular

1.5 WASTE MANAGEMENT AND DISPOSAL

.1 Separate waste materials for reuse and recycling when possible.

or other telecommunications means.

- .2 Removal and proper disposal of all surface equipment at the Site, including, but not limited to, tanks, pipelines, production equipment, debris, etc in accordance with the Plan. Pipelines may be decommissioned in place with the prior written approval of the MNR. Where pipelines are left in place, they shall be flushed if possible, and, where they cannot be easily removed, cut at regular intervals and capped.
- .3 Divert unused plugging materials from landfill to local facility as approved by Departmental Representative.
- .4 Divert unused backfill materials from landfill to facility for reuse as approved by Departmental Representative.

PWGSC Ontario Region Project Number R.059392.001		OIL & GAS WELL ABANDONMENT	Section 33 29 00 Page 7 2013-09-10
1.6 PROJECT CONDITIONS	.1	The properties may or may considerate of the tenant for the tenant.	
	.2	Overhead wires, structures restrict access to the wor	_
1.7 WORK SCHEDULE	.1	All wells must be abandone	ed.
	.2	All landscape work include seeding/sodding work must Contract completion date.	
PART 2 - PRODUCTS			
2.1 MATERIALS	.1	Oil Well abandonment plug and Salt Resources Act, R	
	.2	Clean sand fill material: 153/04, under Part XV.1 or Protection Act, table 1.	_
	.3	Topsoil: Material capable vegetative growth and suit dressing, landscaping and	table for use in top
	. 4	Fertilizer: 8-32-16 raked rate of 350 kg per hectare	-
	.5	Grass seed: Certified Canada, Seed Kentucky Blue grass, 45% Norlea perennial rye; 75% purity applied at a rate of Water all restored areas a saturated to a depth of 5	ds Regulations, 50% Creeping Red Fescue, 5% germination, 97% of 100 kg per hectare. until topsoil is

PWGSC Ontario	OIL & GAS WELL	Section 33 29 00
Region Project	ABANDONMENT	Page 8
Number R.059392.001		2013-09-10

PART 3 - EXECUTION

3.1 REVIEW OF AVAILABLE INFORMATION

- .1 Attached Appendices 2 and 3 provide a partial description of the wells to decommission.
- .2 For sites where the well depth of wells is not known, Contractor will be paid for the actual hours to abandon the well as set out in the Contract unit price.

3.2 WELL PLUGGING .1

- Perform all work in accordance with the specifications as listed in section 11 of the Ontario Provincial Standards Version 2 dated January 2002. Abandonment includes, but is not necessarily limited to:
 - .1 Preparation of a Decommissioning Plan for approval by PWGSC.
 - .2 Accessing the site.
 - .3 Clearing and grubbing
 - .4 Re-entering the well.
 - .5 Removal of tubing and casing wherever possible.
 - .6 Cleaning out of the casing.
 - .7 Filling the casing with cement to surface.
 - .8 Excavation of the area around the casing.
 - .9 Disposal of contaminated soil.
 - .10 Cutting off and removing the casing at least one metre below grade.
 - .11 Welding a metal cap on to the casing.
 - .12 Backfilling the excavation.
 - .13 Restoration of disturbed areas to condition acceptable to departamental representative.
- .2 Control, divert, and dispose of Sweet or Sour Gas.
- .3 Clean the casing of loose material and check to see if the Well is open to total depth. Maintain Well open and casing free of contaminating materials.
- .4 Remove and properly dispose of any contaminated fluids, soil, or other substances and materials from the Site, and subsequent related clean-up. Only uncontaminated water may be wasted to the surface ground level as long as it does not cause erosion or siltation.
 - .1 All oily debris (e.g. rocks, wood, etc. contaminated with oil) and metal products produced as a result of this Project, or

3.2 WELL PLUGGING (Cont'd)

.4 (Cont'd) .1 (Cont'd)

otherwise remaining, shall be removed from the Site and disposed of at the contractor's sole risk and responsibility according to all applicable legislation and Industry Standards. During plugging operations and prior to disposal, contaminated fluids are to be temporarily stored in suitable sealable containers prior to disposal. All material contaminated with oil, etc., that is removed from or around the Well, shall be temporarily contained or stockpiled on impermeable oil resistant tarps and covered, or stored in sealable drums or other suitable containers to prevent contamination of clean surrounding areas.

- .5 Should the Contractor determine that conditions in the Well prevent plugging as originally planned, immediately inform Departmental Representative of the condition and the proposed alternative method of plugging. Obtain Departmental Representative's approval prior to proceeding with an alternative plugging and abandonment procedures.
- of all federal, provincial and municipal legislation, including without limitation Provincial Standards, and Industry Standards, including without limitation running caliper, and gamma ray/neutron or other wireline logs, placing neat cement and bentonite grout plugs in abandoned Well, perforating and squeezing cement behind casing or removing casing entirely to achieve isolation of porous formations, and properly disposing of solid and fluid wastes, including those contaminated by hydrocarbons, salt, or other formation fluids.

3.3 SOIL EXCAVATION .1

- As directed by the Departmental Representative, excavate and remove any visibly or otherwise apparently contaminated soil for proper waste disposal. Communicate with the Departmental Representative, daily, during excavation of visibly or otherwise apparently contaminated soil to discuss estimated volumes and costs of removal, to attain preapproval of any changes in the scope of work.
- .2 The Departmental Representative must witness and approve the extent of excavation of

3.3 SOIL EXCAVATION .2 (Cont'd)

- (Cont'd) contaminated soil and the taking of soil samples to confirm that the perimeter and floor of the excavation is clean.
- .3 Confirmatory soil sampling will be undertaken as directed and will be paid for by the Departmental Representative to ensure soil contaminants are removed.
- .4 The excavation is not to be backfilled until acceptable soil test results from the floor and walls of the excavation are received. Anticipate that the test results will take at least 5 days. Assume that there may have to be two cycles of testing required. ie. Assume waiting 5 days for the first sample results to be received. If the result is negative, further excavation will be completed and a second round of sampling taken which will require a further 5 days to receive presumeably clean results.
 - .1 The confirmatory soil samples will be compared to CCME residential criteria for BTEX and Polyhydrocarbon fractions F1 F4.
- .5 Upon completion of excavation, cut the Well casing off at least one metre below grade and weld a steel plate on top of casing prior to backfill.
- .6 Remove and properly dispose of any associated equipment such as concrete pads, visible pipelines, or other found materials during excavation.

3.4 BACKFILL, TOPSOIL AND SEED

- .1 Provide source of clean backfill and topsoil for inspection and preapproval.
- .2 After soil excavation and acceptable test results, backfill the excavation with pre-approved backfill material.
 .1 Place backfill in 150 mm layers compacted to 95% proctor density.
- .3 Provide 100 mm cover of topsoil and seed at an application rate of 100 kg per hectare for Well #1B and Well #2, and rake smooth to match the surrounding grades, as directed by the Departmental Representative.

PWGSC Ontario	OIL & GAS WELL	Section 33 29 00
Region Project	ABANDONMENT	Page 11
Number R.059392.001		2013-09-10

3.5 CLEAN UP .1

- .1 Contractor is responsible for ensuring that each property is left in equivalent or better condition upon completion of the Work at each property.
- .2 Remove all Well plugging tools, equipment, materials and debris.
- .3 Remove security fencing, warning signs, etc.
- .4 Break down, clean-up and demobilize.