





stamp



01	ISSUED FOR BID	2013/10/04
revision	description	date

Do not scale drawings
Verify all dimensions and conditions on site and
Immediately notify the Departmental Representative of all
discrepancies

	A detail no. no. du détail
	B drawing no. - where detail required dessin no. - où détail exigé
	C drawing no. - where detailed dessin no. - où détaillé

project title
titre du projet
GRAND VALLEY INSTITUTION FOR WOMEN
1575 HOMER WATSON BLVD.
KITCHENER, ONTARIO, N2P 2C5

PRINCIPAL ENTRANCE BUILDING

drawing title
titre du dessin
**CONTROLS REPLACEMENT
SITE PLAN**

drawn by
dessiné par GR

designed by
conçue par JDB


approved by
approuvé par RD

bid
offre RP project manager
administrateur
de projets

project date
date du projet 2013-04-19

project no.
no. du projet DIALOG NO. 09487T.02
R.047995.001

drawing no.
dessiné no. **M7.00**



SCOPE OF WORK
IFSS = INTEGRATE EXISTING CONTROL SYSTEM INTO NEW OPERATORS WORK STATION.
PEB = INSTALL NEW CONTROL SYSTEM.
IIU = INTEGRATE EXISTING CONTROL SYSTEM INTO NEW OPERATORS WORK STATION.
SLE = REPLACE EXISTING SYSTEM AND INTEGRATE EXISTING CONTROL SYSTEM INTO NEW
OPERATORS WORK STATION.
SOUTH STORAGE = INTEGRATE EXISTING CONTROL SYSTEM INTO NEW
OPERATORS WORK STATION.
GVI MAIN BUILDING
BLDG. A = REPLACE EXISTING CONTROL SYSTEM.
BLDG. B = REPLACE EXISTING CONTROL SYSTEM.
BLDG. C = REPLACE EXISTING CONTROL SYSTEM.
MAINTENANCE BUILDING = REPLACE EXISTING OPERATORS WORK STATION

CONTROLS REPLACEMENT PHASING
1. CONTROL REPLACEMENT TO OCCUR WHILE BUILDING IS FULLY OPERATIONAL.
2. CONTROLLERS TO BE REPLACED, TESTED, AND MADE OPERATIONAL ON AN INDIVIDUAL
BASIS TO MINIMIZE NECESSARY EQUIPMENT DOWNTIME.
3. ALL CONTROLLERS TO BE CAPABLE OF OPERATING AS STAND-ALONE.
4. EXISTING OPERATORS WORK STATION TO REMAIN ACTIVE AND FULLY OPERATIONAL
UNTIL ALL EXISTING CONTROLLERS REQUIRING REPLACEMENT HAVE BEEN REPLACED
AND ARE OPERATING STABLE STAND-ALONE FASHION.
5. CONTRACTOR TO ENSURE COMMUNICATION ON THE EXISTING BUS WILL
NOT AT ANY TIME BE IN CONFLICT BETWEEN THE TWO OPERATOR WORK STATIONS.
6. THE CONTRACTOR SHALL MEET WITH THE DEPARTMENTAL REPRESENTATIVE 2 WEEKS
AFTER PROJECT AWARD TO DISCUSS SCHEDULE FOR CONTROL REPLACEMENT SCOPE
OF WORK, ACCESS TO EQUIPMENT AREAS, AND SECURITY REQUIREMENTS.