


DIALOG™

stamp



01 ISSUED FOR BID 2013/10/04

revision date

Do not scale drawings
Verify all dimensions and conditions on site and
immediately notify the Departmental Representative of all
discrepancies

A detail no.
no. du détail
B drawing no. - where detail required
dessin no. - où détail exigé
C drawing no. - where detailed
dessin no. - où détaillé

project title
titre du projet

GRAND VALLEY INSTITUTION FOR WOMEN
1575 HOMER WATSON BLVD.
KITCHENER, ONTARIO, N2P2C5

PRINCIPAL ENTRANCE BUILDING

drawing title
titre du dessin

SECOND FLOOR
PLUMBING PLAN-PEB

drawn by
dessiné par GR

designed by
conc par JDB

approved by
approuvé par RD


bid
offre RP project manager
administrateur de projets

project date
date du projet 2013-04-19

project no.
no. du projet DIALOG NO. 09487T.02
R.047995.001

drawing no.
dessiné no.

M2.06



1 SECOND FLOOR PLUMBING PLAN-PEB
M2.06 1:100

MECHANICAL PLUMBING SERVICE REQUIREMENTS

TAG	DCW (MM)	DHW (MM)	DRAIN (MM)	VENT (MM)	REMARKS
JS	20	20	75	40	
LAV	15	15	40	32	
SK	15	15	40	32	
WC	25	-	100	50	
FD	-	-	75	40	

GENERAL NOTES

1. PROVIDE ALL MATERIALS AND EQUIPMENT AND PERFORM ALL LABOUR AS INDICATED AND AS REQUIRED TO COMPLETE THE WORK
2. UNLESS OTHERWISE NOTED ALL DRAINAGE PIPING 75Ø AND SMALLER TO BE SLOPED AT 2%. ALL DRAINAGE PIPING 100Ø AND LARGER TO BE SLOPED AT 1%.
3. CONTRACTOR TO TRAP, PRIME & VENT ALL DRAINS AND FIXTURES AS PER NATIONAL AND LOCAL BUILDING CODES.
4. FIRE STOP ALL PENETRATIONS THROUGH FIRE RATED ASSEMBLIES WITH APPROVED FIRE STOPPING SYSTEM TO MAINTAIN INTEGRITY OF ASSEMBLY.
5. ALL PIPING BRANCHES TO BE COMPLETE WITH ISOLATION VALVES.
6. HOT WATER RECIRC BALANCING VALVES TO BE PRESSURE INDEPENDENT TYPE.
7. MECHANICAL CONTRACTOR TO TERMINATE VENTS AT COORDINATED LOCATIONS INDICATED ON DWGS.
8. CONTRACTOR IS TO BE RESPONSIBLE FOR FINAL CONNECTIONS TO ALL OWNER SUPPLIED EQUIPMENT.