


stamp



01	ISSUED FOR BID	2013/10/04
revision		date

Do not scale drawings  
Verify all dimensions and conditions on site and  
immediately notify the Departmental Representative of all  
discrepancies

A	detail no. no. du détail
B	drawing no. - where detail required dessin no. - où détail exigé
C	drawing no. - where detailed dessin no. - où détaillé

project title  
titre du projet  
**GRAND VALLEY INSTITUTION FOR WOMEN  
1575 HOMER WATSON BLVD.  
KITCHENER, ONTARIO, N2P2C5**  
**PRINCIPAL ENTRANCE BUILDING**

drawing title  
titre du dessin  
**SECOND FLOOR HVAC  
PIPING PLAN-PEB**

drawn by  
dessiné par  
GR

designed by  
conçu par  
JDB

approved by  
approuvé par  
RD


bid  
offre  
RP

project manager  
administrateur  
de projets

project date  
date du projet  
2013-04-19

project no.  
no. du projet  
DIALOG NO. 09487T.02  
R.047995.001

drawing no.  
dessiné no.  
**M2.08**



1 SECOND FLOOR HVAC PIPING PLAN-PEB  
M2.08 1:100

#### GENERAL NOTES

- REFRIGERANT PIPING TO RUN HIGH WITHIN PLENUM SPACE ABOVE ALL SERVICES.
- GENERAL REFRIGERANT PIPE LAYOUT SHOWN FOR GENERAL INTENT ONLY. MECHANICAL CONTRACTOR TO SIZE REFRIGERANT PIPING AS PER MANUFACTURER RECOMMENDATIONS.
- HEAT RECOVERY UNIT LOCATION AND QUANTITY INDICATED ON DRAWINGS IS DEPENDANT ON MULTI-SPLIT EQUIPMENT MANUFACTURER. MECHANICAL CONTRACTOR IS RESPONSIBLE FOR ADJUSTING THE QUANTITY OF HEAT RECOVERY BOXES TO SUIT MANUFACTURE'S INSTALLATION REQUIREMENTS.

#### KEY NOTES

- THERMOSTAT FOR FAN COIL FC-24 LOCATED ON LOWER LEVEL. REFER TO DWG M2.03
- MECHANICAL CONTRACTOR TO PROVIDE ISOLATION VALVES ON ALL HEAT RECOVERY PORTS TO, OUTDOOR UNITS AND OTHER HEAT RECOVERY BOXES.