


stamp



01	ISSUED FOR BID	2013/10/04
----	----------------	------------

revision	description	date
----------	-------------	------

Do not scale drawings
Verify all dimensions and conditions on site and
immediately notify the Departmental Representative of all
discrepancies

	A detail no. no. du détail
B	drawing no. - where detail required dessin no. - où détail exigé
C	drawing no. - where detailed dessin no. - où détaillé

project title
titre du projet
GRAND VALLEY INSTITUTION FOR WOMEN
1575 HOMER WATSON BLVD.
KITCHENER, ONTARIO, N2P 2C5

PRINCIPAL ENTRANCE BUILDING

drawing title
titre du dessin
**GROUND FLOOR FIRE
PROTECTION DEMOLITION &
UPGRADE PLAN-A**

drawn by
dessiné par GR

designed by
conçue par JDB

approved by
approuvé par RD

bid
offre RP project manager
administrateur de projets

project date
date du projet 2013-04-19

project no.
no. du projet DIALOG NO. 09487T.02
R.047995.001

drawing no.
dessiné no. **M1.13**




1 GROUND FLOOR FIRE PROTECTION DEMOLITION PLAN-A
M1.13 SCALE: 1:100

GENERAL NOTES

- THIS DRAWING INDICATES GENERAL INTENT OF DESIGN ONLY. CONTRACTOR TO VERIFY EXISTING SITE CONDITION. PRIOR TO ORDERING MATERIALS AND COMMENCING WORK. REPORT TO DEPARTMENTAL REPRESENTATIVE ANY DISCREPANCIES BETWEEN EXISTING AND DESIGN DRAWINGS.
- DEMOLISH WORK AS INDICATED.
- REMOVE ALL DEBRIS AND RUBBISH ONCE JOB IS COMPLETE.
- COORDINATE DEMOLITION AND REPAIR WITH ALL TRADES.

KEY NOTES

- REMOVE SPRINKLERS TO FACILITATE CEILING MODIFICATIONS.



2 GROUND FLOOR FIRE PROTECTION UPGRADE PLAN-A
M1.13 SCALE: 1:100

GENERAL NOTES

- THIS DRAWING INDICATES GENERAL INTENT OF DESIGN ONLY. CONTRACTOR TO VERIFY EXISTING SITE CONDITIONS. PRIOR TO ORDERING MATERIALS AND COMMENCING WORK. REPORT TO DEPARTMENTAL REPRESENTATIVE ANY DISCREPANCIES BETWEEN EXISTING AND DESIGN DRAWINGS.
- ZONE COVERAGE TO BE LIGHT HAZARD UNLESS OTHERWISE SPECIFIED.
- REFER TO SPECIFICATIONS FOR SPRINKLER TYPES TO BE INSTALLED BASED ON CEILING FINISHES.
- COORDINATE INSTALLATION OF NEW WORK WITH ALL TRADES.

KEYNOTES

- SPRINKLERS WITHIN ELECTRICAL AND COMMUNICATIONS ROOMS TO BE INTERMEDIATE TEMPERATURE RATED.