

RETURN BIDS TO:
RETOURNER LES SOUMISSIONS À:
Regional Manager/Real Property
Contracting/PWGSC
Ontario Region, Tendering Office
12th Floor, 4900 Yonge Street
Toronto, Ontario
M2N 6A6
Ontario

SOLICITATION AMENDMENT MODIFICATION DE L'INVITATION

The referenced document is hereby revised; unless otherwise indicated, all other terms and conditions of the Solicitation remain the same.

Ce document est par la présente révisé; sauf indication contraire, les modalités de l'invitation demeurent les mêmes.

Comments - Commentaires

Vendor/Firm Name and Address
Raison sociale et adresse du
fournisseur/de l'entrepreneur

Issuing Office - Bureau de distribution
Regional Manager/Real Property Contracting/PWGSC
Ontario Region, Tendering Office
12th Floor, 4900 Yonge Street
Toronto, Ontario
M2N 6A6
Ontario

Title - Sujet Millhaven Institution, electrical d	
Solicitation No. - N° de l'invitation EQ734-141187/A	Amendment No. - N° modif. 004
Client Reference No. - N° de référence du client R.053529.001	Date 2013-11-07
GETS Reference No. - N° de référence de SEAG PW-\$PWL-037-1888	
File No. - N° de dossier PWL-3-36043 (037)	CCC No./N° CCC - FMS No./N° VME
Solicitation Closes - L'invitation prend fin at - à 02:00 PM on - le 2013-11-12	Time Zone Fuseau horaire Eastern Daylight Saving Time EDT
F.O.B. - F.A.B. Plant-Usine: <input type="checkbox"/> Destination: <input checked="" type="checkbox"/> Other-Autre: <input type="checkbox"/>	
Address Enquiries to: - Adresser toutes questions à: Dhillon, Ambreen	Buyer Id - Id de l'acheteur pwl037
Telephone No. - N° de téléphone (416) 590-8253 ()	FAX No. - N° de FAX (416) 512-5862
Destination - of Goods, Services, and Construction: Destination - des biens, services et construction: Correctional Services Canada Millhaven Institution Highway 33 Bath, ON K0H 1G0	

Instructions: See Herein

Instructions: Voir aux présentes

Delivery Required - Livraison exigée	Delivery Offered - Livraison proposée
Vendor/Firm Name and Address Raison sociale et adresse du fournisseur/de l'entrepreneur	
Telephone No. - N° de téléphone Facsimile No. - N° de télécopieur	
Name and title of person authorized to sign on behalf of Vendor/Firm (type or print) Nom et titre de la personne autorisée à signer au nom du fournisseur/ de l'entrepreneur (taper ou écrire en caractères d'imprimerie)	
Signature	Date

Amendment 004

This amendment is being raised to provide the answers asked by bidders and to provide a revision to the specifications.

Specifications:

Please note that "Appendix A: Designated Substances Report" on Section 02 82 00.02 of the Specifications document should be "Appendix B and C: Designated Substances Report".

Additional information for the already answered questions no. 4 on Amendment 002:

4) It is noted that we are to provide new breakers in S1 and S2 panels. Please verify that it is the intent to shut down both panels in a night outage at different times to change the breakers. If this is the intent then 6 panels will be down at each outage. Please confirm that these meets approval

Questions and Answers:

Answer:

Contractor is to include in the bid price for the following to minimize duration and extent of power outages:

a) During work on Essential Distribution Panel 'S1', and secondary water supply feeder, provide and connect a diesel generator with sufficient fuel to back up the 150HP, 600 volt, 3 phase fire pump.

b) Prior to work on Essential Distribution Panel 'S1', install temporary jumpers from main bus of normal distribution panels to essential distribution panels as follows:

NPPA-600 to EPPA-600, NPPE-600 to EPPE-600, NPPJ-600 to EPPJ-600, NPPS-600 to EPPS-600, NPPT-600 to EPPT-600, NPPU-600 to EPPU-600.

c) Provide appropriate double lugs in all new distribution panels to facilitate installation of jumpers.

d) For one week prior to, and during work on Essential Distribution Panel 'S1', provide recording ammeter on each panel 'S1 and 'S2' to establish total load on panel 'S1' and 'S2' prior to connection of temporary jumpers described above and during period when jumpers are installed. Coordinate load shedding of lower priority loads as required with the institution prior to installing jumpers.

e) Prior to replacing each normal and essential distribution panel or raising transformers, provide an appropriate temporary distribution panel with sufficient breakers, and temporarily connect to the bus of the other panel, (normal or essential), adjacent to the panel being replaced. Use appropriate temporary jumpers to power all branch circuit loads from the temporary panel while the new panel is being installed. Transfer loads one by one to the new panel after the new panel is energized.

f) Submit a workable plan for each of the above items prior to implementation. The actual implementation will be coordinated with the institution.

Solicitation No. - N° de l'invitation

EQ734-141187/A

Client Ref. No. - N° de réf. du client

R.053529.001

Amd. No. - N° de la modif.

004

File No. - N° du dossier

PWL-3-36043

Buyer ID - Id de l'acheteur

pw1037

CCC No./N° CCC - FMS No/ N° VME

2) The Specifications indicate keeping security running at all times. In order for us to provide a costing for this we require further information as to what security components are required to stay functional, as there is no information as to what security items are on UPS back up and what are not. Would it be possible to address the Security requirements as a cash allowance, to be carried at the time of Tender. Please advise/provide further information in order to account for this in our quote.

Answer:

See answer to question 1 above.