

PART 1 - GENERAL

- | | | |
|---------------------------------------|----|---------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|
| <u>1.1 SECTION INCLUDES</u> | .1 | Barriers. |
| | .2 | Traffic Controls. |
| <u>1.2 INSTALLATION AND REMOVAL</u> | .1 | Provide temporary controls in order to execute work expeditiously. |
| | .2 | Remove from site all such work after use. |
| <u>1.3 HOARDING</u> | .1 | Erect temporary site enclosure using new 1.2 m high snow fence wired to rolled steel "T" bar fence posts spaced at 2.4 m centres. Provide one lockable truck gate. Maintain fence in good repair. |
| <u>1.4 GUARD RAILS AND BARRICADES</u> | .1 | Provide secure, rigid guard rails and barricades around open excavations. |
| | .2 | Provide barricades along wharf structure when wheelguard is removed. |
| | .3 | Provide as required by governing authorities. |
| <u>1.5 ACCESS TO SITE</u> | .1 | Provide and maintain access to adjacent harbour facilities. |
| <u>1.6 PUBLIC TRAFFIC FLOW</u> | .1 | Provide and maintain competent signal flag operators, traffic signals, barricades and flares, lights, or lanterns as required to perform work and protect the public. |

- 1.7 FIRE ROUTES .1 Maintain access to property including overhead clearances for use by emergency response vehicles.
- 1.8 PROTECTION FOR OFF-SITE AND PUBLIC PROPERTY .1 Protect surrounding private and public property from damage during performance of work.
- .2 Be responsible for damage incurred.