

## **GENERAL**

The following changes/ clarifications in the tender documents are effective immediately. This Addendum will form part of the Contract Documents.

## **GENERAL CLARIFICATIONS**

1. Man Lift or crane will be required in most locations for access to windows over man-walks and structures below.

## **ARCHITECTURAL DRAWINGS**

### **Drawing A-1 (E) Partial Plan**

1. Provide Plywood sheets between existing shed and frame supporting ducts on South facing windows to shelter access to shed and tank area below from falling debris from window work.

### **Drawing A-1 -1 Landing 1 Floor Plan**

1. Provide offset for mechanical duct & grill as required to suit new frame location.

## **SPECIFICATION SECTIONS**

### **01 11 55 –General Instructions**

#### **5 Time of Completion**

Delete :

- ~~.1 Complete all work, within 12 weeks of Contact Award.~~

Add :

- .1 Complete all work, within 18 weeks of Contact Award.

### **01 51 00 –General Instructions**

Add :

- .10 Tarp all openings to minimise rain ingress when it will not interfere with work.

### **08 50 00 –Aluminium Windows**

Add :

#### **2.3 Components**

- .6 Provide restrictors for all operable windows.

END OF ADDENDUM 2