



DRAWING KEYNOTES:

1. CONCRETE STEPS TO CONCRETE LANDING @ GRADE. SLOPE SURROUNDING GRADE UP TO MEET LANDING SLAB.
2. RELOCATED EXISTING GALVANIZED STEEL HANDRAIL & GUARDRAIL. MODIFY AS REQUIRED TO SUIT NEW CONSTRUCTION.
3. EXISTING CONCRETE STEPS.
4. PARTIAL HEIGHT GLAZED STOREFRONT WALL PANELS AS WIND PROTECTION, TYPICAL.
5. EXISTING HANDRAIL & GUARDRAIL TO REMAIN.
6. RELOCATED DOCK BUMPERS @ OH DOOR.
7. CUT & REMOVE EXISTING GALVANIZED STEEL GUARDRAILS AND SUPPORTS AND HANDRAILS FOR REUSE.
8. EDGE OF ROOF CANOPY ABOVE.
9. NEW CONCRETE STAIRS & LANDING.
10. PROVIDE UPRIGHT TYPE SPRINKLER HEADS AND CONNECT TO NEAREST SUITABLE EXISTING DRY PIPE SPRINKLER SYSTEM. PROVIDE LOW POINT DRAIN AS REQUIRED. SEE MF-1 FOR TIE IN.
11. TRAFFIC DOORS PER SCHEDULE.
12. REMOVE AND REMOUNT EXISTING DOOR & FRAME AS SHOWN. PROVIDE NEW FRAME.
13. DEMOLISH EXISTING CONCRETE STAIRS & REMOVE EXISTING GUARDRAILS FOR RELOCATION. PATCH & REPAIR ASPHALT AS REQUIRED.
14. REMOVE 3X EXISTING DOCK BUMPERS FOR RELOCATION TO ANGLED LOADING DOCK.

DO NOT SCALE DRAWINGS

1	ADDENDUM NO. 1	2013/11/12
0	ISSUED FOR CONSTRUCTION	2013/07/10
Revision/	Description/Description	Date/Date
Revision		

Client/client

PUBLIC WORKS
AND GOVERNMENT SERVICES
CANADA

JC WILT INFECTIOUS DISEASES
RESEARCH CENTRE

Project title/Titre du projet

745 LOGAN AVENUE
WINNIPEG, MANITOBA

JC WILT LOADING
DOCK CANOPY

Approved by/Approuvé par

LW

Designed by/Concept par

DM

Drawn by/Dessiné par

CR

PWGSC Project Manager/Administrateur de Projets TPSGC

TOM MELANCHUK

PWGSC, Architectural and Engineering Resources Manager/
Ressources Architectural et de Directeur d'Ingénierie, TPSGC

Client/client

PUBLIC WORKS AND GOVERNMENT SERVICES CANADA

Drawing title/Titre du dessin

MAIN FLOOR PLAN
LOADING DOCK CANOPY

Project No./No. du projet

R.015646.023

Sheet/Feuille

A110
OF XX

Revision no./
La Révision no.

1