

RETURN BIDS TO:
RETOURNER LES SOUMISSIONS À:
Regional Manager/Real Property
Contracting/PWGSC
Ontario Region, Tendering Office
12th Floor, 4900 Yonge Street
Toronto, Ontario
M2N 6A6
Ontario

SOLICITATION AMENDMENT MODIFICATION DE L'INVITATION

The referenced document is hereby revised; unless otherwise indicated, all other terms and conditions of the Solicitation remain the same.

Ce document est par la présente révisé; sauf indication contraire, les modalités de l'invitation demeurent les mêmes.

Comments - Commentaires

Vendor/Firm Name and Address
Raison sociale et adresse du
fournisseur/de l'entrepreneur

Issuing Office - Bureau de distribution
Regional Manager/Real Property Contracting/PWGSC
Ontario Region, Tendering Office
12th Floor, 4900 Yonge Street
Toronto, Ontario
M2N 6A6
Ontario

Title - Sujet Kingston, ON - Lasalle Causeway con	
Solicitation No. - N° de l'invitation EQ754-141415/A	Amendment No. - N° modif. 002
Client Reference No. - N° de référence du client R.013375.025	Date 2013-11-13
GETS Reference No. - N° de référence de SEAG PW-\$PWL-037-1891	
File No. - N° de dossier PWL-3-36057 (037)	CCC No./N° CCC - FMS No./N° VME
Solicitation Closes - L'invitation prend fin at - à 02:00 PM on - le 2013-11-19	Time Zone Fuseau horaire Eastern Standard Time EST
F.O.B. - F.A.B. Plant-Usine: <input type="checkbox"/> Destination: <input checked="" type="checkbox"/> Other-Autre: <input type="checkbox"/>	
Address Enquiries to: - Adresser toutes questions à: Dhillon, Ambreen	Buyer Id - Id de l'acheteur pwl037
Telephone No. - N° de téléphone (416) 590-8259 ()	FAX No. - N° de FAX (416) 512-5862
Destination - of Goods, Services, and Construction: Destination - des biens, services et construction: PWGSC-TPSGC Joseph Shepard Building 32 4900 Yonge Street Toronto, ON M2N 6A6	

Instructions: See Herein

Instructions: Voir aux présentes

Delivery Required - Livraison exigée	Delivery Offered - Livraison proposée
Vendor/Firm Name and Address Raison sociale et adresse du fournisseur/de l'entrepreneur	
Telephone No. - N° de téléphone Facsimile No. - N° de télécopieur	
Name and title of person authorized to sign on behalf of Vendor/Firm (type or print) Nom et titre de la personne autorisée à signer au nom du fournisseur/ de l'entrepreneur (taper ou écrire en caractères d'imprimerie)	
Signature	Date

Amendment 002

This amendment is being raised to provide the answers to questions submitted during the solicitation period

Questions and Answers:

Q1) May you please provide us with a section or clarification of the following concrete slab, noted on the Partial Site Plan:

· 200 mm Thick Conc slab reinforced with 15M @ 300 E.W in Mid Depth

A1) Please find sketch attached.

Q2) In regards to the stock pile of counter weight and bent metal, located near the construction of the new reinforced concrete retaining wall (west wharf). Where is this stock pile being re-located, please clarify and provide us with site instructions.

A2) Contractor to haul away from site and dispose all galvanized railing pile up by the proposed new retaining wall. Green steel plates are to be kept on site. Contractor to relocate plates during work to a location to be determined by the Departmental Representative.

Q3) In regards to the southeast wingwall at the conduit concrete bank repairs. To perform our form work, pour and allow concrete to cure, is there enough slack in the cable to perform our work. Please clarify and provide us with site instructions.

A3) We understand that the question refers to black electrical conduit fastened to the wing wall. The Contractor shall remove the conduit, temporarily, and restore to its original state as soon as the concrete work is completed. Only qualified, licensed electrician can perform this work.

Q4) At the southeast wingwall at the conduit concrete bank repair, we had noticed a few pipes that are coated with lead. Well is be a concern to our workers health, since we are pouring concrete and conducting various other tasks in this area. Please clarify and provide us with site instructions.

A4) We understand that the question refers to two existing submarine bell cables. Material composition of those cables is not known at the present time. Exposed conduits complete with armoring shall be protected during construction from damage due to construction activities. Area in question is to be covered with concrete, see section C/101. Conduit covers are not to be disturbed.

Q5) In regards to Drawing #101, section D/101, E/101, A/101 and C/101. We would like to know if we will be encountering any existing rebar, during the removal of existing concrete of 150 mm with 75 mm saw cut deep.

A5) The Contractor shall anticipate reinforcing bars presence during concrete excavation shown on drawing 101 in sections A/101, D/101 and E/101. Size, number and location is unknown. There is no concrete excavation shown on section C/101.