

RECOMMENDED BY	DATE
<i>[Signature]</i>	Mar 20/73
APPROVED & RECOMMENDED	DATE
<i>[Signature]</i>	Mar 22/73
APPROVED & RECOMMENDED	DATE
<i>[Signature]</i>	Mar 28/73
CHECKED FOR HISTORICAL ACCURACY	DATE
<i>[Signature]</i>	April 27, 1973

revisions	date
-----------	------

NOTES CONT.

② - ALL STRUCTURAL MEMBERS TO BE #1 CONSTRUCTION OR STRUCTURAL GRADE SPRUCE OR HEMLOCK.

③ - ALL TIMBER SIZES ARE FINISHED SIZES UNLESS OTHERWISE NOTED.

Door 102 is not rigid style. *ff*

Stairway at west end of building has been added for convenience of visitors. *ff*

A detail no.	détail no.
B location dwg. no. / sur dessin no.	
C drawing no.	dessin no.

drawn by / tracé par  
*L. E. B.*

scale / échelle  
AS SHOWN

designed by / établi par  
*L. E. B.*

checked by / vérifié par  
*L. E. B.*

job captain / chef du projet

date

responsible officer / officier responsable

date

project title

titre du projet

DUNAGET HOUSE  
LOT "G"  
BLOCK "F"

drawing title

titre du dessin

CROSS SECTION "A-A"

reference no.  
no de référence  
HAFLR/78/P2

dwg no.  
dessin no.  
5

ROOF CONSTRUCTION.

- ① WOOD SHINGLES. (5" TO THE WEATHER)
- ② #15 BUILDING FELT.
- ③ ROOF SHEATHING (1/4" SNIPLAPPED)
- ④ COMMON RAFTERS - 14" x 14" (SPRUCE - N.H.)
- ⑤ PRINCIPAL RAFTERS - 7 1/2" x 8 1/2" (SPRUCE - N.H.)
- ⑥ RIDGE BEAM - 8" x 10 1/2" (SPRUCE - N.H.)
- ⑦ KING POST - 7 1/2" x 8 1/2" (SPRUCE - N.H.)
- ⑧ TIE BEAM - 7 1/2" x 8 1/2" (SPRUCE - N.H.)
- ⑨ PURLINS - 1 1/2" x 7 1/2" (SPRUCE - N.H.)
- ⑩ CLARKE - 7 1/2" x 8 1/2" DEEP x 11'-0" (SPRUCE - N.H.)
- ⑪ BRACES - 6 3/8" x 1 3/8" (SPRUCE - N.H.)
- ⑫ WALL PLATE - 1 1/2" x 8 1/2" (SPRUCE - N.H.)

