



- ## — GENERAL NOTES

- ① ALL CONCRETE TO HAVE A COMPRESSIVE STRENGTH OF NOT LESS THAN 3,000 # @ 28 DAYS.
- ② DAMPROOFING - TOP OF FOUND. WALL - FIRST COAT - PRIMER STERNSON- # 160 (PROTECTO COAT). SECOND COAT - STERNSON # 165 (PROTECTO COAT.)
- ③ WATERPROOFING ADMIXTURE: (A) STEAR # 320 OR EQUAL FOR ALL MORTAR.
(B) STEAR # 320 OR EQUAL FOR ALL CONCRETE.
- ④ THIS DRAWING TO BE READ IN CONJUNCTION WITH ALL ARCHITECTURAL, MECHANICAL AND ELECTRICAL DRAWINGS.
- ⑤ ALL DIMENSIONS TO BE CHECKED ON SITE AND ANY DISCREPANCIES ARE TO BE REPORTED.
- ⑥ BASE OF WALL ELEVATIONS SUBJECT TO BEDROCK CONDITIONS BUT SHALL BE AT LEAST BELOW FEET PENETRATION & WHERE CONCRETE FOOTINGS WHERE POSSIBLE.
- ⑦ EXISTING FOUNDATION WALLS - TO BE EXAMINED & TESTED FOR STRENGTH AND USED AS MUCH AS POSSIBLE.
- ⑧ BRICK PAVE - IN PART OF EAST END SECTION TO BE PRESERVED.

