

Architectural Specification

Division 1

- DELETE original Division 1 and REPLACE with revised Division 1. (see attached Division 1)

Section 07 52 00 Modified Bituminous Membrane Roofing

- CLARIFY intent of roofing section is to patch existing removed penetration, provide new penetrations and site verify existing roofing system.
- MODIFY article 2.8.1, remove expanded polystyrene insulation.

Section 09 21 16 Gypsum Board Assemblies

- ADD section, see attached, see attached specification section.

Section 09 65 16 Resilient Sheet Flooring

- ADD article 2.1.1.2, all suppliers to provide a declaration that there will be no polish, spray buff enhancers or maintainers required for the lifetime of the product. Provide five Canadian references where the product proposed has been cleaned and maintained, include contact names and numbers.

Section 09 91 23 – Interior Painting

- MODIFY article 2.5 Interior Painting Systems, see attached specification section.

Section 10 99 99 – Miscellaneous Specialties

- ADD model name and number for new dishwashers, Labconco Catalogue #4420320 Standard Undercounter, includes additional standard upper rack Catalogue #4595900
- ADD article 3.3, schedule for quantity of base cabinets for each fume hood.

Section 12 35 53.13 Steel Laboratory Casework

- ADD article 2.6.8, All Laboratory Casework to be supplied from laboratory casework supplier, with minimum 5 years experience of laboratory casework.
- ADD requirement for new laboratory casework furniture to be compatible with existing. Existing system is by Bedcolab.
- ADD generic specification for Bedcolab, Opus system
- ADD generic specification for Bedcolab, Chorus system
- ADD information on bedcolab, suspended cabinet system

Architectural Drawings

A0.2 Construction Phasing Plan

- ADD for information only, 2 sets of existing double doors, see attached sketch RA0.2-1.

A1.2 Main Floor Demolition Plan

- ADD for information only, set of existing double doors, see attached sketch RA1.2-1.
- ADD contractor to cap off plumbing drain flush to wall, see mechanical and attached sketch RA1.2-2
- MODIFY demolition note # 7, replace “OWNER SURPLUS” with “AAFC Loading Dock” typical for all references to OWNER SURPLUS.

A1.3 Main Floor Demolition Plan

- ADD for information only, set of existing double doors, see attached sketch RA1.3-1

- *DELETE* contractor removal of dishwasher in Rm. 143. Existing dishwasher is to remain, see attached sketch RA1.3-2
- *DELETE* contractor removal of dishwasher in Rm. 147. Existing dishwasher is to remain, see attached sketch RA1.3-3
- *MODIFY* demolition note # 7, replace "OWNER SURPLUS" with "AAFC Loading Dock" typical for all references to OWNER SURPLUS.

A1.4 Main Floor Demolition Plan

- *MODIFY* demolition note # 7, replace "OWNER SURPLUS" with "AAFC Loading Dock" typical for all references to OWNER SURPLUS.

A2.1 Construction Plan

- *REVISE* owner relocated equipment in Rm. 177 / Rm178: 2 x fridges, 1 x autoclaves with built in boiler and 1 x 72" wide laminar flow hood. Contractor to provide exhaust fan and electrical see mechanical and electrical addendum. See attached sketch RA2.1-1

A2.2 Construction Plan

- *ADD* contractor to provide new countertop to match existing adjacent countertop complete with backsplash. See attached sketch RA2.2-1
- *REVISE* location of owner installed centrifuge from north wall in Rm. 149 to south wall, see attached sketch RA2.2-2.

A2.3 Construction Plan

- *ADD* new upper cabinets to North wall of rm. 164
- *CLARIFY* extent and type of existing upper cabinets on North wall of rm. 164, See attached sketch RA2.3-1

MECHANICAL

MECHANICAL SPECIFICATION REVISIONS

- .1 23 31 13.01 Metal Ducts – Low Pressure to 500pa
 - .1 Clause 2.4 Duct Leakage
 - .1 Add sentence 2.4.2
 - “2.4.2 Visually and audibly check new ductwork installed in areas of work, refer to drawings.
 1. Visually and audibly check for air leaks that can be heard or felt under normal operating conditions. Repair all leaks in ductwork.
 2. Tests shall be performed by Section 23 05 93.
 3. Section 23 31 13.01 shall provide all necessary temporary connections, blank-offs, tees, required for testing. Section 23 05 93 shall provide all test fans, equipment and labour required for testing.
 4. Section 23 31 13.01 shall clean all ducts before testing.
 5. After preliminary tests, repair all leaks.
 6. Be responsible for any damage resulting from failure of items under test.
 7. Section 23 31 13.01 shall repair all leaks in duct system.
 8. Section 23 05 93 shall retest ductwork after leaks have been repaired.
 9. Section 23 31 13.01 and 23 05 93 shall co-ordinate work to ensure that all ductwork is tested:
 - a. Before ducts are insulated.
 - b. Before ducts are concealed.”
- .2 23 05 93 Testing, Adjusting And Balancing for HVAC
 - .1 Clause 1.21 Duct Leakage Test Report
 - .1 Add sentence 1.21.2
 - “1.21.2 Refer to Section 23 31 13.01 clause 2.4.2”
- .3 25 90 01 EMCS: Sequences of Operation
 - .1 Clause 1.2.4 Cylinder Storage Exhaust Fan(s): Rm.173-1
 - .1 Revise sentence .3
 - “.3 Fan status shall be monitored, alarmed and be capable of being turned on/off at the EMCS.”

MECHANICAL DRAWING REVISIONS


- .1 M1.1 Plumbing Demolition Plan
 - .1 In Rm.177 there is an existing abandoned drain line exposed located along the south wall; this existing drain line shall be capped-off flush with wall. Refer to architectural revision detail RA1.2-2 for approximate location.
 - .2 M1.2 Plumbing Demolition Plan
 - .1 In Rm.143, the existing dishwasher shall remain. Delete note 1, 2, 5 at this location.
 - .2 In Rm.147, the existing dishwasher shall remain. Delete note 1, 2, 5 at this location.
-

- .3 M2.1 Plumbing Construction Plan
 - .1 New Autocalve located in Rm.177/178. Refer to attached detail ADM1-1, ADM1-2.

- .4 M2.3 Plumbing Construction Plan
 - .1 In Rm.167 the drain line from the new sink shall drop down into the crawlspace and tie-into existing drain line in the crawlspace.

- .5 M3.1 HVAC Construction Plan
 - .1 In Rm.177/178 coordinate location of new diffusers with new lights.
 - .2 Install new fire dampers in existing ductwork shown in attached revision details. Refer to attached details ADM1-3.

- .6 M3.2 HVAC Construction Plan
 - .1 Install new fire dampers in existing ductwork shown in attached revision details. Refer to attached details ADM1-5.
 - .2 In Rm.146/146-1 relocate diffusers as required to suit new wall. Coordinate with architectural drawings reflected ceiling plan. Refer to revision detail ADM1-4



KEY NOTES

10. TIE INTO EXISTING SERVICES IN CRAWLSPACE BELOW.
11. TIE NEW DRAIN LINE INTO EXISTING DRAIN LINE IN CRAWLSPACE APPROXIMATELY AS SHOWN.
12. PROVIDE REDUCED PRESSURE ZONE BACKFLOW PREVENTER (WILKINS 975XL) FOR 19mm COLD AND 13mm HOT WATER LINES TO STERILIZER. PIPE DRAIN LINE FROM BACKFLOW PREVENTER INDIRECTLY OVER FUNNEL FLOOR DRAIN. COORDINATE CONNECTION WITH EQUIPMENT ON SITE.
13. PIPE 38mm DRAIN LINE FROM STERILIZER INDIRECTLY OVER FUNNEL FLOOR DRAIN.
14. NEW FUNNEL FLOOR DRAIN.
15. INDIVIDUAL COPPER RELIEF VENT LINES UP AND OUT THROUGH NEW PITCH BOX ON ROOF. INSULATE LINES 3 METERS BACK FROM ROOF PENETRATION.

THIS DRAWING TO BE READ IN CONJUNCTION WITH DRAWING M2.1 & REVISION DETAIL ADM1-2

SMS ENGINEERING

SMS Engineering Ltd. Consulting Engineers
 770 Bradford Street Winnipeg MB Canada R3H 0N3
 Telephone 204.775.0291 Fax 204.772.2153
 sms@smseng.com


Lab Renovations
 Morden Research Station
 Agriculture and Agri-Food
 Canada

WINNIPEG

MANITOBA

Plumbing Construction Plan
 Laboratory Rooms: 177 and 178

Drawn By JPL	Reviewed By RE	Reference ADM1
File No. 13-130-01	Date NOV. 2013	Detail Sheet ADM1-1



Steam Pressure Reducing Valves						
P.R.V. NO.	LOCATION	CAPACITY (lbs/hr) (kg/hr)	PRESSURE		SIZE	TYPE
			INLET (psig)	OUTLET (kPa)		
PRV-1	Rm. 177	192 87	75 517	50 345	1/2"	Fisher 92C

Relief Valves					
VALVE NO.	LOCATION	CAPACITY (lbs/hr) (kg/hr)	SET PRES. (psig) (kPa)	SIZE	TYPE
SV-1	Rm. 177	2861 1300.45	60 413.64	1-1/2" x 2-1/2"	Consolidated Type 1511-H

THIS DRAWING TO BE READ IN CONJUNCTION WITH DRAWING M2.1 & REVISION DETAIL ADM1-1


SMS ENGINEERING
 SMS Engineering Ltd. Consulting Engineers
 770 Bradford Street Winnipeg MB Canada R3H 0N3
 Telephone 204.775.0291 Fax 204.772.2153
 sms@smseng.com

Lab Renovations
 Morden Research Station
 Agriculture and Agri-Food
 Canada

WINNIPEG MANITOBA

Schematic Plan

Drawn By JPL	Reviewed By RE	Reference ADM1
File No. 13-130-01	Date NOV. 2013	Detail Sheet ADM1-2



THIS DRAWING TO BE READ IN CONJUNCTION WITH DRAWING M3.1

SMS ENGINEERING

SMS Engineering Ltd. Consulting Engineers
 770 Bradford Street Winnipeg MB Canada R3H 0N3
 Telephone 204.775.0291 Fax 204.772.2153
 sms@smseng.com


Lab Renovations
 Morden Research Station
 Agriculture and Agri-Food
 Canada

WINNIPEG

MANITOBA

HVAC Construction Plan
 Laboratory Rooms: 116

Drawn By JPL	Reviewed By RE	Reference ADM1
File No. 13-130-01	Date NOV. 2013	Detail Sheet ADM1-3



KEY NOTES [#]

- 1 8. RELOCATE EXISTING DIFFUSERS TO SUIT NEW RCP. REBALANCE AS SHOWN.
- 9. 350X300 ACOUSTICALLY LINED TRANSFER AIR DUCT.

THIS DRAWING TO BE READ IN CONJUNCTION WITH DRAWING M3.2

SMS ENGINEERING

SMS Engineering Ltd. Consulting Engineers
 770 Bradford Street Winnipeg MB Canada R3H 0N3
 Telephone 204.775.0291 Fax 204.772.2153
 sms@smseng.com


Lab Renovations
 Morden Research Station
 Agriculture and Agri-Food
 Canada

WINNIPEG

MANITOBA

HVAC Construction Plan
 Laboratory Rooms: 116

Drawn By JPL	Reviewed By RE	Reference ADM1
File No. 13-130-01	Date NOV. 2013	Detail Sheet ADM1-4



THIS DRAWING TO BE READ IN CONJUNCTION WITH DRAWING M3.2

SMS ENGINEERING

SMS Engineering Ltd. Consulting Engineers
 770 Bradford Street Winnipeg MB Canada R3H 0N3
 Telephone 204.775.0291 Fax 204.772.2153
 sms@smseng.com

Lab Renovations
 Morden Research Station
 Agriculture and Agri-Food
 Canada

WINNIPEG

MANITOBA

HVAC Construction Plan
 Laboratory Rooms: 150 AND 151

Drawn By JPL	Reviewed By RE	Reference ADM1
File No. 13-130-01	Date NOV. 2013	Detail Sheet ADM1-5

ELECTRICAL

ELECTRICAL SPECIFICATION REVISIONS

- .1 26 05 00 Common Work Results – For Electrical
 - .1 3.15 Fireproofing add
 - .5 Provide re-penetratable fire stop for all Voice/Data cable penetrations through rated separations. System to Abesco Ltd. Fire Clamp CT 120 Cable Transit System.

ELECTRICAL DETAIL SHEET REVISIONS


- .1 ED-1 Refer to attached detail sheet ED-1 for revisions to room 177.

ELECTRICAL DRAWING REVISIONS

- .1 E0.1 Electrical Drawing List and Symbol Legend
 - .1 Add General Note E
 - “E” Refer to Architectural Drawing A0.2 for Construction Phasing Plan.
 - .2 E1.2 Electrical Demolition Plan Laboratory Rooms
 - .1 Room 143; Existing Dishwasher shown on Grid Line 3 to remain.
 - .2 Room 147; Existing Dishwasher shown on Grid Line 7 to remain.
 - .3 E1.4 Electrical Construction Plan Laboratory Rooms
 - .1 Room 177; Remove all wiring back to source for all equipment disconnected and removed by owner.
 - .4 E2.2 Electrical Construction Plan Laboratory Rooms
 - .1 Room 143; existing dishwasher on grid line 3 to remain.
 - .2 Room 147; existing dishwasher on grid line 7 to remain.
 - .3 Room 149; Relocate Centrifuge # 503424 to south wall by 2 door cooler. Plug unit into existing receptacle on wireway circuit NL-1228. See Architectural detail sheet RA2.2-2
-

KEY NOTES


15. NEW AUTOCLAVE TO PLUG INTO EXISTING RECEPTACLE MOUNTED IN EXISTING WIREWAY.
16. RELOCATE EXISTING CEILING 120V 1Ø OUTLET TO WALL. EXTEND WIRE AND CONDUIT AS REQUIRED. CONNECT NEW FLOW HOOD.



1
E2.4

ELECTRICAL CONSTRUCTION PLAN ROOM 177, 178

SCALE: 1:100



SMS ENGINEERING

SMS Engineering Ltd. Consulting Engineers
770 Bradford Street Winnipeg MB Canada R3H 0N3
Telephone 204.775.0291 Fax 204.772.2153
sms@smseng.com

LAB RENOVATIONS
MORDEN RESEARCH
STATION

MORDEN

MANITOBA

ELECTRICAL CONSTRUCTION PLAN
ROOM 177,178

Drawn By IN	Approved By ALG	Reference E2.4
File No. 13-130-01	Date NOV. 2013	Detail Sheet ED-1

Revised DIVISION 1

2013-11-21

Part I General

I.1 WORK COVERED BY CONTRACT DOCUMENTS

- .1 Work of this Contract comprises renovation of Morden Research Station's laboratories located at Morden, Manitoba.

I.2 WORK BY OTHERS

- .1 Co-operate with owner in carrying out their respective works and carry out instructions from Departmental Representative.
- .2 Co-ordinate work with that of owner. If any part of work under this Contract depends for its proper execution or result upon work of owner, report promptly to Departmental Representative, in writing, any defects which may interfere with proper execution of Work.
- .3 Work of Project executed prior to start of or during Work of this Contract, and which is specifically excluded from this Contract:
 - .1 See plans.

I.3 WORK SEQUENCE

- .1 Construct Work in phases to accommodate Owner's continued use of premises during construction.
- .2 Co-ordinate Progress Schedule and co-ordinate with Owner Occupancy during construction.
- .3 Required phases:
 - .1 See plans.
- .4 Maintain fire access/control.

I.4 CONTRACTOR USE OF PREMISES

- .1 Restricted use of site. Contractor to confirm extent of site availability with Departmental Representative at start-up meeting.
- .2 Limit use of premises for Work, for storage, for access, to allow:
 - .1 Owner occupancy.
- .3 Co-ordinate use of premises under direction of Departmental Representative.
- .4 Obtain and pay for use of additional storage or work areas needed for operations under this Contract.
- .5 Remove or alter existing work to prevent injury or damage to portions of existing work which remain.
- .6 Repair or replace portions of existing work which have been altered during construction operations to match existing or adjoining work, as directed by Departmental Representative.

- .7 At completion of operations condition of existing work: equal to or better than that which existed before new work started.

I.5 OWNER OCCUPANCY

- .1 Owner will occupy premises during entire construction period for execution of normal operations.
- .2 Co-operate with Owner in scheduling operations to minimize conflict and to facilitate Owner usage.

I.6 ALTERATIONS, ADDITIONS OR REPAIRS TO EXISTING BUILDING

- .1 Execute work with least possible interference or disturbance to building operations occupants, public and normal use of premises. Arrange with Departmental Representative to facilitate execution of work.

I.7 EXISTING SERVICES

- .1 Notify, Departmental Representative and utility companies of intended interruption of services and obtain required permission.
- .2 Where Work involves breaking into or connecting to existing services, give Departmental Representative 48 hours notice for necessary interruption of mechanical or electrical service throughout course of work. Minimize duration of interruptions. Carry out work at times as directed by governing authorities with minimum disturbance to pedestrian, vehicular traffic and tenant operations.
- .3 Establish location and extent of service lines in area of work before starting Work. Notify Departmental Representative of findings.
- .4 Submit schedule to and obtain approval from Departmental Representative for any shut-down or closure of active service or facility including power and communications services. Adhere to approved schedule and provide notice to affected parties.
- .5 Provide temporary services when directed by Departmental Representative to maintain critical building and tenant systems.
- .6 Where unknown services are encountered, immediately advise Departmental Representative and confirm findings in writing.
- .7 Protect, relocate or maintain existing active services. When inactive services are encountered, cap off in manner approved by authorities having jurisdiction.
- .8 Record locations of maintained, re-routed and abandoned service lines.
- .9 Construct barriers in accordance with Section 01 56 00 - Temporary Barriers and Enclosures.

I.8 DOCUMENTS REQUIRED

- .1 Maintain at job site, one copy each document as follows:
 - .1 Contract Drawings.
 - .2 Specifications.
 - .3 Addenda.
 - .4 Reviewed Shop Drawings.

- .5 List of Outstanding Shop Drawings.
- .6 Change Orders.
- .7 Other Modifications to Contract.
- .8 Field Test Reports.
- .9 Copy of Approved Work Schedule.
- .10 Health and Safety Plan and Other Safety Related Documents.
- .11 Other documents as specified.

Part 2 Products

2.1 NOT USED

- .1 Not used.

Part 3 Execution

3.1 NOT USED

- .1 Not used.

END OF SECTION

Part I General

I.1 ACCESS AND EGRESS

- .1 Design, construct and maintain temporary "access to" and "egress from" work areas, including stairs, runways, ramps or ladders, independent of finished surfaces and in accordance with relevant municipal, provincial and other regulations.

I.2 USE OF SITE AND FACILITIES

- .1 Execute work with least possible interference or disturbance to normal use of premises. Make arrangements with Departmental Representative to facilitate work as stated.
- .2 Maintain existing services to building and provide for personnel and vehicle access.
- .3 Where security is reduced by work provide temporary means to maintain security.
- .4 Departmental Representative will assign sanitary facilities for use by Contractor's personnel. Keep facilities clean.
- .5 Closures: protect work temporarily until permanent enclosures are completed.

I.3 ALTERATIONS, ADDITIONS OR REPAIRS TO EXISTING BUILDING

- .1 Execute work with least possible interference or disturbance to building operations occupants, public and normal use of premises. Arrange with Departmental Representative to facilitate execution of work.

I.4 EXISTING SERVICES

- .1 Notify, Departmental Representative and utility companies of intended interruption of services and obtain required permission.
- .2 Where Work involves breaking into or connecting to existing services, give Departmental Representative 48 hours of notice for necessary interruption of mechanical or electrical service throughout course of work. Keep duration of interruptions minimum. Carry out interruptions after normal working hours of occupants, preferably on weekends only after written authorization from Departmental Representative.
- .3 Provide for personnel pedestrian and vehicular traffic.
- .4 Construct barriers in accordance with Section 01 56 00 - Temporary Barriers and Enclosures.

I.5 SPECIAL REQUIREMENTS

- .1 Carry out noise generating Work as per Departmental Representative's written instruction.
- .2 Submit schedule in accordance with Section 01 32 16.07 - Construction Progress Schedule - Bar (GANNT) Chart.
- .3 Ensure Contractor's personnel employed on site become familiar with and obey regulations including safety, fire, traffic and security regulations.

- .4 Keep within limits of work and avenues of ingress and egress.
- .5 Deliver materials outside of peak traffic hours as per Departmental Representative's written instruction.

I.6 HOURS OF WORK

- .1 7am to 7pm, Monday to Friday
- .2 Weekend access can be arranged with the Department Representative one week in advance.

I.7 SECURITY

- .1 Facility access to be as per AAFC requirements. AAFC requirements to be discussed once tender is awarded.

I.8 BUILDING SMOKING ENVIRONMENT

- .1 Smoking is not permitted.

Part 2 Products

2.1 NOT USED

- .1 Not Used.

Part 3 Execution

3.1 NOT USED

- .1 Not Used.

END OF SECTION

Part 1 General

I.1 APPOINTMENT AND PAYMENT

- .1 Departmental Representative will appoint and pay for services of testing laboratory except follows:
 - .1 Inspection and testing required by laws, ordinances, rules, regulations or orders of public authorities.
 - .2 Inspection and testing performed exclusively for Contractor's convenience.
 - .3 Testing, adjustment and balancing of conveying systems, mechanical and electrical equipment and systems.
 - .4 Mill tests and certificates of compliance.
 - .5 Tests specified to be carried out by Contractor under supervision of Departmental Representative.
- .2 Where tests or inspections by designated testing laboratory reveal Work not in accordance with contract requirements, pay costs for additional tests or inspections as required by Departmental Representative to verify acceptability of corrected work.

I.2 CONTRACTOR'S RESPONSIBILITIES

- .1 Provide labour, equipment and facilities to:
 - .1 Provide access to Work for inspection and testing.
 - .2 Facilitate inspections and tests.
 - .3 Make good Work disturbed by inspection and test.
 - .4 Provide storage on site for laboratory's exclusive use to store equipment and cure test samples.
- .2 Notify Departmental Representative 48 hours minimum sufficiently in advance of operations to allow for assignment of laboratory personnel and scheduling of test.
- .3 Where materials are specified to be tested, deliver representative samples in required quantity to testing laboratory.
- .4 Pay costs for uncovering and making good Work that is covered before required inspection or testing is completed and approved by Departmental Representative.

Part 2 Products

2.1 NOT USED

- .1 Not Used.

Part 3 Execution

3.1 NOT USED

- .1 Not Used.

END OF SECTION

Part I General

I.1 ADMINISTRATIVE

- .1 Schedule and administer project meetings throughout the progress of the work at the call of Departmental Representative.
- .2 Prepare agenda for meetings.
- .3 Distribute written notice of each meeting four days in advance of meeting date to Departmental Representative.
- .4 Provide physical space and make arrangements for meetings.
- .5 Preside at meetings.
- .6 Record the meeting minutes. Include significant proceedings and decisions. Identify actions by parties.
- .7 Reproduce and distribute copies of minutes within three days after meetings and transmit to meeting participants and, affected parties not in attendance and Departmental Representative.
- .8 Representative of Contractor, Subcontractor and suppliers attending meetings will be qualified and authorized to act on behalf of party each represents.

I.2 PRECONSTRUCTION MEETING

- .1 Within 7 days after award of Contract, request a meeting of parties in contract to discuss and resolve administrative procedures and responsibilities.
- .2 Departmental Representative, Contractor, major Subcontractors, field inspectors and supervisors will be in attendance.
- .3 Establish time of meeting and notify parties concerned minimum 5 days before meeting.
- .4 Location of meeting to be at Morden Research Station.
- .5 Incorporate mutually agreed variations to Contract Documents into Agreement, prior to signing.
- .6 Agenda to include:
 - .1 Appointment of official representative of participants in the Work.
 - .2 Schedule of Work: in accordance with Section 01 32 16.07 - Construction Progress Schedules - Bar (GANNT) Chart.
 - .3 Schedule of submission of shop drawings, samples, colour chips. Submit submittals in accordance with Section 01 33 00 - Submittal Procedures.
 - .4 Requirements for temporary facilities, site sign, offices, storage sheds, utilities, in accordance with Section 01 52 00 - Construction Facilities.
 - .5 Delivery schedule of specified equipment in accordance with Section 01 61 00 – Common Product Requirements.
 - .6 Proposed changes, change orders, procedures, approvals required, mark-up percentages permitted, time extensions, overtime, administrative requirements.
 - .7 Owner provided products.

- .8 Record drawings in accordance with Section 01 33 00 - Submittal Procedures.
- .9 Maintenance manuals in accordance with Section 01 78 00 - Closeout Submittals.
- .10 Take-over procedures, acceptance, warranties in accordance with Section 01 78 00 - Closeout Submittals.
- .11 Monthly progress claims, administrative procedures, photographs, hold backs.
- .12 Appointment of inspection and testing agencies or firms.
- .13 Insurances, transcript of policies.

I.3 PROGRESS MEETINGS

- .1 During course of Work and 2 weeks prior to project completion, schedule progress meetings biweekly.
- .2 Contractor, major Subcontractors involved in Work Departmental Representative are to be in attendance.
- .3 Notify parties minimum 5 days prior to meetings.
- .4 Record minutes of meetings and circulate to attending parties and affected parties not in attendance within 5 days after meeting.
- .5 Agenda to include the following:
 - .1 Review, approval of minutes of previous meeting.
 - .2 Review of Work progress since previous meeting.
 - .3 Field observations, problems, conflicts.
 - .4 Problems which impede construction schedule.
 - .5 Review of off-site fabrication delivery schedules.
 - .6 Corrective measures and procedures to regain projected schedule.
 - .7 Revision to construction schedule.
 - .8 Progress schedule, during succeeding work period.
 - .9 Review submittal schedules: expedite as required.
 - .10 Maintenance of quality standards.
 - .11 Review proposed changes for affect on construction schedule and on completion date.
 - .12 Other business.

Part 2 Products

2.1 NOT USED

- .1 Not Used.

Part 3 Execution

3.1 NOT USED

- .1 Not Used.

END OF SECTION

Part I General

I.1 DEFINITIONS

- .1 Activity: element of Work performed during course of Project. Activity normally has expected duration, and expected cost and expected resource requirements. Activities can be subdivided into tasks.
- .2 Bar Chart (GANTT Chart): graphic display of schedule-related information. In typical bar chart, activities or other Project elements are listed down left side of chart, dates are shown across top, and activity durations are shown as date-placed horizontal bars. Generally Bar Chart should be derived from commercially available computerized project management system.
- .3 Baseline: original approved plan (for project, work package, or activity), plus or minus approved scope changes.
- .4 Construction Work Week: Monday to Friday, inclusive, will provide five day work week and define schedule calendar working days as part of Bar (GANTT) Chart submission.
- .5 Duration: number of work periods (not including holidays or other nonworking periods) required to complete activity or other project element. Usually expressed as workdays or workweeks.
- .6 Master Plan: summary-level schedule that identifies major activities and key milestones.
- .7 Milestone: significant event in project, usually completion of major deliverable.
- .8 Project Schedule: planned dates for performing activities and the planned dates for meeting milestones. Dynamic, detailed record of tasks or activities that must be accomplished to satisfy Project objectives. Monitoring and control process involves using Project Schedule in executing and controlling activities and is used as basis for decision making throughout project life cycle.
- .9 Project Planning, Monitoring and Control System: overall system operated by Departmental Representative to enable monitoring of project work in relation to established milestones.

I.2 REQUIREMENTS

- .1 Ensure Master Plan and Detail Schedules are practical and remain within specified Contract duration.
- .2 Plan to complete Work in accordance with prescribed milestones and time frame.
- .3 Limit activity durations to maximum of approximately 10 working days, to allow for progress reporting.
- .4 Ensure that it is understood that Award of Contract or time of beginning, rate of progress, Interim Certificate and Final Certificate as defined times of completion are of essence of this contract.

I.3 ACTION AND INFORMATIONAL SUBMITTALS

- .1 Provide submittals in accordance with Section 01 33 00 - Submittal Procedures.

- .2 Submit to Departmental Representative within seven (7) working days of Award of Contract Bar (GANTT) Chart as Master Plan for planning, monitoring and reporting of project progress.
- .3 Submit Project Schedule to Departmental Representative within 5 working days of receipt of acceptance of Master Plan.

I.4 PROJECT MILESTONES

- .1 Project milestones form interim targets for Project Schedule.
 - .1 Phase 1.
 - .2 Phase 2.
 - .3 Phase 3.

I.5 MASTER PLAN

- .1 Structure schedule to allow orderly planning, organizing and execution of Work as Bar Chart (GANTT).
- .2 Departmental Representative will review and return revised schedules within 5 working days.
- .3 Revise impractical schedule and resubmit within 5 working days.
- .4 Accepted revised schedule will become Master Plan and be used as baseline for updates.

I.6 PROJECT SCHEDULE

- .1 Develop detailed Project Schedule derived from Master Plan.
- .2 Ensure detailed Project Schedule includes as minimum milestone and activity types as follows:
 - .1 Award.
 - .2 Shop Drawings, Samples.
 - .3 Permits.
 - .4 Mobilization.
 - .5 Structural Steel.
 - .6 Interior Architecture (Walls, Floors and Ceiling).
 - .7 Plumbing.
 - .8 Lighting.
 - .9 Electrical.
 - .10 Piping.
 - .11 Controls.
 - .12 Heating, Ventilating, and Air Conditioning.
 - .13 Millwork.
 - .14 Fire Systems.
 - .15 Testing and Commissioning.
 - .16 Supplied equipment long delivery items.

.17 Engineer supplied equipment required dates.

1.7 PROJECT SCHEDULE REPORTING

- .1 Update Project Schedule on weekly basis reflecting activity changes and completions, as well as activities in progress.
- .2 Include as part of Project Schedule, narrative report identifying Work status to date, comparing current progress to baseline, presenting current forecasts, defining problem areas, anticipated delays and impact with possible mitigation.

1.8 PROJECT MEETINGS

- .1 Discuss Project Schedule at regular site meetings, identify activities that are behind schedule and provide measures to regain slippage. Activities considered behind schedule are those with projected start or completion dates later than current approved dates shown on baseline schedule.
- .2 Weather related delays with their remedial measures will be discussed and negotiated.

Part 2 Products

2.1 NOT USED

- .1 Not used.

Part 3 Execution

3.1 NOT USED

- .1 Not used.

END OF SECTION

Part I General

I.1 ADMINISTRATIVE

- .1 Submit to Departmental Representative submittals listed for review. Submit promptly and in orderly sequence to not cause delay in Work. Failure to submit in ample time is not considered sufficient reason for extension of Contract Time and no claim for extension by reason of such default will be allowed.
- .2 Do not proceed with Work affected by submittal until review is complete.
- .3 Present shop drawings, product data, samples and mock-ups in SI Metric units.
- .4 Where items or information is not produced in SI Metric units, both SI Metric and Imperial shall be provided.
- .5 Review submittals prior to submission to Departmental Representative. This review represents that necessary requirements have been determined and verified, or will be, and that each submittal has been checked and co-ordinated with requirements of Work and Contract Documents. Submittals not stamped, signed, dated and identified as to specific project will be returned without being examined and considered rejected.
- .6 Notify Departmental Representative, in writing at time of submission, identifying deviations from requirements of Contract Documents stating reasons for deviations.
- .7 Verify field measurements and affected adjacent Work are co-ordinated.
- .8 Contractor's responsibility for errors and omissions in submission is not relieved by Departmental Representative's review of submittals.
- .9 Contractor's responsibility for deviations in submission from requirements of Contract Documents is not relieved by Departmental Representative review.
- .10 Keep one reviewed copy of each submission on site.

I.2 SHOP DRAWINGS AND PRODUCT DATA

- .1 The term "shop drawings" means drawings, diagrams, illustrations, schedules, performance charts, brochures and other data which are to be provided by Contractor to illustrate details of a portion of Work.
- .2 Submit drawings stamped and signed by professional engineer registered or licensed in the Province of Manitoba, of Canada.
- .3 Indicate materials, methods of construction and attachment or anchorage, erection diagrams, connections, explanatory notes and other information necessary for completion of Work. Where articles or equipment attach or connect to other articles or equipment, indicate that such items have been co-ordinated, regardless of Section under which adjacent items will be supplied and installed. Indicate cross references to design drawings and specifications.
- .4 Allow seven (7) days for Departmental Representative's review of each submission.
- .5 Adjustments made on shop drawings by Departmental Representative are not intended to change Contract Price. If adjustments affect value of Work, state such in writing to Departmental Representative prior to proceeding with Work.

- .6 Make changes in shop drawings as Departmental Representative may require, consistent with Contract Documents. When resubmitting, notify Departmental Representative in writing of revisions other than those requested.
- .7 Accompany submissions with transmittal letter, in duplicate, containing:
 - .1 Date.
 - .2 Project title and number.
 - .3 Contractor's name and address.
 - .4 Identification and quantity of each shop drawing, product data and sample.
 - .5 Other pertinent data.
- .8 Submissions include:
 - .1 Date and revision dates.
 - .2 Project title and number.
 - .3 Name and address of:
 - .1 Subcontractor.
 - .2 Supplier.
 - .3 Manufacturer.
 - .4 Contractor's stamp, signed by Contractor's authorized representative certifying approval of submissions, verification of field measurements and compliance with Contract Documents.
 - .5 Details of appropriate portions of Work as applicable:
 - .1 Fabrication.
 - .2 Layout, showing dimensions, including identified field dimensions, and clearances.
 - .3 Setting or erection details.
 - .4 Capacities.
 - .5 Performance characteristics.
 - .6 Standards.
 - .7 Operating weight.
 - .8 Wiring diagrams.
 - .9 Single line and schematic diagrams.
 - .10 Relationship to adjacent work.
- .9 After Departmental Representative's review, distribute copies.
- .10 Submit electronic copies of product data sheets or brochures for requirements requested in specification Sections and as requested by Departmental Representative where shop drawings will not be prepared due to standardized manufacture of product.
- .11 Submit electronic copies of test reports for requirements requested in specification Sections and as requested by Departmental Representative.
 - .1 Report signed by authorized official of testing laboratory that material, product or system identical to material, product or system to be provided has been tested in accord with specified requirements.
 - .2 Testing must have been within 3 years of date of contract award for project.

- .12 Submit electronic copies of certificates for requirements requested in specification Sections and as requested by Departmental Representative.
 - .1 Statements printed on manufacturer's letterhead and signed by responsible officials of manufacturer of product, system or material attesting that product, system or material meets specification requirements.
 - .2 Certificates must be dated after award of project contract complete with project name.
- .13 Submit electronic copies of manufacturers instructions for requirements requested in specification Sections and as requested by Departmental Representative.
 - .1 Pre-printed material describing installation of product, system or material, including special notices and Material Safety Data Sheets concerning impedances, hazards and safety precautions.
- .14 Submit electronic copies of Manufacturer's Field Reports for requirements requested in specification Sections and as requested by Departmental Representative.
- .15 Documentation of the testing and verification actions taken by manufacturer's representative to confirm compliance with manufacturer's standards or instructions.
- .16 Submit electronic copies of Operation and Maintenance Data for requirements requested in specification Sections and as requested by Departmental Representative.
- .17 Delete information not applicable to project.
- .18 Supplement standard information to provide details applicable to project.
- .19 If upon review by Departmental Representative, no errors or omissions are discovered or if only minor corrections are made, copies will be returned and fabrication and installation of Work may proceed. If shop drawings are rejected, noted copy will be returned and resubmission of corrected shop drawings, through same procedure indicated above, must be performed before fabrication and installation of Work may proceed.
- .20 The review of shop drawings by Public Works and Government Services Canada (PWGSC) is for sole purpose of ascertaining conformance with general concept.
 - .1 This review shall not mean that PWGSC approves detail design inherent in shop drawings, responsibility for which shall remain with Contractor submitting same, and such review shall not relieve Contractor of responsibility for errors or omissions in shop drawings or of responsibility for meeting requirements of construction and Contract Documents.
 - .2 Without restricting generality of foregoing, Contractor is responsible for dimensions to be confirmed and correlated at job site, for information that pertains solely to fabrication processes or to techniques of construction and installation and for co-ordination of Work of sub-trades.

I.3 SAMPLES

- .1 Submit for review samples in triplicate as requested in respective specification Sections. Label samples with origin and intended use.
- .2 Deliver samples prepaid to Departmental Representative's business address.

- .3 Notify Departmental Representative in writing, at time of submission of deviations in samples from requirements of Contract Documents.
- .4 Where colour, pattern or texture is criterion, submit full range of samples.
- .5 Adjustments made on samples by Departmental Representative are not intended to change Contract Price. If adjustments affect value of Work, state such in writing to Departmental Representative prior to proceeding with Work.
- .6 Make changes in samples which Departmental Representative may require, consistent with Contract Documents.
- .7 Reviewed and accepted samples will become standard of workmanship and material against which installed Work will be verified.

I.4 MOCK-UPS

- .1 Erect mock-ups in accordance with 01 45 00 - Quality Control.

I.5 PHOTOGRAPHIC DOCUMENTATION

- .1 Submit electronic copy of colour digital photography in jpg format, standard resolution monthly with progress statement as directed by Departmental Representative.
- .2 Project identification: name and number of project and date of exposure indicated.
- .3 Number of viewpoints: 2 locations.
 - .1 Viewpoints and their location as determined by Departmental Representative.
- .4 Frequency of photographic documentation: monthly as directed by Departmental Representative.
 - .1 Upon completion of services before concealment, of Work, as directed by Departmental Representative.

I.6 CERTIFICATES AND TRANSCRIPTS

- .1 Immediately after award of Contract, submit Workers' Compensation Board status.
- .2 Submit transcription of insurance immediately after award of Contract.

Part 2 Products

2.1 NOT USED

- .1 Not Used.

Part 3 Execution

3.1 NOT USED

- .1 Not Used.

END OF SECTION

Part I General

I.1 REFERENCES

- .1 Definitions:
 - .1 Environmental Pollution and Damage: presence of chemical, physical, biological elements or agents which adversely affect human health and welfare; unfavourably alter ecological balances of importance to human life; affect other species of importance to humans; or degrade environment aesthetically, culturally and/or historically.
 - .2 Environmental Protection: prevention/control of pollution and habitat or environment disruption during construction.
- .2 Reference Standards:
 - .1 U.S. Environmental Protection Agency (EPA)/Office of Water
 - .1 EPA 832/R-92-005-92, Storm Water Management for Construction Activities, Chapter 3.
 - .2 EPA General Construction Permit (GCP) 2012.

I.2 ACTION AND INFORMATIONAL SUBMITTALS

- .1 Submit in accordance with Section 01 33 00 - Submittal Procedures.
- .2 Product Data:
 - .1 Submit manufacturer's instructions, printed product literature and data sheets for all miscellaneous equipment and include product characteristics, performance criteria, physical size, finish and limitations.
 - .2 Submit 2 copies of WHMIS MSDS in accordance with Section 01 35 29.06 - Health and Safety Requirements 01 35 43 - Environmental Procedures.
- .3 Before commencing construction activities or delivery of materials to site, submit Environmental Protection Plan for review and approval by Departmental Representative.
- .4 Environmental Protection Plan must include comprehensive overview of known or potential environmental issues to be addressed during construction.
- .5 Address topics at level of detail commensurate with environmental issue and required construction tasks.
- .6 Include in Environmental Protection Plan:
 - .1 Names of persons responsible for ensuring adherence to Environmental Protection Plan.
 - .2 Names and qualifications of persons responsible for manifesting hazardous waste to be removed from site.
 - .3 Names and qualifications of persons responsible for training site personnel.
 - .4 Descriptions of environmental protection personnel training program.
 - .5 Erosion and sediment control plan identifying type and location of erosion and sediment controls to be provided including monitoring and reporting requirements to assure that control measures are in compliance with erosion

and sediment control plan, Federal, Provincial, and Municipal laws and regulations and EPA 832/R-92-005, Chapter 3.

- .6 Work area plan showing proposed activity in each portion of area and identifying areas of limited use or non-use.
 - .1 Plan to include measures for marking limits of use areas and methods for protection of features to be preserved within authorized work areas.
- .7 Spill Control Plan to include procedures, instructions, and reports to be used in event of unforeseen spill of regulated substance.
- .8 Non-Hazardous solid waste disposal plan identifying methods and locations for solid waste disposal including clearing debris.
- .9 Air pollution control plan detailing provisions to assure that dust, debris, materials, and trash, are contained on project site.
- .10 Contaminant Prevention Plan identifying potentially hazardous substances to be used on job site; intended actions to prevent introduction of such materials into air, water, or ground; and detailing provisions for compliance with Federal, Provincial, and Municipal laws and regulations for storage and handling of these materials.
- .11 Waste Water Management Plan identifying methods and procedures for management discharge of waste waters which are directly derived from construction activities, such as concrete curing water, clean-up water, dewatering of ground water, disinfection water, hydrostatic test water, and water used in flushing of lines.
- .12 Historical, archaeological, cultural resources biological resources and wetlands plan that defines procedures for identifying and protecting historical, archaeological, cultural resources, biological resources and wetlands.
- .13 Pesticide treatment plan to be included and updated, as required.

I.3 FIRES

- .1 Fires and burning of rubbish on site is not permitted.

I.4 POLLUTION CONTROL

- .1 Maintain temporary erosion and pollution control features installed under this Contract.
- .2 Control emissions from equipment and plant in accordance with local authorities' emission requirements.
- .3 Prevent sandblasting and other extraneous materials from contaminating air and waterways beyond application area.
 - .1 Provide temporary enclosures where directed by Departmental Representative.
- .4 Cover or wet down dry materials and rubbish to prevent blowing dust and debris. Provide dust control for temporary roads.

1.5 NOTIFICATION

- .1 Departmental Representative will notify Contractor in writing of observed noncompliance with Federal, Provincial or Municipal environmental laws or regulations, permits, and other elements of Contractor's Environmental Protection plan.
- .2 Contractor: after receipt of such notice, inform Departmental Representative of proposed corrective action and take such action for approval by Departmental Representative.
 - .1 Take action only after receipt of written approval by Departmental Representative.
- .3 Departmental Representative will issue stop order of work until satisfactory corrective action has been taken.
- .4 No time extensions granted or equitable adjustments allowed to Contractor for such suspensions.

Part 2 Products

2.1 NOT USED

- .1 Not Used.

Part 3 Execution

3.1 CLEANING

- .1 Progress Cleaning: clean in accordance with Section 01 74 11 - Cleaning.
 - .1 Leave Work area clean at end of each day.
- .2 Ensure public waterways, storm and sanitary sewers remain free of waste and volatile materials disposal.
- .3 Final Cleaning: upon completion remove surplus materials, rubbish, tools and equipment in accordance with Section 01 74 11 - Cleaning.
- .4 Waste Management: separate waste materials for recycling in accordance with Section 01 74 21 - Construction/Demolition Waste Management and Disposal
 - .1 Remove recycling containers and bins from site and dispose of materials at appropriate facility.

END OF SECTION

Part 1 General

1.1 REFERENCES AND CODES

- .1 Perform Work in accordance with National Building Code of Canada (NBC) including amendments up to tender closing date and other codes of provincial or local application provided that in case of conflict or discrepancy, more stringent requirements apply.
- .2 Meet or exceed requirements of:
 - .1 Contract documents.
 - .2 Specified standards, codes and referenced documents.

1.2 HAZARDOUS MATERIAL DISCOVERY

- .1 PCB: Polychlorinated Biphenyl: stop work immediately when material resembling Polychlorinated Biphenyl is encountered during demolition work. Notify Departmental Representative.
- .2 Mould: stop work immediately when material resembling mould is encountered during demolition work. Notify Departmental Representative.

1.3 BUILDING SMOKING ENVIRONMENT

- .1 Comply with smoking restrictions and municipal by-laws.

Part 2 Products

2.1 NOT USED

- .1 Not Used.

Part 3 Execution

3.1 NOT USED

- .1 Not Used.

END OF SECTION

Part I General

I.1 INSPECTION

- .1 Allow Departmental Representative access to Work. If part of Work is in preparation at locations other than Place of Work, allow access to such Work whenever it is in progress.
- .2 Give timely notice requesting inspection if Work is designated for special tests, inspections or approvals by Departmental Representative instructions, or law of Place of Work.
- .3 If Contractor covers or permits to be covered Work that has been designated for special tests, inspections or approvals before such is made, uncover such Work, have inspections or tests satisfactorily completed and make good such Work.
- .4 Departmental Representative will order part of Work to be examined if Work is suspected to be not in accordance with Contract Documents. If, upon examination such work is found not in accordance with Contract Documents, correct such Work and pay cost of examination and correction. If such Work is found in accordance with Contract Documents, Departmental Representative shall pay cost of examination and replacement.

I.2 INDEPENDENT INSPECTION AGENCIES

- .1 Independent Inspection/Testing Agencies will be engaged by Departmental Representative for purpose of inspecting and/or testing portions of Work. Cost of such services will be borne by Departmental Representative.
- .2 Provide equipment required for executing inspection and testing by appointed agencies.
- .3 Employment of inspection/testing agencies does not relax responsibility to perform Work in accordance with Contract Documents.
- .4 If defects are revealed during inspection and/or testing, appointed agency will request additional inspection and/or testing to ascertain full degree of defect. Correct defect and irregularities as advised by Departmental Representative at no cost to Departmental Representative. Pay costs for retesting and reinspection.

I.3 ACCESS TO WORK

- .1 Allow inspection/testing agencies access to Work, off site manufacturing and fabrication plants.
- .2 Co-operate to provide reasonable facilities for such access.

I.4 PROCEDURES

- .1 Notify appropriate agency and Departmental Representative in advance of requirement for tests, in order that attendance arrangements can be made.
- .2 Submit samples and/or materials required for testing, as specifically requested in specifications. Submit with reasonable promptness and in orderly sequence to not cause delays in Work.

- .3 Provide labour and facilities to obtain and handle samples and materials on site. Provide sufficient space to store and cure test samples.

I.5 REJECTED WORK

- .1 Remove defective Work, whether result of poor workmanship, use of defective products or damage and whether incorporated in Work or not, which has been rejected by Departmental Representative as failing to conform to Contract Documents. Replace or re-execute in accordance with Contract Documents.
- .2 Make good other Contractor's work damaged by such removals or replacements promptly.
- .3 If in opinion of Departmental Representative Departmental Representative it is not expedient to correct defective Work or Work not performed in accordance with Contract Documents, Owner will deduct from Contract Price difference in value between Work performed and that called for by Contract Documents, amount of which will be determined by .

I.6 REPORTS

- .1 Submit 3 copies of inspection and test reports to Departmental Representative.
- .2 Provide copies to subcontractor of work being inspected or tested and, or manufacturer or fabricator of material being inspected or tested.

I.7 TESTS AND MIX DESIGNS

- .1 Furnish test results and mix designs as requested.
- .2 Cost of tests and mix designs beyond those called for in Contract Documents or beyond those required by law of Place of Work will be appraised by Departmental Representative and may be authorized as recoverable.

I.8 MOCK-UPS

- .1 Prepare mock-ups for Work specifically requested in specifications. Include for Work of Sections required to provide mock-ups.
- .2 Construct in locations acceptable to Departmental Representative.
- .3 Prepare mock-ups for Departmental Representative review with reasonable promptness and in orderly sequence, to not cause delays in Work.
- .4 Failure to prepare mock-ups in ample time is not considered sufficient reason for extension of Contract Time and no claim for extension by reason of such default will be allowed.
- .5 If requested, Departmental Representative will assist in preparing schedule fixing dates for preparation.
- .6 Remove mock-up at conclusion of Work or when acceptable to Departmental Representative.
- .7 Mock-ups may remain as part of Work.
- .8 Specification section identifies whether mock-up may remain as part of Work or if it is to be removed and when.

1.9 MILL TESTS

- .1 Submit mill test certificates as requested by Departmental Representative.

1.10 EQUIPMENT AND SYSTEMS

- .1 Submit adjustment and balancing reports for mechanical, electrical and building equipment systems.

Part 2 Products

2.1 NOT USED

- .1 Not Used.

Part 3 Execution

3.1 NOT USED

- .1 Not Used.

END OF SECTION

Part I General

I.1 REFERENCES

- .1 Canadian General Standards Board (CGSB)
 - .1 CAN/CGSB 1.189-00, Exterior Alkyd Primer for Wood.
 - .2 CGSB 1.59-97, Alkyd Exterior Gloss Enamel.
- .2 Canadian Standards Association (CSA International)
 - .1 CSA-A23.1/A23.2-04, Concrete Materials and Methods of Concrete Construction/Methods of Test and Standard Practices for Concrete.
 - .2 CSA-0121-M1978(R2003), Douglas Fir Plywood.
 - .3 CAN/CSA-S269.2-M1987(R2003), Access Scaffolding for Construction Purposes.
 - .4 CAN/CSA-Z321-96(R2001), Signs and Symbols for the Occupational Environment.
- .3 Public Works Government Services Canada (PWGSC) Standard Acquisition Clauses and Conditions (SACC)-ID: R0202D, Title: General Conditions 'C', In Effect as of: May 14, 2004.

I.2 ACTION AND INFORMATIONAL SUBMITTALS

- .1 Provide submittals in accordance with Section 01 33 00 - Submittal Procedures.

I.3 INSTALLATION AND REMOVAL

- .1 Prepare site plan indicating proposed location and dimensions of area to be fenced and used by Contractor, number of trailers to be used, avenues of ingress/egress to fenced area and details of fence installation.
- .2 Identify areas which have to be gravelled to prevent tracking of mud if applicable.
- .3 Indicate use of supplemental or other staging area if applicable.
- .4 Provide construction facilities in order to execute work expeditiously.
- .5 Remove from site all such work after use.

I.4 SCAFFOLDING

- .1 Scaffolding in accordance with CAN/CSA-S269.2.
- .2 Provide and maintain scaffolding, ramps and ladders.

I.5 HOISTING

- .1 Provide, operate and maintain hoists required for moving of workers, materials and equipment. Make financial arrangements with Subcontractors for their use of hoists.
- .2 Hoists to be operated by qualified operator.

I.6 SITE STORAGE/LOADING

- .1 Confine work and operations of employees by Contract Documents. Do not unreasonably encumber premises with products.
- .2 Do not load or permit to load any part of Work with weight or force that will endanger Work.

I.7 CONSTRUCTION PARKING

- .1 Parking will be permitted on site provided it does not disrupt performance of Work.
- .2 Provide and maintain adequate access to project site.
- .3 Clean runways and taxi areas where used by Contractor's equipment.

I.8 SECURITY

- .1 Provide and pay for responsible security personnel to guard site and contents of site after working hours and during holidays.

I.9 OFFICES

- .1 Provide office heated to 20 degrees C, lighted 750 lx and ventilated, of sufficient size to accommodate site meetings and furnished with drawing laydown table.
- .2 Provide marked and fully stocked first-aid case in a readily available location.
- .3 Subcontractors to provide their own offices as necessary. Direct location of these offices.

I.10 EQUIPMENT, TOOL AND MATERIALS STORAGE

- .1 Provide and maintain, in clean and orderly condition, lockable weatherproof sheds for storage of tools, equipment and materials.
- .2 Locate materials not required to be stored in weatherproof sheds on site in manner to cause least interference with work activities.

I.11 SANITARY FACILITIES

- .1 Owner to provide sanitary facilities for work force in accordance with governing regulations and ordinances.
- .2 Departmental Representative to assign sanitary facilities for contractor for each phase of work.

I.12 CONSTRUCTION SIGNAGE

- .1 No signs or advertisements, other than warning signs, are permitted on site.
- .2 Direct requests for approval to erect Consultant/Contractor signboard to Departmental Representative. For consideration general appearance of Consultant/Contractor signboard must conform to project identification site sign. Wording in both official languages.
- .3 Signs and notices for safety and instruction in both official languages Graphic symbols to CAN/CSA-Z321.

- .4 Maintain approved signs and notices in good condition for duration of project, and dispose of off site on completion of project or earlier if directed by Departmental Representative.

1.13 CLEAN-UP

- .1 Remove construction debris, waste materials, packaging material from work site daily.
- .2 Clean dirt or mud tracked onto paved or surfaced roadways.
- .3 Store materials resulting from demolition activities that are salvageable.

Part 2 Products

2.1 NOT USED

- .1 Not Used.

Part 3 Execution

3.1 NOT USED

- .1 Not Used.

END OF SECTION

Part I General

I.1 REFERENCES

- .1 Canadian General Standards Board (CGSB)
 - .1 CGSB I.59-97, Alkyd Exterior Gloss Enamel.
 - .2 CAN/CGSB I.189-00, Exterior Alkyd Primer for Wood.
- .2 Canadian Standards Association (CSA International)
 - .1 CSA-O121-M1978(R2003), Douglas Fir Plywood.
- .3 Public Works Government Services Canada (PWGSC) Standard Acquisition Clauses and Conditions (SACC)-ID: R0202D, Title: General Conditions 'C', In Effect as Of: May 14, 2004.

I.2 INSTALLATION AND REMOVAL

- .1 Provide temporary controls in order to execute Work expeditiously.
- .2 Remove from site all such work after use.

I.3 DUST TIGHT SCREENS

- .1 Provide dust tight screens or insulated partitions to localize dust generating activities, and for protection of workers, finished areas of Work and public.
- .2 Maintain and relocate protection until such work is complete.

I.4 ACCESS TO SITE

- .1 Provide and maintain access roads, sidewalk crossings, ramps and construction runways as may be required for access to Work.

I.5 FIRE ROUTES

- .1 Maintain access to property including overhead clearances for use by emergency response vehicles.

I.6 PROTECTION FOR OFF-SITE AND PUBLIC PROPERTY

- .1 Protect surrounding private and public property from damage during performance of Work.
- .2 Be responsible for damage incurred.

I.7 PROTECTION OF BUILDING FINISHES

- .1 Provide protection for finished and partially finished building finishes and equipment during performance of Work.
- .2 Provide necessary screens, covers, and hoardings.
- .3 Confirm with Departmental Representative locations and installation schedule 3 days prior to installation.

- .4 Be responsible for damage incurred due to lack of or improper protection.

1.8 WASTE MANAGEMENT AND DISPOSAL

- .1 Separate waste materials for reuse recycling in accordance with Section 01 74 21 - Construction/Demolition Waste Management And Disposal.

Part 2 Products

2.1 NOT USED

- .1 Not Used.

Part 3 Execution

3.1 NOT USED

- .1 Not Used.

END OF SECTION

Part I General

I.1 REFERENCES

- .1 Conform to these reference standards, in whole or in part as specifically requested in specifications.
- .2 If there is question as to whether products or systems are in conformance with applicable standards, Departmental Representative reserves right to have such products or systems tested to prove or disprove conformance.
- .3 Cost for such testing will be born by Departmental Representative in event of conformance with Contract Documents or by Contractor in event of non-conformance.

I.2 QUALITY

- .1 Products, materials, equipment and articles incorporated in Work shall be new, not damaged or defective, and of best quality for purpose intended. If requested, furnish evidence as to type, source and quality of products provided.
- .2 Procurement policy is to acquire, in cost effective manner, items containing highest percentage of recycled and recovered materials practicable consistent with maintaining satisfactory levels of competition. Make reasonable efforts to use recycled and recovered materials and in otherwise utilizing recycled and recovered materials in execution of work.
- .3 Defective products, whenever identified prior to completion of Work, will be rejected, regardless of previous inspections. Inspection does not relieve responsibility, but is precaution against oversight or error. Remove and replace defective products at own expense and be responsible for delays and expenses caused by rejection.
- .4 Should disputes arise as to quality or fitness of products, decision rests strictly with Departmental Representative based upon requirements of Contract Documents.
- .5 Unless otherwise indicated in specifications, maintain uniformity of manufacture for any particular or like item throughout building.
- .6 Permanent labels, trademarks and nameplates on products are not acceptable in prominent locations, except where required for operating instructions, or when located in mechanical or electrical rooms.

I.3 AVAILABILITY

- .1 Immediately upon signing Contract, review product delivery requirements and anticipate foreseeable supply delays for items. If delays in supply of products are foreseeable, notify Departmental Representative of such, in order that substitutions or other remedial action may be authorized in ample time to prevent delay in performance of Work.
- .2 In event of failure to notify Departmental Representative at commencement of Work and should it subsequently appear that Work may be delayed for such reason, Departmental Representative reserves right to substitute more readily available products of similar character, at no increase in Contract Price or Contract Time.

I.4 STORAGE, HANDLING AND PROTECTION

- .1 Handle and store products in manner to prevent damage, adulteration, deterioration and soiling and in accordance with manufacturer's instructions when applicable.
- .2 Store packaged or bundled products in original and undamaged condition with manufacturer's seal and labels intact. Do not remove from packaging or bundling until required in Work.
- .3 Store products subject to damage from weather in weatherproof enclosures.
- .4 Store cementitious products clear of earth or concrete floors, and away from walls.
- .5 Keep sand, when used for grout or mortar materials, clean and dry. Store sand on wooden platforms and cover with waterproof tarpaulins during inclement weather.
- .6 Store sheet materials, lumber on flat, solid supports and keep clear of ground. Slope to shed moisture.
- .7 Store and mix paints in heated and ventilated room. Remove oily rags and other combustible debris from site daily. Take every precaution necessary to prevent spontaneous combustion.
- .8 Remove and replace damaged products at own expense and to satisfaction of Departmental Representative.
- .9 Touch-up damaged factory finished surfaces to Departmental Representative's. Use touch-up materials to match original. Do not paint over name plates.

I.5 TRANSPORTATION

- .1 Pay costs of transportation of products required in performance of Work.
- .2 Transportation cost of products supplied by Owner will be paid for by Departmental Representative. Unload, handle and store such products.

I.6 MANUFACTURER'S INSTRUCTIONS

- .1 Unless otherwise indicated in specifications, install or erect products in accordance with manufacturer's instructions. Do not rely on labels or enclosures provided with products. Obtain written instructions directly from manufacturers.
- .2 Notify Departmental Representative in writing, of conflicts between specifications and manufacturer's instructions, so that Departmental Representative will establish course of action.
- .3 Improper installation or erection of products, due to failure in complying with these requirements, authorizes Departmental Representative to require removal and re-installation at no increase in Contract Price or Contract Time.

I.7 QUALITY OF WORK

- .1 Ensure Quality of Work is of highest standard, executed by workers experienced and skilled in respective duties for which they are employed. Immediately notify Departmental Representative if required Work is such as to make it impractical to produce required results.
- .2 Do not employ anyone unskilled in their required duties. Departmental Representative reserves right to require dismissal from site, workers deemed incompetent or careless.

- .3 Decisions as to standard or fitness of Quality of Work in cases of dispute rest solely with Departmental Representative, whose decision is final.

I.8 CO-ORDINATION

- .1 Ensure co-operation of workers in laying out Work. Maintain efficient and continuous supervision.
- .2 Be responsible for coordination and placement of openings, sleeves and accessories.

I.9 CONCEALMENT

- .1 In finished areas conceal pipes, ducts and wiring in floors, walls and ceilings, except where indicated otherwise.
- .2 Before installation inform Departmental Representative if there is interference. Install as directed by Departmental Representative.

I.10 REMEDIAL WORK

- .1 Perform remedial work required to repair or replace parts or portions of Work identified as defective or unacceptable. Co-ordinate adjacent affected Work as required.
- .2 Perform remedial work by specialists familiar with materials affected. Perform in a manner to neither damage nor put at risk any portion of Work.

I.11 LOCATION OF FIXTURES

- .1 Consider location of fixtures, outlets, and mechanical and electrical items indicated as approximate.
- .2 Inform Departmental Representative of conflicting installation. Install as directed.

I.12 FASTENINGS

- .1 Provide metal fastenings and accessories in same texture, colour and finish as adjacent materials, unless indicated otherwise.
- .2 Prevent electrolytic action between dissimilar metals and materials.
- .3 Space anchors within individual load limit or shear capacity and ensure they provide positive permanent anchorage. Wood, or any other organic material plugs are not acceptable.
- .4 Keep exposed fastenings to a minimum, space evenly and install neatly.
- .5 Fastenings which cause spalling or cracking of material to which anchorage is made are not acceptable.

I.13 FASTENINGS - EQUIPMENT

- .1 Use fastenings of standard commercial sizes and patterns with material and finish suitable for service.
- .2 Bolts may not project more than one diameter beyond nuts.
- .3 Use plain type washers on equipment, sheet metal and soft gasket lock type washers where vibrations occur. Use resilient washers with stainless steel.

I.14 PROTECTION OF WORK IN PROGRESS

- .1 Prevent overloading of parts of building. Do not cut, drill or sleeve load bearing structural member, unless specifically indicated without written approval of Departmental Representative.

I.15 EXISTING UTILITIES

- .1 When breaking into or connecting to existing services or utilities, execute Work at times directed by local governing authorities, with minimum of disturbance to Work, and/or building occupants and pedestrian and vehicular traffic.
- .2 Protect, relocate or maintain existing active services. When services are encountered, cap off in manner approved by authority having jurisdiction. Stake and record location of capped service.

Part 2 Products

2.1 NOT USED

- .1 Not Used.

Part 3 Execution

3.1 NOT USED

- .1 Not Used.

END OF SECTION

Part 1 General

1.1 EXISTING SERVICES

- .1 Before commencing work, establish location and extent of service lines in area of Work and notify Departmental Representative of findings.
- .2 Remove abandoned service lines within 2m of structures. Cap or otherwise seal lines at cut-off points as directed by Departmental Representative.

1.2 LOCATION OF EQUIPMENT AND FIXTURES

- .1 Location of equipment, fixtures and outlets indicated or specified are to be considered as approximate.
- .2 Locate equipment, fixtures and distribution systems to provide minimum interference and maximum usable space and in accordance with manufacturer's recommendations for safety, access and maintenance.
- .3 Inform Departmental Representative of impending installation and obtain approval for actual location.
- .4 Submit field drawings to indicate relative position of various services and equipment when required by Departmental Representative.

1.3 RECORDS

- .1 Record locations of maintained, re-routed and abandoned service lines.

1.4 SUBSURFACE CONDITIONS

- .1 Promptly notify Consultant in writing if subsurface conditions at Place of Work differ materially from those indicated in Contract Documents, or a reasonable assumption of probable conditions based thereon.
- .2 After prompt investigation, should Consultant determine that conditions do differ materially, instructions will be issued for changes in Work as provided in Changes and Change Orders.

Part 2 Products

2.1 NOT USED

- .1 Not Used.

Part 3 Execution

3.1 NOT USED

- .1 Not Used.

END OF SECTION

Part I General

I.1 ACTION AND INFORMATIONAL SUBMITTALS

- .1 Submittals: in accordance with Section 01 33 00 - Submittal Procedures.
- .2 Submit written request in advance of cutting or alteration which affects:
 - .1 Structural integrity of elements of project.
 - .2 Integrity of weather-exposed or moisture-resistant elements.
 - .3 Efficiency, maintenance, or safety of operational elements.
 - .4 Visual qualities of sight-exposed elements.
 - .5 Work of Owner or separate contractor.
- .3 Include in request:
 - .1 Identification of project.
 - .2 Location and description of affected Work.
 - .3 Statement on necessity for cutting or alteration.
 - .4 Description of proposed Work, and products to be used.
 - .5 Alternatives to cutting and patching.
 - .6 Effect on Work of Owner or separate contractor.
 - .7 Written permission of affected separate contractor.
 - .8 Date and time work will be executed.

I.2 MATERIALS

- .1 Required for original installation.
- .2 Change in Materials: Submit request for substitution in accordance with Section 01 33 00 - Submittal Procedures.

I.3 PREPARATION

- .1 Inspect existing conditions, including elements subject to damage or movement during cutting and patching.
- .2 After uncovering, inspect conditions affecting performance of Work.
- .3 Beginning of cutting or patching means acceptance of existing conditions.
- .4 Provide supports to assure structural integrity of surroundings; provide devices and methods to protect other portions of project from damage.
- .5 Provide protection from elements for areas which are to be exposed by uncovering work; maintain excavations free of water.

I.4 EXECUTION

- .1 Execute cutting, fitting, and patching including excavation and fill, to complete Work.
- .2 Fit several parts together, to integrate with other Work.
- .3 Uncover Work to install ill-timed Work.

- .4 Remove and replace defective and non-conforming Work.
- .5 Remove samples of installed Work for testing.
- .6 Provide openings in non-structural elements of Work for penetrations of mechanical and electrical Work.
- .7 Execute Work by methods to avoid damage to other Work, and which will provide proper surfaces to receive patching and finishing.
- .8 Employ original installer to perform cutting and patching for weather-exposed and moisture-resistant elements, and sight-exposed surfaces.
- .9 Cut rigid materials using masonry saw or core drill. Pneumatic or impact tools not allowed on masonry work without prior approval.
- .10 Restore work with new products in accordance with requirements of Contract Documents.
- .11 Fit Work to pipes, sleeves, ducts, conduit, and other penetrations through surfaces.
- .12 At penetration of fire rated wall, ceiling, or floor construction, completely seal voids with firestopping material in accordance with Section 07 84 00 - Firestopping, full thickness of the construction element.
- .13 Refinish surfaces to match adjacent finishes: Refinish continuous surfaces to nearest intersection. Refinish assemblies by refinishing entire unit.
- .14 Conceal pipes, ducts and wiring in floor, wall and ceiling construction of finished areas except where indicated otherwise.

I.5 WASTE MANAGEMENT AND DISPOSAL

- .1 Separate waste materials for recycling in accordance with Section 01 74 21 - Construction/Demolition Waste Management And Disposal.

Part 2 Products

2.1 NOT USED

- .1 Not Used.

Part 3 Execution

3.1 NOT USED

- .1 Not Used.

END OF SECTION

Part I General

I.1 REFERENCES

- .1 Public Works Government Services Canada (PWGSC) Standard Acquisition Clauses and Conditions (SACC)-ID: R0202D, Title: General Conditions "C", In Effect as Of: May 14, 2004.

I.2 PROJECT CLEANLINESS

- .1 Maintain Work in tidy condition, free from accumulation of waste products and debris, other than that caused by Owner or other Contractors.
- .2 Remove waste materials from site at daily regularly scheduled times or dispose of as directed by Departmental Representative. Do not burn waste materials on site, unless approved by Departmental Representative.
- .3 Make arrangements with and obtain permits from authorities having jurisdiction for disposal of waste and debris.
- .4 Provide on-site containers for collection of waste materials and debris.
- .5 Provide and use marked separate bins for recycling. Refer to Section 01 74 21 - Construction/Demolition Waste Management and Disposal.
- .6 Clean interior areas prior to start of finishing work, and maintain areas free of dust and other contaminants during finishing operations.
- .7 Store volatile waste in covered metal containers, and remove from premises at end of each working day.
- .8 Provide adequate ventilation during use of volatile or noxious substances. Use of building ventilation systems is not permitted for this purpose.
- .9 Use only cleaning materials recommended by manufacturer of surface to be cleaned, and as recommended by cleaning material manufacturer.
- .10 Schedule cleaning operations so that resulting dust, debris and other contaminants will not fall on wet, newly painted surfaces nor contaminate building systems.

I.3 FINAL CLEANING

- .1 When Work is Substantially Performed remove surplus products, tools, construction machinery and equipment not required for performance of remaining Work.
- .2 Remove waste products and debris other than that caused by others, and leave Work clean and suitable for occupancy.
- .3 Prior to final review remove surplus products, tools, construction machinery and equipment.
- .4 Remove waste products and debris other than that caused by Owner or other Contractors.
- .5 Clean and polish glass, mirrors, hardware, wall tile, stainless steel, chrome, porcelain enamel, baked enamel, plastic laminate, and mechanical and electrical fixtures. Replace broken, scratched or disfigured glass.

- .6 Remove stains, spots, marks and dirt from decorative work, electrical and mechanical fixtures, furniture fitments, walls, floors.
- .7 Clean lighting reflectors, lenses, and other lighting surfaces.
- .8 Vacuum clean and dust building interiors, behind grilles, louvres and screens.
- .9 Wax, seal, shampoo or prepare floor finishes, as recommended by manufacturer.
- .10 Inspect finishes, fitments and equipment and ensure specified workmanship and operation.
- .11 Clean equipment and fixtures to sanitary condition; clean or replace filters of mechanical equipment.
- .12 Remove debris and surplus materials from crawl areas and other accessible concealed spaces.

I.4 WASTE MANAGEMENT AND DISPOSAL

- .1 Separate waste materials for recycling in accordance with Section 01 74 21 - Construction/Demolition Waste Management And Disposal.

Part 2 Products

2.1 NOT USED

- .1 Not Used.

Part 3 Execution

3.1 NOT USED

- .1 Not Used.

END OF SECTION

Part I General

I.1 WASTE MANAGEMENT GOALS

- .1 Prior to start of Work conduct meeting with Departmental Representative to review and discuss PWGSC's Waste Management Plan and Goals.
- .2 PWGSC's Waste Management Goal 75 percent of total Project Waste to be diverted from landfill sites. Provide Departmental Representative documentation certifying that waste management, recycling, reuse of recyclable and reusable materials have been extensively practiced.
- .3 Accomplish maximum control of solid construction waste.
- .4 Preserve environment and prevent pollution and environment damage.

I.2 DEFINITIONS

- .1 Class III: non-hazardous waste - construction renovation and demolition waste.
- .2 Cost/Revenue Analysis Workplan (CRAW): based on information from WRW, and intended as financial tracking tool for determining economic status of waste management practices.
- .3 Demolition Waste Audit (DWA): relates to actual waste generated from project.
- .4 Inert Fill: inert waste - exclusively asphalt and concrete.
- .5 Materials Source Separation Program (MSSP): consists of series of ongoing activities to separate reusable and recyclable waste material into material categories from other types of waste at point of generation.
- .6 Recyclable: ability of product or material to be recovered at end of its life cycle and re-manufactured into new product for reuse.
- .7 Recycle: process by which waste and recyclable materials are transformed or collected for purpose of being transferred into new products.
- .8 Recycling: process of sorting, cleansing, treating and reconstituting solid waste and other discarded materials for purpose of using in altered form. Recycling does not include burning, incinerating, or thermally destroying waste.
- .9 Reuse: repeated use of product in same form but not necessarily for same purpose.
Reuse includes:
 - .1 Salvaging reusable materials from re-modelling projects, before demolition stage, for resale, reuse on current project or for storage for use on future projects.
 - .2 Returning reusable items including pallets or unused products to vendors.
- .10 Salvage: removal of structural and non-structural materials from deconstruction/disassembly projects for purpose of reuse or recycling.
- .11 Separate Condition: refers to waste sorted into individual types.
- .12 Source Separation: acts of keeping different types of waste materials separate beginning from first time they became waste.

- .13 Waste Management Co-ordinator (WMC) : contractor representative responsible for supervising waste management activities as well as coordinating related, required submittal and reporting requirements.
- .14 Waste Reduction Workplan (WRW): written report which addresses opportunities for reduction, reuse, or recycling of materials. Refer to Schedule B. WRW is based on information acquired from WA (Schedule A).

I.3 DOCUMENTS

- .1 Maintain at job site, one copy of following documents:
 - .1 Waste Reduction Workplan.
 - .2 Material Source Separation Plan.
 - .3 Schedules A B C D E completed for project.

I.4 ACTION AND INFORMATIONAL SUBMITTALS

- .1 Submittals in accordance with Section 01 33 00 - Submittal Procedures.
- .2 Prepare and submit following prior to project start-up:
 - .1 Submit 2 copies of completed Waste Audit (WA): Schedule A.
 - .2 Submit 2 copies of completed Waste Reduction Workplan (WRW): Schedule B.
- .3 Submit before final payment summary of waste materials salvaged for reuse, recycling or disposal by project using deconstruction/disassembly material audit form.
 - .1 Failure to submit could result in hold back of final payment.
 - .2 Provide receipts, scale tickets, waybills, and show quantities and types of materials reused, recycled, co-mingled and separated off-site or disposed of.
 - .3 For each material reused, sold or recycled from project, include amount in tonnes quantities by number, type and size of items and the destination.
 - .4 For each material land filled or incinerated from project, include amount in tonnes of material and identity of landfill, incinerator or transfer station.

I.5 WASTE REDUCTION WORKPLAN (WRW)

- .1 Prepare WRW prior to project start-up.
- .2 WRW should include but not limited to:
 - .1 Destination of materials listed.
 - .2 Deconstruction/disassembly techniques and sequencing.
 - .3 Schedule for deconstruction/disassembly.
 - .4 Location.
 - .5 Security.
 - .6 Protection.
 - .7 Clear labelling of storage areas.
 - .8 Details on materials handling and removal procedures.
 - .9 Quantities for materials to be salvaged for reuse or recycled and materials sent to landfill.

- .3 Structure WRW to prioritize actions and follow 3R's hierarchy, with Reduction as first priority, followed by Reuse, then Recycle.
- .4 Describe management of waste.
- .5 Identify opportunities for reduction, reuse, and recycling of materials. Based on information acquired from WA.
- .6 Post WRW or summary where workers at site are able to review content.
- .7 Set realistic goals for waste reduction, recognize existing barriers and develop strategies to overcome these barriers.
- .8 Monitor and report on waste reduction by documenting total volume and cost of actual waste removed from project.

I.6 DEMOLITION WASTE AUDIT (DWA)

- .1 Prepare DWA prior to project start-up.
- .2 Complete DWA: Schedule C.
- .3 Provide inventory of quantities of materials to be salvaged for reuse, recycling, or disposal.

I.7 WASTE PROCESSING SITES

- .1 Contractor to verify waste processing site locations.

I.8 STORAGE, HANDLING AND PROTECTION

- .1 Store, materials to be reused, recycled and salvaged in locations as directed by Departmental Representative.
- .2 Unless specified otherwise, materials for removal become Contractor's property.
- .3 Protect, stockpile, store and catalogue salvaged items.
- .4 Separate non-salvageable materials from salvaged items. Transport and deliver non-salvageable items to licensed disposal facility.
- .5 Protect structural components not removed for demolition from movement or damage.
- .6 Support affected structures. If safety of building is endangered, cease operations and immediately notify Departmental Representative.
- .7 Protect surface drainage, mechanical and electrical from damage and blockage.
- .8 Separate and store materials produced during dismantling of structures in designated areas.
- .9 Prevent contamination of materials to be salvaged and recycled and handle materials in accordance with requirements for acceptance by designated facilities.
 - .1 On-site source separation is recommended.
 - .2 Remove co-mingled materials to off-site processing facility for separation.
 - .3 Provide waybills for separated materials.

1.9 DISPOSAL OF WASTES

- .1 Do not bury rubbish or waste materials.
- .2 Do not dispose of waste, volatile materials, mineral spirits, oil, paint thinner into waterways, storm, or sanitary sewers.
- .3 Keep records of construction waste including:
 - .1 Number and size of bins.
 - .2 Waste type of each bin.
 - .3 Total tonnage generated.
 - .4 Tonnage reused or recycled.
 - .5 Reused or recycled waste destination.
- .4 Remove materials from deconstruction as deconstruction/disassembly Work progresses.
- .5 Prepare project summary to verify destination and quantities on a material-by-material basis as identified in pre-demolition material audit.

1.10 USE OF SITE AND FACILITIES

- .1 Execute work with least possible interference or disturbance to normal use of premises.
- .2 Maintain security measures established by existing facility Departmental Representative.

1.11 SCHEDULING

- .1 Co-ordinate Work with other activities at site to ensure timely and orderly progress of Work.

Part 2 Products

2.1 NOT USED

- .1 Not Used.

Part 3 Execution

3.1 APPLICATION

- .1 Do Work in compliance with WRW.
- .2 Handle waste materials not reused, salvaged, or recycled in accordance with appropriate regulations and codes.

3.2 CLEANING

- .1 Remove tools and waste materials on completion of Work, and leave work area in clean and orderly condition.
- .2 Clean-up work area as work progresses.
- .3 Source separate materials to be reused/recycled into specified sort areas.

3.3 WASTE AUDIT (WA)

.1 Schedule A - Waste Audit (WA):

(1) Material Category	(2) Material Quantity Unit	(3) Estimated Waste %	(4) Total Quantity of Waste (unit)	(5) Generation Point	(6) % Recycled	(7) % Reused
Wood and Plastics Material Description						
Off-cuts						
Warped Pallet Forms						
Plastic Packaging						
Cardboard Packaging						
Other						
Doors and Windows Material Description						
Painted Frames						
Glass						
Wood						
Metal						
Other						

3.4 WASTE REDUCTION WORKPLAN (WRW)

.1 Schedule B:

(1) Material Category	(2) Person(s) Responsible	(3) Total Quantity of Waste (unit)	(4) Reused Amount (units) Projected	Actual	(5) Recycled Amount (unit) Projected	Actual	(6) Material(s) Destination
Wood and Plastics Material Description							
Chutes							
Warped Pallet							

Forms							
Plastic Packag ing							
Card-board Packag ing							
Other							
Doors and Windows Material Description							
Painted Frames							
Glass							
Wood							
Metal							
Other							

3.5 CANADIAN GOVERNMENTAL DEPARTMENTS CHIEF RESPONSIBILITY FOR THE ENVIRONMENT

.1 Schedule E - Government Chief Responsibility for the Environment:

Province	Address	General Inquires	Fax
Manitoba	Manitoba Environment Building 2, 139 Tuxedo Avenue, Winnipeg, MB R3N 0H6	204-945-7100	
	The Clean Environment Commission 284 Reimer Avenue, Box 21420 Steinback MB R0A 2T3	204-326-2395	204-326-2472

END OF SECTION

Part I General

I.1 REFERENCES

- .1 Canadian Environmental Protection Act (CEPA)
 - .1 SOR/2008-197, Storage Tank Systems for Petroleum Products and Allied Petroleum Products Regulations.

I.2 ADMINISTRATIVE REQUIREMENTS

- .1 Acceptance of Work Procedures:
 - .1 Contractor's Inspection: Contractor: conduct inspection of Work, identify deficiencies and defects, and repair as required to conform to Contract Documents.
 - .1 Notify Departmental Representative in writing of satisfactory completion of Contractor's inspection and submit verification that corrections have been made.
 - .2 Request Departmental Representative inspection.
 - .2 Departmental Representative Inspection:
 - .1 Departmental Representative and Contractor to inspect Work and identify defects and deficiencies.
 - .2 Contractor to correct Work as directed.
 - .3 Completion Tasks: submit written certificates in English that tasks have been performed as follows:
 - .1 Work: completed and inspected for compliance with Contract Documents.
 - .2 Defects: corrected and deficiencies completed.
 - .3 Equipment and systems: tested, adjusted, balanced and fully operational.
 - .4 Certificates required by Boiler Inspection Branch Fire Commissioner Utility companies: submitted.
 - .5 Operation of systems: demonstrated to Owner's personnel.
 - .6 Commissioning of mechanical systems: completed in accordance with 01 91 13 - General Commissioning (Cx) Requirements and copies of final Commissioning Report submitted to Departmental Representative DCC Representative Consultant.
 - .7 Work: complete and ready for final inspection.
 - .4 Final Inspection:
 - .1 When completion tasks are done, request final inspection of Work by Departmental Representative, and Contractor.
 - .2 When Work is incomplete according to Owner Departmental Representative, complete outstanding items and request re-inspection.
 - .5 Declaration of Substantial Performance: when Departmental Representative considers deficiencies and defects corrected and requirements of Contract

substantially performed, make application for Certificate of Substantial Performance.

- .6 Commencement of Lien and Warranty Periods: date of Owner's acceptance of submitted declaration of Substantial Performance to be date for commencement for warranty period and commencement of lien period unless required otherwise by lien statute of Place of Work.
- .7 Final Payment:
 - .1 When Departmental Representative considers final deficiencies and defects corrected and requirements of Contract met, make application for final payment.
 - .2 When Work deemed incomplete by Departmental Representative, complete outstanding items and request re-inspection.
- .8 Payment of Holdback: after issuance of Certificate of Substantial Performance of Work, submit application for payment of holdback amount in accordance with contractual agreement.

I.3 FINAL CLEANING

- .1 Clean in accordance with Section 01 74 11 - Cleaning.
 - .1 Remove surplus materials, excess materials, rubbish, tools and equipment.
- .2 Waste Management: separate waste materials for reuse recycling in accordance with Section 01 74 21 - Construction/Demolition Waste Management and Disposal

Part 2 Products

2.1 NOT USED

- .1 Not Used.

Part 3 Execution

3.1 NOT USED

- .1 Not Used.

END OF SECTION

Part I General

I.1 REFERENCES

- .1 Canadian Environmental Protection Act (CEPA)
 - .1 SOR/2008-197, Storage Tank Systems for Petroleum Products and Allied Petroleum Products Regulations.

I.2 ADMINISTRATIVE REQUIREMENTS

- .1 Pre-warranty Meeting:
 - .1 Convene meeting one week prior to contract completion with contractor's representative, Departmental Representative, in accordance with Section 01 31 19 - Project Meetings to:
 - .1 Verify Project requirements.
 - .2 Review warranty requirements manufacturer's installation instructions.
 - .2 Departmental Representative to establish communication procedures for:
 - .1 Notifying construction warranty defects.
 - .2 Determine priorities for type of defects.
 - .3 Determine reasonable response time.
 - .3 Contact information for bonded and licensed company for warranty work action: provide name, telephone number and address of company authorized for construction warranty work action.
 - .4 Ensure contact is located within local service area of warranted construction, is continuously available, and is responsive to inquiries for warranty work action.

I.3 ACTION AND INFORMATIONAL SUBMITTALS

- .1 Provide submittals in accordance with Section 01 33 00 - Submittal Procedures.
- .2 Two weeks prior to Substantial Performance of the Work, submit to the Departmental Representative, three final copies of operating and maintenance manuals in English.
- .3 Provide spare parts, maintenance materials and special tools of same quality and manufacture as products provided in Work.
- .4 Provide evidence, if requested, for type, source and quality of products supplied.

I.4 FORMAT

- .1 Organize data as instructional manual.
- .2 Binders: vinyl, hard covered, 3 'D' ring, loose leaf 219 x 279 mm with spine and face pockets.
- .3 When multiple binders are used correlate data into related consistent groupings.
 - .1 Identify contents of each binder on spine.
- .4 Cover: identify each binder with type or printed title 'Project Record Documents'; list title of project and identify subject matter of contents.

- .5 Arrange content by systems, process flow, under Section numbers and sequence of Table of Contents.
- .6 Provide tabbed fly leaf for each separate product and system, with typed description of product and major component parts of equipment.
- .7 Text: manufacturer's printed data, or typewritten data.
- .8 Drawings: provide with reinforced punched binder tab.
 - .1 Bind in with text; fold larger drawings to size of text pages.

I.5 CONTENTS - PROJECT RECORD DOCUMENTS

- .1 Table of Contents for Each Volume: provide title of project;
 - .1 Date of submission; names.
 - .2 Addresses, and telephone numbers of Consultant and Contractor with name of responsible parties.
 - .3 Schedule of products and systems, indexed to content of volume.
- .2 For each product or system:
 - .1 List names, addresses and telephone numbers of subcontractors and suppliers, including local source of supplies and replacement parts.
- .3 Product Data: mark each sheet to identify specific products and component parts, and data applicable to installation; delete inapplicable information.
- .4 Drawings: supplement product data to illustrate relations of component parts of equipment and systems, to show control and flow diagrams.
- .5 Typewritten Text: as required to supplement product data.
 - .1 Provide logical sequence of instructions for each procedure, incorporating manufacturer's instructions specified in Section 01 45 00 - Quality Control.
- .6 Training: refer to Section 01 79 00 - Demonstration and Training.

I.6 AS - BUILT DOCUMENTS AND SAMPLES

- .1 Maintain, in addition to requirements in General Conditions, at site for Departmental Representative one record copy of:
 - .1 Contract Drawings.
 - .2 Specifications.
 - .3 Addenda.
 - .4 Change Orders and other modifications to Contract.
 - .5 Reviewed shop drawings, product data, and samples.
 - .6 Field test records.
 - .7 Inspection certificates.
 - .8 Manufacturer's certificates.
- .2 Store record documents and samples in field office apart from documents used for construction.
 - .1 Provide files, racks, and secure storage.

- .3 Label record documents and file in accordance with Section number listings in List of Contents of this Project Manual.
 - .1 Label each document "PROJECT RECORD" in neat, large, printed letters.
- .4 Maintain record documents in clean, dry and legible condition.
 - .1 Do not use record documents for construction purposes.
- .5 Keep record documents and samples available for inspection by Departmental Representative.
- .6 Provide hard copy of as-built documents to Departmental Representative.

I.7 RECORDING INFORMATION ON PROJECT RECORD DOCUMENTS

- .1 Record information on set of blue line black line opaque drawings, and in copy of Project Manual, provided by Departmental Representative .
- .2 Use felt tip marking pens, maintaining separate colours for each major system, for recording information.
- .3 Record information concurrently with construction progress.
 - .1 Do not conceal Work until required information is recorded.
- .4 Contract Drawings and shop drawings: mark each item to record actual construction, including:
 - .1 Measured depths of elements of foundation in relation to finish first floor datum.
 - .2 Measured horizontal and vertical locations of underground utilities and appurtenances, referenced to permanent surface improvements.
 - .3 Measured locations of internal utilities and appurtenances, referenced to visible and accessible features of construction.
 - .4 Field changes of dimension and detail.
 - .5 Changes made by change orders.
 - .6 Details not on original Contract Drawings.
 - .7 References to related shop drawings and modifications.
- .5 Specifications: mark each item to record actual construction, including:
 - .1 Manufacturer, trade name, and catalogue number of each product actually installed, particularly optional items and substitute items.
 - .2 Changes made by Addenda and change orders.
- .6 Other Documents: maintain manufacturer's certifications, inspection certifications, field test records, required by individual specifications sections.
- .7 Provide digital photos, if requested, for site records.

I.8 EQUIPMENT AND SYSTEMS

- .1 For each item of equipment and each system include description of unit or system, and component parts.
 - .1 Give function, normal operation characteristics and limiting conditions.

- .2 Include performance curves, with engineering data and tests, and complete nomenclature and commercial number of replaceable parts.
- .2 Panel board circuit directories: provide electrical service characteristics, controls, and communications.
- .3 Include installed colour coded wiring diagrams.
- .4 Operating Procedures: include start-up, break-in, and routine normal operating instructions and sequences.
 - .1 Include regulation, control, stopping, shut-down, and emergency instructions.
 - .2 Include summer, winter, and any special operating instructions.
- .5 Maintenance Requirements: include routine procedures and guide for trouble-shooting; disassembly, repair, and reassembly instructions; and alignment, adjusting, balancing, and checking instructions.
- .6 Provide servicing and lubrication schedule, and list of lubricants required.
- .7 Include manufacturer's printed operation and maintenance instructions.
- .8 Include sequence of operation by controls manufacturer.
- .9 Provide original manufacturer's parts list, illustrations, assembly drawings, and diagrams required for maintenance.
- .10 Provide installed control diagrams by controls manufacturer.
- .11 Provide Contractor's co-ordination drawings, with installed colour coded piping diagrams.
- .12 Provide charts of valve tag numbers, with location and function of each valve, keyed to flow and control diagrams.
- .13 Provide list of original manufacturer's spare parts, current prices, and recommended quantities to be maintained in storage.
- .14 Include test and balancing reports as specified in Section 01 45 00 - Quality Control.
- .15 Additional requirements: as specified in individual specification sections.

I.9 MATERIALS AND FINISHES

- .1 Building products, applied materials, and finishes: include product data, with catalogue number, size, composition, and colour and texture designations.
 - .1 Provide information for re-ordering custom manufactured products.
- .2 Instructions for cleaning agents and methods, precautions against detrimental agents and methods, and recommended schedule for cleaning and maintenance.
- .3 Moisture-protection and weather-exposed products: include manufacturer's recommendations for cleaning agents and methods, precautions against detrimental agents and methods, and recommended schedule for cleaning and maintenance.
- .4 Additional requirements: as specified in individual specifications sections.

I.10 MAINTENANCE MATERIALS

- .1 Spare Parts:

- .1 Provide spare parts, in quantities specified in individual specification sections.
- .2 Provide items of same manufacture and quality as items in Work.
- .3 Deliver to site location as directed; place and store.
- .4 Receive and catalogue items.
 - .1 Submit inventory listing to Departmental Representative.
 - .2 Include approved listings in Maintenance Manual.
- .5 Obtain receipt for delivered products and submit prior to final payment.
- .2 Extra Stock Materials:
 - .1 Provide maintenance and extra materials, in quantities specified in individual specification sections.
 - .2 Provide items of same manufacture and quality as items in Work.
 - .3 Deliver to location as directed; place and store.
 - .4 Receive and catalogue items.
 - .1 Submit inventory listing to Departmental Representative.
 - .2 Include approved listings in Maintenance Manual.
 - .5 Obtain receipt for delivered products and submit prior to final payment.
- .3 Special Tools:
 - .1 Provide special tools, in quantities specified in individual specification section.
 - .2 Provide items with tags identifying their associated function and equipment.
 - .3 Deliver to site location as directed; place and store.
 - .4 Receive and catalogue items.
 - .1 Submit inventory listing to Departmental Representative.
 - .2 Include approved listings in Maintenance Manual.

I.11 DELIVERY, STORAGE AND HANDLING

- .1 Store spare parts, maintenance materials, and special tools in manner to prevent damage or deterioration.
- .2 Store in original and undamaged condition with manufacturer's seal and labels intact.
- .3 Store components subject to damage from weather in weatherproof enclosures.
- .4 Store paints and freezable materials in a heated and ventilated room.
- .5 Remove and replace damaged products at own expense and for review by Departmental Representative.

I.12 WARRANTIES AND BONDS

- .1 Develop warranty management plan to contain information relevant to Warranties.
- .2 Submit warranty management plan, 30 days before planned pre-warranty conference, to Departmental Representative approval.
- .3 Warranty management plan to include required actions and documents to assure that Departmental Representative receives warranties to which it is entitled.

- .4 Provide plan in narrative form and contain sufficient detail to make it suitable for use by future maintenance and repair personnel.
- .5 Submit, warranty information made available during construction phase, to Departmental Representative for approval prior to each monthly pay estimate.
- .6 Assemble approved information in binder, submit upon acceptance of work and organize binder as follows:
 - .1 Separate each warranty or bond with index tab sheets keyed to Table of Contents listing.
 - .2 List subcontractor, supplier, and manufacturer, with name, address, and telephone number of responsible principal.
 - .3 Obtain warranties and bonds, executed in duplicate by subcontractors, suppliers, and manufacturers, within ten days after completion of applicable item of work.
 - .4 Verify that documents are in proper form, contain full information, and are notarized.
 - .5 Co-execute submittals when required.
 - .6 Retain warranties and bonds until time specified for submittal.
- .7 Except for items put into use with Owner's permission, leave date of beginning of time of warranty until Date of Substantial Performance is determined.
- .8 Conduct joint 12 month warranty inspection, measured from time of acceptance, by Departmental Representative.
- .9 Include information contained in warranty management plan as follows:
 - .1 Roles and responsibilities of personnel associated with warranty process, including points of contact and telephone numbers within the organizations of Contractors, subcontractors, manufacturers or suppliers involved.
 - .2 Listing and status of delivery of Certificates of Warranty for extended warranty items, to include HVAC balancing, pumps, motors, transformers, commissioned systems fire protection, alarm systems, lightning protection systems,.
 - .3 Provide list for each warranted equipment, item, feature of construction or system indicating:
 - .1 Name of item.
 - .2 Model and serial numbers.
 - .3 Location where installed.
 - .4 Name and phone numbers of manufacturers or suppliers.
 - .5 Names, addresses and telephone numbers of sources of spare parts.
 - .6 Warranties and terms of warranty: include one-year overall warranty of construction. Indicate items that have extended warranties and show separate warranty expiration dates.
 - .7 Cross-reference to warranty certificates as applicable.
 - .8 Starting point and duration of warranty period.
 - .9 Summary of maintenance procedures required to continue warranty in force.

- .10 Cross-Reference to specific pertinent Operation and Maintenance manuals.
- .11 Organization, names and phone numbers of persons to call for warranty service.
- .12 Typical response time and repair time expected for various warranted equipment.
- .4 Contractor's plans for attendance at 12 month post-construction warranty inspections.
- .5 Procedure and status of tagging of equipment covered by extended warranties.
- .6 Post copies of instructions near selected pieces of equipment where operation is critical for warranty and/or safety reasons.
- .10 Respond in timely manner to oral or written notification of required construction warranty repair work.
- .11 Written verification to follow oral instructions.
 - .1 Failure to respond will be cause for the Departmental Representative to proceed with action against Contractor.

1.13 WARRANTY TAGS

- .1 Tag, at time of installation, each warranted item. Provide durable, oil and water resistant tag approved by Departmental Representative.
- .2 Attach tags with copper wire and spray with waterproof silicone coating.
- .3 Leave date of acceptance until project is accepted for occupancy.
- .4 Indicate following information on tag:
 - .1 Type of product/material.
 - .2 Model number.
 - .3 Serial number.
 - .4 Contract number.
 - .5 Warranty period.
 - .6 Inspector's signature.
 - .7 Construction Contractor.

Part 2 Products

2.1 NOT USED

- .1 Not Used.

Part 3 Execution

3.1 NOT USED

- .1 Not Used.

END OF SECTION

Part I General

I.1 ADMINISTRATIVE REQUIREMENTS

- .1 Demonstrate scheduled, operation and maintenance of equipment and systems to Owner's personnel two weeks prior to date of substantial performance.
- .2 Owner: provide list of personnel to receive instructions, and co-ordinate their attendance at agreed-upon times.
- .3 Preparation:
 - .1 Verify conditions for demonstration and instructions comply with requirements.
 - .2 Verify designated personnel are present.
 - .3 Ensure testing, adjusting, and balancing has been performed in accordance with Section 01 91 13 - General Commissioning (Cx) Requirements and equipment and systems are fully operational.
- .4 Demonstration and Instructions:
 - .1 Demonstrate start-up, operation, control, adjustment, trouble-shooting, servicing, and maintenance of each item of equipment at scheduled times, at the designated location.
 - .2 Instruct personnel in phases of operation and maintenance using operation and maintenance manuals as basis of instruction.
 - .3 Review contents of manual in detail to explain aspects of operation and maintenance.
 - .4 Prepare and insert additional data in operations and maintenance manuals when needed during instructions.
- .5 Time Allocated for Instructions: ensure adequate amount of time required for instruction of each item of equipment or system.

I.2 ACTION AND INFORMATIONAL SUBMITTALS

- .1 Provide submittals in accordance with Section 01 33 00 - Submittal Procedures.
- .2 Submit schedule of time and date for demonstration of each item of equipment and each system two weeks prior to designated dates, for Departmental Representative's approval.
- .3 Submit reports within one week after completion of demonstration, that demonstration and instructions have been satisfactorily completed.
- .4 Give time and date of each demonstration, with list of persons present.
- .5 Provide copies of completed operation and maintenance manuals for use in demonstrations and instructions.

I.3 QUALITY ASSURANCE

- .1 When specified in individual Sections requiring manufacturer to provide authorized representative to demonstrate operation of equipment and systems:
 - .1 Instruct Owner's personnel.

- .2 Provide written report that demonstration and instructions have been completed.

Part 2 Products

2.1 NOT USED

- .1 Not Used.

Part 3 Execution

3.1 NOT USED

- .1 Not Used.

END OF SECTION

PART 1 - General

1.1 Applicability

- .1 The work in this section lays out the responsibilities and the work required of the:
 - .1 General contractor or Construction Manager
 - .2 Mechanical contractor
 - .3 Electrical Contractor
 - .4 Controls contractor
 - .5 Testing, Adjusting, and Balancing Contractor
 - .6 Other contractors providing services under the requirements of this contract as may be noted in this or other related parts of the specifications

1.2 DESCRIPTION

- .1 Commissioning is a systematic process of ensuring that all building systems installed in accordance with the drawings and specifications, manufacturer's requirements and good industry practice. Commissioning also ensures that equipment operates and performs, in and of itself as well as in the system, as was intended by the designers in response to the owner's requirements. Finally commissioning ensures the owner has the documentation and training required to operate the equipment and systems in a safe, efficient and long lasting manner.
 - .1 During the construction phase, commissioning will include the following specific activities:
 - .1 Verify equipment is installed in accordance with the manufacturer's recommendations and industry accepted standards including review of completed manufacturers' start-up sheets, supplemented where required with commissioning installation verification checklists provided by the CxA. Contractor shall complete check sheets as required by the CxA
 - .2 Verify equipment is set-up, adjusted and balanced to perform as specified. This will include review of Testing, Adjusting, and Balancing (TAB) procedures, review of TAB reports and spot checking measurements on site. The TAB contractor shall cooperate with the CxA providing information requested and tools and manpower for spot checking measurements as required by the CxA.
 - .3 Functional Performance Testing (FPT) of mechanical and systems to ensure proper, complete and efficient operation under the range of conditions they are expected to encounter. Contractors shall provide manpower, tools and other services as required by the CxA to perform the FPT
 - .4 CxA will review O&M documentation provided to the owner to ensure it is complete and acceptable for ongoing operation and maintenance of the equipment. The review shall be sent to the Departmental Representative for incorporation with his comments. The Contractors shall provide changes as required by the Engineer.
 - .5 The CxA will witness the Owner's operating personnel training to verify it was adequate and complete to ensure they fully understand the requirements of operating and maintaining the equipment. Contractors shall ensure training meets the approval of the CxA and provide additional training if requested.
 - .2 Commissioning does not take away from, reduce responsibility of or in any way diminish the requirement for system designers and installing contractors to provide a complete, finished and fully functioning product.

I.3 COORDINATION

- .1 Commissioning Team. The following contractors will be required to participate in commissioning and to assist the commissioning team with verification, testing and documentation preparation:
 - .1 General Contractor (GC or Contractor)
 - .2 Construction Manager (CM)
 - .3 Mechanical Contractor (MC)
 - .4 Electrical Contractor (EC)
 - .5 Testing, Adjusting and Balancing contractor (TAB)
 - .6 Controls Contractor (CC)
 - .7 Contractors installing insulation, windows and doors, air barrier or other building shell components.
 - .8 Any other installing Subcontractors or suppliers of equipment.
- .2 Other members of the commissioning team include:
 - .1 Commissioning Agent (CxA)
 - .2 Owner's Project Manager (PM)
 - .3 Designated representative of the owner's Operations and Maintenance personnel (O&M)
 - .4 Architect and Design Engineers - particularly the mechanical engineer

.2 Management: Contractors shall cooperate fully with the CxA who will be the Owner's representative for commissioning during all commissioning activities. Contractors shall work together and with the other members of the commissioning team as required to fulfil their contracted responsibilities and meet the objectives of commissioning.

.3 Scheduling: The GC/CM will work with the CxA to schedule the commissioning activities required of contractors and subcontractors. All parties will address scheduling problems and make necessary notifications in a timely manner in order to expedite the commissioning process.

The CxA will provide the initial schedule of primary commissioning events at the commissioning scoping meeting. As construction progresses more detailed schedules may be developed by the GC/CM.

The GC/CM shall be responsible for ensuring that the mechanical and controls sub-contractors will return to the building approximately 10 months after the start of the warrantee period to review system operation and to address operational issues.

I.4 RELATED SECTIONS

- | | | |
|----|---|------------------|
| .1 | Plumbing | Division 22 |
| .2 | Heating, Ventilation and Air Conditioning | Division 23 |
| .3 | Testing, Adjusting and Balancing for HVAC | Section 23 05 93 |
| .4 | EMCS | Section 25 90 01 |
| .5 | Common Works Results – For Electrical | Section 26 05 00 |

I.5 RESPONSIBILITIES

- .1 Mechanical Contractor:
 - .1 Attend initial commissioning coordination meeting.
 - .2 Provide a complete set of all submittals for mechanical equipment for the CxA

- .3 Provide complete equipment and systems start-up including personnel and tools, as required for safe, proper and complete start-up of all mechanical equipment.
 - .4 Perform installation verification, start-up and complete required documentation as directed by CxA.
 - .5 Correct all deficiencies found during installation verification, start-up and TAB to ensure that all equipment and systems are fully functional and ready for functional performance testing.
 - .6 Prepare O&M manuals and supplementary information on all equipment as directed by CxA and assemble in binders tabbed and indexed. Supplementary information may include, but is not limited to, such items as power/control field wiring diagrams, equipment maintenance schedule, vendor and maintenance contact lists. Submit to CxA when requested.
 - .7 Prepare preliminary schedule for O&M manuals submission, owner training, pipe and duct system testing, flushing and cleaning, equipment start-up, and TAB for use by the CxA. Update schedule throughout the construction period.
 - .8 Notify CxA a minimum of two weeks in advance of equipment and system start-up and/or installation verification testing.
 - .9 Set-up and schedule vendors and contractors required to participate in the owner training sessions for all equipment and systems.
 - .10 Provide a complete set of as-built record drawings and schematics, include a copy to the CxA.
 - .11 Return to site with the GC/CM, O&M and CxA approximately 10 months after the start of the warranty period to review system operation and to address operational issues.
- .2 TAB Contractor(s)
- .1 Attend initial commissioning coordination meeting.
 - .2 Submit TAB procedures to CxA and Mechanical Consultant for review and acceptance.
 - .3 Provide a preliminary TAB report showing that the system is complete and capable of being balanced. Provide an additional copy of the preliminary report labelled "For CxA".
 - .4 Attend TAB review meeting scheduled by the CxA. Be prepared to discuss procedures that shall be followed in TAB and findings of preliminary TAB.
 - .5 Submittal of final TAB report showing all flows, pressures, motor speeds, voltages and amperages etc., as required for a full and complete balancing report on all systems. Provide an additional copy of the TAB final report labelled "For CxA", and include as-built distribution systems schematics.
 - .6 Participate in verification of the TAB report, which includes of repeating selected measurement contained in the TAB report where required by the CxA for verification or diagnostic purposes.
- .3 Building Controls and Automation System Contractor(s)
- .1 Attend initial commissioning coordination meeting.
 - .2 Attend Sequence of Operation and Graphics review meeting scheduled by the CxA. Be prepared to discuss all sequences including all changes, and provide a schematic for each proposed graphic.
 - .3 Provide the following submittals to the CxA at time of FPT. (Note: The following shall be updated to as-built conditions).

- .1 Hardware and software submittals and shop drawings.
- .2 Narrative description of each control sequence for each piece of equipment or system controlled.
- .3 Point-to-point and sensor calibration verification checklists
- .4 As-built diagrams showing all control points, sensor locations, point names, actuators, controllers and, where necessary, points of access, superimposed on diagrams of the physical equipment.
- .5 Printout of panel layouts including all analog input, analog output, digital input, and digital output connections. Provide a separate list for each stand alone control unit.
- .6 Printout of final control programming algorithms, include current values of all parameters for each system point.
- .7 Owners operation and maintenance manuals.
- .4 Provide complete training to operating personnel on hardware, operation and programming, and the application program for the system.
- .5 Demonstrate system performance to CxA. including all modes of system operation. (e.g. normal, abnormal, emergency).
- .6 Provide control system technician to operate systems as required by and under the direction of the CxA during system verification and functional performance testing.
- .7 Provide support and coordination with TAB contractor on all interfaces between their scopes of work. Provide all devices, such as portable operators' terminals, for TAB use in completing TAB procedures.
- .8 Provide any trend logs as may be required by the CxA.
- .9 Return to site with the GC/CM, O&M and CxA approximately 10 months after the start of the warranty period to review system operation and to address operational issues.
- .4 Electrical Contractor
 - .1 Attend commissioning meetings scheduled by the CxA.
 - .2 Correct all deficiencies found during Installation Verification Inspection (IVI), start-up, TAB and FPT to ensure all equipment and systems are fully functional and in complete and proper working order.
 - .3 Provide electrical system technicians to assist during system verification and functional performance testing as required by the CxA.

1.6 EQUIPMENT/SYSTEMS TO BE COMMISSIONED

- .1 Systems to be commissioned under this part are primarily associated with HVAC for the building and central plant but do not include process or special purpose equipment such as:
 - .1 life safety systems such as fire alarm, sprinkler, fire pumps
 - .2 security systems such as card readers, automatic door locks, CC cameras
 - .3 Communication systems such as data, paging and telephone systems
 - .4 specialty equipment such as kitchen cooking and refrigeration equipment, medical gas, elevators, laboratory equipment, etc. but scope does include exhaust hoods and fans
 - .5 Plumbing piping systems such as drainage and storm water management but scope does include booster pumps, hot water generation, cistern pumping and control systems for these

- .2 All major mechanical equipment and their controls will be commissioned using a series of installation verification and functional checks. Equipment to be commissioned during the course of this project includes but is not limited to:

- .1 New Building Automation System (Controls System) Components and Sequences
- .2 New/Relocated VAV Boxes
- .3 New/Relocated Split Fan Coil Units

Other major new/relocated equipment as may be included in construction but may have been left off of this list will also be required to be included in commissioning.

PART 2 - Products

2.1 TEST EQUIPMENT

- .1 All standard testing equipment required to perform start-up and installation verification and required functional performance testing shall be provided by the division contractor for the equipment being tested.
- .2 Special test equipment, tools or instruments required by the contract documents shall be provided for commissioning and shall be left on site.
- .3 All testing equipment shall have had a certified calibration, traceable to a national standard, performed within the past year. If not otherwise noted, temperature sensors and digital thermometers shall have an accuracy of $\pm 0.1^{\circ}\text{F}$, pressure sensors shall have an accuracy of $\pm 1.0\%$ for each range available on the instrument (not the full range of the meter). All equipment shall be re-calibrated when dropped or damaged.

PART 3 - Execution

3.1 MEETINGS

- .1 Commissioning Meetings: Soon after construction commences, the CxA will conduct an initial commissioning scoping meeting with the entire commissioning team in attendance. Commissioning requirements, procedures, responsibilities and schedule will be reviewed. Other commissioning meetings will be conducted as required throughout construction. These meetings will cover coordination, deficiency resolution and planning issues with particular Contractors and Subs.

3.2 SUBMITTALS

- .1 Contractors and Subs shall comply with specific requests for submittal documentation from the CxA in a timely fashion to ensure commissioning work continues as scheduled. At a minimum, the request will include the manufacturer's printed installation and start-up procedures, O&M data and manuals, final shop drawings, power and control field wiring drawings, sequences of operation, and results of required tests.
- .2 Final completion of the O&M manuals including all required submittals is the responsibility of the Contractor. The CxA will review and forward comments to the engineer of record for follow-up.
- .3 TAB contractor shall supply an extra copy of the preliminary and the final TAB report marked "for CxA" for review. The CxA will review and forward comments to the engineer of record for follow-up.

3.3 START-UP AND INSTALLATION VERIFICATION CHECKS

- .1 The installing Contractor or Sub-contractor shall be responsible for performing and documenting start-up based on manufacturer's requirements and/or good industry practice.

They shall perform all required procedures and checks and document the results. Start-up documents as requested by the CxA shall be provided.

- .2 Controls and Sensor Point-to-Point Checks. Control system point-to-point checks and calibration checks for all sensors shall be included as part of installation verification. The results shall be documented and provided to CxA.
- .3 Execution of Start-up and Installation Verification (IV/S-U).
 - .1 IV/S-U checklists shall be developed and provided by CxA. Where appropriate manufacturers checklists and procedures shall be combined or accepted in lieu of CxAs checklists.
 - .2 The contractor, sub-contractor, manufacturer's rep or supplier shall perform IV/S-U. They shall complete the checklist on each piece of equipment. IV/S-U shall be successfully completed prior to any FPT.
 - .3 At his sole discretion the CxA shall observe, recheck or verify the IV/S-U documentation of any or all equipment. The contractor shall cooperate with and provide support to the CxA as requested.
 - .4 Only individuals with direct knowledge of and who personally witnessed any IV/S-U shall sign off the checklists.
 - .5 It will be the responsibility of the contractor to remedy all deficiencies found. Retesting by the contractor may be required to demonstrate corrections have been made.
- .4 Deficiencies, Non-Conformance and Approval of IV/S-U Checklists.
 - .1 Dates for remedy of deficiencies shall be provided to the CxA with the initial IV/S-U documents.
 - .2 The CxA will work with all parties as required to affect proper corrective measures, correct and retest deficiencies or uncompleted items.
 - .3 Items left incomplete or not properly corrected, causing delays or multiple call-backs for retest may result in back-charges to the party at fault.

3.4 TESTING, ADJUSTING, AND BALANCING (TAB)

- .1 A preliminary TAB balancing shall be done prior to final balancing. System deficiencies requiring correction prior to final TAB shall be documented.
- .2 All deficiencies shall be corrected by the contractor prior to final balancing.
- .3 Participate in repeating selected measurement as required by the CxA for verification or diagnostic purposes.

3.5 FUNCTIONAL PERFORMANCE TESTING (FPT)

- .1 In general, functional performance testing is conducted after IV/S-U have been satisfactorily completed, the control system is fully operational, and TAB is complete.
- .2 The installing Contractor or Sub-contractor, under the direction of the CA, shall execute all FPT and shall maintain responsibility for all equipment tested.
- .3 In general, each system shall be operated through all modes of operation (seasonal, occupied, unoccupied, warm-up, cool-down, part-load, full-load). Proper responses to such modes and emergency conditions (e.g., power failure, freeze condition, no flow, equipment failure, etc.) shall be verified.
- .4 FPT verification may be achieved by manual testing (persons manipulate the equipment and observe performance) or by monitoring the performance and analyzing the results using the

control system's trend log capabilities or by stand-alone data loggers. The CxA will determine which method is most appropriate.

- .5 The CxA will schedule FPTs through the GC/CM and affected Contractors and Subs.
- .6 Corrections of minor deficiencies identified during FPT may be made by the Contractor or Sub during the tests.
- .7 Where a deficiency cannot be corrected immediately, the Contractor or Sub shall provide a reasonable timeline for correction. The CxA shall document the deficiency and reschedule the FPT.
- .8 Where there is a dispute regarding whether a problem is a deficiency or who is responsible, the deficiency shall be documented and resolution attempted by parties in attendance. Final acceptance of proposed resolution lies with the Owner or designated representative.
- .9 The burden of responsibility to solve and correct deficiencies lies with the A/M/E, manufacturers, vendors, GC/CM, Contractors, and Subs. The CxA may recommend solutions to problems in consultation with these parties.
- .10 Cost of Retesting:
 - .1 If the Contractor or Sub is responsible for a deficiency then they shall carry the cost to rework the deficiency and complete the IV/S-U or FPT.
 - .2 The CxA will direct the first retesting of the equipment at no charge.
 - .3 If corrections of deficiencies have been reported to be successfully completed but are determined during testing to be faulty or otherwise incomplete, the time for the CxA to direct second or subsequent retests will be charged back.

3.6 DEFERRED TESTING

- .1 If any check or test cannot be completed due to weather conditions, the building structure, required occupancy condition or other deficiency, execution of IV/S-U and/or FPT may be delayed upon approval of the Owner.

END OF SECTION

Additional SPEC Sections

2013-11-21

Part I General

I.1 REFERENCES

- .1 Aluminum Association (AA)
 - .1 AA DAF 45-03(R2009), Designation System for Aluminum Finishes.
- .2 ASTM International
 - .1 ASTM C475-02(2007), Standard Specification for Joint Compound and Joint Tape for Finishing Gypsum Board.
 - .2 ASTM C514-04(2009e1), Standard Specification for Nails for the Application of Gypsum Board.
 - .3 ASTM C557-03(2009)e1, Standard Specification for Adhesives for Fastening Gypsum Wallboard to Wood Framing.
 - .4 ASTM C840-08, Standard Specification for Application and Finishing of Gypsum Board.
 - .5 ASTM C954-07, Standard Specification for Steel Drill Screws for the Application of Gypsum Panel Products or Metal Plaster Bases to Steel Studs From 0.033 in. (0.84 mm) to 0.112 in. (2.84 mm) in Thickness.
 - .6 ASTM C1002-07, Standard Specification for Steel Self-Piercing Tapping Screws for the Application of Gypsum Panel Products or Metal Plaster Bases to Wood Studs or Steel Studs.
 - .7 ASTM C1047-09, Standard Specification for Accessories for Gypsum Wallboard and Gypsum Veneer Base.
 - .8 ASTM C1280-99, Standard Specification for Application of Gypsum Sheathing.
 - .9 ASTM C1177/C1177M-08, Standard Specification for Glass Mat Gypsum Substrate for Use as Sheathing.
 - .10 ASTM C1178/C1178M-08, Standard Specification for Glass Mat Water-Resistant Gypsum Backing Board.
 - .11 ASTM C1396/C1396M-09a, Standard Specification for Gypsum Wallboard.
- .3 Association of the Wall and Ceilings Industries International (AWCI)
 - .1 AWCI Levels of Gypsum Board Finish-97.
- .4 Canadian General Standards Board (CGSB)
 - .1 CAN/CGSB-51.34-M86(R1988), Vapour Barrier, Polyethylene Sheet for Use in Building Construction.
 - .2 CAN/CGSB-71.25-M88, Adhesive, for Bonding Drywall to Wood Framing and Metal Studs.
- .5 Green Seal Environmental Standards (GS)
 - .1 GS-11-2008, 2nd Edition, Paints and Coatings.
- .6 Underwriters' Laboratories of Canada (ULC)
 - .1 CAN/ULC-S102-07, Standard Method of Test of Surface Burning Characteristics of Building Materials and Assemblies.

I.2 ACTION AND INFORMATIONAL SUBMITTALS

- .1 Submit in accordance with Section 01 33 00 - Submittal Procedures.
- .2 Product Data:

- .1 Submit manufacturer's instructions, printed product literature and data sheets for gypsum board assemblies and include product characteristics, performance criteria, physical size, finish and limitations.

I.3 DELIVERY, STORAGE AND HANDLING

- .1 Deliver, store and handle materials in accordance with Section 01 61 00 - Common Product Requirements with manufacturer's written instructions.
- .2 Delivery and Acceptance Requirements: deliver materials to site in original factory packaging, labelled with manufacturer's name and address.
- .3 Storage and Handling Requirements:
 - .1 Store gypsum board assemblies materials level off ground indoors in dry location and in accordance with manufacturer's recommendations in clean, dry, well-ventilated area.
 - .2 Store and protect gypsum board assemblies from nicks, scratches, and blemishes.
 - .3 Protect from weather, elements and damage from construction operations.
 - .4 Handle gypsum boards to prevent damage to edges, ends or surfaces.
 - .5 Protect prefinished aluminum surfaces with wrapping strippable coating. Do not use adhesive papers or sprayed coatings which bond when exposed to sunlight or weather.
 - .6 Replace defective or damaged materials with new.
- .4 Develop Construction Waste Management Plan Waste Reduction Workplan related to Work of this Section.
- .5 Packaging Waste Management: remove for reuse and return by manufacturer of pallets, crates, padding, packaging materials as specified in Construction Waste Management Plan Waste Reduction Workplan in accordance with Section 01 74 21 - Construction/Demolition Waste Management and Disposal.

I.4 AMBIENT CONDITIONS

- .1 Maintain temperature 10 degrees C minimum, 21 degrees C maximum for 48 hours prior to and during application of gypsum boards and joint treatment, and for 48 hours minimum after completion of joint treatment.
- .2 Apply board and joint treatment to dry, frost free surfaces.
- .3 Ventilation: ventilate building spaces as required to remove excess moisture that would prevent drying of joint treatment material immediately after its application.

Part 2 Products

2.1 MATERIALS

- .1 Standard board: to ASTM C1396/C1396M regular, 16mm thick, 1200 mm wide x maximum practical length, ends square cut, edges bevelled.
- .2 Drywall furring channels: 0.5 mm core thickness galvanized steel channels for screw attachment of gypsum board.
- .3 Resilient clips drywall furring : 0.5 mm base steel thickness galvanized steel for resilient attachment of gypsum board.
- .4 Nails: to ASTM C514.
- .5 Steel drill screws: to ASTM C1002.
- .6 Stud adhesive: to CAN/CGSB-71.25 ASTM C557.

- .7 Laminating compound: as recommended by manufacturer, asbestos-free.
- .8 Casing beads, corner beads, control joints and edge trim: to ASTM C1047, zinc-coated by hot-dip process, 0.5 mm base thickness, perforated flanges, one piece length per location.
- .9 Sealants: in accordance with Section 07 92 00 - Joint Sealants.
 - .1 VOC limit 250 g/L maximum to SCAQMD Rule 1168.
 - .2 Acoustic sealant: in accordance with Section 07 92 00 - Joint Sealants.
- .10 Polyethylene: to CAN/CGSB-51.34, Type 2.
- .11 Joint compound: to ASTM C475, asbestos-free.

2.2 FINISHES

- .1 Texture finish: asbestos-free standard white texture coating and primer-sealer, recommended by gypsum board manufacturer.
 - .1 Primer: VOC limit 50 g/L maximum to GS-11 SCAQMD Rule 1113.

Part 3 Execution

3.1 EXAMINATION

- .1 Verification of Conditions: verify conditions of substrates previously installed under other Sections or Contracts are acceptable for gypsum board assemblies installation in accordance with manufacturer's written instructions.
 - .1 Visually inspect substrate in presence of Departmental Representative.
 - .2 Inform Departmental Representative of unacceptable conditions immediately upon discovery.
 - .3 Proceed with installation only after unacceptable conditions have been remedied and after receipt of written approval to proceed from Departmental Representative.

3.2 ERECTION

- .1 Do application and finishing of gypsum board to ASTM C840 except where specified otherwise.
- .2 Do application of gypsum sheathing to ASTM C1280.
- .3 Erect hangers and runner channels for suspended gypsum board ceilings to ASTM C840 except where specified otherwise.
- .4 Support light fixtures by providing additional ceiling suspension hangers within 150 mm of each corner and at maximum 600 mm around perimeter of fixture.
- .5 Install work level to tolerance of 1:1200.
- .6 Frame with furring channels, perimeter of openings for access panels, light fixtures, diffusers, grilles.
- .7 Install 19 x 64 mm furring channels parallel to, and at exact locations of steel stud partition header track.
- .8 Furr for gypsum board faced vertical bulkheads within and at termination of ceilings.
- .9 Furr above suspended ceilings for gypsum board fire and sound stops and to form plenum areas as indicated.
- .10 Install wall furring for gypsum board wall finishes to ASTM C840, except where specified otherwise.

- .11 Furr duct shafts, beams, columns, pipes and exposed services where indicated.
- .12 Erect drywall resilient furring transversely across studs joists between the layers of gypsum board, spaced maximum 600 mm on centre and not more than 150 mm from ceiling/wall juncture. Secure to each support with 38 mm common nail 25 mm drywall screw.

3.3 APPLICATION

- .1 Apply gypsum board after bucks, anchors, blocking, sound attenuation, electrical and mechanical work have been approved.
- .2 Apply single layer gypsum board to metal furring or framing using screw fasteners. Maximum spacing of screws 300 mm on centre.
 - .1 Single-Layer Application:
 - .1 Apply gypsum board on ceilings prior to application of walls to ASTM C840.
 - .2 Apply gypsum board vertically or horizontally, providing sheet lengths that will minimize end joints.
- .3 Apply single layer gypsum board to concrete concrete block surfaces, where indicated, using laminating adhesive.
 - .1 Comply with gypsum board manufacturer's recommendations.
 - .2 Brace or fasten gypsum board until fastening adhesive has set.
 - .3 Mechanically fasten gypsum board at top and bottom of each sheet.
- .4 Install gypsum board on walls vertically to avoid end-butt joints. At stairwells and similar high walls, install boards horizontally with end joints staggered over studs, except where local codes or fire-rated assemblies require vertical application.
- .5 Install gypsum board with face side out.
- .6 Do not install damaged or damp boards.
- .7 Locate edge or end joints over supports. Stagger vertical joints over different studs on opposite sides of wall.

3.4 INSTALLATION

- .1 Erect accessories straight, plumb or level, rigid and at proper plane. Use full length pieces where practical. Make joints tight, accurately aligned and rigidly secured. Mitre and fit corners accurately, free from rough edges. Secure using contact adhesive for full length at 150 mm on centre.
- .2 Install casing beads around perimeter of suspended ceilings.
- .3 Install casing beads where gypsum board butts against surfaces having no trim concealing junction and where indicated. Seal joints with sealant.
- .4 Install insulating strips continuously at edges of gypsum board and casing beads abutting metal window and exterior door frames, to provide thermal break.
- .5 Install expansion joint straight and true.
- .6 Fit cornice cap over partition, secure to partition track with two rows of sheet metal screws staggered at 300 mm on centre.
- .7 Splice corners and intersections together and secure to each member with 3 screws.
- .8 Install access doors to electrical and mechanical fixtures specified in respective sections.
 - .1 Rigidly secure frames to furring or framing systems.

- .9 Finish face panel joints and internal angles with joint system consisting of joint compound, joint tape and taping compound installed according to manufacturer's directions and feathered out onto panel faces.
- .10 Gypsum Board Finish: finish gypsum board walls and ceilings to following levels in accordance with AWC Levels of Gypsum Board Finish:
 - .1 Levels of finish:
 - .1 Level 4: embed tape for joints and interior angles in joint compound and apply three separate coats of joint compound over joints, angles, fastener heads and accessories; surfaces smooth and free of tool marks and ridges.
 - .11 Finish corner beads, control joints and trim as required with two coats of joint compound and one coat of taping compound, feathered out onto panel faces.
 - .12 Fill screw head depressions with joint and taping compounds to bring flush with adjacent surface of gypsum board so as to be invisible after surface finish is completed.
 - .13 Sand lightly to remove burred edges and other imperfections. Avoid sanding adjacent surface of board.
 - .14 Completed installation to be smooth, level or plumb, free from waves and other defects and ready for surface finish.
 - .15 Apply one coat of white primer sealer over surface to be textured. When dry apply textured finish in accordance with manufacturer's instructions.
 - .16 Mix joint compound slightly thinner than for joint taping.
 - .17 Apply thin coat to entire surface using trowel or drywall broad knife to fill surface texture differences, variations or tool marks.
 - .18 Allow skim coat to dry completely.
 - .19 Remove ridges by light sanding or wiping with damp cloth.

3.5 CLEANING

- .1 Progress Cleaning: clean in accordance with Section 01 74 11 - Cleaning.
 - .1 Leave Work area clean at end of each day.
 - .2 Final Cleaning: upon completion remove surplus materials, rubbish, tools and equipment in accordance with Section 01 74 11 - Cleaning.
- .2 Waste Management: separate waste materials for recycling in accordance with Section 01 74 21 - Construction/Demolition Waste Management and Disposal.
 - .1 Remove recycling containers and bins from site and dispose of materials at appropriate facility.

3.6 PROTECTION

- .1 Protect installed products and components from damage during construction.
- .2 Repair damage to adjacent materials caused by gypsum board assemblies installation.

END OF SECTION

Part I General

I.1 REFERENCES

- .1 Department of Justice Canada (Jus)
 - .1 Canadian Environmental Protection Act (CEPA), 1999, c. 33
- .2 Environmental Protection Agency (EPA)
 - .1 EPA Test Method for Measuring Total Volatile Organic Compound Content of Consumer Products, Method 24 - 1995, (for Surface Coatings).
- .3 Health Canada / Workplace Hazardous Materials Information System (WHMIS)
 - .1 Material Safety Data Sheets (MSDS).
- .4 Master Painters Institute (MPI)
 - .1 MPI Architectural Painting Specifications Manual, 2004.
- .5 National Fire Code of Canada - 1995
- .6 Society for Protective Coatings (SSPC)
 - .1 SSPC Painting Manual, Volume Two, 8th Edition, Systems and Specifications Manual.
- .7 Transport Canada (TC)
 - .1 Transportation of Dangerous Goods Act (TDGA), 1992, c. 34 .

I.2 QUALITY ASSURANCE

- .1 Qualifications:
 - .1 Contractor: minimum of five years proven satisfactory experience. Provide list of last three comparable jobs including, job name and location, specifying authority, and project manager.
 - .2 Journeymen: qualified journeymen who have "Tradesman Qualification Certificate of Proficiency" engaged in painting work.
 - .3 Apprentices: working under direct supervision of qualified trades person in accordance with trade regulations.
- .2 Pre-Installation Meeting:
 - .1 Convene pre-installation meeting one week prior to beginning work of this Section on-site installations in accordance with Section 01 32 16.07 - Construction Progress Schedules - Bar (GANTT) Chart.
 - .1 Verify project requirements.
 - .2 Review installation and substrate conditions.
 - .3 Coordination with other building subtrades.
 - .4 Review manufacturer's installation instructions and warranty requirements.

- .3 Verification: contractor's verification in accordance with Section 01 47 17 - Sustainable Requirements: Contractor's Verification.

I.3 SCHEDULING

- .1 Submit work schedule for various stages of painting to Departmental Representative for review. Submit schedule minimum of 48 hours in advance of proposed operations.
- .2 Obtain written authorization from Departmental Representative for changes in work schedule.
- .3 Schedule painting operations to prevent disruption of occupants.

I.4 ACTION AND INFORMATIONAL SUBMITTALS

- .1 Submittals in accordance with Section 01 33 00 - Submittal Procedures.
- .2 Product Data:
 - .1 Submit product data and instructions for each paint and coating product to be used.
 - .2 Submit product data for the use and application of paint thinner.
 - .3 Submit two copies of Workplace Hazardous Materials Information System (WHMIS) Material Safety Data Sheets (MSDS) in accordance with Section 01 33 00 - Submittal Procedures. Indicate VOCs during application and curing.
- .3 Samples:
 - .1 Submit full range colour sample chips to indicate where colour availability is restricted.
 - .2 Retain reviewed samples on-site to demonstrate acceptable standard of quality for appropriate on-site surface.
 - .3 Test reports: submit certified test reports for paint from approved independent testing laboratories, indicating compliance with specifications for specified performance characteristics and physical properties.
 - .1 Lead, cadmium and chromium: presence of and amounts.
 - .2 Mercury: presence of and amounts.
 - .3 Organochlorines and PCBs: presence of and amounts.
 - .4 Certificates: submit certificates signed by manufacturer certifying that materials comply with specified performance characteristics and physical properties.
 - .5 Manufacturer's Instructions:
 - .1 Submit manufacturer's installation application instructions.
 - .6 Closeout Submittals: submit maintenance data for incorporation into manual specified in Section 01 78 00 - Closeout Submittals include following:
 - .1 Product name, type and use.
 - .2 Manufacturer's product number.
 - .3 Colour numbers.
 - .4 MPI Environmentally Friendly classification system rating.

I.5 MAINTENANCE

- .1 Extra Materials:

- .1 Deliver to extra materials from same production run as products installed. Package products with protective covering and identify with descriptive labels. Comply with Section 01 78 00 - Closeout Submittals.
- .2 Quantity: provide one - four litre can of each type and colour of primer stain finish coating. Identify colour and paint type in relation to established colour schedule and finish system.
- .3 Delivery, storage and protection: comply with Departmental Representative requirements for delivery and storage of extra materials.

I.6 DELIVERY, STORAGE AND HANDLING

- .1 Packing, Shipping, Handling and Unloading:
 - .1 Pack, ship, handle and unload materials in accordance with Section 01 61 00 - Common Product Requirements and manufacturer's written instructions.
- .2 Acceptance at Site:
 - .1 Identify products and materials with labels indicating:
 - .1 Manufacturer's name and address.
 - .2 Type of paint or coating.
 - .3 Compliance with applicable standard.
 - .4 Colour number in accordance with established colour schedule.
- .3 Remove damaged, opened and rejected materials from site.
- .4 Storage and Protection:
 - .1 Provide and maintain dry, temperature controlled, secure storage.
 - .2 Store materials and supplies away from heat generating devices.
 - .3 Store materials and equipment in well ventilated area with temperature range 7 degrees C to 30 degrees C.
- .5 Store temperature sensitive products above minimum temperature as recommended by manufacturer.
- .6 Keep areas used for storage, cleaning and preparation clean and orderly. After completion of operations, return areas to clean condition.
- .7 Remove paint materials from storage only in quantities required for same day use.
- .8 Fire Safety Requirements:
 - .1 Provide one 9 kg Type B fire extinguisher adjacent to storage area.
 - .2 Store oily rags, waste products, empty containers and materials subject to spontaneous combustion in ULC approved, sealed containers and remove from site on a daily basis.
 - .3 Handle, store, use and dispose of flammable and combustible materials in accordance with National Fire Code of Canada requirements.
- .9 Waste Management and Disposal:
 - .1 Separate waste materials for recycling in accordance with Section 01 74 21 - Construction/Demolition Waste Management and Disposal.

- .2 Remove from site and dispose of packaging materials at appropriate recycling facilities.
- .3 Collect and separate for disposal paper plastic polystyrene corrugated cardboard packaging material in appropriate on-site bins for recycling in accordance with Waste Management Plan (WMP).
- .4 Separate for reuse recycling and place in designated containers Steel Metal Plastic waste in accordance with Waste Management Plan (WMP).
- .5 Place materials defined as hazardous or toxic in designated containers.
- .6 Handle and dispose of hazardous materials in accordance with CEPA, TDGA, Regional and Municipal, regulations.
- .7 Ensure emptied containers are sealed and stored safely.
- .8 Unused paint coating materials must be disposed of at official hazardous material collections site as approved by Departmental Representative
- .9 Paint, stain and wood preservative finishes and related materials (thinners, and solvents) are regarded as hazardous products and are subject to regulations for disposal. Information on these controls can be obtained from Provincial Ministries of Environment and Regional levels of Government.
- .10 Material which cannot be reused must be treated as hazardous waste and disposed of in an appropriate manner.
- .11 Place materials defined as hazardous or toxic waste, including used sealant and adhesive tubes and containers, in containers or areas designated for hazardous waste.
- .12 To reduce the amount of contaminants entering waterways, sanitary/storm drain systems or into ground follow these procedures:
 - .1 Retain cleaning water for water-based materials to allow sediments to be filtered out.
 - .2 Retain cleaners, thinners, solvents and excess paint and place in designated containers and ensure proper disposal.
 - .3 Return solvent and oil soaked rags used during painting operations for contaminant recovery, proper disposal, or appropriate cleaning and laundering.
 - .4 Dispose of contaminants in approved legal manner in accordance with hazardous waste regulations.
 - .5 Empty paint cans are to be dry prior to disposal or recycling (where available).
- .13 Where paint recycling is available, collect waste paint by type and provide for delivery to recycling or collection facility.

I.7 SITE CONDITIONS

- .1 Heating, Ventilation and Lighting:
 - .1 Ventilate enclosed spaces.
 - .2 Provide heating facilities to maintain ambient air and substrate temperatures above 10 degrees C for 24 hours before, during and after paint application until paint has cured sufficiently.

- .3 Provide continuous ventilation for seven days after completion of application of paint.
- .4 Coordinate use of existing ventilation system with Departmental Representative and ensure its operation during and after application of paint as required.
- .5 Provide temporary ventilating and heating equipment where permanent facilities are not available or supplemental ventilating and heating equipment if ventilation and heating from existing system is inadequate to meet minimum requirements.
- .6 Provide minimum lighting level of 323 Lux on surfaces to be painted.
- .2 Temperature, Humidity and Substrate Moisture Content Levels:
 - .1 Unless pre-approved written approval by Specifying body Paint Inspection Agency Authority and product manufacturer, perform no painting when:
 - .1 Ambient air and substrate temperatures are below 10 degrees C.
 - .2 Substrate temperature is above 32 degrees C unless paint is specifically formulated for application at high temperatures.
 - .3 Substrate and ambient air temperatures are not expected to fall within MPI or paint manufacturer's prescribed limits.
 - .4 The relative humidity is under 85% or when the dew point is more than 3 degrees C variance between the air/surface temperature. Paint should not be applied if the dew point is less than 3 degrees C below the ambient or surface temperature. Use sling psychrometer to establish the relative humidity before beginning paint work.
 - .5 Rain or snow are forecast to occur before paint has thoroughly cured or when it is foggy, misty, raining or snowing at site.
 - .6 Ensure that conditions are within specified limits during drying or curing process, until newly applied coating can itself withstand 'normal' adverse environmental factors.
 - .2 Perform painting work when maximum moisture content of the substrate is below:
 - .1 Allow new concrete and masonry to cure minimum of 28 days.
 - .2 15% for wood.
 - .3 12% for plaster and gypsum board.
 - .3 Test for moisture using calibrated electronic Moisture Meter. Test concrete floors for moisture using "cover patch test".
 - .4 Test concrete, masonry and plaster surfaces for alkalinity as required.
- .3 Surface and Environmental Conditions:
 - .1 Apply paint finish in areas where dust is no longer being generated by related construction operations or when wind or ventilation conditions are such that airborne particles will not affect quality of finished surface.
 - .2 Apply paint to adequately prepared surfaces and to surfaces within moisture limits.
 - .3 Apply paint when previous coat of paint is dry or adequately cured.
- .4 Additional interior application requirements:

- .1 Apply paint finishes when temperature at location of installation can be satisfactorily maintained within manufacturer's recommendations.
- .2 Apply paint in occupied facilities during silent hours only. Schedule operations to approval of Departmental Representative such that painted surfaces will have dried and cured sufficiently before occupants are affected.

Part 2 Products

2.1 MATERIALS

- .1 Paint materials listed in the MPI Approved Products List (APL) are acceptable for use on this project.
- .2 Provide paint materials for paint systems from single manufacturer.
- .3 Only qualified products with E3 "Environmentally Friendly" rating are acceptable for use on this project.
- .4 Conform to latest MPI requirements for interior painting work including preparation and priming.
- .5 Materials (primers, paints, coatings, varnishes, stains, lacquers, fillers, thinners, solvents, etc.) in accordance with MPI Architectural Painting Specification Manual "Approved Product" listing.
- .6 Linseed oil, shellac, and turpentine: highest quality product from approved manufacturer listed in MPI Architectural Painting Specification Manual, compatible with other coating materials as required.
- .7 Paints, coatings, adhesives, solvents, cleaners, lubricants, and other fluids:
 - .1 Water-based Water soluble Water clean-up.
 - .2 non-flammable biodegradable.
 - .3 Manufactured without compounds which contribute to ozone depletion in the upper atmosphere.
 - .4 Manufactured without compounds which contribute to smog in the lower atmosphere.
 - .5 Do not contain methylene chloride, chlorinated hydrocarbons, toxic metal pigments.
- .8 Formulate and manufacture water-borne surface coatings with no aromatic solvents, formaldehyde, halogenated solvents, mercury, lead, cadmium, hexavalent chromium or their compounds.
- .9 Flash point: 61.0 degrees C or greater for water-borne surface coatings and recycled water-borne surface coatings.
- .10 Ensure manufacture and process of both water-borne surface coatings and recycled water-borne surface coatings does not release:
 - .1 Matter in undiluted production plant effluent generating 'Biochemical Oxygen Demand' (BOD) in excess of 15 mg/L to natural watercourse or sewage treatment facility lacking secondary treatment.

- .2 Total Suspended Solids (TSS) in undiluted production plant effluent in excess of 15 mg/L to natural watercourse or a sewage treatment facility lacking secondary treatment.
- .11 Water-borne paints and stains, recycled water-borne surface coatings and water borne varnishes to meet minimum "Environmentally Friendly" E2 rating.
- .12 Recycled water-borne surface coatings to contain 50 % post-consumer material by volume.
- .13 Recycled water-borne surface coatings must not contain:
 - .1 Lead in excess of 600.0 ppm weight/weight total solids.
 - .2 Mercury in excess of 50.0ppm weight/weight total product.
 - .3 Cadmium in excess of 1.0ppm weight/weight total product.
 - .4 Hexavalent chromium in excess of 3.0 ppm weight/weight total product.
 - .5 Organochlorines or polychlorinated biphenyls (PCBS) in excess of 1.0 ppm weight/weight total product.

2.2 COLOURS

- .1 Departmental Representative after Contract award, submit proposed Colour Schedule to Departmental Representative for review.
- .2 Colour schedule will be based upon selection of five base colours and three accent colours. No more than eight colours will be selected for entire project and no more than three colours will be selected in each area.
- .3 Selection of colours from manufacturers full range of colours.
- .4 Where specific products are available in restricted range of colours, selection based on limited range.
- .5 Second coat in three coat system to be tinted slightly lighter colour than top coat to show visible difference between coats.

2.3 MIXING AND TINTING

- .1 Perform colour tinting operations prior to delivery of paint to site. Obtain written approval from Departmental Representative for tinting of painting materials.
- .2 Mix paste, powder or catalyzed paint mixes in accordance with manufacturer's written instructions.
- .3 Use and add thinner in accordance with paint manufacturer's recommendations. Do not use kerosene or similar organic solvents to thin water-based paints.
- .4 Thin paint for spraying in accordance with paint manufacturer's instructions.
- .5 Re-mix paint in containers prior to and during application to ensure break-up of lumps, complete dispersion of settled pigment, and colour and gloss uniformity.

2.4 GLOSS/SHEEN RATINGS

- .1 Paint gloss is defined as sheen rating of applied paint, in accordance with following values:

	Gloss @ 60 degrees	Sheen @ 85 degrees
--	--------------------	--------------------

Gloss Level 1 - Matte Finish (flat)	Max. 5	Max. 10
Gloss Level 2 - Velvet-Like Finish	Max.10	10 to 35
Gloss Level 3 - Eggshell Finish	10 to 25	10 to 35
Gloss Level 4 - Satin-Like Finish	20 to 35	min. 35
Gloss Level 5 - Traditional Semi-Gloss Finish	35 to 70	
Gloss Level 6 - Traditional Gloss	70 to 85	
Gloss Level 7 - High Gloss Finish	More than 85	

- .2 Gloss level ratings of painted surfaces as indicated as noted on Finish Schedule.

2.5 INTERIOR PAINTING SYSTEMS

- .1 Concrete horizontal surfaces: floors and stairs:
- .1 INT 3.2C - Epoxy finish.
- .2 Concrete masonry units: smooth and split face block and brick:
- .1 INT 4.2A - Latex insert gloss level finish.
- .3 Structural steel and metal fabrications: columns, beams, joists:
- .1 INT 5.1A - Quick dry enamel gloss semi-gloss finish.
- .4 Dimension lumber: columns, beams, exposed joists, underside of decking:
- .1 INT 6.2A - Latex insert gloss level finish (over alkyd primer).
- .5 Dressed lumber: including doors, door and window frames, casings, mouldings:
- .1 INT 6.3A - High performance architectural latex insert gloss level finish.
- .6 Plaster and gypsum board: gypsum wallboard, drywall, "sheet rock type material", and textured finishes:
- .1 INT 9.2A - Latex insert gloss level finish (over latex sealer).

2.6 SOURCE QUALITY CONTROL

- .1 Perform following tests on each batch of consolidated post-consumer material before surface coating is reformulated and canned. Testing by laboratory or facility which has been accredited by Standards Council of Canada.
- .1 Lead, cadmium and chromium are to be determined using ICP-AES (Inductively Coupled Plasma - Atomic Emission Spectroscopy) technique no. 6010 as defined in EPA SW-846.
 - .2 Mercury is to be determined by Cold Vapour Atomic Absorption Spectroscopy using Technique no. 7471 as defined in EPA SW-846.
 - .3 Organochlorines and PCBs are to be determined by Gas Chromatography using Technique no. 8081 as defined in EPA SW-846.

Part 3 Execution

3.1 MANUFACTURER'S INSTRUCTIONS

- .1 Compliance: comply with manufacturer's written recommendations or specifications, including product technical bulletins, handling, storage and installation instructions, and data sheet.

3.2 GENERAL

- .1 Perform preparation and operations for interior painting in accordance with MPI Architectural Painting Specifications Manual except where specified otherwise.
- .2 Apply paint materials in accordance with paint manufacturer's written application instructions.

3.3 EXAMINATION

- .1 Investigate existing substrates for problems related to proper and complete preparation of surfaces to be painted. Report to Departmental Representative damages, defects, unsatisfactory or unfavourable conditions before proceeding with work.
- .2 Conduct moisture testing of surfaces to be painted using properly calibrated electronic moisture meter, except test concrete floors for moisture using simple "cover patch test". Do not proceed with work until conditions fall within acceptable range as recommended by manufacturer.
- .3 Maximum moisture content as follows:
 - .1 Stucco, plaster and gypsum board: 12%.
 - .2 Concrete: 12%.
 - .3 Clay and Concrete Block/Brick: 12%.
 - .4 Wood: 15%.

3.4 PREPARATION

- .1 Protection:
 - .1 Protect existing building surfaces and adjacent structures from paint spatters, markings and other damage by suitable non-staining covers or masking. If damaged, clean and restore surfaces as directed by Departmental Representative.
 - .2 Protect items that are permanently attached such as Fire Labels on doors and frames.
 - .3 Protect factory finished products and equipment.
 - .4 Protect passing pedestrians, building occupants and general public in and about the building.
- .2 Surface Preparation:
 - .1 Remove electrical cover plates, light fixtures, surface hardware on doors, bath accessories and other surface mounted equipment, fittings and fastenings prior to undertaking painting operations. Identify and store items in secure location and re-installed after painting is completed.

- .2 Move and cover furniture and portable equipment as necessary to carry out painting operations. Replace as painting operations progress.
- .3 Place "WET PAINT" signs in occupied areas as painting operations progress. Signs to approval of Departmental Representative.
- .3 Clean and prepare surfaces in accordance with MPI Architectural Painting Specification Manual requirements. Refer to MPI Manual in regard to specific requirements and as follows:
 - .1 Remove dust, dirt, and other surface debris by vacuuming, wiping with dry, clean cloths or compressed air.
 - .2 Wash surfaces with a biodegradable detergent and bleach where applicable and clean warm water using a stiff bristle brush to remove dirt, oil and other surface contaminants.
 - .3 Rinse scrubbed surfaces with clean water until foreign matter is flushed from surface.
 - .4 Allow surfaces to drain completely and allow to dry thoroughly.
 - .5 Prepare surfaces for water-based painting, water-based cleaners should be used in place of organic solvents.
 - .6 Use trigger operated spray nozzles for water hoses.
 - .7 Many water-based paints cannot be removed with water once dried. Minimize use of mineral spirits or organic solvents to clean up water-based paints.
- .4 Prevent contamination of cleaned surfaces by salts, acids, alkalis, other corrosive chemicals, grease, oil and solvents before prime coat is applied and between applications of remaining coats. Apply primer, paint, or pretreatment as soon as possible after cleaning and before deterioration occurs.
- .5 Where possible, prime non-exposed surfaces of new wood surfaces before installation. Use same primers as specified for exposed surfaces.
 - .1 Apply vinyl sealer to MPI #36 over knots, pitch, sap and resinous areas.
 - .2 Apply wood filler to nail holes and cracks.
 - .3 Tint filler to match stains for stained woodwork.
- .6 Sand and dust between coats as required to provide adequate adhesion for next coat and to remove defects visible from a distance up to 1000 mm.
- .7 Clean metal surfaces to be painted by removing rust, loose mill scale, welding slag, dirt, oil, grease and other foreign substances in accordance with MPI requirements. Remove traces of blast products from surfaces, pockets and corners to be painted by brushing with clean brushes blowing with clean dry compressed air vacuum cleaning.
- .8 Touch up of shop primers with primer as specified.
- .9 Do not apply paint until prepared surfaces have been accepted by Departmental Representative.

3.5 APPLICATION

- .1 Method of application to be as approved by Departmental Representative. Apply paint by brush roller air sprayer airless sprayer. Conform to manufacturer's application instructions unless specified otherwise.

- .2 Brush and Roller Application:
 - .1 Apply paint in uniform layer using brush and/or roller type suitable for application.
 - .2 Work paint into cracks, crevices and corners.
 - .3 Paint surfaces and corners not accessible to brush using spray, daubers and/or sheepskins. Paint surfaces and corners not accessible to roller using brush, daubers or sheepskins.
 - .4 Brush and/or roll out runs and sags, and over-lap marks. Rolled surfaces free of roller tracking and heavy stipple.
 - .5 Remove runs, sags and brush marks from finished work and repaint.
- .3 Spray application:
 - .1 Provide and maintain equipment that is suitable for intended purpose, capable of atomizing paint to be applied, and equipped with suitable pressure regulators and gauges.
 - .2 Keep paint ingredients properly mixed in containers during paint application either by continuous mechanical agitation or by intermittent agitation as frequently as necessary.
 - .3 Apply paint in uniform layer, with overlapping at edges of spray pattern. Back roll first coat application.
 - .4 Brush out immediately all runs and sags.
 - .5 Use brushes and rollers to work paint into cracks, crevices and places which are not adequately painted by spray.
- .4 Use dipping, sheepskins or daubers only when no other method is practical in places of difficult access.
- .5 Apply coats of paint continuous film of uniform thickness. Repaint thin spots or bare areas before next coat of paint is applied.
- .6 Allow surfaces to dry and properly cure after cleaning and between subsequent coats for minimum time period as recommended by manufacturer.
- .7 Sand and dust between coats to remove visible defects.
- .8 Finish surfaces both above and below sight lines as specified for surrounding surfaces, including such surfaces as tops of interior cupboards and cabinets and projecting ledges.
- .9 Finish inside of cupboards and cabinets as specified for outside surfaces.
- .10 Finish closets and alcoves as specified for adjoining rooms.
- .11 Finish top, bottom, edges and cutouts of doors after fitting as specified for door surfaces.

3.6 MECHANICAL/ELECTRICAL EQUIPMENT

- .1 Paint finished area exposed conduits, piping, hangers, ductwork and other mechanical and electrical equipment with colour and finish to match adjacent surfaces, except as indicated.
- .2 Boiler room, mechanical and electrical rooms: paint exposed conduits, piping, hangers, ductwork and other mechanical and electrical equipment.

- .3 Other unfinished areas: leave exposed conduits, piping, hangers, ductwork and other mechanical and electrical equipment in original finish and touch up scratches and marks.
- .4 Touch up scratches and marks on factory painted finishes and equipment with paint as supplied by manufacturer of equipment.
- .5 Do not paint over nameplates.
- .6 Keep sprinkler heads free of paint.
- .7 Paint inside of ductwork where visible behind grilles, registers and diffusers with primer and one coat of matt black paint.
- .8 Paint fire protection piping red.
- .9 Paint disconnect switches for fire alarm system and exit light systems in red enamel.
- .10 Paint natural gas piping yellow.
- .11 Paint both sides and edges of backboards for telephone and electrical equipment before installation. Leave equipment in original finish except for touch-up as required, and paint conduits, mounting accessories and other unfinished items.
- .12 Do not paint interior transformers and substation equipment.

3.7 SITE TOLERANCES

- .1 Walls: no defects visible from a distance of 1000 mm at 90 degrees to surface.
- .2 Ceilings: no defects visible from floor at 45 degrees to surface when viewed using final lighting source.
- .3 Final coat to exhibit uniformity of colour and uniformity of sheen across full surface area.

3.8 FIELD QUALITY CONTROL

- .1 Interior painting and decorating work shall be inspected by a Paint Inspection Agency (inspector) acceptable to the specifying authority and local Painting Contractor's Association. Painting contractor shall notify Paint Inspection Agency a minimum of one week prior to commencement of work and provide a copy of project painting specification, plans and elevation drawings (including pertinent details) as well as a Finish Schedule.
- .2 Interior surfaces requiring painting shall be inspected by Paint Inspection Agency who shall notify Departmental Representative and General Contractor in writing of defects or problems, prior to commencing painting work, or after prime coat shows defects in substrate.
- .3 Where "special" painting, coating or decorating system applications (i.e. elastomeric coatings) or non-MPI listed products or systems are to be used, paint or coating manufacturer shall provide as part of this work, certification of surfaces and conditions for specific paint or coating system application as well as on site supervision, inspection and approval of their paint or coating system application as required at no additional cost to Departmental Representative.
- .4 Standard of Acceptance:
 - .1 Walls: no defects visible from a distance of 1000 mm at 90 degrees to surface.

- .2 Ceilings: no defects visible from floor at 45 degrees degrees to surface when viewed using final lighting source.
- .3 Final coat to exhibit uniformity of colour and uniformity of sheen across full surface area.
- .5 Field inspection of painting operations to be carried out by independent inspection firm as designated by Departmental Representative.
- .6 Advise Departmental Representative when surfaces and applied coating is ready for inspection. Do not proceed with subsequent coats until previous coat has been approved.
- .7 Cooperate with inspection firm and provide access to areas of work.
- .8 Retain purchase orders, invoices and other documents to prove conformance with noted MPI requirements when requested by Departmental Representative.

3.9 RESTORATION

- .1 Clean and re-install hardware items removed before undertaken painting operations.
- .2 Remove protective coverings and warning signs as soon as practical after operations cease.
- .3 Remove paint splashings on exposed surfaces that were not painted. Remove smears and spatter immediately as operations progress, using compatible solvent.
- .4 Protect freshly completed surfaces from paint droppings and dust to approval of Departmental Representative. Avoid scuffing newly applied paint.
- .5 Restore areas used for storage, cleaning, mixing and handling of paint to clean condition as approved by Departmental Representative.

END OF SECTION