



Project Title: East Ramp Rehabilitation
Building 88
Central Experimental Farm (CEF), Ottawa (Ontario)

Solicitation No: 13-1308

November 26, 2013

The following changes in the tender documents are effective immediately. This addendum will form part of the contract documents

Q & A

Q1. Can you give precisions on removal and disposal of temporary shoring?

A1. Remove and appropriately dispose of all existing temporary shoring off site as per Specification Section 02 41 19, Selective Structure Demolition.

Q2. Can you give precisions on sodding and landscape materials?

A2. Reinstate to original, all sodding and other landscape materials damaged during the work as per Specification Section 31 23 10, Excavation, Trenching and Backfill, Part 2.01.3.

Q3. Asphalt is not available at this time of year, how should we proceed?

A3. The requirement for asphalt surfacing of the new ramp as shown on drawing S-00 is being removed. Therefore, asphalt surfacing will not be part of this requirement. Provide compacted granular sub-base for future asphalt as per Specification Section 32 12 17, Asphalt Paving, placed flush with adjacent finishes at each end. Provide level even surface to granular material and slope to suit ramp. Provide straight clean saw cut at transition between asphalt to remain and new granular base.

Q4. Can you confirm if the fence shown at drawing S-00 is part of the specifications?

A4. The requirements for temporary construction fence to guide pedestrian access on the North side of the building, as indicated on drawing S-00 are modified to maintain the requirement for construction fencing around the work area. Construction access from the parking lot north of the work area will be allowed and also the removal of the AAFC fencing as required to access the work area. Reinstate AAFC fencing to match existing, upon completion of the work.

Q5. In reference to Section 4 of drawing S-02, is a footing required?

A5. As per Section 4 of drawing S-02, no footing is required under the curb.

Q6. Can you confirm if concrete foundation and walls are to be included in this contract? If applicable, can you confirm the elevations of the walls and length of the elevation of walls?

A6. Yes, concrete walls are included in the work. Dimensions and elevations are to be obtained on site and the intention is to recreate the existing appearance, length and elevations.

Q7. Can you provide the length of new curved concrete ramp walls?

A7. The contractor is to match existing as advised. The Contractor is to take site measurements and recreate existing extents, elevations etc.

Q8. At drawing S-02, what is the thickness of the wall in Section 2?

A8. The wall is approximately 900mm thick.



Project Title: East Ramp Rehabilitation
Building 88
Central Experimental Farm (CEF), Ottawa (Ontario)

Solicitation No: 13-1308

November 26, 2013

Q9. At drawing S-02, there is a reference to a geotechnical report, will it be provided?

A9. This report is being provided as part of this addendum.

INVITATION TO TENDER

1. At Appendix 1 “Combined Price Form”, Item 4:

Delete: in-site

Insert: in-situ

SPECIFICATIONS

1. At Division 01, Section 01 35 30 “Health and Safety Requirements”, article 1.4.2:

Delete: Ground areas below area of work on the roof must be fenced off to keep all pedestrian traffic a minimum of 4.5m from building.

Replace with: Ground areas must be fenced off to keep all pedestrian traffic a minimum of 4.5m from building.

2. At Division 32, Section 32 12 17 “Asphalt Paving”:

Delete the following Articles in their entirety: 2.01.2
2.01.3
2.01.4
3.01.5
3.01.6
3.03
3.04

3. At the Table of Contents:

Add: Annex 1 – Frost Protection for Footings

DRAWINGS

1. At Drawing S-04 “Sections”:

Replace the originally provided copy of the drawing with the revised copy that includes the picture.

ALL OTHER TERMS AND CONDITIONS REMAIN THE SAME