

## **1 GENERAL**

### **1.1 ACCESS AND EGRESS**

- .1 Design, construct and maintain temporary "access to" and "egress from" work areas, including stairs, runways, ramps or ladders and scaffolding, independent of finished surfaces and in accordance with relevant municipal, provincial and other regulations.

### **1.2 USE OF SITE AND FACILITIES**

- .1 Execute work with least possible interference or disturbance to normal use of premises. Make arrangements with Ministerial Representative to facilitate work as stated.
- .2 Maintain existing services to building and provide for personnel and vehicle access.
- .3 Where security is reduced by work provide temporary means to maintain security.
- .4 Ministerial Representative will assign sanitary facilities for use by Contractor's personnel. Keep facilities clean.
  - .1 Use only elevators, dumbwaiters, existing in building for moving workers and material.
  - .2 Protect walls of passenger elevators, to approval of Ministerial Representative prior to use.
  - .2 Accept liability for damage, safety of equipment and overloading of existing equipment.
- .6 Closures: protect work temporarily until permanent enclosures are completed.

### **1.3 ALTERATIONS, ADDITIONS OR REPAIRS TO EXISTING BUILDING**

- .1 Execute work with least possible interference or disturbance to building operations occupants, public and normal use of premises. Arrange with Ministerial Representative to facilitate execution of work.

### **1.4 EXISTING SERVICES**

- .1 Notify, Ministerial Representative and utility companies of intended interruption of services and obtain required permission.
- .2 Where Work involves breaking into or connecting to existing services, give Ministerial Representative 48hours of notice for necessary interruption of mechanical or electrical service throughout course of work. Keep duration of interruptions minimum. Carry out interruptions after normal working hours of occupants, preferably on weekends.
- .3 Provide for personnel, pedestrian and vehicular traffic.
- .4 Construct barriers in accordance with Section 01 56 00 - Temporary Barriers and Enclosures.

### **1.5 SPECIAL REQUIREMENTS**

- .1 Paint and carpet public or Ministerial Representative occupied areas Monday to Friday from 20:00 to 05:00hours only and on Saturdays, Sundays, and statutory holidays.
- .2 The works of certain indicated zones where evenings / night works will be made, must be cleaned and restorations for the use of the staff during day.

- .3 For the works to be executed in the restrooms of the 2nd and 3rd floor, the Contractor has to preserve a restroom always operational for the men and women Therefore, the works cannot be executed at the same moment for these two zones
- .4 Carry out noise generating Work Monday to Friday from 20:00 to 05:00 hours and on Saturdays, Sundays, and statutory holidays.
- .5 Submit schedule in accordance with Section 01 32 16.06 - Construction Progress Schedule - Critical Path Method (CPM)] 01 32 16.07 - Construction Progress Schedule - Bar (GANTT) Chart.
- .6 Ensure Contractor's personnel employed on site become familiar with and obey regulations including safety, fire, traffic and security regulations.
- .7 Keep within limits of work and avenues of ingress and egress.
- .8 Ingress and egress of Contractor vehicles at site is limited by Ministerial Representative.
- .9 Deliver materials outside of peak traffic unless otherwise approved by Ministerial Representative.

## **1.6 SECURITY**

- .1 Where security has been reduced by Work of Contract, provide temporary means to maintain security.
- .2 Security clearances:
  - .1 Personnel employed on this project will be subject to security check. Obtain clearance, as instructed, for each individual who will require to enter premises.
  - .2 Obtain requisite clearance, as instructed, for each individual required to enter premises.
  - .3 Personnel will be checked daily at start of work shift and provided with pass which must be worn at all times. Pass must be returned at end of work shift and personnel checked out.
  - .4 Contractor's personnel will require satisfactory RCMP initiated security screening in order to complete Work in premises and on site.

## **1.7 BUILDING SMOKING ENVIRONMENT**

- .1 Comply with smoking restrictions. Smoking is not permitted.

## **2 PRODUCTS**

### **2.1 NOT USED**

- .1 Not Used.

## **3 EXECUTION**

### **3.1 NOT USED**

- .1 Not Used.

**END OF SECTION**