

RETURN BIDS TO:
RETOURNER LES SOUMISSIONS À:
Public Works and Government Services Canada
Telus Plaza North/Plaza Telus Nord
10025 Jasper Ave./10025 ave. Jaspe
5th floor/5e étage
Edmonton
Alberta
T5J 1S6
Bid Fax: (780) 497-3510

SOLICITATION AMENDMENT
MODIFICATION DE L'INVITATION

The referenced document is hereby revised; unless otherwise indicated, all other terms and conditions of the Solicitation remain the same.

Ce document est par la présente révisé; sauf indication contraire, les modalités de l'invitation demeurent les mêmes.

Comments - Commentaires

Vendor/Firm Name and Address
Raison sociale et adresse du
fournisseur/de l'entrepreneur

Issuing Office - Bureau de distribution
Public Works and Government Services Canada
Telus Plaza North/Plaza Telus Nord
10025 Jasper Ave./10025 ave. Jasper
5th floor/5e étage
Edmonton
Alberta
T5J 1S6

Title - Sujet Video Monitoring System	
Solicitation No. - N° de l'invitation 47780-146527/A	Amendment No. - N° modif. 001
Client Reference No. - N° de référence du client CBSA	Date 2013-12-11
GETS Reference No. - N° de référence de SEAG PW-\$EDM-023-9998	
File No. - N° de dossier EDM-3-36155 (023)	CCC No./N° CCC - FMS No./N° VME
Solicitation Closes - L'invitation prend fin at - à 02:00 PM on - le 2013-12-18	Time Zone Fuseau horaire Mountain Standard Time MST
F.O.B. - F.A.B. Plant-Usine: <input type="checkbox"/> Destination: <input checked="" type="checkbox"/> Other-Autre: <input type="checkbox"/>	
Address Enquiries to: - Adresser toutes questions à: Taylor, Ian	Buyer Id - Id de l'acheteur edm023
Telephone No. - N° de téléphone (780) 497-3621 ()	FAX No. - N° de FAX (780) 497-3510
Destination - of Goods, Services, and Construction: Destination - des biens, services et construction:	

Instructions: See Herein

Instructions: Voir aux présentes

Delivery Required - Livraison exigée	Delivery Offered - Livraison proposée
Vendor/Firm Name and Address Raison sociale et adresse du fournisseur/de l'entrepreneur	
Telephone No. - N° de téléphone Facsimile No. - N° de télécopieur	
Name and title of person authorized to sign on behalf of Vendor/Firm (type or print) Nom et titre de la personne autorisée à signer au nom du fournisseur/ de l'entrepreneur (taper ou écrire en caractères d'imprimerie)	
Signature	Date

This solicitation amendment has been raised to answer questions asked by potential bidders during the tendering period.

Site visit Comments and Question.

Comments:

- Camera #27 identified on the plans has been moved and is now located above the rear door.
- In the wet cells, the camera is to be above the toilet. No masking is allowed. Camera may only view the knees.
 - Contractor will have to drill through the chase wall. Must avoid any services (i.e. plumbing, wiring, etc) within wall.
- Site access to complete work will be Monday through Friday, 7:00am until 5:00pm MST.
- The audio recorder in the interview room is to be desk mounted.
- The Contractor will be responsible for the installation and setup of the software.
- The commissioning will include all the camera views.

Questions:

Answers:

1. Who will be responsible for the 'FIBRE' connections between the switches and the CCTV Room identified in Section 3 - Distribution Diagram?
 - i. There was an error in the Distribution Diagram and there is no fiber in this project. All cabling is Category 6 UTP cable. The Parkade switch and Floor 1 switch identified in the Diagram are actually laptops. Each Camera/monitor in the Parkade and Floor 1 is cabled back to the 1st Floor LAN Room where the cables are terminated into a patch panel in the CCTV 2-Post Rack. Each Camera/monitor on the 2nd Floor is cabled back to the 2nd Floor main CCTV Room where the cables are terminated into a patch panel in the CCTV 4-Post Rack. There are six CAT6 cables running between the 2nd Floor CCTV 4-Post Rack and the 1st Floor CCTV 2 Post Rack located in the 1st Floor LAN Room. These copper cables will act as your backbone between the main CCTV equipment on the 2nd Floor and the 1st Floor switches.
 - ii. The diagram in Section 3 will not be updated.
2. How firm is the completion date of January 31, 2014?
 - i. CBSA is willing to extend the completion date to February 15, 2014, but no further. All work must be completed by February 15, 2014.
3. Who will be responsible for the setup of the I.P. structure (i.e. Gateway, subnet mask, etc)?
 - i. The successful CCTV contractor is responsible for the setup of the I.P. structure.
4. Will the switches be bridged to another network or are they stand-alone?
 - i. The switches are stand-alone.

Solicitation No. - N° de l'invitation

47780-146527/A

Client Ref. No. - N° de réf. du client

CBSA

Amd. No. - N° de la modif.

001

File No. - N° du dossier

EDM-3-36155

Buyer ID - Id de l'acheteur

edm023

CCC No./N° CCC - FMS No/ N° VME

The following is a list of the attendees present at the Mandatory Site Visit:

COMPANY NAME	REPRESENTATIVE NAME
Anixter	Richard Toppmann
Contava	Alex Edlund
Delco Security	Mark Peterson
Genesis Integration	Cliff Ziegler
Johnson Controls	Andrew Coates
LJ Audio & Visual	Steve Kondrat
Siemens	Robert Creaser
Stanley Security Solutions	Laura Hyshka
Stanley Security Solutions	Keith Colby

If the answers affect your bid, you must forward an updated copy of your offer to the Bid Receiving Unit by closing date and time indicated on the front of the solicitation document.

If you have any further questions please forward them to the Contracting Authority in accordance with Part 2 - Bidder Instructions, Section 3 - Enquiries - Bid Solicitation contained within the solicitation document.

All other terms and conditions of the Request For Proposal remain unchanged.