



**Addendum / Addenda**

No./N<sup>o</sup>  
2

Project Description / Description de projet <b>M-4 Autoclave Replacement</b>		
Solicitation No./ No de sollicitation <b>13-22086</b>	Project No./N <sup>o</sup> de projet <b>M-4-3865</b>	W.O. No./N <sup>o</sup> d'ordre de travail <b>A1-000083-01-02</b>
Departmental Representative / représentant ministériel <b>Chris Day</b>		Date <b>December 12, 2013</b>
<p><b>Notice:</b> This addendum shall form part of the tender documents and all conditions shall apply and be read in conjunction with the original plans and specifications.</p>		<p><b>Nota:</b> Cet addenda fait partie intégrale des dossiers d'appel d'offres; toutes les conditions énoncées doivent être lues et appliquées en conjonction avec les plans et les devis originaux.</p>

Mechanical :

1. Clarification to Note 6 on Drawing 3865-M01 : There are three existing cooling tower water pipes to be demolished, two 1 1/4" cooling tower water return, one 1 1/4 " cooling tower water supply. The 2" main cooling tower water pipes enters the building almost directly under the riser. The length of pipe in the basement is approximately 15'. The shut-off valves are located in the service tunnel outside of the building.
2. The building crane has a certified capacity of 20,000 lbs. The existing autoclave weighs 16,800 lbs. The new autoclave weighs 13,000 lbs.