



PROPOSED	EXISTING
--- LIMIT OF CONTRACT	---
--- EDGE OF ROAD	---
--- STORM SEWER	---
--- SANITARY SEWER	---
--- DOMESTIC WATER	---
--- FIRE PROTECTION	---
--- FENCE	---
○ FH	○ M.H.
○ CS	○ PP
○ PP	○ V
○ V	○ PIV
○ PIV	○ CB
○ CB	○ CB
ASPHALT	ASPHALT
SIDEWALK/CONC. PAD	SIDEWALK/CONC. PAD

GENERAL NOTES

- DIMENSIONS ARE IN METRIC UNITS UNLESS NOTED OTHERWISE.
- ELEVATIONS ARE REFERENCED FROM A BENCHMARK CONTROL NB MON 3705.
- THE DEPARTMENTAL REPRESENTATIVE, BELL-AJANT, NB POWER AND ENDSIDE GAS NB SHALL BE COORDINATED PRIOR TO THE START OF CONSTRUCTION TO COORDINATE FIELD LOCATES OF SERVICES BEFORE STARTING CONSTRUCTION.
- FIELD SURVEY INFORMATION PROVIDED TO CBCL LIMITED BY OTHERS. THE SURVEY IS DATED MARCH 2013.
- GAS MAIN LOCATE IS REQUIRED BY LAW BEFORE WORK BEGINS. GAS MAIN MUST BE DAYLIGHTED WHEN EXCAVATING WITHIN 1.0m OF LOCATE.
- ALL EXISTING INVERTS TO BE CONFIRMED PRIOR TO PIPE LAYING.
- ALL CUT/FILL SLOPES TO BE MAX 3H : 1V AND STABILIZED WITH 150mm TOPSOIL, SEED AND STRAW MULCH UNLESS OTHERWISE INDICATED.
- REINSTATE DISTURBED SURFACES WITH MATERIALS AND THICKNESSES TO MATCH EXISTING.

ABBREVIATIONS

FA	FINISHED ASPHALT	INV	INVERT
FG	FINISHED GRADE	CB	CATCH BASIN
FFA	FINISHED FLOOR ELEVATION	BTM	BOTTOM OF SUMP
EX	EXISTING	EL	ELEVATION
MH	MANHOLE	POC	POINT OF CONNECTION
ID	INSIDE DIAMETER	PV	POST INDICATOR VALVE



revisions	description	date
4	ISSUED FOR TENDER	NOV. 28 2013
3	ISSUED FOR 99% SUBMISSION	NOV. 1 2013
2	ISSUED FOR 90% SUBMISSION	SEP. 21 2013
1	ISSUED FOR 50% SUBMISSION	AUG. 30 2013

NEW FOOD SERVICES BUILDING WESTMORLAND INSTITUTION

DORCHESTER, NB

SITE GRADING PLAN AND DETAILS

designed	BST	conçu	
date	2013/09/20		
drawn	BST	dessiné	
date	2013/09/20		
approved	BST	approuvé	
date	2013/11/29		
drawn	Ram. Col	dessiné	13.12.10
project number	R.061828.001	no. du projet	
drawing no.	C3.0	no. du dessin	