

---

**ADDENDUM NUMBER: SEPW No. TWO**

**PROJECT: WINDOW REPLACEMENT  
REGINA, SK**

---

This Addendum forms part of the Contract Documents and amends the original Drawings and Specifications as noted below. This addendum consists of **2** pages and **0** drawings as noted below.

Ensure that all parties are aware of all items included in this Addendum.

**The following revised or additional Drawings accompany and form an integral part of this Addendum:**

<b>Dwg. No.</b>	<b>Title</b>	<b>Date of Issue</b>
N/A	N/A	N/A

**A2-1 SPECIFICATION SECTION 01 35 29 HEALTH AND SAFETY REQUIREMENTS**

- .1 Item 1.10 ADD Sentence .5 as follows: “The locations of known hazardous materials has been identified in the assessment appended to the Section. This has been provided so that those working in the areas are aware of the materials. It is not the intent to include abatement of the asbestos as part of this Work. Where asbestos presents a hazard to workers they shall stop work in that area and identify this situation to the Departmental Representative. The Departmental Representative will be responsible for the removal of the hazardous materials where they present a hazard.”

**A2-2 SPECIFICATION SECTION 01 56 00 TEMPORARY BARRIERS AND ENCLOSURES**

- .1 Item 1.4 ADD Sentence .5 as follows: “There will be heating provided within the building by the existing mechanical system. The Contractor shall take care and precautions to avoid leaving openings unprotected for any longer than necessary. Where required the Contractor shall provide and pay for supplemental heating to avoid freezing pipes or damage to the interior or discomfort to occupant within occupied areas of the building.”

**A2-3 SPECIFICATION SECTION 08 54 13 FIBERGLASS WINDOWS**

- .1 Item 2.1.4.5.2 CHANGE to read, “high performance soft coat low e”.
- .2 Item 2.1.4.7 CHANGE to read, “high performance warm edge spacer, black colour”.
- .3 Item 2.1.4. CLARIFICATION: argon filled cavities were deleted in SEPW Addendum No. 1; upon award, the window manufacturer will be required to provide performance information showing both argon filled cavity and comparable non-argon cavity. The performance called up in the specification is for argon filled cavities.”

**A2-4 REF. DRAWING A3.0 WINDOW DETAILS, EXISTING WINDOW DEMO DETAILS**

.1 Reference ALL DETAILS

- .1 CLARIFICATION: location where painting of walls to match existing is called up on details; it shall apply to the entire wall surface up to column buildouts on first level and for entire wall on second, third and fourth levels.
- .2 CLARIFICATION: Paint inside of recesses at all windows on the first and second floors where affected by this Work. Unless damaged or marred by work associated with removals and installation of new windows, all existing bulkheads shall remain as is. Where damage occurs on the first or second floors, then repaint the entire underside of the bulkhead to match existing.
- .3 CLARIFICATION: As part of a separate project the bulkheads on the upper two floors will be removed. The timing of when that work will take place is not known at this time. The successful contractor will need to cooperate with the contractor doing other interior renovations during the course of the window replacement work.

**A2-5 REF. DRAWING A3.0 WINDOW DETAILS, EXISTING WINDOW DEMO DETAILS**

.1 Reference DETAIL 1

- .1 CHANGE: note regarding removal and replacement of existing cabinet top to read, "Remove and dispose of existing cabinet top as required (3<sup>rd</sup> and 4<sup>th</sup> floors). These do not need to be reinstalled. "

.2 Reference DETAIL 4

- .1 CHANGE: note regarding removal and reinstallation of blinds to read, "Remove for salvage all horizontal louvre (Venetian) blinds. Inspect each blind and document condition prior to removal. Wrap to protect blinds following removal. Store in location as directed by Departmental Representative. Provide documentation to Departmental Representative. Reinstall blinds on first and second floors. Repair blinds where damage has occurred due to this Work. (Departmental Representative will provide specification on blind manufacturer and colour at that time.) Existing damage (documented) does not have to be repaired. Hand over salvaged blinds from third and fourth floors upon request by the Departmental Representative. "

**END OF SECTION**