



Do not scale drawings.
Verify all dimensions and conditions on site and immediately notify the Departmental Representative of all discrepancies.

This drawing has been prepared for the use of AECOM's client and may not be used, reproduced or relied upon by third parties, except as agreed by AECOM and its client, as required by law or for use by governmental reviewing agencies. AECOM accepts no responsibility, and denies any liability whatsoever, to any party that modifies this drawing without AECOM's express written consent.

Do not scale this document. All measurements must be obtained from stated dimensions.

DEMOLITION PLAN

drawn by
dessine par

designed by	PL
conc par	

approved by approuvé par	PI
-----------------------------	----

bid	project manager
offre	administrateur de projets

project date date du projet	2013-10-29
--------------------------------	------------

project no.
no. du projet

R.033225.001

drawing no.
dessine no.
WDR-WW03-A-04

AECOM PROJECT No.: 60163582

1. REMOVE ALL FLOOR FINISHES AS SHOWN TO CONCRETE SUBSTRATE
2. MAKE GOOD CONCRETE SUBSTRATE AS REQUIRED

3. DEMOLITION CONTRACTOR TO COORDINATE WITH ALL REQUIREMENTS OF THE DESIGNATED SUBSTANCES AND HAZARDOUS MATERIAL SURVEY- REFER TO DESIGNATED SUBSTANCES AND HAZARDOUS MATERIALS SURVEYS IN ANNEX A

① CARPET FLOORING TO BE REMOVED

② VINYL TILE FLOORING TO BE REMOVED. PREPARE SUBSTRATE TO RECEIVE NEW FLOORING. ALL VINYL FLOOR AND MASTIC IS CONSIDERED TO BE ASBESTOS CONTAINING. REFER TO DESIGNATED SUBSTANCE AND HAZARDOUS MATERIALS SURVEYS IN ANNEX A.

③ VINYL SHEET FLOORING TO BE REMOVED. PREPARE SUBSTRATE TO RECEIVE NEW FLOORING

④ CERAMIC FLOORING TO BE REMOVED

⑤ SEALED CONCRETE TO REMAIN

⑥ TERRAZZO TILE FLOORING TO REMAIN

⑦ VINYL TILE FLOORING TO BE REMOVED. PREPARE SUBSTRATE TO RECEIVE NEW FLOORING

1 BUILDING 3- FIRST FLOOR FINISHES DEMOLITION PLAN
A-01 1.75