



RECEIVED
Project #: R.033225.001
DATE: 2013.09.09
Tender Review
PRR Control #: 13-09-148
The review of these drawings and/or specifications by PWGSC does not relieve the designer of the responsibility for accuracy, correctness and compliance with National Codes and other applicable codes and standards.
PWGSC - A&E Resources
Professional & Technical Programs



| | | |
|----------|------------------------------|------------|
| 04 | ISSUED FOR TENDER | 2013/09/03 |
| 03 | ISSUED FOR 100% OWNER REVIEW | 2013/07/25 |
| 02 | SUBMITTED FOR 99% DESIGN | 2011/07/18 |
| 01 | ISSUED FOR REVIEW | 2011/02/15 |
| revision | | date |

Do not scale drawings. Verify all dimensions and conditions on site and immediately notify the Departmental Representative of all discrepancies.



This drawing has been prepared for the use of AECOM's client and may not be used, reproduced or relied upon by third parties, except as agreed by AECOM and its client, as required by law or for use by governmental reviewing agencies. AECOM accepts no responsibility, and denies any liability whatsoever, to any party that modifies this drawing without AECOM's express written consent. Do not scale this document. All measurements must be obtained from stated dimensions.

project title
titre du projet
WARKWORTH Ontario
MEDIUM SECURITY INSTITUTION
UNDERGROUND DUCT REPLACEMENT

drawing title
titre du dessin
BLDG. WW03
1ST FLOOR PLAN
HVAC-HYDRONIC PIPING

drawn by
dessiné par L. TAURO

designed by
conçu par A. KABBANI

approved by
approuvé par D. DOVAS

bid
offre O. TABAREZ project manager
administrateur
de projets

project date
date du projet 2013-07-25

project no.
no. du projet R.033225.001

drawing no.
dessiné no. WDR-WW03-H-03

| ROOM INDEX | | | |
|------------|-------------------|------|-------------------|
| 101 | FOYER | 109 | JANITOR'S CLOSET |
| 102 | INMATE WAITING RM | 110 | OFFICE |
| 103 | LAVATORY | 110A | ELECTRICAL CLOSET |
| 104 | LAVATORY | 111 | BOARDROOM |
| 105 | LAN ROOM | 112 | OFFICE |
| 106 | OFFICE | 113 | OFFICE |
| 107 | OFFICE | 114 | OFFICE |
| 108 | OFFICE | 115 | OFFICE |
| | | 116 | OFFICE |
| | | 117 | OFFICE |
| | | 118 | OFFICE |
| | | 119 | OFFICE |
| | | 120 | LAVATORY |
| | | 121 | GENERAL OFFICE |
| | | 122 | BOARDROOM |
| | | 123 | OFFICE |
| | | 124 | FOYER |
| | | 125 | OFFICE |
| | | 126 | WOMEN'S W/R |
| | | 127 | LOUNGE |
| | | 128 | OFFICE |
| | | 129 | INTERVIEW ROOM |
| | | 130 | MECHANICAL ROOM |
| | | 131 | CORRIDOR |
| | | 132 | COFFEE |
| | | 133 | COFFEE |
| | | 134 | MEN'S W/R |
| | | 135 | BOARDROOM |
| | | 136 | OFFICE |
| | | 137 | OFFICE |
| | | 138 | OFFICE |

- GENERAL NOTES:**
- ALL INDICATED PIPE SIZES ARE I.D.
 - SLOPE HORIZONTAL PIPING MAINS TO PROVIDE A MINIMUM CONTINUOUS UPGRADE OF 25MM IN 6M TO HIGH POINTS. SLOPE BRANCH SUPPLY AND RETURN PIPING CONNECTIONS TO EQUIPMENT AT A MINIMUM OF 25MM IN 1.2M. LEAVE SUFFICIENT ROOM AT HIGH POINTS FOR INSTALLATION OF AIR VENTS.
 - PROVIDE PIPING EXPANSION JOINTS. PIPING ALIGNMENT GUIDES & PIPE ANCHORS AS SPECIFIED.
 - CONTRACTOR TO MOUNT HEAT EXCHANGER (HEX-1) ON FLOOR OR WALL.

5. ASBESTOS CONTAINING PLASTER FITTINGS LOCATED IN ROOM 130. REFER TO DESIGNATED SUBSTANCES AND HAZARDOUS MATERIALS SURVEYS IN ANNEX A.