

---

**ADDENDUM NUMBER: SEPW No. THREE**  
**PROJECT: WINDOW REPLACEMENT**  
**REGINA, SK**

---

This Addendum forms part of the Contract Documents and amends the original Drawings and Specifications as noted below. This addendum consists of 1 page and 0 drawings as noted below.

Ensure that all parties are aware of all items included in this Addendum.

**The following revised or additional Drawings accompany and form an integral part of this Addendum:**

Dwg. No.	Title	Date of Issue
N/A	N/A	N/A

**A3-1 GENERAL QUESTION**

- .1 A question has been raised by one of the Bidders as to whether the existing wood post between windows is a structural component of the wall. Similarly the question was asked as to whether the post in the new windows is structural.

Response: Based on the construction of the building, steel frame with masonry infill, there is no reason to believe the existing post is a structural component of the wall. The new window is to fit into the approximately 1800 x 1800 opening following the removal of the existing wood window assembly with a deflection gap at the head. The post between windows is part of the window assembly and is not to carry any building load.

**A3-2 SPECIFICATION SECTION 08 54 13 FIBERGLASS WINDOWS**

- .1 Item 1.2.6.1 CHANGE to read, "Total system maximum U value of .18".
- .2 Item 2.1.6 CHANGE to read, "Interior jambs/sills: provide jamb extensions on interior as indicated and to suit conditions. Material to be 19mm select flat sliced, white birch plywood, stain grade (to match sill).

**A3-3 REF. DRAWING A3.0 WINDOW DETAILS, EXISTING WINDOW DEMO DETAILS**

- .1 Reference DETAIL 8 AND 9
- .1 CHANGE: Carry stool (sill) plywood continuous without joint into receiver on frame.

**END OF SECTION**