



NCR, Materiel Management
200 Kent Street, Station 9W088
Ottawa, Ontario
K1A 0E6

FP802-130356

January 28, 2014

**Subject: REQUEST FOR Quotations: FP802-130356
 Matane-Construction and Installation of floating docks**

ADDENDUM NO. 3

Further to the above mentioned Request for Quotations, Addendum (#3) is to advise potential bidders of the question(s) received during this tender call to date. Both the question(s) and the response(s) are indicated below:

Question 1:

For concrete blocks anchor, are prefab blocks accepted? (or cast in place block mandatory?)

Answer 1:

Prefab blocks are accepted

Question 2:

Does hot dip galvanization have to be executed after blasting? This raise cost of components. Is it mandatory for all steel components?

Answer 2:

Yes

Question 3:

In section 06 03 00 Wood Embankment, it is indicated that the tip of wood pieces exposed to salt water shall be covered with a prong mending plate. Is it the same for floating docks? Is crib considered as exposed to salt water?

Answer 3:

Only end of wooden pieces facing water. Not required for floating docks

Question 4:

Wood supplier said that wood cannot be cut on site because CCA preservative is not available? How bracing or other wood pieces with angles cut be fitted?

Answer 4:

Wood could be adjusted on site and fresh cut shall be protected with 3 layers of an equivalent preservative product.



Fisheries and Oceans
Canada

Pêches et Océans
Canada

All other Terms and Conditions for this requirement remain unchanged.

Yours truly,

Patrizia Marinelli

A/Manager, Contracting Officer,

NCR Materiel Management, Materiel and Procurement Services