

Part 1 General

1.1 TAXES

- .1 Pay all taxes properly levied by law (including Federal, Provincial and Municipal).

1.2 FEES, PERMITS and CERTIFICATES

- .1 Pay all fees and obtain all permits. Provide authorities with plans and information for acceptance certificates. Provide inspection certificates as evidence that work conforms to requirements of Authority having jurisdiction.

1.3 CONSTRUCTION PROGRESS SCHEDULE

- .1 On award of contract submit bar chart construction schedule for work, indicating anticipated progress stages within time of completion. When the Departmental Representative has reviewed schedule, take necessary measures to complete work within scheduled time. Do not change schedule without notifying Departmental Representative.
- .2 Carry out work during "regular hour", Monday to Friday from 07:00 to 18:00 hours and on Saturdays, Sundays and statutory holidays.
- .3 Carry out interior painting in occupied areas during "off hours", Monday to Friday from 18:00 to 07:00 hours and on Saturdays, Sundays, and statutory holidays. Thoroughly ventilate areas painted during "off hours".
- .4 Carry out noise generating work during "off hours" Monday to Friday from 18:00 to 07:00 hours and on Saturdays, Sundays, and statutory holidays.
- .5 Give the Departmental Representative 48 hours notice for work to be carried out during "off hours".

1.4 REGULATORY REQUIREMENTS

- .1 References and Codes:
 - .1 Materials shall be new and work shall conform to the minimum applicable standards of the "References" indicated in the specification sections, the National Building Code of Canada 2010 (NBC) and all applicable Provincial and Municipal codes. In the case of conflict or discrepancy the most stringent requirement shall apply.
- .2 Building Smoking Environment:
 - .1 Smoking is not permitted in the Building. Obey smoking restrictions on building property.
- .3 Hazardous Material Discovery:

- .1 Stop work immediately when material resembling spray or trowel-applied asbestos, Polychlorinated Biphenyl (PCB), mould or other designated substance is encountered during demolition work.
 - .1 Take preventative measure and promptly notify Departmental Representative.
 - .2 Do not proceed until written instructions have been received from Departmental Representative.

1.5 FIRE SAFETY REQUIREMENTS

- .1 Comply with both the National Building Code of Canada 2010 and the National Fire Code of Canada 2010 for safety of persons in buildings in the event of a fire and the protection of buildings from the effects of fire, as follows;
 - .1 The National Building Code (NBC): for fire safety and fire protection features that are required to be incorporated in a building during construction.
 - .2 The National Fire Code (NFC):
 - .1 The on-going maintenance and use of the fire safety and fire protection features incorporated in buildings.
 - .2 The conduct of activities that might cause fire hazards in and around buildings.
 - .3 Limitations on hazardous contents in and around buildings.
 - .4 The establishment of fire safety plans.
 - .5 Fire safety at construction and demolition sites.
- .2 Comply with Human Resources and Skills Development Canada (HRSDC), Fire Commissioner of Canada Standards:
 - .1 Retain all fire safety documents and standards on site.
- .3 Welding and cutting:
 - .1 Before welding, soldering, grinding and/or cutting work, obtain a permit from the Real property Service Provider as directed by the Departmental Representative. Store flammable liquids in approved CSA containers. No open flame shall be used unless authorized by the Real property Service Provider
 - .2 At least 48 hours prior to commencing cutting, welding or soldering procedure, provide to Departmental Representative:
 - .1 Notice of intent, indicating devices affected, time and duration of isolation or bypass.
 - .2 Completed welding permit.
 - .3 Return welding permit to Departmental Representative immediately upon completion of procedures for which permit was issued.

- .3 Comply with NFC5.2.3.1(2) when welding or cutting operations are carried out in areas where combustible materials within 15m may be ignited by conduction or radiation.
- .4 Where work requires interruption or cause activation of fire alarms or fire suppression, extinguishing or protection systems:
 - .1 Provide "Watchman Service" as described in NFC 2010; In general, watchman service is defined as an individual conversant with "Fire Emergency Procedures", performing fire picket duty within an unprotected and unoccupied (no workers) area once per hour.
 - .2 Retain services of manufacturer for fire protection systems on daily basis or as approved by Departmental Representative, to isolate and protect all devices relating to:
 - .1 modification of fire alarms, fire suppression, extinguishing or protection systems; and/or
 - .2 cutting, welding, soldering or other construction activities that might activate fire protection systems.
 - .3 Immediately upon completion of work, restore fire protection systems to normal operation and verify that all devices are fully operational.
 - .4 Inform fire alarm system monitoring agency and local Fire Department immediately prior to isolation and immediately upon restoration of normal operation.
- .5 Designated contractor: shall hire the services of Siemens to do all the work related to the fire alarm system and Direct Energy for any work relating to EMCS.

1.6 **QUALITY CONTROL**

- .1 Testing Laboratory Services:
 - .1 Departmental Representative will appoint and pay for costs of inspection and testing services, unless indicated otherwise.
 - .2 Provide safe working areas and assist with testing procedures, including provisions for materials or services and co-ordination, as required by testing agency and as authorized by Departmental Representative.
 - .3 Where tests indicate non-compliance with specifications, contractor to pay for initial test and all subsequent testing of work to verify acceptability of corrected work.

1.7 HAZARDOUS MATERIALS

- .1 Hazardous Materials: product, substance, or organism that may cause adverse impact to environment or adversely affect health of persons, animals, or plant life when released into the environment.
- .2 Comply with the requirements of the Workplace Hazardous Materials Information System (WHMIS) regarding use, handling, storage, and disposal of hazardous materials; and regarding labelling and the provision of Material Safety Data Sheets (MSDS).
- .3 For work in occupied buildings, give the Department Representative 48 hours notice to 1 week for work involving designated substances (Ontario Bill 208), hazardous substances (Canada Labour Code Part II Section 10), and before painting, caulking, installing carpet or using adhesives and other materials, that cause off gassing.

1.8 TEMPORARY UTILITIES

- .1 Existing services required for work, excluding power required for space temporary heating, may be used by the Contractor without charge. Ensure capacity is adequate prior to imposing additional loads. Connect and disconnect at own expense and responsibility.
- .2 Notify the Departmental Representative and utility companies of intended interruption of services and obtain requisite permission.
- .3 Give the Departmental Representative 48 hours to 1 week notice related to each necessary interruption of any mechanical or electrical service throughout the course of the work. Keep duration of these interruptions to a minimum. Carry out all interruptions after normal working hours of the occupants, preferably on weekends.

1.9 CONSTRUCTION FACILITIES

- .1 Designated elevators: freight elevators to be used by construction personnel and transporting of materials.
 - .1 Co-ordinate with Departmental Representative.
 - .2 Protect from damage, safety hazards and overloading of existing equipment.
- .2 Site Storage:
 - .1 The Departmental Representative will assign storage space that shall be equipped and maintained by the Contractor.
 - .2 Do not unreasonably encumber site with materials or equipment.
 - .3 Move stored products or equipment that interfere with operations of Departmental Representative or other contractors.

- .4 Obtain and pay for use of additional storage or work areas needed for operations.
- .5 Do not load or permit to load any part of work with weight or force that will endanger work.
- .3 Where security is reduced by work provide temporary means to maintain security.
- .4 Sanitary facilities: will be assigned for Contractor's personnel. Others shall not be used. Keep facilities clean.
- .5 Signage:
 - .1 Provide common-use signs related to traffic control, information, instruction, use of equipment, public safety devices, etcetera, in both official languages or by the use of commonly understood graphic symbols and to approval of the Departmental Representative.
 - .2 No advertising will be permitted on this project.
 - .3 Maintain approved signs and notices in good condition for duration of project and dispose of off site, on completion of project or earlier, as directed by Departmental Representative.

1.10 TEMPORARY BARRIERS AND ENCLOSURES

- .1 Maintain existing services to building and provide for personnel and vehicle access. The contractor shall agree to install proper site separation and identification in order to maintain "Time and Space" at all times throughout the life of the project. When Building Operations staff requires access to equipment in order to operate the building, proper coordination and communication must exist between all parties involved
- .2 Dust Control:
 - .1 Provide dust tight screens or partitions to localize dust-generating activities, and for protection of workers, finished areas of work and public.
 - .2 Maintain and relocate protection until such work is complete.
 - .3 Protect all furnishings within work area with 0.102mm thick polyethylene film during construction. Remove film during non-construction hours and leave premises in clean, unencumbered and safe manner for normal daytime function.
- .3 Protection:
 - .1 Protect work against damage until take-over.
 - .2 Protect adjacent work against the spread of dust and dirt beyond the work areas.
 - .3 Protect operatives and other users of site from all hazards.

1.11 EXAMINATION and PREPARATION

- .1 Examine site and conditions likely to affect work and be familiar and conversant with existing conditions.
- .2 Before commencing work, establish location and extent of services lines in area of work and notify Departmental Representative of findings.

1.12 FIELD QUALITY CONTROL

- .1 Carry out Work using qualified licensed workers or apprentices in accordance with Provincial Act respecting manpower vocational training and qualification.
- .2 Permit employees registered in Provincial apprenticeship program to perform specific tasks only if under direct supervision of qualified licensed workers.
- .3 Determine permitted activities and tasks by apprentices, based on level of training attended and demonstration of ability to perform specific duties.

1.13 SIGNS

- .1 .1: Provide common-use signs related to traffic control, information, instruction, use of equipment, public safety devices, etc., in both official languages or by the use of commonly-understood graphic symbols to the Departmental Representative's approval.

1.14 EXECUTION

- .1 Cut, Patch and Make Good:
 - .1 Cut existing surfaces as required to accommodate new work.
 - .2 Remove all items so shown or specified.
 - .3 Patch and make good surfaces cut, damaged or disturbed, to Departmental Representative's approval. Match existing material, colour, finish and texture.
- .2 Firestop and smoke seal systems: in accordance with CAN-ULC-S115-05 - Standard Method of Fire Test of Firestop Systems. Install around pipe, ductwork, cables, and other objects penetrating fire separations to provide fire resistance not less than the fire resistance rating of surrounding floor, ceiling, and wall assembly.
- .3 Sleeves, Hangers and Inserts: co-ordinate setting and packing of sleeves and supply and installation of hangers and inserts. Obtain Departmental Representative's approval before cutting into structure.
- .4 Unless otherwise specified, materials for removal become the Contractor's property and shall be taken from site.

1.15 WASTE MANAGEMENT

- .1 Comply with Environmental Protection Act, Ontario Regulations: O. Reg. 102/94 - Waste Audits and Waste Reduction Work Plans; and O. Reg. 103/94 - Industrial, Commercial and Institutional Source Separation Programs; for waste management on construction and demolition projects.
- .2 Conduct "waste audit" to determine what waste will be generated during construction and demolition operations. Prepare written "waste reduction work plan" and implement the principles to reduce, reuse and recycle materials to the extent that is possible.
- .3 Provide a "source separation program" to disassemble and collect in an orderly fashion the following "materials designated for alternative disposal" from the "general waste" stream:
 - .1 brick and Portland cement concrete;
 - .2 cardboard (corrugated);
 - .3 gypsum board (unfinished);
 - .4 steel; and
 - .5 wood (not including painted, treated or laminated wood).
- .4 Submit complete records of all removals from site for both "materials designated for alternative disposal" and "general waste" including:
 - .1 time and date of removal;
 - .2 description of material and quantities; and
 - .3 proof that materials have been received at an approved Waste Processing Site or certified Waste Disposal Site as required.

1.16 CLEANING

- .1 Clean up as work progresses. At the end of each work period, and more often if ordered by the Departmental Representative, remove debris from site, neatly stack material for use, and clean up generally.
- .2 Upon completion remove scaffolding, temporary protection and surplus materials. Make good defects noted at this stage.
- .3 Clean and polish glass, mirrors, ceramic tile, aluminum, chrome, stainless steel, baked or porcelain enamel, plastic laminate and other plastic surfaces, floors, hardware and washroom fixtures. Clean manufactured articles in accordance with manufacturer's written instructions.
- .4 Clean areas under contract to a condition equal to what previously existed and to approval of Departmental Representative.

1.17 SECURITY CHECK

- .1 All personnel employed on this project will be subject to security check. Obtain requisite clearance, as instructed, for each individual required to enter the premises.
- .2 Personnel will be checked daily at start of work shift and given a pass, which must be worn at all times. Pass must be returned at end of work shift and personnel checked out.

1.18 SECURITY ESCORT

- .1 All personnel employed on this project shall be escorted when executing work in non-public areas during normal working hours. Personnel shall be escorted in all areas after normal working hours.
- .2 Submit an escort request to Departmental Representative at least 14 days before the service is needed. For requests submitted within the time mentioned above, the Departmental Representative will pay for the costs of the security escort. The cost incurred by a late request will be charged to the Contractor.
- .3 Any escort request may be cancelled free of charge if notification of cancellation is given at least 4 hours before the scheduled time of the escort. The cost incurred by a late cancellation will be charged to the Contractor.
- .4 The calculation of costs will be based on the average hourly rate of a security officer for a minimum of 8 hours per day for a late service request and 4 hours for late cancellations.

1.19 COST BREAKDOWN

- .1 Before submitting first progress claim, submit breakdown of Contract Amount in detail as directed by Departmental Representative and aggregating the Contract Amount. After approval by Departmental Representative cost breakdown will be used as the basis of progress payments.

1.20 PRECEDENCE

- .1 For Federal Government projects, Division 01 Sections take precedence over technical specification sections in other Divisions of this Project Manual.

1.21 SIGNS

- .1 .1: Provide common-use signs related to traffic control, information, instruction, use of equipment, public safety devices, etc., in both official languages or by the use of commonly-understood graphic symbols to the Departmental Representative's approval.

Project No.
R.066591.002

Section 01 00 10
GENERAL INSTRUCTIONS
Page 9

Part 2 Products

2.1 NOT USED

.1 Not used.

Part 3 Execution

3.1 NOT USED

.1 Not used.

END OF SECTION

PART 1 – GENERAL

1.1 REGULATORY REQUIREMENTS

.1 An investigation into the presence of designated substances for the Floor Refurbishment Project for the Jeanne-Mance building, located at the 200 Elgantine Drive in Ottawa, Ontario, was performed in order to meet the requirements of the Canada Labour Code under Part II, Section 124 that every employer shall ensure that the health and safety at work of every person employed by the employer is protected. Also, it was performed to meet the requirements of Section 30 of the Ontario Occupational Health and Safety Act, Revised Statutes of Ontario, 1990, Chapter 0.1. Furthermore, Section 125(1)(z.14) of the *Canada Labour Code* stipulates that the employer will take all reasonable care to ensure that all persons granted access to the work place, other than the employer's employees, are informed of every known or foreseeable health and safety hazard to which they are likely to be exposed in the work place. By having a Designated Substances Report (DSR) conducted, the PWGSC Departmental Representative will be able to inform his or her employees, contractors, and tenants of any designated substances that may be present and possibly disturbed throughout the duration of the project. The informed Departmental Representative will then be able to impose appropriate health and safety precautions for all applicable personnel as required.

.2 The designated substances identified in the *Occupational Health and Safety Act* and its corresponding regulations are:

- .1 **Acrylonitrile:** "Designated Substances"
O. Reg 490/09, as amended.
- .2 **Arsenic:** "Designated Substances"
O. Reg 490/09, as amended.
- .3 **Asbestos:**
 - .1 "Designated Substances"
O. Reg 490/09, as amended.
 - .2 "*General – Waste Management*"
O. Reg 347/09, as amended
 - .3 "Designated Substance – Asbestos on Construction Projects and in Buildings and Repair Operations"
O. Reg 278/05 (as amended)
 - .4 *PWGSC Departmental Policy DP 057 – "Asbestos Management"*
- .4 **Benzene:** "Designated Substances"
O. Reg 490/09, as amended.
- .5 **Coke Oven Emissions:** "Designated Substances" *O. Reg 490/09*, as amended.

- .6 **Ethylene Oxide:** "Designated Substances"
O. Reg 490/09, as amended.
- .7 **Isocyanates:** "Designated Substances"
O. Reg 490/09, as amended.
- .8 **Lead:**
 - .1 "Designated Substances"
O. Reg 490/09, as amended.
 - .2 "General – Waste Management"
O. Reg 347/09, as amended
 - .3 Hazardous Products Act's *Surface Coating Materials Regulations*
SOR/2005-109, as amended (2011)
- .9 **Mercury:**
 - .1 "Designated Substances"
O. Reg 490/09, as amended.
 - .2 "General – Waste Management"
O. Reg 347/09, as amended
- .10 **Silica:** "Designated Substances"
O. Reg 490/09, as amended.
- .11 **Vinyl Chloride:** "Designated Substances"
O. Reg 490/09, as amended.
- .3 All contractors requesting tenders from subcontractors shall furnish this report to subcontractors.

1.2 VALIDITY DATE

- .1 DST Consulting Engineers Inc. (DST), conducted the on-site survey for this report on November 12, 2013.
- .2 DST staff completed a visual inspection of building materials for the presence of suspected designated substances at 200 Elgantine Drive on November 12, 2013. The DSR specifically included the following areas likely to be impacted by the Floor Refurbishment Project, hereafter referred to as 'the project areas':
 - 4th, 5th and 10th Floors of the Jeanne-Mance Building, located at 200 Elgantine Drive;
 - Note that it was reported to DST by the on-site building representative (from SNC Lavalin) that flooring would not be impacted as part of the renovations and was therefore not included as part of this survey;
- .1 The scope of work for this report involved a visual inspection of building materials and contents for the presence of suspected designated substances within the project areas. Some telecom closets within the

- project areas could not be entered, and were thus not included in the survey.
- .2 From the visual inspection, suspect materials were sampled and analyzed, (where necessary), for select designated substances. On the basis of this inspection, a total of twenty-seven (27) bulk sample layers of suspected asbestos-containing material samples were collected from the project areas.
 - .3 Samples were then submitted for their respective analysis at Paracel Laboratories Ltd., (accredited by the CALA) located at 300-2319 St. Laurent Boulevard, Ottawa, ON K1G 4J8.
 - .4 The survey was limited to those areas that could be accessed by non-destructive means. The visual inspection and sampling was limited to readily accessible areas. Destructive testing was not included in the investigation. Due to the nature of building construction, some inherent limitations exist as to the possible thoroughness of the designated substance survey. The survey did not include the demolition of floors, floor finishes, solid ceilings or walls, or the sampling of pipe insulations, pipe fitting insulations and floor coverings.
 - .5 It is possible that designated substances are present in non-accessible areas and concealed spaces (i.e., wall and ceiling cavities), or additional confined spaces. No other areas outside the defined work boundaries have been assessed.
 - .6 Prior to beginning work, it must be confirmed with the Departmental Representative that no additional designated substances have been brought to the project area.
 - .7 In addition, the survey refers to Polychlorinated Biphenyls (PCBs) and Halocarbons; however, it does not refer to other substances that may be present in the day-to-day usage for specialized equipment or areas in buildings (i.e., lead shields, fume hoods, chemicals, etc.).
 - .8 There is a possibility that materials that could not be reasonably identified within the scope of this assessment or which were not apparent during previous site visits may exist. Should any designated substance be encountered in the course of demolition or renovation, work must be stopped,

preventative measures taken, and the Departmental Representative must be notified immediately. **Do not proceed until written instructions have been received.**

PART 2 - DESIGNATED SUBSTANCES

2.1 SURVEY RESULTS

.1 **ACRYLONITRILE:** Not Identified

.2 **ARSENIC:** Not Identified

.3 **ASBESTOS:** Not Identified

Asbestos is a naturally occurring material. In general, it has historically been intentionally added to many building materials in the construction industry to increase thermal or chemical resistance properties. More common uses are thermal insulation for pipes and boilers, structural steelwork fireproofing, floor tiles and in-wall and ceiling plasters. There are two classes of asbestos-containing materials: friable and non-friable. Friable asbestos-containing materials are loose in composition or can be easily crumbled using hand pressure. Non-friable asbestos-containing materials are more durable and are held together by a binder such as cement, vinyl or asphalt.

Representative bulk samples, collected from materials located within the project areas have been analyzed for asbestos. Analytical results indicate that select samples contain asbestos in the project areas.

Table 1 summarizes the analytical results of bulk samples collected during the site investigation:

Table 1: Asbestos Sample Results by PLM

Sample number	Material	Location	Asbestos Type	Asbestos content (%)
01A	Pipe penetration lining	10 th floor Janitor closet	n/d	n/a
01B			n/d	n/a
01C			n/d	n/a

Sample number	Material	Location	Asbestos Type	Asbestos content (%)
02A	Wall Plaster (white and grey layers)	10 th floor core areas	n/d	n/a
02B		10 th floor core areas	n/d	n/a
02C		5 th floor core areas	n/d	n/a
02D		5 th floor core areas	n/d	n/a
02E		4 th floor core areas	n/d	n/a
02F		4 th floor core areas	n/d	n/a
02G		10 th floor core areas	n/d	n/a
03A	Drywall joint compound	10 th floor core areas	n/d	n/a
03B		10 th floor core areas	n/d	n/a
03C		5 th floor core areas	n/d	n/a
03D		5 th floor core areas	n/d	n/a
03E		4 th floor core areas	n/d	n/a
03F		4 th floor core areas	n/d	n/a
03G		4 th floor core areas	n/d	n/a
04A	2'x4' Ceiling tiles	10 th floor	n/d	n/a
04B		5 th floor	n/d	n/a
04C		4 th floor	n/d	n/a

n/d – none detected, n/a- not applicable

Based on analytical sampling and limited observations noted during the survey, no asbestos-containing materials were identified in the project areas.

.4 **BENZENE:** Not Identified

.5 **COKE OVEN EMISSIONS:** Not Identified

.6 **ETHYLENE OXIDE:** Not Identified

.7 **ISOCYANATES:** Not Identified

.8 **LEAD: Suspected**

Lead is a naturally occurring metal. It was used primarily in paint prior to the 1980s to increase the drying process. Lead in paint becomes a danger when it is old or damaged, as it creates lead dust and chips. Lead can also be found in soldered joints installed on piping up to the mid-1990s and in older cast iron bell and spigot joints.

.1 According to the Hazard Products Act's *Surface Coating Materials Regulations* SOR/2005-109, as amended, allowable concentration of lead of

surface coatings is 0.009 percent by weight (weight of lead to weight of paint), which is equivalent to 90 parts per million (ppm).

- .2 Even at very low concentrations, there may be potential for exposure to very high levels of lead depending on the activities performed that disturb the lead-containing materials. At low lead concentrations, conducting a risk assessment to assess the potential for exposure is required to determine the need to follow precautionary measures.
- .3 Older interior paint finishes throughout the project area are suspected to contain detectable concentrations of lead.
- .4 Lead is expected to be present within solder on copper piping throughout the project areas.

.9 **MERCURY: Identified**

Mercury is assumed present in vapour form and in the phosphor coating of T-8 fluorescent light tubes throughout the project areas.

.10 **SILICA: Identified**

Free crystalline silica is assumed present in concrete, plaster and drywall throughout the project areas.

.11 **VINYL CHLORIDE MONOMER: Not Identified**

.12 **POLYCHLORINATED BIPHENYLS (PCBs): Not Identified**

.13 **HALOCARBONS: Assumed**

Domestic refrigerators and wall mounted water fountains were observed within the project area. Halocarbons are assumed to be present within these units.

2.2 RECOMMENDATIONS

1. LEAD

If suspected lead-containing materials are disturbed (i.e. during dry sanding, grinding, polishing and sawing operations), then proper precautions, as outlined under "Designated Substances" O.Reg 490/09, as amended, of the Occupational Health and Safety Act, must be followed.

Under Ontario Regulation 490/09, as amended of the Occupational Health and Safety Act, regulatory limits have been established for occupational exposure limits to airborne lead that may be present in a workplace. The Time Weighted Average Exposure Values (TWAEV) to airborne lead dust or fumes should not exceed the Ministry of Labour's 0.05 milligram per cubic metre (mg/m^3) limit during the removal of paints and products containing any concentration of lead. The TWAEV represents the time-weighted average concentration for a conventional 8-hour workday and a 40-hour workweek, to which it is believed that nearly all workers may be repeatedly exposed, day after day, without adverse health effects.

Contractors performing work that requires disturbance of lead-containing materials are responsible to ensure that the workers are not exposed to airborne lead dust levels in excess of the time-weighted average and Maximum Exposure Concentration for lead-containing paints.

.1 Ontario Ministry of Labour (MoL) has published the document entitled "*Guideline: Lead on Construction Projects*". This document classifies all disturbances of lead-containing materials as Type 1, Type 2a, Type 2b, Type 3a or Type 3b work, based on presumed airborne concentrations of lead generated during the work each of which will have defined work practices. Although this document is not a regulation, Ministry of Labour Inspectors use it as guidance during site inspections. Where there is conflict with the exposure limits and respiratory protection required by "Designated Substances" Regulation O.Reg 490/09, as amended, the most stringent requirements of Regulation 490/09 must apply

.2 The disposal of construction waste containing lead is controlled by "General – Waste Management" O.Reg 347/09, as amended, under the *Ontario Environmental Protection Act*. The classification of the waste is dependent upon the result(s) of leachate test(s). The waste can be classified as "hazardous", "non-hazardous" or "registerable solid waste", depending on the results of the leachate test.

Prior to disposal, the concentration of leachable lead must be determined for waste materials with elevated lead contents following the Toxicity Characteristic Leaching Procedure (TCLP). Based upon the concentration of lead identified within the paint within the work area, the painted surfaces would be characterized as non-hazardous for disposal.

2. MERCURY

.1 Mercury is governed by "Designated Substances" *O.Reg 490/09*, as amended, under the Occupational Health and Safety Act. The regulation provides requirements for allowable exposure levels.

.2 In addition, mercury waste is considered a hazardous waste under "General – Waste Management" *O.Reg 347/09, as amended*, of the *Ontario Environmental Protection Act*. Fluorescent lamp tubes are considered hazardous material and should be recycled if removed from service. For information regarding the collection of fluorescent lamp tubes, please consult the PWGSC Departmental Representative.

3. SILICA

.1 Silica occurs as crystalline material in cement. Crystalline silica is regulated under "Designated Substances" *O.Reg 490/09*, as amended, of the *Occupational Health and Safety Act* as a Designated Substance.

.2 Silica dust can be generated through such processes as blasting, grinding, crushing, and sandblasting silica-containing material. Since silica is presumed present in concrete, plaster and drywall within the project areas, appropriate respiratory protection and ventilation must be donned during the demolition and modifications of these structures.

.3 The Occupational Health and Safety Branch of the MoL has published the document entitled "*Guideline: Silica on Construction Projects*". This document classifies the disturbance of materials containing silica as Type 1, Type 2 or Type 3 work, and assigns different levels of respiratory protection and work procedures for each classification. These work procedures should be followed when performing work involving the disturbance of silica-containing materials.

4. HALOCARBONS

(NOT RECOGNIZED AS A DESIGNATED SUBSTANCE)

.1 When halocarbon-containing equipment requires dismantling or disposal, this equipment must be

tagged by a certified technician before it can be dismantled or disposed, as per the requirements of the Federal Halocarbon Regulations (2003) and "Refrigerants" O.Reg 189/94, as amended by O.Reg 238/01 or "Ozone Depleting Substances and Other Halocarbons", O.Reg. 463/10. If the units are to be removed, no release of the refrigerant shall occur in accordance with the Canadian Environmental Protection Act. If the units are being disposed, a qualified ODS technician with environmental awareness training must drain and remove the ODSs. ODS recycling and recovery initiatives must be undertaken for any ODS-containing units being displaced by proposed work.

.2 The Ozone-Depleting Substances (ODS) Regulations made under the Canadian Environmental Protection Act came into force on June 2, 1994. These regulations control the reclamation, recovery and recycling of ODSs. Environment Canada has prepared a Code of Practice for the Reduction of Chlorofluorocarbon Emissions from Refrigeration and Air Conditioning Systems (1991) which outlines practices to be followed when conducting maintenance on these refrigerant-containing units. The Federal Halocarbon Regulation which came into effect in 1999, regulates releases, recovery and recycling of ODS and their halocarbon alternatives in the federal domain and also to ensure that these releases are minimized. Even though halocarbon alternatives to ODSs may have no impact on the ozone layer, they are greenhouse gases and thus contribute to climate change. The Regulations ensure that actions are taken to prevent releases of ODS and their halocarbon alternatives; to report these releases; that adequate training is provided to personnel; that operational and emergency procedures and strategic plans are developed for the use, control and phase-out of these substances. During this project, these regulations must be followed when dealing with ODSs.

5. CONTRACTORS DUTIES

The contractor must review the designated substance report and take the necessary precautions to protect the health and safety of the workers and the environment. As per Section 30(4) of the *Ontario Occupational Health and Safety Act*, the party hiring the contractor (i.e., PWGSC Departmental Representative) shall ensure that the contractor and subcontractor (if any) for the project has received a copy of the designated substance report prior to entering a binding contract for the supply of work on the project. As per Section 27(2) (a, b, and c) of the *Ontario Occupational Health and*

Safety Act, while onsite, the contractor supervisor shall exercise every reasonable precaution for the protection of a worker. If you have any questions about the designated substance report, please contact the PWGSC Departmental Representative.

The contractor shall also complete all reporting requirements to comply with applicable regulations.

END OF SECTION

PART 1 - GENERAL1.1 RELATED
REQUIREMENTS

- .1 Section 01 10 10 - General Instructions.

1.2 ADMINISTRATIVE

- .1 Submit to Departmental Representative submittals listed for review. Submit promptly and in orderly sequence to not cause delay in Work. Failure to submit in ample time is not considered sufficient reason for extension of Contract Time and no claim for extension by reason of such default will be allowed.
- .2 Do not proceed with Work affected by submittal until review is complete.
- .3 Present shop drawings, product data, samples and mock-ups in SI Metric units.
- .4 Where items or information is not produced in SI Metric units converted values are acceptable.
- .5 Review submittals prior to submission to Departmental Representative . This review represents that necessary requirements have been determined and verified, or will be, and that each submittal has been checked and co-ordinated with requirements of Work and Contract Documents. Submittals not stamped, signed, dated and identified as to specific project will be returned without being examined and considered rejected.
- .6 Notify Departmental Representative , in writing at time of submission, identifying deviations from requirements of Contract Documents stating reasons for deviations.
- .7 Verify field measurements and affected adjacent Work are co-ordinated.
- .8 Contractor's responsibility for errors and omissions in submission is not relieved by Departmental Representative's review of submittals.
- .9 Contractor's responsibility for deviations in submission from requirements of Contract Documents is not relieved by Departmental Representative review.
- .10 Keep one reviewed copy of each submission on site.

1.3 SHOP DRAWINGS
AND PRODUCT DATA

- .1 The term "shop drawings" means drawings, diagrams, illustrations, schedules, performance charts, brochures and other data which are to be provided by Contractor to illustrate details of a portion of Work.
- .2 Submit drawings stamped and signed by professional engineer registered or licensed in Province of Ontario.
- .3 Indicate materials, methods of construction and attachment or anchorage, erection diagrams, connections, explanatory notes and other information necessary for completion of Work. Where articles or equipment attach or connect to other articles or equipment, indicate that such items have been co-ordinated, regardless of Section under which adjacent items will be supplied and installed. Indicate cross references to design drawings and specifications.
- .4 Allow 2 days for Departmental Representative's review of each submission.
- .5 Adjustments made on shop drawings by Departmental Representative are not intended to change Contract Price. If adjustments affect value of Work, state such in writing to Departmental Representative prior to proceeding with Work.
- .6 Make changes in shop drawings as Departmental Representative may require, consistent with Contract Documents. When resubmitting, notify Departmental Representative Consultant in writing of revisions other than those requested.
- .7 Accompany submissions with transmittal letter, containing:
 - .1 Date.
 - .2 Project title and number.
 - .3 Contractor's name and address.
 - .4 Identification and quantity of each shop drawing, product data and sample.
 - .5 Other pertinent data.
- .8 Submissions include:
 - .1 Date and revision dates.
 - .2 Project title and number.
 - .3 Name and address of:
 - .1 Subcontractor.
 - .2 Supplier.
 - .3 Manufacturer.
 - .4 Contractor's stamp, signed by Contractor's authorized representative certifying approval of submissions, verification of field measurements and

compliance with Contract Documents.

.5 Details of appropriate portions of Work as applicable:

- .1 Fabrication.
- .2 Layout, showing dimensions, including identified field dimensions, and clearances.
- .3 Setting or erection details.
- .4 Capacities.
- .5 Performance characteristics.
- .6 Standards.
- .7 Operating weight.
- .8 Wiring diagrams.
- .9 Single line and schematic diagrams.
- .10 Relationship to adjacent work.

- .9 After Departmental Representative's review, distribute copies.
- .10 Submit electronic copy of shop drawings for each requirement requested in specification Sections and as Departmental Representative may reasonably request.
- .11 Submit electronic copies of product data sheets or brochures for requirements requested in specification Sections and as requested by Departmental Representative where shop drawings will not be prepared due to standardized manufacture of product.
- .12 Submit electronic copies of test reports for requirements requested in specification Sections and as requested by Departmental Representative.
 - .1 Report signed by authorized official of testing laboratory that material, product or system identical to material, product or system to be provided has been tested in accord with specified requirements.
 - .2 Testing must have been within 3 years of date of contract award for project.
- .13 Submit electronic copies of certificates for requirements requested in specification Sections and as requested by Departmental Representative.
 - .1 Statements printed on manufacturer's letterhead and signed by responsible officials of manufacturer of product, system or material attesting that product, system or material meets specification requirements.
 - .2 Certificates must be dated after award of project contract complete with project name.
- .14 Submit electronic copies of manufacturers instructions for requirements requested in specification Sections and as requested by Departmental Representative.
 - .1 Pre-printed material describing installation of product, system or material, including special notices and Material Safety Data Sheets concerning impedances, hazards and safety precautions.

-
- .15 Submit electronic copies of Manufacturer's Field Reports for requirements requested in specification Sections and as requested by Departmental Representative.
 - .16 Documentation of the testing and verification actions taken by manufacturer's representative to confirm compliance with manufacturer's standards or instructions.
 - .17 Submit electronic copies of Operation and Maintenance Data for requirements requested in specification Sections and as requested by Departmental Representative.
 - .18 Delete information not applicable to project.
 - .19 Supplement standard information to provide details applicable to project.
 - .20 If upon review by Departmental Representative, no errors or omissions are discovered or if only minor corrections are made, copies will be returned and fabrication and installation of Work may proceed. If shop drawings are rejected, noted copy will be returned and resubmission of corrected shop drawings, through same procedure indicated above, must be performed before fabrication and installation of Work may proceed.
 - .21 The review of shop drawings by Public Works and Government Services Canada (PWGSC) is for sole purpose of ascertaining conformance with general concept.
 - .1 This review shall not mean that PWGSC approves detail design inherent in shop drawings, responsibility for which shall remain with Contractor submitting same, and such review shall not relieve Contractor of responsibility for errors or omissions in shop drawings or of responsibility for meeting requirements of construction and Contract Documents.
 - .2 Without restricting generality of foregoing, Contractor is responsible for dimensions to be confirmed and correlated at job site, for information that pertains solely to fabrication processes or to techniques of construction and installation and for co-ordination of Work of sub-trades.

1.4 SAMPLES

- .1 Submit for review samples in duplicate as requested in respective specification Sections. Label samples with origin and intended use.
- .2 Deliver samples prepaid to Departmental Representative's business address.
- .3 Notify Departmental Representative in writing, at time of submission of deviations in samples from

requirements of Contract Documents.

- .4 Where colour, pattern or texture is criterion, submit full range of samples.
- .5 Adjustments made on samples by Departmental Representative are not intended to change Contract Price. If adjustments affect value of Work, state such in writing to Departmental Representative prior to proceeding with Work.
- .6 Make changes in samples which Departmental Representative may require, consistent with Contract Documents.
- .7 Reviewed and accepted samples will become standard of workmanship and material against which installed Work will be verified.

1.5 CERTIFICATES AND TRANSCRIPTS

- .1 Immediately after award of Contract, submit Workers' Compensation Board status.
- .2 Submit transcription of insurance immediately after award of Contract.

PART 2 - PRODUCTS

2.1 NOT USED

- .1 Not Used.

PART 3 - EXECUTION

3.1 NOT USED

- .1 Not Used.

PART 1 - GENERAL

<u>1.1 RELATED REQUIREMENTS</u>	.1	Section 01 00 10 - General Instructions.
-------------------------------------	----	--

<u>1.2 REFERENCES</u>	.1	Province of Ontario .1 Occupational Health and Safety Act and Regulations for Construction Projects, R.S.O. 1990, c. 0.1, as amended and O. Reg. 213/91, as amended.
-----------------------	----	---

<u>1.3 ACTION AND INFORMATIONAL SUBMITTALS</u>	.1	Make submittals in accordance with Section 01 33 00 - Submittal Procedures.
	.2	Submit site-specific Health and Safety Plan: Within 7 days after date of Notice to Proceed and prior to commencement of Work. Health and Safety Plan must include: .1 Results of site specific safety hazard assessment. .2 Results of safety and health risk or hazard analysis for site tasks and operation found in work plan.
	.3	Submit a copy of Contractor's authorized representative's work site health and safety inspection reports to Departmental Representative weekly.
	.4	Submit copies of reports or directions issued by Federal and Provincial health and safety inspectors.
	.5	Submit copies of incident and accident reports within 24 hours.
	.6	Submit WHMIS MSDS - Material Safety Data Sheets in accordance with Section 01 00 10 - General Instructions.
	.7	Departmental Representative will review Contractor's site-specific Health and Safety Plan and provide comments to Contractor within 7 days after receipt of plan. Revise plan as appropriate and resubmit plan to Departmental Representative within 7 days after receipt of comments from Departmental Representative.
	.8	Departmental Representative's review of Contractor's final Health and Safety plan should not be construed as approval and does not reduce the Contractor's overall responsibility for construction Health and Safety.

	.9	Medical Surveillance: where prescribed by legislation, regulation or safety program, submit certification of medical surveillance for site personnel prior to commencement of Work, and submit additional certifications for any new site personnel to Departmental Representative.
<u>1.4 FILING OF NOTICE</u>	.1	File Notice of Project with Provincial authorities prior to beginning of Work.
<u>1.5 SAFETY ASSESSMENT</u>	.1	Perform site specific safety hazard assessment related to project.
<u>1.6 MEETINGS</u>	.1	Schedule and administer Health and Safety meeting with Departmental Representative prior to commencement of Work.
<u>1.7 PROJECT/SITE CONDITIONS</u>	.1	Work at site will involve contact with: <div>.1 TBC</div>
<u>1.8 GENERAL REQUIREMENTS</u>	.1	Develop written site-specific Health and Safety Plan based on hazard assessment prior to beginning site Work and continue to implement, maintain, and enforce plan until final demobilization from site. Health and Safety Plan must address project specifications.
	.2	Departmental Representative may respond in writing, where deficiencies or concerns are noted and may request re-submission with correction of deficiencies or concerns.
<u>1.9 RESPONSIBILITY</u>	.1	Be responsible and assume the role of "Constructor" as described in the Ontario Occupational Health & Safety Act and Regulations for Construction Projects.
<u>1.10 COMPLIANCE REQUIREMENTS</u>	.1	Comply with the Ontario Occupational Health and Safety Act, R.S.O. 1990, c. 0.1.
	.2	Comply with the Ontario Regulations for Construction Projects, O. Reg. 213/91.
	.3	Comply with CAN/CSA, Z462-12 (Workplace Electrical

Safety Standard)

- .4 Comply with CAN/CSA-Z460-05 (R2010) - Control of Hazardous Energy.

1.11 UNFORSEEN HAZARDS

- .1 When unforeseen or peculiar safety-related factor, hazard, or condition occur during performance of Work, follow procedures in place for Employee's Right to Refuse Work in accordance with Acts and Regulations of Province having jurisdiction and advise Departmental Representative verbally and in writing.

1.12 RESERVED

1.13 POSTING OF DOCUMENTS

- .1 Ensure applicable items, articles, notices and orders are posted in conspicuous location on site in accordance with Acts and Regulations of Province having jurisdiction, and in consultation with Departmental Representative.

1.14 CORRECTION OF NON-COMPLIANCE

- .1 Immediately address health and safety non-compliance issues identified by authority having jurisdiction or by Departmental Representative.
- .2 Provide Departmental Representative with written report of action taken to correct non-compliance of health and safety issues identified.
- .3 Departmental Representative may stop Work if non-compliance of health and safety regulations is not corrected.

1.15 POWDER ACTUATED DEVICES

- .1 Use powder actuated devices only after receipt of written permission from Departmental Representative.

1.16 WORK STOPPAGE

- .1 Give precedence to safety and health of public and site personnel and protection of environment over cost and schedule considerations for Work.

PART 2 - PRODUCTS

2.1 NOT USED

- .1 Not used.

PART 3 - EXECUTION

3.1 NOT USED

- .1 Not used.

PART 1 - GENERAL

1.1 RELATED
REQUIREMENTS

- .1 Section 01 00 10 - General Instructions.

1.2 REFERENCES

- .1 Within text of each specifications section, reference may be made to reference standards.
- .2 Conform to these reference standards, in whole or in part as specifically requested in specifications.
- .3 If there is question as to whether products or systems are in conformance with applicable standards, Departmental Representative reserves right to have such products or systems tested to prove or disprove conformance.
- .4 Cost for such testing will be born by Departmental Representative in event of conformance with Contract Documents or by Contractor in event of non-conformance.

1.3 QUALITY

- .1 Products, materials, equipment and articles incorporated in Work shall be new, not damaged or defective, and of best quality for purpose intended. If requested, furnish evidence as to type, source and quality of products provided.
- .2 Procurement policy is to acquire, in cost effective manner, items containing highest percentage of recycled and recovered materials practicable consistent with maintaining satisfactory levels of competition. Make reasonable efforts to use recycled and recovered materials and in otherwise utilizing recycled and recovered materials in execution of work.
- .3 Defective products, whenever identified prior to completion of Work, will be rejected, regardless of previous inspections. Inspection does not relieve responsibility, but is precaution against oversight or error. Remove and replace defective products at own expense and be responsible for delays and expenses caused by rejection.
- .4 Should disputes arise as to quality or fitness of products, decision rests strictly with Departmental Representative based upon requirements of Contract Documents.
- .5 Unless otherwise indicated in specifications, maintain

uniformity of manufacture for any particular or like item throughout building.

- .6 Permanent labels, trademarks and nameplates on products are not acceptable in prominent locations, except where required for operating instructions, or when located in mechanical or electrical rooms.

1.4 STORAGE, HANDLING AND PROTECTION

- .1 Handle and store products in manner to prevent damage, adulteration, deterioration and soiling and in accordance with manufacturer's instructions when applicable.
- .2 Store packaged or bundled products in original and undamaged condition with manufacturer's seal and labels intact. Do not remove from packaging or bundling until required in Work.
- .3 Store products subject to damage from weather in weatherproof enclosures.
- .4 Store cementitious products clear of earth or concrete floors, and away from walls.
- .5 Keep sand, when used for grout or mortar materials, clean and dry. Store sand on wooden platforms and cover with waterproof tarpaulins during inclement weather.
- .6 Store sheet materials and lumber on flat, solid supports and keep clear of ground.
- .7 Store and mix paints in heated and ventilated room. Remove oily rags and other combustible debris from site daily. Take every precaution necessary to prevent spontaneous combustion.
- .8 Remove and replace damaged products at own expense and to satisfaction of Departmental Representative.
- .9 Touch-up damaged factory finished surfaces to Departmental Representative's satisfaction. Use touch-up materials to match original. Do not paint over name plates.

1.5 TRANSPORTATION

- .1 Pay costs of transportation of products required in performance of Work.
- .2 Transportation cost of products supplied by Owner will be paid for by Departmental Representative. Unload, handle and store such products.

1.6 MANUFACTURER'S INSTRUCTIONS

- .1 Unless otherwise indicated in specifications, install or erect products in accordance with manufacturer's instructions. Do not rely on labels or enclosures provided with products. Obtain written instructions

directly from manufacturers.

- .2 Notify Departmental Representative in writing, of conflicts between specifications and manufacturer's instructions, so that Departmental Representative will establish course of action.
- .3 Improper installation or erection of products, due to failure in complying with these requirements, authorizes Departmental Representative to require removal and re-installation at no increase in Contract Price or Contract Time.

1.7 QUALITY OF WORK

- .1 Ensure Quality of Work is of highest standard, executed by workers experienced and skilled in respective duties for which they are employed. Immediately notify Departmental Representative if required Work is such as to make it impractical to produce required results.
- .2 Do not employ anyone unskilled in their required duties. Departmental Representative reserves right to require dismissal from site, workers deemed incompetent or careless.
- .3 Decisions as to standard or fitness of Quality of Work in cases of dispute rest solely with Departmental Representative, whose decision is final.

1.7 CO-ORDINATION

- .1 Ensure co-operation of workers in laying out Work. Maintain efficient and continuous supervision.
- .2 Be responsible for coordination and placement of openings, sleeves and accessories.

1.9 CONCEALMENT

- .1 In finished areas conceal pipes, ducts and wiring in floors, walls and ceilings, except where indicated otherwise.
- .2 Before installation inform Departmental Representative if there is interference. Install as directed by Departmental Representative.

1.10 REMEDIAL WORK

- .1 Perform remedial work required to repair or replace parts or portions of Work identified as defective or unacceptable. Co-ordinate adjacent affected Work as required.
- .2 Perform remedial work by specialists familiar with materials affected. Perform in a manner to neither damage nor put at risk any portion of Work.

1.11 LOCATION OF FIXTURES

- .1 Consider location of fixtures, outlets, and mechanical and electrical items indicated as approximate.

- | | | |
|--|----|--|
| | .2 | Inform Departmental Representative of conflicting installation. Install as directed. |
| <u>1.12 FASTENINGS</u> | .1 | Provide metal fastenings and accessories in same texture, colour and finish as adjacent materials, unless indicated otherwise. |
| | .2 | Prevent electrolytic action between dissimilar metals and materials. |
| | .3 | Use non-corrosive hot dip galvanized steel fasteners and anchors for securing exterior work, unless stainless steel or other material is specifically requested in affected specification Section. |
| | .4 | Space anchors within individual load limit or shear capacity and ensure they provide positive permanent anchorage. Wood, or any other organic material plugs are not acceptable. |
| | .5 | Keep exposed fastenings to a minimum, space evenly and install neatly. |
| | .6 | Fastenings which cause spalling or cracking of material to which anchorage is made are not acceptable. |
| <u>1.13 FASTENINGS - EQUIPMENT</u> | .1 | Use fastenings of standard commercial sizes and patterns with material and finish suitable for service. |
| | .2 | Use heavy hexagon heads, semi-finished unless otherwise specified. Use No. 304 stainless steel for exterior areas. |
| | .3 | Bolts may not project more than one diameter beyond nuts. |
| | .4 | Use plain type washers on equipment, sheet metal and soft gasket lock type washers where vibrations occur. Use resilient washers with stainless steel. |
| <u>1.14 PROTECTION OF WORK IN PROGRESS</u> | .1 | Prevent overloading of parts of building. Do not cut, drill or sleeve load bearing structural member, unless specifically indicated without written approval of Departmental Representative. |
| <u>1.15 EXISTING UTILITIES</u> | .1 | When breaking into or connecting to existing services or utilities, execute Work at times directed by local governing authorities, with minimum of disturbance to Work, and/or building occupants. |
| | .2 | Protect, relocate or maintain existing active services. When services are encountered, cap off in manner approved by authority having jurisdiction. Stake and record location of capped service. |

PART 2 - PRODUCTS

2.1 NOT USED .1 Not Used.

PART 3 - EXECUTION

3.1 NOT USED .1 Not Used.

PART 1 - GENERAL1.1 RELATED
REQUIREMENTS

- .1 Section 01 00 10 - General Instructions.

1.2 REFERENCES

- .1 Canadian Environmental Protection Act (CEPA)
 - .1 SOR/2008-197, Storage Tank Systems for Petroleum Products and Allied Petroleum Products Regulations.

1.3 ADMINISTRATIVE
REQUIREMENTS

- .1 Pre-warranty Meeting:
 - .1 Convene meeting one week prior to contract completion with Departmental Representative, in accordance with to:
 - .1 Verify Project requirements.
 - .2 Review manufacturer's installation instructions and warranty requirements.
 - .2 Departmental Representative to establish communication procedures for:
 - .1 Notifying construction warranty defects.
 - .2 Determine priorities for type of defects.
 - .3 Determine reasonable response time.
 - .3 Contact information for bonded and licensed company for warranty work action: provide name, telephone number and address of company authorized for construction warranty work action.
 - .4 Ensure contact is located within local service area of warranted construction, is continuously available, and is responsive to inquiries for warranty work action.

1.4 ACTION AND
INFORMATIONAL
SUBMITTALS

- .1 Provide submittals in accordance with Section 01 33 00 - Submittal Procedures.
- .2 Two weeks prior to Substantial Performance of the Work, submit to the Departmental Representative , four final copies of operating and maintenance manuals in English.
- .3 Provide spare parts, maintenance materials and special tools of same quality and manufacture as products provided in Work.
- .4 Provide evidence, if requested, for type, source and quality of products supplied.

1.5 FORMAT

- .1 Organize data as instructional manual.
- .2 Binders: vinyl, hard covered, 3 'D' ring, loose leaf

219 x 279 mm with spine and face pockets.

- .3 When multiple binders are used correlate data into related consistent groupings.
 - .1 Identify contents of each binder on spine.
- .4 Cover: identify each binder with type or printed title 'Project Record Documents'; list title of project and identify subject matter of contents.
- .5 Arrange content by systems, under Section numbers and sequence of Table of Contents.
- .6 Provide tabbed fly leaf for each separate product and system, with typed description of product and major component parts of equipment.
- .7 Text: manufacturer's printed data, or typewritten data.
- .8 Drawings: provide with reinforced punched binder tab.
 - .1 Bind in with text; fold larger drawings to size of text pages.

1.6 CONTENTS - PROJECT RECORD DOCUMENTS

- .1 Table of Contents for Each Volume: provide title of project;
 - .1 Date of submission; names.
 - .2 Addresses, and telephone numbers of Consultant and Contractor with name of responsible parties.
 - .3 Schedule of products and systems, indexed to content of volume.
- .2 For each product or system:
 - .1 List names, addresses and telephone numbers of subcontractors and suppliers, including local source of supplies and replacement parts.
- .3 Product Data: mark each sheet to identify specific products and component parts, and data applicable to installation; delete inapplicable information.
- .4 Drawings: supplement product data to illustrate relations of component parts of equipment and systems, to show control and flow diagrams.

1.7 AS -BUILT DOCUMENTS AND SAMPLES

- .1 Maintain, at site for Departmental Representative one record copy of:
 - .1 Contract Drawings.
 - .2 Specifications.
 - .3 Addenda.
 - .4 Change Orders and other modifications to Contract.
 - .5 Reviewed shop drawings, product data, and samples.
 - .6 Field test records.

1.8 RECORDING INFORMATION ON PROJECT RECORD DOCUMENTS

- .7 Inspection certificates.
- .8 Manufacturer's certificates.
- .2 Store record documents and samples in field office apart from documents used for construction.
 - .1 Provide files, racks, and secure storage.
- .3 Label record documents and file in accordance with Section number listings in List of Contents of this Project Manual.
 - .1 Label each document "PROJECT RECORD" in neat, large, printed letters.
- .4 Maintain record documents in clean, dry and legible condition.
 - .1 Do not use record documents for construction purposes.
- .5 Keep record documents and samples available for inspection by Departmental Representative.
- .1 Record information on set of black line opaque drawings, provided by Departmental Representative.
- .2 Use felt tip marking pens, maintaining separate colours for each major system, for recording information.
- .3 Record information concurrently with construction progress.
 - .1 Do not conceal Work until required information is recorded.
- .4 Contract Drawings and shop drawings: mark each item to record actual construction, including:
 - .1 Measured depths of elements of foundation in relation to finish first floor datum.
 - .2 Measured horizontal and vertical locations of underground utilities and appurtenances, referenced to permanent surface improvements.
 - .3 Measured locations of internal utilities and appurtenances, referenced to visible and accessible features of construction.
 - .4 Field changes of dimension and detail.
 - .5 Changes made by change orders.
 - .6 Details not on original Contract Drawings.
 - .7 References to related shop drawings and modifications.
- .5 Specifications: mark each item to record actual construction, including:
 - .1 Manufacturer, trade name, and catalogue number of each product actually installed, particularly optional items and substitute items.
 - .2 Changes made by Addenda and change orders.

1.9 EQUIPMENT AND SYSTEMS

- .6 Other Documents: maintain manufacturer's certifications, inspection certifications, field test records, required by individual specifications sections.
- .7 Provide digital photos, if requested, for site records.
- .1 For each item of equipment and each system include description of unit or system, and component parts.
 - .1 Give function, normal operation characteristics and limiting conditions.
 - .2 Include performance curves, with engineering data and tests, and complete nomenclature and commercial number of replaceable parts.
- .2 Panel board circuit directories: provide electrical service characteristics, controls, and communications.
- .3 Include installed colour coded wiring diagrams.
- .4 Operating Procedures: include start-up, break-in, and routine normal operating instructions and sequences.
 - .1 Include regulation, control, stopping, shut-down, and emergency instructions.
 - .2 Include summer, winter, and any special operating instructions.
- .5 Maintenance Requirements: include routine procedures and guide for trouble-shooting; disassembly, repair, and reassembly instructions; and alignment, adjusting, balancing, and checking instructions.
- .6 Provide servicing and lubrication schedule, and list of lubricants required.
- .7 Include manufacturer's printed operation and maintenance instructions.
- .8 Include sequence of operation by controls manufacturer.
- .9 Provide original manufacturer's parts list, illustrations, assembly drawings, and diagrams required for maintenance.
- .10 Provide installed control diagrams by controls manufacturer.
- .11 Provide Contractor's Design-Builder's co-ordination drawings, with installed colour coded piping diagrams.
- .12 Provide charts of valve tag numbers, with location and function of each valve, keyed to flow and control diagrams.

1.10 MATERIALS AND FINISHES

- .13 Provide list of original manufacturer's spare parts, current prices, and recommended quantities to be maintained in storage.
- .14 Include test and balancing reports as specified.
- .15 Additional requirements: as specified in individual specification sections.
- .1 Building products, applied materials, and finishes: include product data, with catalogue number, size, composition, and colour and texture designations.
 - .1 Provide information for re-ordering custom manufactured products.
- .2 Instructions for cleaning agents and methods, precautions against detrimental agents and methods, and recommended schedule for cleaning and maintenance.
- .3 Moisture-protection and weather-exposed products: include manufacturer's recommendations for cleaning agents and methods, precautions against detrimental agents and methods, and recommended schedule for cleaning and maintenance.
- .4 Additional requirements: as specified in individual specifications sections.

1.11 MAINTENANCE MATERIALS

- .1 Spare Parts:
 - .1 Provide spare parts, in quantities specified in individual specification sections.
 - .2 Provide items of same manufacture and quality as items in Work.
 - .3 Deliver to site; place and store.
 - .4 Receive and catalogue items.
 - .1 Submit inventory listing to Departmental Representative.
 - .2 Include approved listings in Maintenance Manual.
 - .5 Obtain receipt for delivered products and submit prior to final payment.
- .2 Extra Stock Materials:
 - .1 Provide maintenance and extra materials, in quantities specified in individual specification sections.
 - .2 Provide items of same manufacture and quality as items in Work.
 - .3 Deliver to site; place and store.
 - .4 Receive and catalogue items.
 - .1 Submit inventory listing to Departmental Representative.
 - .2 Include approved listings in Maintenance Manual.
 - .5 Obtain receipt for delivered products and submit

prior to final payment.

- .3 Special Tools:
 - .1 Provide special tools, in quantities specified in individual specification section.
 - .2 Provide items with tags identifying their associated function and equipment.
 - .3 Deliver to site; place and store.
 - .4 Receive and catalogue items.
 - .1 Submit inventory listing to Departmental Representative.
 - .2 Include approved listings in Maintenance Manual.

1.12 DELIVERY, STORAGE AND HANDLING

- .1 Store spare parts, maintenance materials, and special tools in manner to prevent damage or deterioration.
- .2 Store in original and undamaged condition with manufacturer's seal and labels intact.
- .3 Store components subject to damage from weather in weatherproof enclosures.
- .4 Store paints and freezable materials in a heated and ventilated room.
- .5 Remove and replace damaged products at own expense and for review by Departmental Representative.

1.13 WARRANTIES AND BONDS

- .1 Develop warranty management plan to contain information relevant to Warranties.
- .2 Submit warranty management plan, 30 days before planned pre-warranty conference, to Departmental Representative approval.
- .3 Warranty management plan to include required actions and documents to assure that Departmental Representative receives warranties to which it is entitled.
- .4 Provide plan in narrative form and contain sufficient detail to make it suitable for use by future maintenance and repair personnel.
- .5 Submit, warranty information made available during construction phase, to Departmental Representative for approval prior to each monthly pay estimate.
- .6 Assemble approved information in binder, submit upon acceptance of work and organize binder as follows:
 - .1 Separate each warranty or bond with index tab sheets keyed to Table of Contents listing.
 - .2 List subcontractor, supplier, and manufacturer, with name, address, and telephone number of responsible principal.

-
- .3 Obtain warranties and bonds, executed in duplicate by subcontractors, suppliers, and manufacturers, within ten days after completion of applicable item of work.
 - .4 Verify that documents are in proper form, contain full information, and are notarized.
 - .5 Co-execute submittals when required.
 - .6 Retain warranties and bonds until time specified for submittal.
 - .7 Except for items put into use with Owner's permission, leave date of beginning of time of warranty until Date of Substantial Performance is determined.
 - .8 Conduct joint 4 month and 9 month warranty inspection, measured from time of acceptance, by Departmental Representative .
 - .9 Include information contained in warranty management plan as follows:
 - .1 Roles and responsibilities of personnel associated with warranty process, including points of contact and telephone numbers within the organizations of Contractors, subcontractors, manufacturers or suppliers involved.
 - .2 Listing and status of delivery of Certificates of Warranty for extended warranty items, to include HVAC balancing, pumps, motors, transformers, and commissioned systems such as fire protection, alarm systems, sprinkler systems, lightning protection systems,.
 - .3 Provide list for each warranted equipment, item, feature of construction or system indicating:
 - .1 Name of item.
 - .2 Model and serial numbers.
 - .3 Location where installed.
 - .4 Name and phone numbers of manufacturers or suppliers.
 - .5 Names, addresses and telephone numbers of sources of spare parts.
 - .6 Warranties and terms of warranty: include one-year overall warranty of construction. Indicate items that have extended warranties and show separate warranty expiration dates.
 - .7 Cross-reference to warranty certificates as applicable.
 - .8 Starting point and duration of warranty period.
 - .9 Summary of maintenance procedures required to continue warranty in force.
 - .10 Cross-Reference to specific pertinent Operation and Maintenance manuals.
 - .11 Organization, names and phone numbers of persons to call for warranty service.
 - .12 Typical response time and repair time expected for various warranted equipment.

- .4 Contractor's plans for attendance at 4 and 9 month post-construction warranty inspections.
- .5 Procedure and status of tagging of equipment covered by extended warranties.
- .6 Post copies of instructions near selected pieces of equipment where operation is critical for warranty and/or safety reasons.

- .10 Respond in timely manner to oral or written notification of required construction warranty repair work.
- .11 Written verification to follow oral instructions.
 - .1 Failure to respond will be cause for the Departmental Representative to proceed with action against Contractor.

1.14 WARRANTY TAGS

- .1 Tag, at time of installation, each warranted item. Provide durable, oil and water resistant tag approved by Departmental Representative.
- .2 Attach tags with copper wire and spray with waterproof silicone coating.
- .3 Leave date of acceptance until project is accepted for occupancy.
- .4 Indicate following information on tag:
 - .1 Type of product/material.
 - .2 Model number.
 - .3 Serial number.
 - .4 Contract number.
 - .5 Warranty period.
 - .6 Inspector's signature.
 - .7 Construction Contractor.

PART 2 - PRODUCTS

2.1 NOT USED

- .1 Not Used.

PART 3 - EXECUTION

3.1 NOT USED

- .1 Not Used.

PART 1 - GENERAL

1.1 SUMMARY

- .1 Section Includes:
 - .1 General requirements relating to commissioning of project's components and systems, specifying general requirements to PV of components, equipment, sub-systems, systems, and integrated systems.
- .2 Related Requirements
 - .1 Section 01 00 10 - General Instructions.
- .3 Acronyms:
 - .1 AFD - Alternate Forms of Delivery, service provider.
 - .2 BMM - Building Management Manual.
 - .3 Cx - Commissioning.
 - .4 EMCS - Energy Monitoring and Control Systems.
 - .5 O&M - Operation and Maintenance.
 - .6 PI - Product Information.
 - .7 PV - Performance Verification.
 - .8 TAB - Testing, Adjusting and Balancing.

1.2 GENERAL

- .1 Cx is a planned program of tests, procedures and checks carried out systematically on systems and integrated systems of the finished Project. Cx is performed after systems and integrated systems are completely installed, functional and Contractor's Performance Verification responsibilities have been completed and approved. Objectives:
 - .1 Verify installed equipment, systems and integrated systems operate in accordance with contract documents and design criteria and intent.
 - .2 Ensure appropriate documentation is compiled into the BMM.
 - .3 Effectively train O&M staff.
- .2 Contractor assists in Cx process, operating equipment and systems, troubleshooting and making adjustments as required.
 - .1 Systems to be operated at full capacity under various modes to determine if they function correctly and consistently at peak efficiency. Systems to be interactively with each other as intended in accordance with Contract Documents and design criteria.
 - .2 During these checks, adjustments to be made to enhance performance to meet environmental or user requirements.
- .3 Design Criteria: as per client's requirements or determined by designer. To meet Project functional and operational requirements.

1.3 COMMISSIONING OVERVIEW

- .4 AFD managed projects the term Departmental Representative in Cx specifications to be interpreted as AFD Service Provider.
- .1 For Cx responsibilities refer to Section
- .2 Cx to be a line item of Contractor's cost breakdown.
- .3 Cx activities supplement field quality and testing procedures described in relevant technical sections.
- .4 Cx is conducted in concert with activities performed during stage of project delivery. Cx identifies issues in Planning and Design stages which are addressed during Construction and Cx stages to ensure the built facility is constructed and proven to operate satisfactorily under weather, environmental and occupancy conditions to meet functional and operational requirements. Cx activities includes transfer of critical knowledge to facility operational personnel.
- .5 Departmental Representative will issue Interim Acceptance Certificate when:
 - .1 Completed Cx documentation has been received, reviewed for suitability and approved by Departmental Representative.
 - .2 Equipment, components and systems have been commissioned.
 - .3 O&M training has been completed.

1.4 NON-CONFORMANCE TO PERFORMANCE VERIFICATION REQUIREMENTS

- .1 Should equipment, system components, and associated controls be incorrectly installed or malfunction during Cx, correct deficiencies, re-verify equipment and components within the unfunctional system, including related systems as deemed required by Departmental Representative, to ensure effective performance.
- .2 Costs for corrective work, additional tests, inspections, to determine acceptability and proper performance of such items to be borne by Contractor. Above costs to be in form of progress payment reductions or hold-back assessments.

1.5 PRE-CX REVIEW

- .1 Before Construction:
 - .1 Review contract documents, confirm by writing to Departmental Representative.
 - .1 Adequacy of provisions for Cx.
 - .2 Aspects of design and installation pertinent to success of Cx.
- .2 During Construction:

.1 Co-ordinate provision, location and installation of provisions for Cx.

.3 Before start of Cx:

- .1 Have completed Cx Plan up-to-date.
- .2 Ensure installation of related components, equipment, sub-systems, systems is complete.
- .3 Fully understand Cx requirements and procedures.
- .4 Have Cx documentation shelf-ready.
- .5 Understand completely design criteria and intent and special features.
- .6 Submit complete start-up documentation to Departmental Representative.
- .7 Have Cx schedules up-to-date.
- .8 Ensure systems have been cleaned thoroughly.
- .9 Complete TAB procedures on systems, submit TAB reports to Departmental Representative for review and approval.
- .10 Ensure "As-Built" system schematics are available.

.4 Inform Departmental Representative in writing of discrepancies and deficiencies on finished works.

1.6 CONFLICTS

- .1 Report conflicts between requirements of this section and other sections to Departmental Representative before start-up and obtain clarification.
- .2 Failure to report conflict and obtain clarification will result in application of most stringent requirement.

1.7 ACTION AND INFORMATIONAL SUBMITTALS

- .1 Submittals: in accordance with Section 01 33 00 - Submittal Procedures.
 - .1 Submit no later than 4 weeks after award of Contract:
 - .1 Name of Contractor's Cx agent.
 - .2 Draft Cx documentation.
 - .3 Preliminary Cx schedule.
 - .2 Request in writing to Departmental Representative for changes to submittals and obtain written approval at least 8 weeks prior to start of Cx.
 - .3 Submit proposed Cx procedures to Departmental Representative where not specified and obtain written approval at least 8 weeks prior to start of Cx.
 - .4 Provide additional documentation relating to Cx process required by Departmental Representative.

1.8 COMMISSIONING DOCUMENTATION

- .1 Departmental Representative to review and approve Cx documentation.

	.2	Provide completed and approved Cx documentation to Departmental Representative.
<u>1.9 COMMISSIONING SCHEDULE</u>	.1	Provide detailed Cx schedule as part of construction schedule.
	.2	Provide adequate time for Cx activities prescribed in technical sections and commissioning sections including: <ul style="list-style-type: none">.1 Approval of Cx reports..2 Verification of reported results..3 Repairs, retesting, re-commissioning, re-verification..4 Training.
<u>1.10 STARTING AND TESTING</u>	.1	Contractor assumes liabilities and costs for inspections. Including disassembly and re-assembly after approval, starting, testing and adjusting, including supply of testing equipment.
<u>1.11 WITNESSING OF STARTING AND TESTING</u>	.1	Provide 14 days notice prior to commencement.
	.2	Departmental Representative to witness of start-up and testing.
<u>1.12 MANUFACTURER'S INVOLVEMENT</u>		<u>SPEC NOTE:</u> Add the following wording to the relevant technical sections of the contract documents.
	.1	Factory testing: manufacturer to: <ul style="list-style-type: none">.1 Coordinate time and location of testing..2 Provide testing documentation for approval by Departmental Representative..3 Arrange for Departmental Representative to witness tests..4 Obtain written approval of test results and documentation from Departmental Representative before delivery to site.
	.2	Obtain manufacturers installation, start-up and operations instructions prior to start-up of components, equipment and systems and review with Departmental Representative. <ul style="list-style-type: none">.1 Compare completed installation with manufacturer's published data, record discrepancies, and review with manufacturer..2 Modify procedures detrimental to equipment performance and review same with manufacturer before start-up.
	.3	Integrity of warranties: <ul style="list-style-type: none">.1 Use manufacturer's trained start-up personnel where specified elsewhere in other divisions or required to maintain integrity of warranty.

.2 Verify with manufacturer that testing as specified will not void warranties.

- .4 Qualifications of manufacturer's personnel:
- .1 Experienced in design, installation and operation of equipment and systems.
 - .2 Ability to interpret test results accurately.
 - .3 To report results in clear, concise, logical manner.

1.13 PROCEDURES

- .1 Verify that equipment and systems are complete, clean, and operating in normal and safe manner prior to conducting start-up, testing and Cx.
- .2 Conduct start-up and testing in following distinct phases:
- .1 Included in delivery and installation:
 - .1 Verification of conformity to specification, approved shop drawings and completion of PI report forms.
 - .2 Visual inspection of quality of installation.
 - .2 Start-up: follow accepted start-up procedures.
 - .3 Operational testing: document equipment performance.
 - .4 System PV: include repetition of tests after correcting deficiencies.
 - .5 Post-substantial performance verification: to include fine-tuning.
- .3 Correct deficiencies and obtain approval from Departmental Representative after distinct phases have been completed and before commencing next phase.
- .4 Document require tests on approved PV forms.
- .5 Failure to follow accepted start-up procedures will result in re-evaluation of equipment by an independent testing agency selected by Departmental Representative. If results reveal that equipment start-up was not in accordance with requirements, and resulted in damage to equipment, implement following:
- .1 Minor equipment/systems: implement corrective measures approved by Departmental Representative.
 - .2 Major equipment/systems: if evaluation report concludes that damage is minor, implement corrective measures approved by Departmental Representative.
 - .3 If evaluation report concludes that major damage has occurred, Departmental Representative shall reject equipment.
 - .1 Rejected equipment to be remove from site and replace with new.
 - .2 Subject new equipment/systems to specified start-up procedures.

- | | | |
|--|----|---|
| <u>1.14 START-UP
DOCUMENTATION</u> | .1 | Assemble start-up documentation and submit to Departmental Representative for approval before commencement of commissioning. |
| | .2 | Start-up documentation to include: <ul style="list-style-type: none">.1 Factory and on-site test certificates for specified equipment..2 Pre-start-up inspection reports..3 Signed installation/start-up check lists..4 Start-up reports,.5 Step-by-step description of complete start-up procedures, to permit Departmental Representative to repeat start-up at any time. |
| <u>1.15 OPERATION AND
MAINTENANCE OF
EQUIPMENT AND
SYSTEMS</u> | .1 | After start-up, operate and maintain equipment and systems as directed by equipment/system manufacturer. |
| | .2 | With assistance of manufacturer develop written maintenance program and submit Departmental Representative for approval before implementation. |
| | .3 | Operate and maintain systems for length of time required for commissioning to be completed. |
| | .4 | After completion of commissioning, operate and maintain systems until issuance of certificate of interim acceptance. |
| <u>1.16 TEST RESULTS</u> | .1 | If start-up, testing and/or PV produce unacceptable results, repair, replace or repeat specified starting and/or PV procedures until acceptable results are achieved. |
| | .2 | Provide manpower and materials, assume costs for re-commissioning. |
| <u>1.17 START OF
COMMISSIONING</u> | .1 | Notify Departmental Representative at least 21 days prior to start of Cx. |
| | .2 | Start Cx after elements of building affecting start-up and performance verification of systems have been completed. |
| <u>1.18 INSTRUMENTS /
EQUIPMENT</u> | .1 | Submit to Departmental Representative for review and approval: <ul style="list-style-type: none">.1 Complete list of instruments proposed to be used..2 Listed data including, serial number, current calibration certificate, calibration date, calibration expiry date and calibration accuracy. |
| | .2 | Provide the following equipment as required: <ul style="list-style-type: none">.1 2-way radios. |

- .2 Ladders.
- .3 Equipment as required to complete work.

1.19 COMMISSIONING PERFORMANCE VERIFICATION

- .1 Carry out Cx:
 - .1 Under [actual] operating conditions, over entire operating range, in all modes.
 - .2 On independent systems and interacting systems.
- .2 Cx procedures to be repeatable and reported results are to be verifiable.
- .3 Follow equipment manufacturer's operating instructions.
- .4 EMCS trending to be available as supporting documentation for performance verification.

1.20 WITNESSING COMMISSIONING

- .1 Departmental Representative to witness activities and verify results.

1.21 AUTHORITIES HAVING JURISDICTION

- .1 Where specified start-up, testing or commissioning procedures duplicate verification requirements of authority having jurisdiction, arrange for authority to witness procedures so as to avoid duplication of tests and to facilitate expedient acceptance of facility.
- .2 Obtain certificates of approval, acceptance and compliance with rules and regulation of authority having jurisdiction.
- .3 Provide copies to Departmental Representative within 5 days of test and with Cx report.

1.22 EXTRAPOLATION OF RESULTS

- .1 Where Cx of weather, occupancy, or seasonal-sensitive equipment or systems cannot be conducted under near-rated or near-design conditions, extrapolate part-load results to design conditions when approved by Departmental Representative in accordance with equipment manufacturer's instructions, using manufacturer's data, with manufacturer's assistance and using approved formulae.

1.23 SUNDRY CHECKS AND ADJUSTMENTS

- .1 Make adjustments and changes which become apparent as Cx proceeds.
- .2 Perform static and operational checks as applicable and as required.

1.24 DEFICIENCIES, FAULTS, DEFECTS

- .1 Correct deficiencies found during start-up and Cx to satisfaction of Departmental Representative.
- .2 Report problems, faults or defects affecting Cx to Departmental Representative in writing. Stop Cx until

		problems are rectified. Proceed with written approval from Departmental Representative.
<u>1.25 COMPLETION OF COMMISSIONING</u>	.1	Upon completion of Cx leave systems in normal operating mode.
	.2	Except for warranty and seasonal verification activities specified in Cx specifications, complete Cx prior to issuance of Interim Certificate of Completion.
	.3	Cx to be considered complete when contract Cx deliverables have been submitted and accepted by Departmental Representative.
<u>1.26 ACTIVITIES UPON COMPLETION OF COMMISSIONING</u>	.1	When changes are made to baseline components or system settings established during Cx process, provide updated Cx form for affected item.
<u>1.27 MAINTENANCE MATERIALS, SPARE PARTS, SPECIAL TOOLS</u>	.1	Supply, deliver, and document maintenance materials, spare parts, and special tools as specified in contract.
<u>1.27 OCCUPANCY</u>	.1	Cooperate fully with Departmental Representative during stages of acceptance and occupancy of facility.
<u>1.29 INSTALLED INSTRUMENTATION</u>	.1	Use instruments installed under Contract for TAB and PV if: .1 Accuracy complies with these specifications. .2 Calibration certificates have been deposited with Departmental Representative.
	.2	Calibrated EMCS sensors may be used to obtain performance data provided that sensor calibration has been completed and accepted.
<u>1.30 PERFORMANCE VERIFICATION TOLERANCES</u>	.1	Application tolerances: .1 Specified range of acceptable deviations of measured values from specified values or specified design criteria. Except for special areas, to be within +/- 10% of specified values.
	.2	Instrument accuracy tolerances: .1 To be of higher order of magnitude than equipment or system being tested.
	.3	Measurement tolerances during verification: .1 Unless otherwise specified actual values to be within +/- 2 % of recorded values.

<u>1.31 OWNER'S PERFORMANCE TESTING</u>	.1	Performance testing of equipment or system by Departmental Representative will not relieve Contractor from compliance with specified start-up and testing procedures.
---	----	--

PART 2 - PRODUCTS

<u>2.1 NOT USED</u>	.1	Not Used.
---------------------	----	-----------

PART 3 - EXECUTION

<u>3.1 NOT USED</u>	.1	Not Used.
---------------------	----	-----------