

- | | |
|--|--|
| 1.
Material installation and
removal | <ul style="list-style-type: none">.1 Provide, set-up or lay out necessary installation on site to allow for work to be done within the shortest time possible..2 As work progresses, dismantle material not needed and remove of the site..3 Work done in 2 phases; limits see drawings..4 Scheduling, see section 01 32 18E and Ministerial representative's directives..5 The place of work is within an occupied building. The area bounded by the project will be at the disposal of the contractor..6 Since the site is still in operation, services will remain active at all times and open lanes for local traffic. |
| 2.
On-site storage – Admissible
charges | <ul style="list-style-type: none">.1 Ensure that work is done within the time limits stated in the contract. Do not clutter site unnecessarily with equipment and materials..2 Do not overload or allow overloading on any part of the work so as to not compromise its integrity..3 Provide and install weatherproof containers to store materials, tools and equipment sensitive to damage..4 Container's space must be determined by the Ministerial representative. |
| 3.
Sanitary installation | <ul style="list-style-type: none">.1 Sanitary facilities must be provided inside the security perimeter of the site area. |
| 4.
Signposting | <ul style="list-style-type: none">.1 Install, in pertinent areas, sign panels to indicate site limits, the direction of temporary relocated exits or other pertinent information. |
| 5.
Removal of temporary
installation | <ul style="list-style-type: none">.1 Remove from site all temporary installation when the Ministerial representative will judge it appropriate. |
| 6.
Protection of finished building
surfaces | <ul style="list-style-type: none">.1 During all the work period, protect all finished or partially finished surfaces, the existing equipments and furniture leaved in place..2 Foresee screens, tarps and necessary fences..3 Three (3) days prior to installation of protective components, confirm with the Ministerial representative where each protection will go. Confirm schedule for installation..4 Take all the responsibility for damage caused to works because of lack of protection or unsuitable protection. |
| 7.
Guardrails and barriers | <ul style="list-style-type: none">.1 Provide guardrails and rigid barriers and security and set them around deep excavations, service ducts and stairwells and not enclosed along the edges of floors and roofs. |

- .2 Supply and install these components in accordance with jurisdictional requirements.

***** END *****