



GENERAL NOTES


- WHERE WALL PATCHING OCCURS, PATCH AND PAINT ENTIRE WALL TO INTERSECTING WALLS.
- PROVIDE FIRESTOPPING MATERIALS THROUGH ALL FIRE RATED PARTITIONS AND FLOOR ASSEMBLIES.
- ALL NEW PARTITIONS TO HAVE PAINTED FINISH UNLESS OTHERWISE NOTED.

- KEYNOTES FOR FLOORS 3 & 4**
- PROVIDE ONE LAYER OF 16 TYPE 'X' GYPSUM BOARD ON THIS SIDE OF EXISTING PARTITION.
 - MILLWORK ITEM.
 - NEW LOUVER & WALL INFILL IN EXISTING WINDOW OPENING. SEAL AROUND PERIMETER INSIDE AND OUTSIDE. REFER TO MECHANICAL. INSTALL PARTITION CENTRED ON WINDOW MULLION.
 - INFILL OPENING MATCH EXISTING WALL CONSTRUCTION.
 - ALL NEW SCREENS AND WORKSTATIONS TO BE SUPPLIED AND INSTALLED BY OWNER. COORDINATE ELECTRICAL WORK UNDER THIS CONTRACT.
 - FURNITURE AND EQUIPMENT SHOWN LIGHTWEIGHT SUPPLIED AND INSTALLED BY OWNER.
 - METAL DETECTOR SUPPLIED BY OWNER. INSTALLATION UNDER THIS CONTRACT. COMMISSION EQUIPMENT.
 - X-RAY MACHINE SUPPLIED BY OWNER. INSTALLATION UNDER THIS CONTRACT. COMMISSION EQUIPMENT.
 - 150mm WIDE FLOOR IDENTIFICATION MARKING (CONTRASTING COLOUR OF FLOORING).
 - TV MONITOR CENTERED ON WALL SUPPLIED BY OWNER. PROVIDE PLYWOOD BACKING AND SOLID BLOCKING IN WALL. CONFIRM MOUNTING HEIGHT AND SIZES PRIOR TO INSTALLATION OF BLOCKING. REFER ALSO TO DETAIL 9/A6.1.
 - EXISTING BUILDING CONTROL JOINT. PROVIDE EXPANSION JOINT COVER.
 - PLUMBING FIXTURES: REFER TO MECHANICAL.
 - EXISTING METAL SHELVING (SHOWN LIGHTWEIGHT) TO REMAIN.
 - NEW INSERT EXTERIOR BUILDING EXPANSION JOINT, 4&5/A6.3
 - GALVANIZED METAL OPEN GRATE PLATFORM AND STAIRS, SUPPORTED ON HSS POST. REFER TO STRUCTURAL.
 - KEY SAFE. SUPPLIED BY OWNER, INSTALLED BY CONTRACTOR.
 - PROVIDE NEW CONVEX MIRROR.
 - PROVIDE FABRIC WINDOW SHADE AT EACH WINDOW LOCATION ON THIRD AND FOURTH FLOORS. SEE SPECIFICATION SECTION 12 21 00.
 - PROVIDE BLACK OUT WINDOW SHADE AT CELL WINDOW OPENING. SEE SPECIFICATION SECTION 12 21 00.
 - NEW METAL LOCKERS. SEE SPECIFICATION SECTION 10 51 13.
 - DETENTION FURNITURE.
 - INSTALL PARTITION 25mm OUTSIDE EDGE OF WINDOW FRAME.
 - PROVIDE POCKET WIDTH AND DEPTH TO SUIT MANUFACTURER'S REQUIREMENTS.
 - ELECTRICAL EQUIPMENT.
 - PROVIDE BLACK OUT WINDOW SHADE AT EACH WINDOW OPENING IN ROOM. SEE SPECIFICATION SECTION 12 21 00.
 - FIRE STOP ALL FLOOR AND WALL PENETRATIONS.
 - PROVIDE 450mm WIDE x 1300mm HIGH FIBRE REINFORCED PANELS ON TWO WALLS BEHIND NEW MOP SINK c/w STAINLESS STEEL PERIMETER TRIM; CAULK AT SINK.
 - PAINT GAME LINES ON FLOOR. SEE ALSO SECTION 09 65 19.
 - BREAK CABINET AT WALL. DO NOT CARRY CABINET THROUGH WALL.
 - FURR OUT WALL TO SUIT.
 - NEW MOP SINK- REFER TO MECHANICAL.
 - FLOOR EXPANSION JOINT DETAIL. REFER TO DETAILS 1-4/A6.3
 - AT NEW PARTITION, PROVIDE NEW RUBBER BASE AND PAINT ENTIRE PARTITION ON BOTH SIDES.
 - APPLY LAYER OF 10mm GYPSUM BOARD TO ALL EXTERIOR WALLS IN RENOVATED AREAS OF 3RD & 4TH FLOORS. FINISH INTO WINDOW RECESS (PAINT)
 - FINISH WALL BEHIND CELLS (PAINT)



SEPW Architecture Inc.

100 - 3725 Praeger Street, Regina, SK, S4S 0R8, ph: (306) 968-2255
 1102 - 3718 Victoria Place, Saskatoon, SK, S7P 0A6, ph: (306) 652-6457
 website: www.sepw.ca



DO NOT SCALE DRAWINGS

Revision/Revision	Description/Description	Date/Date
0	ISSUED FOR TENDER	2014-01-17

Project title/Titre du projet
SHARED LEARNING FACILITY
 REGINA, SK

Approved by/Approve par
 Designed by/Concept par
 RP
 Drawn by/Dessine par
 RHM/RP
 Project Manager/Administrateur de Projets
 AC
 Architectural and Engineering Resources Manager/
 Ressources Architectural et de Directeur d'ingénierie

Drawing title/Titre du dessin
FOURTH FLOOR PLAN
PENTHOUSE PLAN

Project No./No. du projet
05/2013
 Sheet/Feuille
A2.12
 Revision no./
 La Révision
0