

**Part 1            General**

**1.1            DESCRIPTION**

- .1        This section specifies requirements for removing wholly or in part various items designated to be removed or partially removed. This section also includes the stockpiling and reinstallation of selected reusable materials and the disposal of the waste construction materials.
- .2        The treated timber material being removed shall become the property of the Contractor and must be disposed as per Section 01 74 19.
- .3        Remove all electrical systems not to be re-used as indicated on the drawings.
- .4        Contractor to salvage existing power poles for re-use where indicated.

**1.2            RELATED WORK**

- .1        Waste Management and Disposal Plan: Section 01 74 19.

**1.3            PROTECTION**

- .1        Protect existing objects designated to remain. In event of damage, immediately replace or make repairs to approval of and at no additional cost to Departmental Representative.

**1.4            MEASUREMENT**

- .1        Site Work:
  - .1        All plant as specified including labour and the cost for the removal of the items of work designated for removal, reuse and disposal will constitute a fixed price item for measurement purposes.
  - .2        It includes materials removed which are:
    - .1        Salvaged and turned over to wharf authority;
    - .2        re-used in the new work and;
    - .3        disposed off the site.
- .2        There will not be any separate payment for the reinstatement of work that was temporarily removed for the installation of the new work. These works include the following:
  - .1        Electrical services.
  - .2        Backfill.
  - .3        Include cost for this work in the lump sum payment.
- .3        There will not be any separate payment for the use of any treated timber material that was removed and reused in the work, including materials use by the Contractor as formwork.

- .4 There will not be any separate payment for implementing the Materials Source Separation Program for this project as described in Section 01 74 19 Waste Management.
- .5 Disposal of Treated Timber: as specified including all plant, labour and the cost for disposal of the treated timber material at an approved regional land fill site will be included in Site Work. Included in this item is the cost for tipping fee to dispose of the waste material at an approved disposal site.
- .6 Disposal of Construction Waste: there will not be any separate item for payment for the disposal of the waste construction material at an approved regional land fill site. Contractor will provide a copy of the weight slip from the disposal facility.

**Part 2 Products**

Not applicable.

**Part 3 Execution**

**3.1 EXECUTION**

- .1 Inspect site and verify with Departmental Representative objects designated for removal.
- .2 Locate and protect utility lines. Preserve in operating condition active utilities transversing site.

**3.2 UTILITIES**

- .1 Make arrangement with utilities for the removal of electrical wires and light fixtures.

**3.3 REMOVAL**

- .1 Remove in their entirety all materials and objects specified for removal. Carefully remove materials designated to be reused.
- .2 Do not disturb adjacent work designated to remain in place.
- .3 Verify with Departmental Representative items to be reused in the work.

**3.4 DISPOSAL OF MATERIAL**

- .1 All demolished materials, except materials designated to be reused or saved will become property of Contractor and will be removed from site and disposed of as stated herein.

- .2 Provide the Departmental Representative with a copy of the proposed disposal site to be used for review and approval.
- .3 Any materials that are salvaged for reuse must be stored in an approved location. The Contractor is required to provide, in writing, the proposed location for the storage of the reusable material for approval.

### **3.5 RESTORATION**

- .1 Upon completion of work, remove debris, trim surfaces and leave work site in clean condition.
- .2 Reinstate areas and existing works outside areas of demolition to conditions that existed prior to commencement of work.

### **3.6 ELECTRICAL**

- .1 The electrical services that are disrupted or removed are to be reinstalled at the completion of the work.

### **3.7 REINSTALLATION**

- .1 Reinstall those items that were removed to permit the completion of the work.

**END OF SECTION**