

RETURN BIDS TO:
RETOURNER LES SOUMISSIONS À:
Public Works and Government Services Canada
Telus Plaza North/Plaza Telus Nord
10025 Jasper Ave./10025 ave. Jaspe
5th floor/5e étage
Edmonton
Alberta
T5J 1S6
Bid Fax: (780) 497-3510

SOLICITATION AMENDMENT

MODIFICATION DE L'INVITATION

The referenced document is hereby revised; unless otherwise indicated, all other terms and conditions of the Solicitation remain the same.

Ce document est par la présente révisé; sauf indication contraire, les modalités de l'invitation demeurent les mêmes.

Comments - Commentaires

Vendor/Firm Name and Address
Raison sociale et adresse du
fournisseur/de l'entrepreneur

Issuing Office - Bureau de distribution
Public Works and Government Services Canada
Telus Plaza North/Plaza Telus Nord
10025 Jasper Ave./10025 ave. Jasper
5th floor/5e étage
Edmonton
Alberta
T5J 1S6

Title - Sujet Parks Canada Trail Bridges Work	
Solicitation No. - N° de l'invitation E0209-142223/A	Amendment No. - N° modif. 005
Client Reference No. - N° de référence du client PARKS - 20142223	Date 2014-03-14
GETS Reference No. - N° de référence de SEAG PW-\$PWU-011-10126	
File No. - N° de dossier PWU-3-36321 (011)	CCC No./N° CCC - FMS No./N° VME
Solicitation Closes - L'invitation prend fin at - à 02:00 PM on - le 2014-03-28	Time Zone Fuseau horaire Mountain Daylight Saving Time MDT
F.O.B. - F.A.B. Plant-Usine: <input type="checkbox"/> Destination: <input checked="" type="checkbox"/> Other-Autre: <input type="checkbox"/>	
Address Enquiries to: - Adresser toutes questions à: Hugo (RPC), Tammey	Buyer Id - Id de l'acheteur pwu011
Telephone No. - N° de téléphone (780) 497-3917 ()	FAX No. - N° de FAX (780) 497-3510
Destination - of Goods, Services, and Construction: Destination - des biens, services et construction:	

Instructions: See Herein

Instructions: Voir aux présentes

Delivery Required - Livraison exigée	Delivery Offered - Livraison proposée
Vendor/Firm Name and Address Raison sociale et adresse du fournisseur/de l'entrepreneur	
Telephone No. - N° de téléphone Facsimile No. - N° de télécopieur	
Name and title of person authorized to sign on behalf of Vendor/Firm (type or print) Nom et titre de la personne autorisée à signer au nom du fournisseur/ de l'entrepreneur (taper ou écrire en caractères d'imprimerie)	
Signature	Date

ADDENDUM FIVE (5)

The following Clarifications to the Tender Documents are affective immediately. This addendum will form part of the contract documents.

SPECIFICATIONS

1.0 SECTION 011155 - GENERAL INSTRUCTIONS

- 1.1 Paragraph 1.22.2, **Revise** to read 'Contractor is responsible for retaining and paying for the services of a professional Geotechnical Engineer registered in the province of British Columbia for the environmental mat use on Fire Road access.'

(from 'Contractor is responsible for retaining and paying for the services of a professional Geotechnical Engineer registered in the province of British Columbia for the environmental mat use on Fire Road access, micro-pile design, foundation bearing, and review of trail subgrade conditions.')

2.0 SECTION 012901 - MEASUREMENT AND PAYMENT

- 2.1 **Delete** Section 012901 - Measurement and Payment. **Clarification**, The Work is to be bid as a Lump Sum contract. Refer to the Bid and Acceptance Form (BA).
- 2.2 **Clarification**, Assume an estimated quantity of 202 lineal metres (m) for the micro-piles.
- 2.3 **Clarification**, Assume an estimated quantity of 250 square metres (m2) for the rip-rap placement.
- 2.4 **Clarification**, Assume an estimated quantity of 12 lineal metres (m) for the trail re-alignment (1.5m width) at Stanley Glacier.
- 2.5 **Clarification**, Assume an estimated quantity of 90 cubic metres (m3) for the rip-rap removal at Paint Pots.

3.0 SECTION 316813 - SOIL ANCHORS

- 3.1 **Delete** Paragraph 2.1.9.
- 3.2 Paragraph 3.1.1, **Revise** to read 'All anchor installation work shall be carried out in accordance with the approval of the Departmental Representative.'
- (from 'All anchor installation work shall be carried out in accordance with the approval of the Contractor's Geotechnical Engineer.')
- 3.3 Paragraph 3.1.14, **Revise** to read 'If the total grout volume consumed in any hole exceeds three times the theoretical volume of the drill hole, work shall be stopped and the Departmental Representative notified immediately.'
- (from 'If the total grout volume consumed in any hole exceeds three times the theoretical volume of the drill hole, work shall be stopped and the Contractor's Geotechnical Engineer and Departmental Representative notified immediately.')

- 3.4 Paragraph 3.2.2, **Revise** to read 'Carry out performance, proof and creep tests in accordance with these specifications by a Testing Agency retained and paid for by the Contractor and approved by the Departmental Representative.'

(from 'Carry out performance, proof and creep tests in accordance with these specifications by a Professional Geotechnical Engineer retained by the Contractor and approved by the Departmental Representative.')

- 3.5 Paragraph 3.2.4, **Revise** to read 'Notify the Departmental Representative 48 hours prior to testing the anchors.'

(from 'Testing shall be reviewed by the Contractor's Geotechnical Engineer. Notify the Departmental Representative 48 hours prior to testing the anchors.')

- 3.6 Paragraph 3.2.13, **Revise** to read 'As directed by the Departmental Representative, anchors which fail any or all of the acceptance criteria will be re-tested, de-rated or replaced.'

(from 'At the Contractor's Geotechnical Engineer's option, anchors which fail any or all of the acceptance criteria will be re-tested, de-rated or replaced.')

End of Addendum