



Project Title: Emergency Generator Installation
Building 56
Central Experimental Farm (CEF), Ottawa (Ontario)

Solicitation No: 13-1427

March 14, 2014

The following changes in the tender documents are effective immediately. This addendum will form part of the contract documents

Q & A

Q17. Is the electric meter at building 56 owned by the Government or by Hydro Ottawa?

A17. AAFC is the owner of the electric meter located at building 56.

Q18. Is the electric transformer feeding building 56 the property of the government or Hydro Ottawa?

A18. The electric transformer feeding building 56 is the property of the Government of Canada.

Q19. Drawing 1/E100 indicates 2x [4-250MCM+GND- 100mm] and drawing 4/E101 indicates 2x4-500MCM+GND-100mmC. Can you provide precisions?

A19. The project requires 2 x 4-250MCM + Malt in a 100mm. See included modifications to drawings.

Q20. In drawing 3/E100 there is a note 20 that does not appear in the details?

A20. Note 20 do not apply and is being deleted.

Q21. At drawing E100, Note 1 “Skip mounted fuel tank complete with fuel pumps”. Is this information complementary and/or compliant with article 2.11.1.1 of section 26 32 14?

A21. Refer to Item 3 of “Specifications” Part of Addendum 1 which indicates “for generator set complete with 48 hour sub-base fuel tank”.

Q22. Can you provide specifications for the exterior light fixtures “B” as per drawing 3/E100?

A22. Those fixtures must be exterior wall pack fully cut-off LED lighting fixture c/w photo-cell control for dusk to dawn operation.

Q23. What are the specifications for the horn/strobe indicated at note 8 of E100?

A23. The provided horn/strobe must be compliant to all applicable codes, laws, norms or rules in effect for exterior use.

Q24. Can you provide the panel schedule for Panel “EA” of note 2 of drawing E101?

A24. Refer to article 2.5.5 of section 26 32 14.

Q25. In the French Specifications, at article 2.3.1.2 is indicated a “compteur numérique sur les deux disjoncteurs d’arrivée”. Can you precise?

A25. See included modifications to the French Specifications.

Q26. What is required in terms of warranty?

A26. Refer to GC3.13 of the General Conditions and clauses under the Contract Documents (CD).



Addendum 2

Project Title: Emergency Generator Installation
Building 56
Central Experimental Farm (CEF), Ottawa (Ontario)

Solicitation No: 13-1427 March 14, 2014

Q27. Article 3.3.1.2.6.15 of section 26 32 14 indicates to “Perform a second 4 hour load testing utilizing building loads. Must a 4 hours 100% load test with resistive load banks on site and then a 4 hours building load test be performed?”

A27. Perform a 4 hours 100% load test with resistive load bank on site and then a 4 hour building load is required.

INVITATION TO TENDER

1. At Front Page “Invitation to Tender”:

Delete: Eastern Standard Time (EST)

Insert: Daytime Saving Time (DST)

SPECIFICATIONS

1. At Section 26 32 14 “Diesel Generator”, Article 2.8.1:

Delete: 24

Replace with: 48

DRAWINGS

1. At Drawing E101 “Partial Basement Ground Floor Plans, Single Line Diagrams”, 4/E101:

Delete: 2 x 4-500MCM+GND-100mmC

Replace with: 2 x 4-250MCM+GND-100mmC

ALL OTHER TERMS AND CONDITIONS REMAIN THE SAME