

VEVTEV – Accumulation Cell 2 Hour Fire Separation

335 River Road
Ottawa, ON

Issued for Tender

November 8, 2013

Project No: K4A22-13-0088

C i v i l t a s A r c h i t e c t u r e I n c .
DesignBuild Architecture Project Management
14 Chamberlain Ave., Suite 101, Ottawa, Ontario. K1S 1V9



DIVISION 00 PROCUREMENT AND CONTRACTING REQUIREMENTS

00 00 01	PROJECT COVER PAGE _____	2
00 00 10	SPECIFICATION INDEX _____	2

DIVISION 01 GENERAL REQUIREMENTS

01 00 10	GENERAL INSTRUCTIONS _____	10
01 30 00	ADMINISTRATIVE REQUIREMENTS _____	4
01 33 00	SUBMITTAL REQUIREMENTS _____	4
01 35 30	HEALTH AND SAFETY REQUIREMENTS _____	4
01 35 43	ENVIRONMENTAL PROCEDURES _____	4
01 41 00	REGULATORY REQUIREMENTS _____	2
01 45 00	QUALITY CONTROL _____	2
01 51 00	TEMPORARY UTILITIES _____	2
01 52 00	CONSTRUCTION FACILITIES _____	2
01 56 00	TEMPORARY BARRIERS AND ENCLOSURES _____	2
01 61 00	COMMON PRODUCT REQUIREMENTS _____	4
01 73 00	EXECUTION REQUIREMENTS _____	2
01 73 29	ALTERATIONS AND MAKING GOOD PROCEDURES _____	4
01 74 11	CLEANING _____	2
01 74 21	CONSTRUCTION/DEMOLITION WASTE MANAGEMENT AND DISPOSAL _____	4
01 77 00	CLOSEOUT PROCEDURES _____	2
01 78 00	CLOSEOUT SUBMITTALS _____	6

DIVISION 02 EXISTING CONDITIONS

02 41 99	DEMOLITION FOR MINOR WORKS _____	2
02 81 01	HAZARDOUS MATERIALS _____	4

DIVISION 05 METALS

05 50 00	METAL FABRICATIONS _____	4
----------	--------------------------	---

DIVISION 07 THERMAL AND MOISTURE PROTECTION

07 21 16	BLANKET INSULATION _____	2
07 81 20	INTUNMESCENT FIRE RESISTIVE MATERIAL _____	4
07 84 00	FIRE STOPPING _____	4
07 92 00	JOINT SEALANTS _____	4

DIVISION 08 OPENINGS

08 11 00	METAL DOORS AND FRAMES _____	4
08 33 23.01	OVERHEAD COILING DOORS AND GRILLES _____	6
08 71 00	DOOR HARDWARE _____	4

DIVISION 09 FINISHES

09 21 16	GYPSUM BOARD ASSEMBLIES _____	4
09 22 16	NON-STRUCTURAL METAL FRAMING _____	4
09 91 23	INTERIOR PAINTING _____	12

END OF SECTION

PAGE INTENTIONALLY LEFT BLANK

-
- 1 Minimum Standards .1 Materials shall be new and work shall conform to the minimum applicable standards of the Canadian General Standards Board, the Canadian Standards Association, the National Building Code of Canada 2010 (NBC) and all applicable Provincial and Municipal codes. In the case of conflict or discrepancy the most stringent requirement shall apply.
- 5 Taxes .1 Pay all taxes properly levied by law (including Federal, Provincial and Municipal).
- 6 Fees, Permits, and Certificates .1 Pay all fees and obtain all permits. Provide authorities with plans and information for acceptance certificates. Provide inspection certificates as evidence that work conforms to requirements of Authority having jurisdiction.
- 7 Fire Safety Requirements .1 Comply with the National Building Code of Canada 2010 (NBC) for fire safety in construction and the National Fire Code of Canada 2010 (NFC) for fire prevention, firefighting and life safety in building in use.
- .2 Welding and cutting:
- .1 Before welding, soldering, grinding and/or cutting work, obtain a permit from the Fire Prevention Unit as directed by the Departmental Representative. Store flammable liquids in approved CSA containers inspected by the Fire Prevention Unit. No open flame shall be used unless authorized by the Fire Prevention Unit.
- .2 At least 48 hours prior to commencing cutting, welding or soldering procedure, provide to Departmental Representative:
- .1 Notice of intent, indicating devices affected, time and duration of isolation or bypass.
- .2 Completed welding permit as defined in FC 302.
- .3 Return welding permit to Departmental Representative immediately upon completion of procedures for which permit was issued.
- .3 A fire watcher as described in FC 302 shall be assigned when welding or cutting operations are carried out in areas where combustible materials within 10m may be ignited by conduction or radiation.
- .3 Where work requires interruption of fire alarms or fire suppression, extinguishing or protection systems:
- .1 Provide watchman service as described in FC 301; In general, watchman service is defined as an individual conversant with Fire Emergency Procedures, performing fire picket duty within an unprotected and unoccupied (no workers) area once per hour.
- .2 Retain services of manufacturer for fire protection systems on daily basis or as approved by FCC, to isolate and protect all devices relating to:
- .1 modification of fire alarms, fire suppression, extinguishing or protection systems; and/or
- .2 cutting, welding, soldering or other construction activities which might activate fire protection systems.
- .4 Immediately upon completion of work, restore fire protection systems to normal operation and verify that all devices are fully operational.
- .5 Inform fire alarm system monitoring agency and local Fire Department immediately prior to isolation and immediately upon restoration of normal operation.
- 8 Field Quality Control .1 Carry out Work using qualified licensed workers or apprentices in

accordance with Provincial Act respecting manpower vocational training and qualification.

- .2 Permit employees registered in Provincial apprenticeship program to perform specific tasks only if under direct supervision of qualified licensed workers.
- .3 Determine permitted activities and tasks by apprentices, based on level of training attended and demonstration of ability to perform specific duties.

9 Hazardous Materials

- .1 Comply with the requirements of the Workplace Hazardous Materials Information System (WHMIS) regarding use, handling, storage, and disposal of hazardous materials; and regarding labeling and the provision of Material Safety Data Sheets (MSDS) acceptable to Human Resources Development Canada, Labour Program.
- .2 For work in occupied buildings give the Departmental Representative 48 hours' notice for work involving designated substances (Ontario Bill 208), hazardous substances (Canada Labour Code Part II Section 10), and before painting, caulking, installing carpet or using adhesives.

11 Removed Materials

- .1 Unless otherwise specified, materials for removal become the Contractor's property and shall be taken from site.

12 Protection

- .1 Protect finished work against damage until take-over.
- .2 Protect adjacent work against the spread of dust and dirt beyond the work areas.
- .3 Protect operatives and other users of site from all hazards.

13 Use of Site and Facilities

- .1 Execute work with least possible interference or disturbance to the normal use of premises. Make arrangements with Departmental Representative to facilitate work as stated. Refer to article 32 Scheduling below for work that must be done during "off hours".
- .2 Maintain existing services to building and provide for personnel and vehicle access.
- .3 Where security is reduced by work provide temporary means to maintain security.
- .4 Where elevators, dumbwaiters, conveyors or escalators exist Contractor may use these at Departmental Representative's discretion. Protect from damage, safety hazards and overloading of existing equipment.
- .5 Sanitary facilities will be assigned for Contractor's personnel. Others shall not be used. Keep facilities clean.
- .6 Closures: Protect work temporarily until permanent enclosures completed.

15 Cut, Patch and Make Good

- .1 Cut existing surfaces as required to accommodate new work.
- .2 Remove all items so shown or specified.
- .3 Patch and make good surfaces cut, damaged or disturbed, to

- Departmental Representative's approval. Match existing material, colour, finish and texture.
- 16 Sleeves, Hangers and Inserts .1 Co-ordinate setting and packing of sleeves and supply and installation of hangers and inserts. Obtain Departmental Representative's approval before cutting into structure.
- 17 Examination .1 Examine site and conditions likely to affect work and be familiar and conversant with existing conditions.
- .2 Provide photographs of surrounding properties, objects and structures liable to be damaged or be the subject of subsequent claims.
- 18 Signs .1 Provide common-use signs related to traffic control, information, instruction, use of equipment, public safety devices, etcetera, in both official languages or by the use of commonly-understood graphic symbols to the Departmental Representative's approval.
- .2 No advertising will be permitted on this project.
- .3 The Departmental Representative will provide a sign describing the project for the information of building users. Install the sign at entrance door of construction space.
- 19 Access and Egress .1 Design, construct and maintain temporary "access to" and "egress from" work areas, including stairs, runways, ramps or ladders and scaffolding, independent of finished surfaces and in accordance with relevant municipal, provincial and other regulations.
- 20 Scaffolds and Work Platforms .1 Design, install, and inspect scaffolds and work platforms required for work in accordance with relevant municipal, provincial and other regulations.
- .2 Provide design drawings, signed and sealed by qualified Professional Departmental Representative licensed in the province of Ontario, where prescribed.
- .3 Additions or modifications to scaffolding must be approved by Professional Departmental Representative in writing.
- 25 Guarantees and Warranties .1 Before completion of work collect all manufacturer's guarantees and warranties and submit to Departmental Representative.
- 27 Security Clearances .1 All personnel employed on this project will be subject to security check. Obtain requisite clearance, as instructed, for each individual required to enter the premises.
- .2 Personnel will be checked daily at start of work shift and given a pass which must be worn at all times. Pass must be returned at end of work shift and personnel checked out.
- 28 Security Escort .1 All personnel employed on this project shall be escorted when executing work in non-public areas during normal working hours. Personnel shall be escorted in all areas after normal working hours.
- .2 Submit an escort request to Departmental Representative at least 14 days before the service is needed. For requests submitted within the

time mentioned above, the costs of the security escort will be paid for by the Departmental Representative. The cost incurred by a late request will be charged to the Contractor.

.3 Any escort request may be cancelled free of charge if notification of cancellation is given at least 4 hours before the scheduled time of the escort. The cost incurred by a late cancellation will be charged to the Contractor.

.4 The calculation of costs will be based on the average hourly rate of a security officer for a minimum of eight hours per day for a late service request and of four hours for late cancellations.

29 Building Smoking Environment .1 Smoking is not permitted in the Building. Obey smoking restrictions on building property.

30 Dust Control .1 Provide dust tight screens or partitions to localize dust generating activities, and for protection of workers, finished areas of work and public.

.2 Maintain and relocate protection until such work is complete.

.3 Protect all furnishings within work area with 0.102 mm thick polyethylene film during construction. Remove film during non-construction hours and leave premises in clean, unencumbered and safe manner for normal daytime function.

32 Scheduling .1 On award of contract submit bar chart construction schedule for work, indicating anticipated progress stages within time of completion. When schedule has been reviewed by the Departmental Representative, take necessary measures to complete work within scheduled time. Do not change schedule without notifying Departmental Representative.

33 Cost Breakdown .1 Before submitting first progress claim submit breakdown of Contract Amount in detail as directed by Departmental Representative and aggregating the Contract Amount. After approval by Departmental Representative cost breakdown will be used as the basis of progress payments

34 Precedence .1 For Federal Government projects, Division 01 Sections take precedence over technical specification sections in other Divisions of this Project Manual.

END OF SECTION

Part 1 General**1.1 COORDINATION**

- .1 Perform coordination of progress schedules, submittals, use of site, temporary utilities, construction facilities, and construction Work, with progress of Work of others.
 - .1 Liaise between all subcontractors and consultant regarding the work. Follow up all verbal communication in writing; receive, review, clarify and acknowledge all communication, including; requests for information, shop drawings, etc., prior to forwarding to Departmental Representative.

1.2 PROJECT MEETINGS

- .1 Schedule and administer bi-weekly project meetings throughout progress of Work as determined by Departmental Representative.
 - .1 Project meetings shall not be used as a forum for detailed construction coordination relating to means, methods, techniques sequences, procedures, etc. between contractors and sub contractors, which are to be dealt with during the course of the work and covered at Construction Progress Meetings between contractor and sub contractors.
 - .2 Typically attendees shall include the project representatives for the contractor, major subcontractors, client, consultant and major sub consultants; schedule representatives for other subcontractors, sub consultants, companies or authorities where required.
- .2 Schedule and administer pre-installation meetings when specified in sections and when required to coordinate related or affected Work.
- .3 Prepare agenda for meetings and distribute written notice of each meeting in advance of meeting date to Departmental Representative.
- .4 Departmental Representative shall provide physical space and make arrangements for meetings.
- .5 Preside at meetings and record minutes. Include significant proceedings and decisions. Identify action by parties.
- .6 Produce and distribute copies of minutes within three (3) days after each meeting and transmit to all meeting participants, affected parties not in attendance.

1.3 CONSTRUCTION ORGANIZATION AND START-UP

- .1 Within five (5) days after award of Contract, request a meeting of parties in contract to discuss and resolve administrative procedures and responsibilities.
- .2 Establish time and location of meeting and notify parties concerned minimum three (3) days before meeting.
- .3 Agenda to include following:
 - .1 Appointment of official representative of participants in Work.
 - .2 Schedule of Work and progress scheduling.
 - .3 Schedule of submission of shop drawings, samples, colour chips.
 - .4 Requirements for temporary facilities, site sign, offices, storage sheds, utilities, fences.

- .5 Delivery schedule of specified equipment.
- .6 Site safety and security.
- .7 Proposed changes, change orders, procedures, approvals required, mark-up percentages permitted, time extensions, overtime, and administrative requirements.
- .8 Owner-furnished Products.
- .9 Record drawings and a process for maintaining them current during the Work.
- .10 Maintenance material and data.
- .11 Take-over procedures, acceptance, and warranties.
- .12 Monthly progress claims, administrative procedures, photographs, and holdbacks.
- .13 Appointment of inspection and testing agencies or firms.
- .14 Insurances and transcript of policies.
- .4 During construction, coordinate use of site and facilities.
- .5 Activate procedures for intra-project communications: Submittals, reports and records, schedules, coordination of drawings, recommendations, and resolution of ambiguities and conflicts.

1.4 SCHEDULES

- .1 Submit preliminary construction progress schedule to Departmental Representative.
- .2 After review, revise and resubmit schedule to comply with revised project schedule.
- .3 During progress of Work revise and resubmit as directed by Departmental Representative.

1.5 CONSTRUCTION PROGRESS MEETINGS

- .1 During course of Work schedule bi-weekly progress meetings.
- .2 Notify affected parties minimum five (5) days prior to meetings.
- .3 Record minutes of meetings and circulate to attending parties and affected parties not in attendance within three (3) days after meeting.
- .4 Agenda to include following:
 - .1 Review, approval of minutes of previous meeting.
 - .2 Review of Work progress since previous meeting.
 - .3 Field observations, problems, conflicts.
 - .4 Problems which impede construction schedule.
 - .5 Review of off-site fabrication delivery schedules.
 - .6 Corrective measures and procedures to regain projected schedule.
 - .7 Revision to construction schedule.
 - .8 Progress schedule, during succeeding work period.
 - .9 Review submittal schedules: expedite as required.
 - .10 Maintenance of quality standards.
 - .11 Review proposed changes for affect on construction schedule and on completion date.
 - .12 Review site safety and security issues.
 - .13 Other business.

1.6 SCHEDULES

- .1 Submit schedules as follows:
 - .1 Submittal schedule for shop drawings, product data, samples, timeliness of Owner-furnished Products and delivery schedule.
 - .2 Shut down or closure activity.
 - .3 Prepare schedule in form of a horizontal Gantt bar chart.
- .2 Schedule Submission
 - .1 Submit initial format of schedules within ten (10) working days after award of Contract.
 - .2 Submit schedules in electronic format, forward by e-mail.
 - .3 Consultant will review schedule and return review copy within five (5) days after receipt.
 - .4 Submit revised progress schedule with each application for payment.

1.7 CONSTRUCTION PROGRESS SCHEDULING

- .1 Submit initial schedule in duplicate within ten (10) days after date of Owner-Contractor Agreement or established in Notice to Proceed.
- .2 Revise and resubmit as required.
- .3 Submit revised schedules with each Application for Payment, identifying changes since previous version.

1.8 WASTE MANAGEMENT PLAN

- .1 Departmental Representative requires waste to be reused, salvaged, or recycled. Waste disposal in landfills shall be minimized.
- .2 Draft a waste management plan within ten (10) days after receipt of notice of award of bid, or prior to any waste removal, whichever occurs sooner; to the Consultant for review.
- .3 Subcontractors and others on site to cooperate fully with Contractor to implement the plan.
- .4 Failure to cooperate may result in Contractor being assessed penalties by a local regulatory jurisdiction.

1.9 STORAGE, HANDLING AND PROTECTION

- .1 Store, materials to be reused, recycled and salvaged in locations as directed by Departmental Representative.
- .2 Protect, stockpile, store salvaged items.
- .3 Separate non-salvageable materials from salvaged items. Transport and deliver non-salvageable items to licensed disposal facility.
- .4 Protect surface drainage, storm sewers, sanitary sewers, and utility services from damage or blockage.
- .5 Handle waste materials not reused, salvaged, or recycled in accordance with appropriate regulations and codes.

1.10 DISPOSAL OF WASTE

- .1 Burying rubbish and waste materials is prohibited.
- .2 Disposal of waste, volatile materials, mineral spirits, oil, paint thinner, into waterways, storm, sanitary sewers, or on site is prohibited.

1.11 CLEANING

- .1 Remove tools and waste materials on completion of work, and leave work area and site in clean and orderly condition.
- .2 Clean-up work area as work progresses.
- .3 Source separate materials to be reused/recycled into specified sort areas.

1.12 PERSONNEL SMOKING

- .1 Comply with regulatory imposed tobacco smoking restrictions during execution of the Work.

END OF SECTION

Part 1 General**1.1 ADMINISTRATIVE**

- .1 Submit to Departmental Representative submittals listed for review. Submit promptly and in orderly sequence to not cause delay in Work. Failure to submit in ample time is not considered sufficient reason for extension of Contract Time and no claim for extension by reason of such default will be allowed.
- .2 Do not proceed with Work affected by submittal until review is complete.
- .3 Present shop drawings, product data, samples and mock-ups in SI Metric units.
- .4 Where items or information is not produced in SI Metric units converted values are acceptable. Review submittals prior to submission to Departmental Representative. This review represents that necessary requirements have been determined and verified, or will be, and that each submittal has been checked and co-ordinated with requirements of Work and Contract Documents. Submittals not stamped, signed, dated and identified as to specific project will be returned without being examined and considered rejected.
- .5 Notify Departmental Representative, in writing at time of submission, identifying deviations from requirements of Contract Documents stating reasons for deviations.
- .6 Verify field measurements and affected adjacent Work is co-ordinated.
- .7 Contractor's responsibility for errors and omissions in submission is not relieved by Departmental Representative's review of submittals.
- .8 Contractor's responsibility for deviations in submission from requirements of Contract Documents is not relieved by Departmental Representative's review.
- .9 Keep one reviewed copy of each submission on site.

1.2 SHOP DRAWINGS AND PRODUCT DATA

- .1 The term "shop drawings" means drawings, diagrams, illustrations, schedules, performance charts, brochures and other data which are to be provided by Contractor to illustrate details of a portion of Work.
- .2 Submit shop drawings bearing stamp and signature of qualified professional engineer registered or licensed in Province of Ontario.
- .3 Indicate materials, methods of construction and attachment or anchorage, erection diagrams, connections, explanatory notes and other information necessary for completion of Work. Where articles or equipment attach or connect to other articles or equipment, indicate that such items have been co-ordinated, regardless of Section under which adjacent items will be supplied and installed. Indicate cross references to design drawings and specifications.
- .4 Allow seven (7) working days for Departmental Representative's review of each submission.
- .5 Adjustments made on shop drawings by Departmental Representative are not intended to change Contract Price. If adjustments affect value of Work, state such in writing to Departmental Representative prior to proceeding with Work.
- .6 Make changes in shop drawings as Departmental Representative may require, consistent with Contract Documents. When resubmitting, notify Departmental Representative in writing of revisions other than those requested.
- .7 Accompany submissions with transmittal letter, in PDF Format, containing:
 - .1 Date.
 - .2 Project title and number.

- .3 Contractor's name and address.
- .4 Identification and quantity of each shop drawing, product data and sample.
- .5 Other pertinent data.
- .8 Submissions include:
 - .1 Date and revision dates.
 - .2 Project title and number.
 - .3 Name and address of:
 - .1 Subcontractor.
 - .2 Supplier.
 - .3 Manufacturer.
 - .4 Contractor's stamp, signed by Contractor's authorized representative certifying approval of submissions, verification of field measurements and compliance with Contract Documents.
 - .5 Details of appropriate portions of Work as applicable:
 - .1 Fabrication.
 - .2 Layout, showing dimensions, including identified field dimensions, and clearances.
 - .3 Setting or erection details.
 - .4 Capacities.
 - .5 Performance characteristics.
 - .6 Standards.
 - .7 Operating weight.
 - .8 Wiring diagrams.
 - .9 Single line and schematic diagrams.
 - .10 Relationship to adjacent work.
- .9 After Departmental Representative's review, distribute copies.
- .10 Submit electronic files, in PDF format, of shop drawings for each requirement requested in specification Sections and as Departmental Representative may reasonably request.
- .11 Submit electronic files, in PDF format, of product data sheets or brochures for requirements requested in specification Sections and as requested by Departmental Representative, where shop drawings will not be prepared due to standardized manufacture of product.
- .12 Submit electronic files, in PDF format, copies of test reports for requirements requested in specification Sections and as requested by Departmental Representative.
 - .1 Report signed by authorized official of testing laboratory that material, product or system identical to material, product or system to be provided has been tested in accord with specified requirements.
 - .2 Testing must have been within 3 years of date of contract award for project.
- .13 Submit electronic files, in PDF format, of certificates for requirements requested in specification Sections and as requested by Departmental Representative.
 - .1 Statements printed on manufacturer's letterhead and signed by responsible officials of manufacturer of product, system or material attesting that product, system or material meets specification requirements.
 - .2 Certificates must be dated after award of project contract complete with project name.
- .14 Submit electronic files, in PDF format, of manufacturers' instructions for requirements requested in specification Sections and as requested by Departmental Representative.

- .1 Pre-printed material describing installation of product, system or material, including special notices and Material Safety Data Sheets concerning impedances, hazards and safety precautions.
- .15 Submit electronic files, in PDF format, copies of Manufacturer's Field Reports for requirements requested in specification Sections and as requested by Departmental Representative.
 - .1 Documentation of the testing and verification actions taken by manufacturer's representative to confirm compliance with manufacturer's standards or instructions.
- .16 Submit four (4) hard copies of Operation and Maintenance Data for requirements requested in specification Sections and as requested by Departmental Representative.
- .17 Delete information not applicable to project.
- .18 Supplement standard information to provide details applicable to project.
- .19 If upon review by Departmental Representative, no errors or omissions are discovered or if only minor corrections are made, electronic copies will be returned and fabrication and installation of Work may proceed. If shop drawings are rejected, noted electronic copy will be returned and resubmission of corrected shop drawings, through same procedure indicated above, must be performed before fabrication and installation of Work may proceed.
- .20 The review of shop drawings by Departmental Representative is for sole purpose of ascertaining conformance with general concept.
 - .1 This review shall not mean that Departmental Representative approves detail design inherent in shop drawings, responsibility for which shall remain with Contractor submitting same, and such review shall not relieve Contractor of responsibility for errors or omissions in shop drawings or of responsibility for meeting requirements of construction and Contract Documents.
 - .2 Without restricting generality of foregoing, Contractor is responsible for dimensions to be confirmed and correlated at job site, for information that pertains solely to fabrication processes or to techniques of construction and installation and for co-ordination of Work of sub-trades.
- .21 Arrange and pay for all deliveries and pick-up, to and from, the Departmental Representative's offices.

1.3 **SAMPLES**

- .1 Submit for review samples in triplicate as requested in respective specification Sections. Label samples with origin and intended use.
- .2 Deliver samples prepaid to Departmental Representative.
- .3 Notify Departmental Representative in writing, at time of submission of deviations in samples from requirements of Contract Documents.
- .4 Where colour, pattern or texture is criterion, submit full range of samples.
- .5 Adjustments made on samples by the Departmental Representative are not intended to change Contract Price. If adjustments affect value of Work, state such in writing to the Departmental Representative prior to proceeding with Work.
- .6 Make changes in samples which Departmental Representative may require, consistent with Contract Documents.
- .7 Reviewed and accepted samples will become standard of workmanship and material against which installed Work will be verified.

1.4 **MOCK-UPS**

- .1 Erect mock-ups in accordance with Section 01 45 00 - Quality Control.

1.5 CERTIFICATES AND TRANSCRIPTS

- .1 Immediately after award of Contract, submit Workers' Compensation Board status.
- .2 Submit transcription of insurance immediately after award of Contract.

Part 2 Products

2.1 NOT USED

- .1 Not Used.

Part 3 Execution

3.1 NOT USED

- .1 Not Used.

END OF SECTION

Part 1 General**1.1 REFERENCES**

- .1 Canada Labour Code, Part 2, Canada Occupational Safety and Health Regulations
- .2 Health Canada/Workplace Hazardous Materials Information System (WHMIS): Material Safety Data Sheets (MSDS).
- .3 Province of Ontario: Occupational Health and Safety Act, R.S.O. 1990 Updated 2011.

1.2 SUBMITTALS

- .1 Make submittals in accordance with Section 01 33 00 - Submittal Procedures.
- .2 Submit site-specific Health and Safety Plan: Within five (5) days after date of Notice to Proceed and prior to commencement of Work. Health and Safety Plan must include:
 - .1 Results of site specific safety hazard assessment.
 - .2 Results of safety and health risk or hazard analysis for site tasks and operation found in work plan.
- .3 Submit two (2) copies of Contractor's authorized representative's work site health and safety inspection reports to Departmental Representative and authority having jurisdiction, weekly.
- .4 Submit copies of reports or directions issued by Provincial health and safety inspectors.
- .5 Submit copies of incident and accident reports.
- .6 Departmental Representative will review Contractor's site-specific Health and Safety Plan and provide comments to Contractor within five (5) days after receipt of plan. Revise plan as appropriate and resubmit plan to Departmental Representative within five (5) days after receipt of comments from Departmental Representative.
- .7 Departmental Representative's review of Contractor's final Health and Safety plan should not be construed as approval and does not reduce the Contractor's overall responsibility for construction Health and Safety.
- .8 Medical Surveillance: where prescribed by legislation, regulation or safety program, submit certification of medical surveillance for site personnel prior to commencement of Work, and submit additional certifications for any new site personnel to Departmental Representative.
- .9 On-site Contingency and Emergency Response Plan: address standard operating procedures to be implemented during emergency situations.

1.3 FILING OF NOTICE

- .1 File Notice of Project with Provincial authorities prior to beginning of Work.

1.4 SAFETY ASSESSMENT

- .1 Perform site specific safety hazard assessment related to project.

1.5 MEETINGS

- .1 Schedule and administer Health and Safety meeting with Departmental Representative prior to commencement of Work.

1.6 REGULATORY REQUIREMENTS

- .1 Do Work in accordance with Section 01 41 00 - Regulatory Requirements.

1.7 GENERAL REQUIREMENTS

- .1 Develop written site-specific Health and Safety Plan based on hazard assessment prior to beginning site Work and continue to implement, maintain, and enforce plan until final demobilization from site. Health and Safety Plan must address project specifications.
- .2 Departmental Representative may respond in writing, where deficiencies or concerns are noted and may request re-submission with correction of deficiencies or concerns.

1.8 RESPONSIBILITY

- .1 Be responsible for health and safety of persons on site, safety of property on site and for protection of persons adjacent to site and environment to extent that they may be affected by conduct of Work.
- .2 Comply with and enforce compliance by employees with safety requirements of Contract Documents, applicable federal, provincial, territorial and local statutes, regulations, and ordinances, and with site-specific Health and Safety Plan.

1.9 COMPLIANCE REQUIREMENTS

- .1 Comply with Ontario Health and Safety Act, R.S.O.
- .2 Comply with Occupational Health and Safety Regulations, 1996.
- .3 Comply with Occupational Health and Safety Act, General Safety Regulations, O.I.C.
- .4 Comply with Canada Labour Code, Canada Occupational Safety and Health Regulations.

1.10 UNFORSEEN HAZARDS

- .1 When unforeseen or peculiar safety related factor, hazard, or condition occur during performance of Work, follow procedures in place for Employee's Right to Refuse Work in accordance with Acts and Regulations of Province having jurisdiction and advise Departmental Representative verbally and in writing.

1.11 HEALTH AND SAFETY CO-ORDINATOR

- .1 Employ and assign to Work, competent and authorized representative as Health and Safety Co-ordinator. Health and Safety Co-ordinator must:
 - .1 Have site related working experience specific to activities associated with the project.
 - .2 Have working knowledge of occupational safety and health regulations.
 - .3 Be responsible for completing Contractor's Health and Safety Training Sessions and ensuring that personnel not successfully completing required training are not permitted to enter site to perform Work.
 - .4 Be responsible for implementing, enforcing daily and monitoring site-specific Contractor's Health and Safety Plan.
 - .5 Be on site during execution of Work and report directly to and be under direction of site supervisor.

1.12 POSTING OF DOCUMENTS

- .1 Ensure applicable items, articles, notices and orders are posted in conspicuous location on site in accordance with Acts and Regulations of Province having jurisdiction, and in consultation with Departmental Representative.

1.13 CORRECTION OF NON-COMPLIANCE

- .1 Immediately address health and safety non-compliance issues identified by authority having jurisdiction or by Departmental Representative.

- .2 Provide Departmental Representative written report of action taken to correct non-compliance of health and safety issues identified.
- .3 Departmental Representative may stop Work if non-compliance of health and safety regulations is not corrected.

1.14 BLASTING

- .1 Blasting or other use of explosives is not permitted without prior receipt of written instruction by Departmental Representative.

1.15 POWDER ACTUATED DEVICES

- .1 Use powder actuated devices only after receipt of written permission from Departmental Representative.

1.16 WORK STOPPAGE

- .1 Give precedence to safety and health of public and site personnel and protection of environment over cost and schedule considerations for Work.

Part 2 Products**2.1 NOT USED**

- .1 Not used.

Part 3 Execution**3.1 NOT USED**

- .1 Not used.

END OF SECTION

PAGE INTENTIONALLY LEFT BLANK

Part 1 General**1.1 DEFINITIONS**

- .1 Environmental Pollution and Damage: presence of chemical, physical, biological elements or agents which adversely affect human health and welfare; unfavourably alter ecological balances of importance to human life; affect other species of importance to humankind; or degrade environment aesthetically, culturally and/or historically.
- .2 Environmental Protection: prevention/control of pollution and habitat or environment disruption during construction. Control of environmental pollution and damage requires consideration of land, water, and air; biological and cultural resources; and includes management of visual aesthetics; noise; solid, chemical, gaseous, and liquid waste; radiant energy and radioactive material as well as other pollutants.

1.2 SUBMITTALS

- .1 Submittals: in accordance with Section 01 33 00 - Submittal Procedures.
- .2 Prior to commencing construction activities or delivery of materials to site, submit Environmental Protection Plan for review and approval by Departmental Representative. Environmental Protection Plan is to present comprehensive overview of known or potential environmental issues which must be addressed during construction.
- .3 Address topics at level of detail commensurate with environmental issue and required construction tasks.
- .4 Environmental protection plan: include:
 - .1 Name of person responsible for ensuring adherence to Environmental Protection Plan, where applicable.
 - .2 Name and qualifications of person responsible for manifesting hazardous waste to be removed from site, where applicable.
 - .3 Name and qualifications of person responsible for training site personnel, where applicable.
 - .4 Descriptions of environmental protection personnel training program, where applicable.
 - .5 Work area plan showing proposed activity in each portion of area and identifying areas of limited use or non-use. Plan to include measures for marking limits of use areas including methods for protection of features to be preserved within authorized work areas.
 - .6 Spill Control Plan: including procedures, instructions, and reports to be used in event of unforeseen spill of regulated substance.
 - .7 Non-Hazardous solid waste disposal plan identifying methods and locations for solid waste disposal including clearing debris.
 - .8 Air pollution control plan detailing provisions to assure that dust, debris, materials, and trash, do not become air borne and travel off project site.
 - .9 Contaminant prevention plan that: identifies potentially hazardous substances to be used on job site; identifies intended actions to prevent introduction of such materials into air, water, or ground; and details provisions for compliance with Federal, Provincial, and Municipal laws and regulations for storage and handling of these materials.
 - .10 Waste water management plan that identifies methods and procedures for management and/or discharge of waste waters which are directly derived from construction activities, such as concrete curing water, clean-up water, dewatering of ground water, disinfection water, hydrostatic test water, and water used in flushing of lines.

1.3 FIRES

- .1 Fires and burning of rubbish on site not permitted.

1.4 DISPOSAL OF WASTES

- .1 Do not bury rubbish and waste materials on site.
- .2 Do not dispose of waste or volatile materials, such as mineral spirits, oil or paint thinner into waterways, storm or sanitary sewers.

1.5 DRAINAGE

- .1 Provide erosion and sediment control plan that identifies type and location of erosion and sediment controls to be provided. Plan: include monitoring and reporting requirements to assure that control measures are in compliance with erosion and sediment control plan, Federal, Provincial, and Municipal laws and regulations.
- .2 Storm Water Pollution Prevention Plan (SWPPP) to be substituted for erosion and sedimentations control plan.
- .3 Provide temporary drainage and pumping as necessary to keep excavations and site free from water.
- .4 Do not pump water containing suspended materials into waterways, sewer or drainage systems.
- .5 Control disposal or runoff of water containing suspended materials or other harmful substances in accordance with local authority requirements.

1.6 POLLUTION CONTROL

- .1 Maintain temporary erosion and pollution control features installed under this contract.
- .2 Control emissions from equipment and plant to local authorities' emission requirements.
- .3 Prevent sandblasting and other extraneous materials from contaminating air and waterways beyond application area, by providing temporary enclosures.
- .4 Cover or wet down dry materials and rubbish to prevent blowing dust and debris. Provide dust control for temporary roads.

1.7 NOTIFICATION

- .1 Departmental Representative will notify Contractor in writing of observed noncompliance with Federal, Provincial or Municipal environmental laws or regulations, permits, and other elements of Contractor's Environmental Protection plan. Contractor, after receipt of such notice, shall inform Departmental Representative of proposed corrective action and take such action for approval by Departmental Representative.
- .2 Departmental Representative will issue stop order of work until satisfactory corrective action has been taken.
- .3 No time extensions granted or equitable adjustments allowed to Contractor for such suspensions.

Part 2 Products**2.1 NOT USED**

- .1 Not Used.

Part 3 Execution

3.1 NOT USED

.1 Not Used.

END OF SECTION

PAGE INTENTIONALLY LEFT BLANK

Part 1 General**1.1 REFERENCES AND CODES**

- .1 Perform Work in accordance with the Ontario Building Code (OBC) and the National Building Code of Canada (NBC) including amendments up to tender closing date and other codes of provincial or local application provided that in case of conflict or discrepancy, more stringent requirements apply.
- .2 Meet or exceed requirements of:
 - .1 Contract documents.
 - .2 Specified standards, codes and referenced documents.

1.2 HAZARDOUS MATERIAL DISCOVERY

- .1 Asbestos: demolition of spray or trowel-applied asbestos is hazardous to health. Stop work immediately when material resembling spray or trowel-applied asbestos is encountered during demolition work. Notify Departmental Representative.
- .2 PCB: Polychlorinated Biphenyl: stop work immediately when material resembling Polychlorinated Biphenyl is encountered during demolition work. Notify Departmental Representative.
- .3 Mould: stop work immediately when material resembling mould is encountered during demolition work. Notify Departmental Representative.

1.3 BUILDING SMOKING ENVIRONMENT

- .1 Comply with smoking restrictions and municipal by-laws.

Part 2 Products**2.1 NOT USED**

- .1 Not Used.

Part 3 Execution**3.1 NOT USED**

- .1 Not Used.

END OF SECTION

PAGE INTENTIONALLY LEFT BLANK

Part 1 General**1.1 INSPECTION**

- .1 Allow Departmental Representative access to Work. If part of Work is in preparation at locations other than Place of Work, allow access to such Work whenever it is in progress.
- .2 Give timely notice requesting inspection if Work is designated for special tests, inspections or approvals by Departmental Representative's instructions, or law of Place of Work.
- .3 If Contractor covers or permits to be covered Work that has been designated for special tests, inspections or approvals before such is made, uncover such Work, have inspections or tests satisfactorily completed and make good such Work.
- .4 Departmental Representative will order part of Work to be examined if Work is suspected to be not in accordance with Contract Documents. If, upon examination such work is found not in accordance with Contract Documents, correct such Work and pay cost of examination and correction. If such Work is found in accordance with Contract Documents, project shall pay cost of examination and replacement.

1.2 INDEPENDENT INSPECTION AGENCIES

- .1 Independent Inspection/Testing Agencies will be engaged by Departmental Representative for purpose of inspecting and/or testing portions of Work. Cost of such services will be borne by the project.
- .2 Provide equipment required for executing inspection and testing by appointed agencies.
- .3 Employment of inspection/testing agencies does not relax responsibility to perform Work in accordance with Contract Documents.
- .4 If defects are revealed during inspection and/or testing, appointed agency will request additional inspection and/or testing to ascertain full degree of defect. Correct defect and irregularities as advised by Departmental Representative at no cost to the project. Pay costs for retesting and re-inspection.

1.3 ACCESS TO WORK

- .1 Allow inspection/testing agencies access to Work, off site manufacturing and fabrication plants.
- .2 Co-operate to provide reasonable facilities for such access.

1.4 PROCEDURES

- .1 Notify appropriate agency and Departmental Representative in advance of requirement for tests, in order that attendance arrangements can be made.
- .2 Submit samples and/or materials required for testing, as specifically requested in specifications. Submit with reasonable promptness and in orderly sequence to not cause delays in Work.
- .3 Provide labour and facilities to obtain and handle samples and materials on site. Provide sufficient space to store and cure test samples.

1.5 REJECTED WORK

- .1 Remove defective Work, whether result of poor workmanship, use of defective products or damage and whether incorporated in Work or not, which has been rejected by Departmental Representative as failing to conform to Contract Documents. Replace or re-execute in accordance with Contract Documents.

- .2 Make good other Contractor's work damaged by such removals or replacements promptly.
- .3 If in opinion of Departmental Representative it is not expedient to correct defective Work or Work not performed in accordance with Contract Documents, Departmental Representative will deduct from Contract Price difference in value between Work performed and that called for by Contract Documents, amount of which will be determined by Departmental Representative.

1.6 REPORTS

- .1 Submit four (4) copies of inspection and test reports to Departmental Representative.
- .2 Provide copies to subcontractor of work being inspected or tested and/or manufacturer or fabricator of material being inspected or tested.

1.7 TESTS AND MIX DESIGNS

- .1 Furnish test results and mix designs as requested.
- .2 Cost of tests and mix designs beyond those called for in Contract Documents or beyond those required by law of Place of Work will be appraised by Departmental Representative and may be authorized as recoverable.

1.8 MILL TESTS

- .1 Submit mill test certificates as requested or required of specification Sections.

1.9 EQUIPMENT AND SYSTEMS

- .1 Submit adjustment and balancing reports for mechanical, electrical and building equipment systems.

Part 2 Products**2.1 NOT USED**

- .1 Not Used.

Part 3 Execution**3.1 NOT USED**

- .1 Not Used.

END OF SECTION

Part 1 General**1.1 SUBMITTALS**

- .1 Provide submittals in accordance with Section 01 33 00 - Submittal Procedures.

1.2 INSTALLATION AND REMOVAL

- .1 Provide temporary utilities controls in order to execute work expeditiously.
- .2 Remove from site all such work after use.

1.3 DEWATERING

- .1 Provide temporary drainage and pumping facilities to keep work and site free from standing water.

1.4 WATER SUPPLY

- .1 The project will provide continuous supply of potable water for construction use.
- .2 The project will pay for utility charges at prevailing rates.

1.5 TEMPORARY HEATING AND VENTILATION

- .1 Provide temporary heating required during construction period, including attendance, maintenance and fuel.
- .2 Construction heaters used inside building must be vented to outside or be non-flameless type. Solid fuel salamanders are not permitted.
- .3 Provide temporary heat and ventilation in enclosed areas as required to:
 - .1 Facilitate progress of Work. Protect Work and products against dampness and cold.
 - .2 Prevent moisture condensation on surfaces.
 - .3 Provide ambient temperatures and humidity levels for storage, installation and curing of materials.
 - .4 Provide adequate ventilation to meet health regulations for safe working environment.
- .4 Maintain temperatures of minimum 10 degrees C in areas where construction is in progress.
- .5 Ventilating:
 - .1 Prevent accumulations of dust, fumes, mists, vapours or gases in areas occupied during construction.
 - .2 Provide local exhaust ventilation to prevent harmful accumulation of hazardous substances into atmosphere of occupied areas.
 - .3 Dispose of exhaust materials in manner that will not result in harmful exposure to persons.
 - .4 Ventilate storage spaces containing hazardous or volatile materials.
 - .5 Ventilate temporary sanitary facilities.
 - .6 Continue operation of ventilation and exhaust system for time after cessation of work process to assure removal of harmful contaminants.
- .6 Permanent heating system of building, not to be used when available. Be responsible for damage to heating system if use is permitted.
- .7 Maintain strict supervision of operation of temporary heating and ventilating equipment to:

- .1 Conform to applicable codes and standards.
- .2 Enforce safe practices.
- .3 Prevent abuse of services.
- .4 Prevent damage to finishes.
- .5 Vent direct-fired combustion units to outside.
- .8 Be responsible for damage to Work due to failure in providing adequate heat and protection during construction.

1.6 TEMPORARY POWER AND LIGHT

- .1 The Departmental Representative will pay for temporary power during construction for temporary lighting and operating of power tools, to a maximum supply of 230 volts 30 amps.
- .2 Arrange for connection with the existing building personnel. Pay costs for installation, maintenance and removal.
- .3 Temporary power for electric cranes and other equipment requiring in excess of above is responsibility of the Contractor.
- .4 Provide and maintain temporary lighting throughout project. Ensure level of illumination on all floors and stairs is not less than 162 lx.
- .5 Connect to existing power supply in accordance with Canadian Electrical Code.

1.7 TEMPORARY COMMUNICATION FACILITIES

- .1 Provide and pay for temporary telephone, fax and data hook up, and equipment necessary for use.

1.8 FIRE PROTECTION

- .1 Provide and maintain temporary fire protection equipment during performance of Work required by insurance companies having jurisdiction and governing codes, regulations and bylaws.
- .2 Burning rubbish and construction waste materials is not permitted.

Part 2 Products

2.1 NOT USED

- .1 Not Used.

Part 3 Execution

3.1 NOT USED

- .1 Not Used.

END OF SECTION

Part 1 General**1.1 RELATED SECTIONS**

- .1 Section 01 33 00 – Submittal Procedures.

1.2 REFERENCES

- .1 Canadian General Standards Board (CGSB)
 - .1 CAN/CGSB 1.189-00, Exterior Alkyd Primer for Wood.
 - .2 CGSB 1.59-97, Alkyd Exterior Gloss Enamel. Canadian Standards Association (CSA International)
 - .3 CSA-A23.1/A23.2-04, Concrete Materials and Methods of Concrete Construction/Methods of Test and Standard Practices for Concrete.
 - .4 CSA-0121-M1978(R2003), Douglas Fir Plywood.
 - .5 CAN/CSA-S269.2-M1987(R2003), Access Scaffolding for Construction Purposes.
 - .6 CAN/CSA-Z321-96(R2001), Signs and Symbols for the Occupational Environment.

1.3 SUBMITTALS

- .1 Provide submittals in accordance with Section 01 33 00 - Submittal Procedures.

1.4 SCAFFOLDING

- .1 Scaffolding in accordance with CAN/CSA-S269.2.
- .2 Provide and maintain scaffolding, ramps, ladders, swing staging, platforms and temporary stairs.

1.5 ELEVATORS

- .1 Designated existing elevator to be used by construction personnel and transporting of materials. Co-ordinate use with Departmental Representative.
- .2 Provide protective coverings for finish surfaces of cars and entrances.

1.6 SITE STORAGE/LOADING

- .1 Confine work and operations of employees by Contract Documents. Do not unreasonably encumber premises with products.
- .2 Do not load or permit to load any part of Work with weight or force that will endanger Work.

1.7 CONSTRUCTION PARKING

- .1 Parking will not be permitted on site.
- .2 Provide and maintain adequate access to project site.

1.8 OFFICES

- .1 On site office will not be provided.

1.9 EQUIPMENT, TOOL AND MATERIALS STORAGE

- .1 Site storage of equipment, tools and materials will not be provided.

1.10 SANITARY FACILITIES

- .1 Existing building facilities may be used.

1.11 CONSTRUCTION SIGNAGE

- .1 Construction signage will not be permitted on site.

1.12 CLEAN-UP

- .1 Remove construction debris, waste materials, packaging material from work site daily.
- .2 Clean dirt or mud tracked onto paved or surfaced roadways.
- .3 Store materials resulting from demolition activities that are salvageable.
- .4 Stack stored new or salvaged material not in construction facilities.

Part 2 Products**2.1 Not Used**

- .1 Not Used.

Part 3 Execution**3.1 Not Used**

- .1 Not Used.

END OF SECTION

Part 1 General**1.1 SUBMITTALS**

- .1 Provide submittals in accordance with Section 01 33 00 - Submittal Procedures.

1.2 INSTALLATION AND REMOVAL

- .1 Provide temporary controls in order to execute Work expeditiously.
- .2 Remove from site all such work after use.

1.3 DUST TIGHT SCREENS

- .1 Provide dust tight screens or partitions to localize dust generating activities, and for protection of workers, finished areas of Work and public.
- .2 Maintain and relocate protection until such work is complete.

1.4 WEATHER ENCLOSURES

- .1 Provide weather tight closures to unfinished window openings and any other types of openings to the floor space.
- .2 Temporarily close off floor areas where window replacement is not finished; seal off other openings; enclose building interior work for temporary heat.
- .3 Design enclosures to withstand wind pressure and snow loading.

1.5 ACCESS TO SITE

- .1 Maintain access roads, sidewalk crossings, ramps and construction runways as may be required for access to Work.

1.6 PUBLIC TRAFFIC FLOW

- .1 Maintain competent signal flag operators, traffic signals, barricades and flares, lights, or lanterns as required to perform Work and protect public.

1.7 FIRE ROUTES

- .1 Maintain access to property including overhead clearances for use by emergency response vehicles.

1.8 PROTECTION OF BUILDING FINISHES

- .1 Provide protection for finished and partially finished building finishes and equipment during performance of Work.
- .2 Provide necessary screens, covers, and hoardings.
- .3 Confirm with Departmental Representative locations and installation schedule five (5) days prior to installation.
- .4 Be responsible for damage incurred due to lack of or improper protection.

1.9 WASTE MANAGEMENT AND DISPOSAL

- .1 Separate waste materials for reuse and recycling in accordance with Section 01 74 21 - Construction/Demolition Waste Management.

Part 2 Products

2.1 NOT USED

.1 Not Used.

Part 3 Execution

3.1 NOT USED

.1 Not Used.

END OF SECTION

Part 1 General**1.1 REFERENCES**

- .1 Within text of each specifications section, reference may be made to reference standards. List of standards reference writing organizations.
- .2 Conform to these reference standards, in whole or in part as specifically requested in specifications.
- .3 If there is question as to whether products or systems are in conformance with applicable standards, Departmental Representative reserves right to have such products or systems tested to prove or disprove conformance.
- .4 Cost for such testing will be borne by the project in event of conformance with Contract Documents or by Contractor in event of non-conformance.

1.2 QUALITY

- .1 Products, materials, equipment and articles incorporated in Work shall be new, not damaged or defective, and of best quality for purpose intended. If requested, furnish evidence as to type, source and quality of products provided.
- .2 Procurement policy is to acquire, in cost effective manner, items containing highest percentage of recycled and recovered materials practicable consistent with maintaining satisfactory levels of competition. Make reasonable efforts to use recycled and recovered materials and in otherwise utilizing recycled and recovered materials in execution of work.
- .3 Defective products, whenever identified prior to completion of Work, will be rejected, regardless of previous inspections. Inspection does not relieve responsibility, but is precaution against oversight or error. Remove and replace defective products at own expense and be responsible for delays and expenses caused by rejection. Should disputes arise as to quality or fitness of products, decision rests strictly with Departmental Representative based upon requirements of Contract Documents.
- .4 Unless otherwise indicated in specifications, maintain uniformity of manufacture for any particular or like item throughout building.
- .5 Permanent labels, trademarks and nameplates on products are not acceptable in prominent locations, except where required for operating instructions, or when located in mechanical or electrical rooms.

1.3 STORAGE, HANDLING AND PROTECTION

- .1 Handle and store products in manner to prevent damage, adulteration, deterioration and soiling and in accordance with manufacturer's instructions when applicable.
- .2 Store packaged or bundled products in original and undamaged condition with manufacturer's seal and labels intact. Do not remove from packaging or bundling until required in Work.
- .3 Store products subject to damage from weather in weatherproof enclosures.
- .4 Store cementitious products clear of earth or concrete floors, and away from walls.
- .5 Keep sand, when used for grout or mortar materials, clean and dry. Store sand on wooden platforms and cover with waterproof tarpaulins during inclement weather.
- .6 Store sheet materials, lumber and panel materials on flat, solid supports and keep clear of ground. Slope to shed moisture.

- .7 Store and mix paints in heated and ventilated room. Remove oily rags and other combustible debris from site daily. Take every precaution necessary to prevent spontaneous combustion.
- .8 Remove and replace damaged products at own expense and to satisfaction of Departmental Representative.
- .9 Touch-up damaged factory finished surfaces to Departmental Representative's satisfaction. Use touch-up materials to match original. Do not paint over name plates.

1.4 TRANSPORTATION

- .1 Pay costs of transportation of products required in performance of Work.
- .2 Transportation cost of products supplied by Departmental Representative will be paid for by the project. Unload, handle and store such products.

1.5 MANUFACTURER'S INSTRUCTIONS

- .1 Unless otherwise indicated in specifications install or erect products in accordance with manufacturer's instructions. Do not rely on labels or enclosures provided with products. Obtain written instructions directly from manufacturers.
- .2 Notify Departmental Representative in writing, of conflicts between specifications and manufacturer's instructions, so the Departmental Representative will establish course of action.
- .3 Improper installation or erection of products, due to failure in complying with these requirements, authorizes Departmental Representative to require removal and re-installation at no increase in Contract Price or Contract Time.
- .4 Ensure Quality of Work is of highest standard, executed by workers experienced and skilled in respective duties for which they are employed. Immediately notify Departmental Representative if required Work is such as to make it impractical to produce required results.
- .5 Do not employ anyone unskilled in their required duties. Departmental Representative reserves right to require dismissal from site, workers deemed incompetent or careless.
- .6 Decisions as to standard or fitness of Quality of Work in cases of dispute rest solely with Departmental Representative, whose decision is final.

1.6 CO-ORDINATION

- .1 Ensure co-operation of workers in laying out Work. Maintain efficient and continuous supervision.
- .2 Be responsible for coordination and placement of openings, sleeves and accessories.

1.7 CONCEALMENT

- .1 In finished areas conceal pipes, ducts and wiring in floors, walls and ceilings, except where indicated otherwise.
- .2 Before installation inform Departmental Representative if there is interference. Install as directed by Departmental Representative.

1.8 REMEDIAL WORK

- .1 In accordance with Section 01 73 03 - Execution Requirements.
- .2 Perform remedial work required to repair or replace parts or portions of Work identified as defective or unacceptable. Co-ordinate adjacent affected Work as required.
- .3 Perform remedial work by specialists familiar with materials affected. Perform in a manner to neither damage nor put at risk any portion of Work.

1.9 LOCATION OF FIXTURES

- .1 Consider location of fixtures, outlets, and mechanical and electrical items indicated as approximate.
- .2 Inform Departmental Representative of conflicting installation. Install as directed.

1.10 FASTENINGS

- .1 Provide metal fastenings and accessories in same texture, colour and finish as adjacent materials, unless indicated otherwise.
- .2 Prevent electrolytic action between dissimilar metals and materials.
- .3 Use non-corrosive hot dip galvanized steel fasteners and anchors for securing exterior work, unless stainless steel or other material is specifically requested in affected specification Section.
- .4 Space anchors within individual load limit or shear capacity and ensure they provide positive permanent anchorage. Wood, or any other organic material plugs are not acceptable.
- .5 Keep exposed fastenings to a minimum, space evenly and install neatly.
- .6 Fastenings which cause spalling or cracking of material to which anchorage is made are not acceptable.

1.11 FASTENINGS - EQUIPMENT

- .1 Use fastenings of standard commercial sizes and patterns with material and finish suitable for service.
- .2 Use heavy hexagon heads, semi-finished unless otherwise specified. Use No. 304 stainless steel for exterior areas.
- .3 Bolts may not project more than one diameter beyond nuts.
- .4 Use plain type washers on equipment, sheet metal and soft gasket lock type washers where vibrations occur. Use resilient washers with stainless steel.

1.12 PROTECTION OF WORK IN PROGRESS

- .1 Prevent overloading of parts of building. Do not cut, drill or sleeve load bearing structural member, unless specifically indicated without written approval of Departmental Representative.

1.13 EXISTING UTILITIES

- .1 When breaking into or connecting to existing services or utilities, execute Work at times directed by local governing authorities, with minimum of disturbance to Work, and/or building occupants and pedestrian and vehicular traffic.
- .2 Protect, relocate or maintain existing active services. When services are encountered, cap off in manner approved by authority having jurisdiction. Stake and record location of capped service.

Part 2 Products**2.1 NOT USED**

- .1 Not Used.

Part 3 Execution

3.1 NOT USED

.1 Not Used.

END OF SECTION

Part 1 General**1.1 SUBMITTALS**

- .1 Submittals: in accordance with Section 01 33 00 - Submittal Procedures.
- .2 Submit written request in advance of cutting or alteration which affects:
 - .1 Structural integrity of elements of project.
 - .2 Integrity of weather-exposed or moisture-resistant elements.
 - .3 Efficiency, maintenance, or safety of operational elements.
 - .4 Visual qualities of sight-exposed elements.
 - .5 Work of Owner or separate contractor.
- .3 Include in request:
 - .1 Identification of project.
 - .2 Location and description of affected Work.
 - .3 Statement on necessity for cutting or alteration.
 - .4 Description of proposed Work, and products to be used.
 - .5 Alternatives to cutting and patching.
 - .6 Effect on Work of Owner or separate contractor.
 - .7 Written permission of affected separate contractor.
 - .8 Date and time work will be executed.

1.2 MATERIALS

- .1 Change in Materials: Submit request for substitution in accordance with Section 01 33 00 - Submittal Procedures.

1.3 PREPARATION

- .1 Inspect existing conditions, including elements subject to damage or movement during cutting and patching.
- .2 After uncovering, inspect conditions affecting performance of Work.
- .3 Beginning of cutting or patching means acceptance of existing conditions.
- .4 Provide supports to assure structural integrity of surroundings; provide devices and methods to protect other portions of project from damage.
- .5 Provide protection from elements for areas which are to be exposed by uncovering work; maintain excavations free of water.

1.4 EXECUTION

- .1 Execute cutting, fitting, and patching including excavation and fill, to complete Work.
- .2 Fit several parts together, to integrate with other Work.

- .3 Uncover Work to install ill-timed Work.
- .4 Remove and replace defective and non-conforming Work.
- .5 Remove samples of installed Work for testing.
- .6 Provide openings in non-structural elements of Work for penetrations of mechanical and electrical Work.
- .7 Execute Work by methods to avoid damage to other Work, and which will provide proper surfaces to receive patching and finishing.
- .8 Employ original installer to perform cutting and patching for weather-exposed and moisture-resistant elements, and sight-exposed surfaces.
- .9 Cut rigid materials using masonry saw or core drill. Pneumatic or impact tools not allowed on masonry work without prior approval.
- .10 Restore work with new products in accordance with requirements of Contract Documents.
- .11 Fit Work airtight to pipes, sleeves, ducts, conduit, and other penetrations through surfaces.
- .12 At penetration of fire rated wall, ceiling, or floor construction, completely seal voids with appropriate fire stopping material in accordance with Section 07 84 00 - Firestopping, full thickness of the construction element.
- .13 Refinish surfaces to match adjacent finishes: Refinish continuous surfaces to nearest intersection. Refinish assemblies by refinishing entire unit.
- .14 Conceal pipes, ducts and wiring in floor, wall and ceiling construction of finished areas except where indicated otherwise.

1.5 WASTE MANAGEMENT AND DISPOSAL

- .1 Separate waste materials for reuse and recycling.

Part 2 Products

2.1 NOT USED

- .1 Not Used.

Part 3 Execution

3.1 NOT USED

- .1 Not Used.

END OF SECTION

PART 1 General**1.1 SUBMITTALS**

- .1 Submittals: in accordance with Section 01 33 00 - Submittal Procedures.
- .2 Submit written request in advance of cutting or alteration which affects:
 - .1 Structural integrity of elements of project.
 - .2 Integrity of weather exposed or moisture resistant elements.
 - .3 Efficiency, maintenance, or safety of operational elements.
 - .4 Visual qualities of sight exposed elements.
 - .5 Work of Owner or separate contractor.
- .3 Include in request:
 - .1 Identification of project.
 - .2 Location and description of affected Work.
 - .3 Statement on necessity for cutting or alteration.
 - .4 Description of proposed Work, and products to be used.
 - .5 Alternatives to cutting and patching.
 - .6 Effect on Work of Owner or separate contractor.
 - .7 Written permission of affected separate contractor.
 - .8 Date and time work will be executed.

1.2 GENERAL REQUIREMENTS

- .1 This Section provides guidelines to the existing building material refurbishment, as indicated on the Drawings, as specified herein and as required for a complete project, as well as requirements and limitations for cutting and patching the Work.
 - .1 Where indicated and required, patch and make good and/or reinstate finishes and assemblies with like materials to match existing finishes which are to remain, or new finishes to be provided.
 - .2 Complete work to extent required using appropriate transition points between existing or between existing and new assemblies to ensure neat consistent, finished appearance over entire surface.
 - .3 Where a smooth transition cannot be achieved in close proximity to the effected work, finish to appropriate transition points including:
 - .1 Intersection of ceiling or floor and wall plane
 - .2 Intersection of wall planes
 - .3 Intersection of other horizontal or vertical surfaces such as bulkheads
 - .4 Inside or outside corner at changes in surface plane.
- .2 Review construction documents and existing conditions at site assessment to ascertain extent of alterations required to meet the requirements described herein.

1.3 PREPARATION

- .1 Inspect existing conditions, including elements subject to damage or movement during cutting and patching.
- .2 After uncovering, inspect conditions affecting performance of Work.
- .3 Beginning of cutting or patching means acceptance of existing conditions.
- .4 Provide supports to assure structural integrity of surroundings; provide devices and methods to protect other portions of project from damage.
- .5 Provide protection from elements for areas which are to be exposed by uncovering work; maintain excavations free of water.

1.4 ALTERATIONS, CUTTING AND PROTECTION

- .1 Extent:
 - .1 Perform cutting and removal work so as not to cut or remove more than is necessary and so as not to damage adjacent work.
- .2 Shoring, Bracing and Capping:
 - .1 Provide shoring, needling and bracing as needed to keep the building structurally secure and free of deflection in all its parts and as needed for the installation of new work.
- .3 Responsibility and Assignment to Trades:
 - .1 The Contractor shall assign the work of moving, removal, cutting, patching and repair to trades under his supervision so as to cause the least damage to each type of work encountered, and so as to return the building as much as possible to the appearance of the new work.
 - .2 Assign patching of finish materials to tradesmen skilled in the work of the finish trade involved.
- .4 Protection:
 - .1 Protect remaining finishes, equipment and adjacent work from damage caused by cutting, moving, removal and patching operations. Protect surfaces which will remain a part of the finished work.

1.5 **PATCHING, EXTENDING AND MATCHING**

- .1 Skill:
 - .1 Patch and extend existing work using skilled tradesmen who are capable of matching the existing quality of workmanship. The quality of patched or extended work shall not be less than that specified in the applicable Sections of the Contract Specifications.
- .2 Patching:
 - .1 In areas where any portion of an existing finished surface is damaged, lifted, stained or otherwise found to be imperfect, patch or replace the imperfect portion of the surface with matching material.
 - .2 Do not incorporate salvaged or used material in new construction, except where small quantities of finish material which are difficult to match or duplicate are approved for patching or extending purposes by the Consultant.
 - .3 Provide adequate support or substrate for patching of finishes.
 - .4 If the imperfect surface is a painted or coated one, repaint or recoat the patched portion in such a way that uniform colour and texture over the entire surface results.
 - .5 If the surrounding surface cannot be matched, repaint or recoat the entire surface to nearest natural break.
- .3 Quality:
 - .1 In the Sections of the Specifications to which these alteration procedures are applicable, products required for patching, matching, extending or replacing existing work have not necessarily been described. Obtain all required products in time to complete the Work on schedule. Provide products of quality equal to or better than the existing products.
- .4 Transitions:
 - .1 Where new work abuts or finishes flush with existing work, make the transition as smooth and workmanlike as possible. Patched work shall match existing adjacent work in texture and appearance, so as to make the patch or transition invisible to the eye at a distance of one metre.
 - .2 Where concrete, drywall, wood, metal or other finished surface is cut in such a way that a smooth transition with new work is not possible, terminate the existing surface in a neat fashion along a straight line at a natural line of division and provide trim appropriate to the finished surface.
- .5 Matching:
 - .1 Where not otherwise specified or indicated, restore existing work that is damaged during construction to a condition equal to its condition at the time of the start of the

Work. At locations in existing areas where partitions are removed, patch the floors, walls and ceilings with finish materials to match adjacent finishes.

- .2 At locations in existing areas where partitions are removed, patch the floors, walls and ceilings with finish materials to match adjacent finishes.

1.6 EXECUTION

- .1 Execute work by methods to avoid damage to other work, and which will provide proper surfaces to receive patching and finishing.
- .2 Use material to match existing.
- .3 Cut rigid materials using a masonry saw or core drill. Pneumatic or impact tools not allowed without prior approval.
- .4 Restore work with new products in accordance with requirements of Contract Documents.
- .5 Fit work airtight to pipes, sleeves, ducts, conduit, and other penetrations through surfaces.
- .6 At penetration of fire rated wall, ceiling, or floor construction, completely seal voids with fire rated materials and firestopping material, full thickness of the construction element, full thickness of the construction element.
- .7 Refinish surfaces to match adjacent finishes. For continuous surfaces, refinish to nearest intersection; for an assembly, refinish entire unit.
- .8 Reinstate work in accordance with the conditions of the surface prior to cutting and patching.
- .9 Reconnect any services damaged due to cutting as part of patching and repairing of the damage area.

1.7 WASTE MANAGEMENT AND DISPOSAL

- .1 Separate waste materials for reuse and recycling in accordance with Section 01 74 21 - Construction/Demolition Waste Management And Disposal.
- .2 Debris:
 - .1 Remove debris promptly from the site each day. Removed material, except that listed or marked by the Consultant for retention, becomes the property of the Contractor. Load removed material directly on trucks for removal from the site. Dispose of removed material legally.
 - .2 Do not let piled material endanger structure.
- .3 Suppress dust. Prevent the occurrence of unsanitary conditions, dirt or debris.

PART 2 Products

2.1 NOT USED

- .1 Not Used.

PART 3 Execution

3.1 NOT USED

- .1 Not Used.

END OF SECTION

PAGE INTENTIONALLY LEFT BLANK

Part 1 General**1.1 PROJECT CLEANLINESS**

- .1 Maintain Work in tidy condition, free from accumulation of waste products and debris, other than that caused by building tenants.
- .2 Remove waste materials from site at daily regularly scheduled times or dispose of as directed by Departmental Representative. Do not burn waste materials on site.
- .3 Provide on-site containers for collection of waste materials and debris.
- .4 Provide and use marked separate bins for recycling. Refer to Section 01 74 21 - Construction/Demolition Waste Management and Disposal.
- .5 Dispose of waste materials and debris off site.
- .6 Clean interior areas prior to start of finishing work, and maintain areas free of dust and other contaminants during finishing operations.
- .7 Store volatile waste in covered metal containers, and remove from premises at end of each working day.
- .8 Provide adequate ventilation during use of volatile or noxious substances. Use of building ventilation systems is not permitted for this purpose.
- .9 Use only cleaning materials recommended by manufacturer of surface to be cleaned, and as recommended by cleaning material manufacturer.
- .10 Schedule cleaning operations so that resulting dust, debris and other contaminants will not fall on wet, newly painted surfaces nor contaminate building systems.

1.2 FINAL CLEANING

- .1 When Work is Substantially Performed remove surplus products, tools, construction machinery and equipment not required for performance of remaining Work.
- .2 Remove waste products and debris other than that caused by others, and leave Work clean and suitable for occupancy.
- .3 Prior to final review remove surplus products, tools, construction machinery and equipment.
- .4 Remove waste products and debris other than that caused by building tenants.
- .5 Remove waste materials from site at regularly scheduled times or dispose of as directed by Departmental Representative. Do not burn waste materials.
- .6 Make arrangements with and obtain permits from authorities having jurisdiction for disposal of waste and debris.
- .7 Clean and polish glass, hardware, stainless steel, chrome, baked enamel, plastic laminate, and mechanical and electrical fixtures. Replace broken, scratched or disfigured glass.
- .8 Remove stains, spots, marks and dirt from decorative work, electrical and mechanical fixtures, furniture fitments, walls, and floors.
- .9 Clean lighting reflectors, lenses, and other lighting surfaces.
- .10 Vacuum clean and dust building interiors, behind grilles, louvres and screens.
- .11 Wax, seal, shampoo or prepare floor finishes, as recommended by manufacturer.
- .12 Inspect finishes, fitments and equipment and ensure specified workmanship and operation.

- .13 Broom clean and wash exterior walks, steps and surfaces; rake clean other surfaces of grounds.
- .14 Remove dirt and other disfiguration from exterior surfaces.
- .15 Clean and sweep roofs, gutters, areaways, and sunken wells.
- .16 Sweep and wash clean paved areas. Clean equipment and fixtures to sanitary condition; clean or replace filters of mechanical equipment.
- .17 Clean roofs, downspouts, and drainage systems.
- .18 Remove debris and surplus materials from crawl areas and other accessible concealed spaces.

1.3 WASTE MANAGEMENT AND DISPOSAL

- .1 Separate waste materials for reuse and recycling in accordance with Section 01 74 21 - Construction/Demolition Waste Management and Disposal.

Part 2 Products

2.1 NOT USED

- .1 Not Used.

Part 3 Execution

3.1 NOT USED

- .1 Not Used.

END OF SECTION

Part 1 General**1.1 WASTE MANAGEMENT GOALS**

- .1 Prior to start of Work conduct meeting with Departmental Representative to review and discuss Waste Management Plan and Goals.
- .2 Waste Management Goal of 75% of total Project Waste to be diverted from landfill sites. Provide Departmental Representative documentation certifying that waste management, recycling, reuse of recyclable and reusable materials have been extensively practiced.
- .3 Accomplish maximum control of solid construction waste.
- .4 Preserve environment and prevent pollution and environment damage.

1.2 DEFINITIONS

- .1 Class III: non-hazardous waste - construction renovation and demolition waste.
- .2 Demolition Waste Audit (DWA): relates to actual waste generated from project.
- .3 Materials Source Separation Program (MSSP): consists of series of ongoing activities to separate reusable and recyclable waste material into material categories from other types of waste at point of generation.
- .4 Recyclable: ability of product or material to be recovered at end of its life cycle and re-manufactured into new product for reuse.
- .5 Recycle: process by which waste and recyclable materials are transformed or collected for purpose of being transferred into new products.
- .6 Recycling: process of sorting, cleansing, treating and reconstituting solid waste and other discarded materials for purpose of using in altered form. Recycling does not include burning, incinerating, or thermally destroying waste.
- .7 Reuse: repeated use of product in same form but not necessarily for same purpose. Reuse includes:
 - .1 Salvaging reusable materials from re-modelling projects, before demolition stage, for resale, reuse on current project or for storage for use on future projects.
 - .2 Returning reusable items including pallets or unused products to vendors.
- .8 Salvage: removal of structural and non-structural materials from deconstruction/disassembly projects for purpose of reuse or recycling.
- .9 Separate Condition: refers to waste sorted into individual types.
- .10 Source Separation: acts of keeping different types of waste materials separate beginning from first time they became waste.
- .11 Waste Management Co-ordinator (WMC): Contractor representative responsible for supervising waste management activities as well as coordinating related, required submittal and reporting requirements.
- .12 Waste Reduction Workplan (WRW): written report which addresses opportunities for reduction, reuse, or recycling of materials.

1.3 DOCUMENTS

- .1 Maintain at job site, one copy of following documents:
 - .1 Waste Reduction Workplan.
 - .2 Material Source Separation Plan.

1.4 SUBMITTALS

- .1 Submittals in accordance with Section 01 33 00 – Submittal Procedures.
- .2 Prepare and submit following prior to project start-up:
 - .1 Submit two (2) copies of completed Waste Reduction Workplan (WRW).
- .3 Submit before final payment, summary of waste materials salvaged for reuse, recycling or disposal by project using deconstruction/disassembly material audit form.
 - .1 Failure to submit could result in hold back of final payment.
 - .2 Provide receipts, scale tickets, waybills, and show quantities and types of materials reused, recycled, or disposed of.
 - .3 For each material reused, sold or recycled from project, include quantities by number, type and size of items and the destination.
 - .4 For each material land filled or incinerated from project, include amount of material.

1.5 WASTE REDUCTION WORKPLAN (WRW)

- .1 Prepare WRW prior to project start-up.
- .2 WRW should include but not limited to:
 - .1 Destination of materials listed.
 - .2 Deconstruction/disassembly techniques and sequencing.
 - .3 Schedule for deconstruction/disassembly.
 - .4 Location.
 - .5 Security.
 - .6 Protection.
 - .7 Clear labelling of storage areas.
 - .8 Details on materials handling and removal procedures.
 - .9 Quantities for materials to be salvaged for reuse or recycled and materials sent to landfill.
- .3 Structure WRW to prioritize actions and follow 3R's hierarchy, with Reduction as first priority, followed by Reuse, then Recycle.
- .4 Describe management of waste.
- .5 Identify opportunities for reduction, reuse, and recycling of materials. Based on information acquired from WA.
- .6 Post WRW or summary where workers at site are able to review content.
- .7 Set realistic goals for waste reduction, recognize existing barriers and develop strategies to overcome these barriers.
- .8 Monitor and report on waste reduction by documenting total volume and cost of actual waste removed from project.

1.6 MATERIALS SOURCE SEPARATION PROGRAM (MSSP)

- .1 Prepare MSSP and have ready for use prior to project start-up.
- .2 Implement MSSP for waste generated on project in compliance with approved methods and as reviewed by Departmental Representative.
- .3 Provide on-site facilities for collection, handling, and storage of anticipated quantities of reusable and recyclable materials.
- .4 Provide containers to deposit reusable and recyclable materials.

- .5 Locate containers in locations, to facilitate deposit of materials without hindering daily operations.
- .6 Locate separated material[s] in area[s] which minimize material damage.
- .7 Collect, handle, store on-site, and transport off-site, salvaged materials in separated condition. Transport to approved and authorized recycling facility.

1.7 STORAGE, HANDLING AND PROTECTION

- .1 Store, materials to be reused, recycled and salvaged.
- .2 Unless specified otherwise, materials for removal become Contractor's property.
- .3 Separate non-salvageable materials from salvaged items. Transport and deliver non-salvageable items to licensed disposal facility.
- .4 Protect structural components not removed for demolition from movement or damage.
- .5 Support affected structures. If safety of building is endangered, cease operations and immediately notify Departmental Representative.
- .6 Protect surface drainage, mechanical and electrical from damage and blockage.
- .7 Separate and store materials produced during dismantling of structures in designated areas. Prevent contamination of materials to be salvaged and recycled and handle materials in accordance with requirements for acceptance by designated facilities.

1.8 DISPOSAL OF WASTES

- .1 Do not bury rubbish or waste materials.
- .2 Do not dispose of waste, volatile materials, mineral spirits, or oil into waterways, storm, or sanitary sewers.
- .3 Keep records of construction waste including:
 - .1 Number and size of bins.
 - .2 Waste type of each bin.
 - .3 Total quantity generated.
 - .4 Total quantity recycled.
 - .5 Reused or recycled waste destination.
- .4 Remove materials from deconstruction as deconstruction/disassembly work progresses.
- .5 Prepare project summary to verify destination and quantities on a material-by-material basis.

1.9 USE OF SITE AND FACILITIES

- .1 Execute work with least possible interference or disturbance to normal use of premises.
- .2 Maintain security measures established by existing facility, provide temporary security measures to work area approved by Departmental Representative.

1.10 SCHEDULING

- .1 Co-ordinate Work with other activities at site to ensure timely and orderly progress of Work.

Part 2 Products

2.1 NOT USED

- .1 Not Used.

Part 3 Execution**3.1 SELECTIVE DEMOLITION**

- .1 Reuse of Building Elements: this project has been designed to result in end of project rates for reuse of building elements as follows: do not demolish building elements beyond what is indicated on Drawings without approval by Departmental Representative.

3.2 APPLICATION

- .1 Do Work in compliance with WRW.
- .2 Handle waste materials not reused, salvaged, or recycled in accordance with appropriate regulations and codes.

3.3 CLEANING

- .1 Remove tools and waste materials on completion of Work, and leave work area in clean and orderly condition.
- .2 Clean-up work area as work progresses.
- .3 Source separate materials to be reused/recycled into specified sort areas.

END OF SECTION

PART 1 GENERAL**1.1 REFERENCES**

- .1 Canadian Construction Documents Committee (CCDC)
 - .1 CCDC 2-2008, Stipulated Price Contract.
- .2 Canadian Environmental Protection Act (CEPA)
 - .1 SOR/2008-197, Storage Tank Systems for Petroleum Products and Allied Petroleum Products Regulations.

1.2 ADMINISTRATIVE REQUIREMENTS

- .1 Acceptance of Work Procedures:
 - .1 Contractor's Inspection: Contractor: conduct inspection of Work, identify deficiencies and defects, and repair as required to conform to Contract Documents.
 - .1 Notify Departmental Representative in writing of satisfactory completion of Contractor's inspection and submit verification that corrections have been made.
 - .2 Request Departmental Representative's inspection.
 - .2 Departmental Representative's Inspection:
 - .1 Departmental Representative and Contractor to inspect Work and identify defects and deficiencies.
 - .2 Contractor to correct Work as directed.
 - .3 Completion Tasks: submit written certificates in English that tasks have been performed as follows:
 - .1 Work: completed and inspected for compliance with Contract Documents.
 - .2 Defects: corrected and deficiencies completed.
 - .3 Equipment and systems: tested, adjusted, balanced and fully operational.
 - .4 Certificates required by Fire Commissioner and Utilities; submitted.
 - .5 Operation of systems: demonstrated to Owner's personnel.
 - .6 Commissioning & Decommissioning of mechanical systems: completed and copies of final Commissioning Report submitted to Departmental Representative.
 - .7 Work: complete and ready for final inspection.
 - .4 Final Inspection:
 - .1 When completion tasks are done, request final inspection of Work by Departmental Representative, and Contractor.
 - .2 When Work incomplete according to Owner and Departmental Representative, complete outstanding items and request re-inspection.
 - .5 Declaration of Substantial Performance: when Departmental Representative considers deficiencies and defects corrected and requirements of Contract substantially performed, make application for Certificate of Substantial Performance.
 - .6 Commencement of Lien and Warranty Periods: date of Owner's acceptance of submitted declaration of Substantial Performance to be date for commencement for warranty period and commencement of lien period unless required otherwise by lien statute of Place of Work.
 - .7 Final Payment:
 - .1 When Departmental Representative considers final deficiencies and defects corrected and requirements of Contract met, make application for final payment.
 - .2 Refer to CCDC 2: when Work deemed incomplete by Departmental Representative, complete outstanding items and request re-inspection.
 - .8 Payment of Holdback: after issuance of Certificate of Substantial Performance of Work, submit application for payment of holdback amount in accordance with contractual agreement.

1.3 FINAL CLEANING

- .1 Clean in accordance with Section 01 74 11 - Cleaning.
 - .1 Remove surplus materials, excess materials, rubbish, tools and equipment.
- .2 Waste Management: separate waste materials for reuse and recycling in accordance with Section 01 74 21 - Construction/Demolition Waste Management.

PART 2 PRODUCTS

2.1 NOT USED

- .1 Not Used.

PART 3 EXECUTION

3.1 NOT USED

- .1 Not Used.

END OF SECTION

Part 1 General**1.1 SUBMITTALS**

- .1 Submittals: in accordance with Section 01 33 00 - Submittal Procedures.
- .2 Prepare instructions and data using personnel experienced in maintenance and operation of described products.
- .3 Copy will be returned after final inspection, with Departmental Representative's comments.
- .4 Revise content of documents as required prior to final submittal.
- .5 Two weeks prior to Substantial Performance of the Work, submit to the Departmental Representative, four (4) final copies of operating and maintenance manuals in English and French.
- .6 Ensure spare parts, maintenance materials and special tools provided are new, undamaged or defective, and of same quality and manufacture as products provided in Work.
 - .1 Deliver and store as directed by Departmental Representative.
 - .2 Provide itemized inventory listing complete with acknowledgment endorsed by Departmental Representative taking delivery of same, including:
 - .1 Date
 - .2 Specification Section
 - .3 Item
 - .4 Quantity
 - .5 Condition
- .7 Furnish evidence, if requested, for type, source and quality of products provided.
- .8 Defective products will be rejected, regardless of previous inspections. Replace products at own expense.
- .9 Pay costs of transportation.

1.2 FORMAT

- .1 Organize data as instructional manual.
- .2 Binders: vinyl, hard covered, 3 'D' ring, loose leaf 219 x 279 mm with spine and face pockets.
- .3 When multiple binders are used correlate data into related consistent groupings. Identify contents of each binder on spine.
- .4 Cover: identify each binder with type or printed title 'Project Record Documents'; list title of project and identify subject matter of contents.
- .5 Arrange content by systems, process flow, under Section numbers and sequence of Table of Contents.
- .6 Provide tabbed fly leaf for each separate product and system, with typed description of product and major component parts of equipment.
- .7 Text: manufacturer's printed data, or typewritten data.
- .8 Drawings: provide with reinforced punched binder tab. Bind in with text; fold larger drawings to size of text pages.

1.3 CONTENTS - EACH VOLUME

- .1 Table of Contents: provide title of project, date of submission; names.
 - .1 Addresses and telephone numbers of Departmental Representative and Contractor, with name of responsible parties.
 - .2 Schedule of products and systems, indexed to content of volume.
- .2 For each product or system:
 - .1 List names, addresses and telephone numbers of subcontractors and suppliers, including local source of supplies and replacement parts.
- .3 Product Data: mark each sheet to identify specific products and component parts, and data applicable to installation; delete inapplicable information.
- .4 Drawings: supplement product data to illustrate relations of component parts of equipment and systems, to show control and flow diagrams.

1.4 AS-BUILTS AND SAMPLES

- .1 Maintain, in addition to requirements in General Conditions, at site for Departmental Representative one record copy of:
 - .1 Contract Drawings.
 - .2 Specifications.
 - .3 Addenda.
 - .4 Change Orders and other modifications to Contract.
 - .5 Reviewed shop drawings, product data, and samples. Field test records.
 - .6 Inspection certificates.
 - .7 Manufacturer's certificates.
- .2 Store record documents and samples in field office apart from documents used for construction. Provide files, racks, and secure storage.
- .3 Label record documents and file in accordance with Section number listings in List of Contents of this Project Manual. Label each document "PROJECT RECORD" in neat, large, printed letters.
- .4 Maintain record documents in clean, dry and legible condition. Do not use record documents for construction purposes.
- .5 Keep record documents and samples available for inspection by Departmental Representative.

1.5 RECORDING ACTUAL SITE CONDITIONS

- .1 Record information on set of black line opaque drawings, provided by Departmental Representative, and one copy within Project Operation and Maintenance Manual.
- .2 Provide felt tip marking pens, maintaining separate colours for each major system, for recording information.
- .3 Record information concurrently with construction progress. Do not conceal Work until required information is recorded.
- .4 Contract Drawings and shop drawings: mark each item to record actual construction, including:
 - .1 Measured depths of elements of foundation in relation to finish first floor datum.
 - .2 Measured horizontal and vertical locations of underground utilities and appurtenances, referenced to permanent surface improvements.
 - .3 Field changes of dimension and detail.
 - .4 Changes made by change orders.

- .5 Details not on original Contract Drawings.
- .6 References to related shop drawings and modifications.
- .5 Specifications: mark each item to record actual construction, including:
 - .1 Manufacturer, trade name, and catalogue number of each product actually installed, particularly optional items and substitute items.
 - .2 Changes made by Addenda and change orders.
- .6 Other Documents: maintain manufacturer's certifications, inspection certifications and field test records, required by individual specifications sections.

1.6 EQUIPMENT AND SYSTEMS

- .1 Each Item of Equipment and Each System: include description of unit or system, and component parts. Give function, normal operation characteristics, and limiting conditions. Include performance curves, with engineering data and tests, and complete nomenclature and commercial number of replaceable parts.
- .2 Panel board circuit directories: provide electrical service characteristics, controls, and communications.
- .3 Include installed colour coded wiring diagrams.
- .4 Operating Procedures: include start-up, break-in, and routine normal operating instructions and sequences. Include regulation, control, stopping, shut-down, and emergency instructions. Include summer, winter, and any special operating instructions.
- .5 Maintenance Requirements: include routine procedures and guide for trouble-shooting; disassembly, repair, and reassembly instructions; and alignment, adjusting, balancing, and checking instructions.
- .6 Provide servicing and lubrication schedule, and list of lubricants required.
- .7 Include manufacturer's printed operation and maintenance instructions.
- .8 Include sequence of operation by controls manufacturer.
- .9 Provide original manufacturer's parts list, illustrations, assembly drawings, and diagrams required for maintenance.
- .10 Provide installed control diagrams by controls manufacturer.
- .11 Provide Contractor's co-ordination drawings, with installed colour coded piping diagrams.
- .12 Provide charts of valve tag numbers, with location and function of each valve, keyed to flow and control diagrams.
- .13 Provide list of original manufacturer's spare parts, current prices, and recommended quantities to be maintained in storage.
- .14 Include test and balancing reports as specified in Section 01 45 00 - Quality Control.
- .15 Additional requirements: as specified in individual specification sections.

1.7 MATERIALS AND FINISHES

- .1 Building Products, Applied Materials, and Finishes: include product data, with catalogue number, size, composition, and colour and texture designations. Provide information for re-ordering custom manufactured products.
- .2 Instructions for cleaning agents and methods, precautions against detrimental agents and methods, and recommended schedule for cleaning and maintenance.
- .3 Moisture-Protection and Weather-Exposed Products: include manufacturer's recommendations for cleaning agents and methods, precautions against detrimental agents and methods, and recommended schedule for cleaning and maintenance.

1.8 STORAGE, HANDLING AND PROTECTION

- .1 Store spare parts, maintenance materials, and special tools in manner to prevent damage or deterioration.
- .2 Store in original and undamaged condition with manufacturer's seal and labels intact.
- .3 Store components subject to damage from weather in weatherproof enclosures.
- .4 Store paints and freezable materials in a heated and ventilated room.
- .5 Remove and replace damaged products at own expense and to satisfaction of Departmental Representative.

1.9 WARRANTIES AND BONDS

- .1 Develop warranty management plan to contain information relevant to Warranties.
- .2 Warranty management plan to include required actions and documents to assure that Owner receives warranties to which it is entitled.
- .3 Provide plan in narrative form and contain sufficient detail to make it suitable for use by future maintenance and repair personnel.
- .4 Assemble approved information in binder and submit upon acceptance of work. Organize binder as follows:
 - .1 Separate each warranty or bond with index tab sheets keyed to Table of Contents listing.
 - .2 List subcontractor, supplier, and manufacturer, with name, address, and telephone number of responsible principal.
 - .3 Obtain warranties and bonds, executed in duplicate by subcontractors, suppliers, and manufacturers, within ten (10) days after completion of applicable item of work.
 - .4 Verify that documents are in proper form, contain full information, and are notarized.
 - .5 Co-execute submittals when required.
 - .6 Retain warranties and bonds until time specified for submittal.
- .5 Except for items put into use with Departmental Representative's permission, leave date of beginning of time of warranty until Date of Substantial Performance is determined.
- .6 Include information contained in warranty management plan as follows:
 - .1 Roles and responsibilities of personnel associated with warranty process, including points of contact and telephone numbers within the organizations of Contractors, subcontractors, manufacturers or suppliers involved.
 - .2 Listing and status of delivery of Certificates of Warranty for extended warranty items, to include roofs, HVAC balancing, and commissioned systems such as alarm systems and lightning protection systems.
 - .3 Provide list for each warranted equipment, item, feature of construction or system indicating:
 - .1 Name of item.
 - .2 Model and serial numbers.
 - .3 Location where installed.
 - .4 Name and phone numbers of manufacturers or suppliers.
 - .5 Names, addresses and telephone numbers of sources of spare parts.
 - .6 Warranties and terms of warranty: include one-year overall warranty of construction. Indicate items that have extended warranties and show separate warranty expiration dates.
 - .7 Cross-reference to warranty certificates as applicable.

- .8 Starting point and duration of warranty period.
- .9 Summary of maintenance procedures required to continue warranty in force.
- .10 Cross-Reference to specific pertinent Operation and Maintenance manuals.
- .11 Organization, names and phone numbers of persons to call for warranty service.
- .12 Typical response time and repair time expected for various warranted equipment.
- .4 Procedure and status of tagging of equipment covered by extended warranties.
- .5 Post copies of instructions near selected pieces of equipment where operation is critical for warranty and/or safety reasons.
- .7 Respond in a timely manner to oral or written notification of required construction warranty repair work.

Part 2 Products

2.1 NOT USED

- .1 Not Used.

Part 3 Execution

3.1 NOT USED

- .1 Not Used.

END OF SECTION

PAGE INTENTIONALLY LEFT BLANK

PART 1 DEPARTMENTAL REPRESENTATIVE GENERAL**1.1 REFERENCES**

- .1 CSA International
 - .1 CSA S350-M1980(R2003), Code of Practice for Safety in Demolition of Structures.
- .2 U.S. Environmental Protection Agency (EPA)/Office of Water
 - .1 EPA 832/R-92-005, Storm Water Management for Construction Activities: Developing Pollution Prevention Plans and Best Management Practices.

1.2 ACTION AND INFORMATIONAL SUBMITTALS

- .1 Submit in accordance with Section 01 33 00 - Submittal Procedures and Section 01 74 21 - Construction/Demolition Waste Management Disposal.
- .2 Submit demolition drawings:
 - .1 Submit for review and approval by Departmental Representative shoring and underpinning drawings stamped and signed by professional engineer registered or licensed in the Province of Ontario Canada, showing proposed method.

1.3 SITE CONDITIONS

- .1 Review "Designated Substance Report" and take precautions to protect environment.
- .2 Should material resembling spray or trowel-applied asbestos or other designated substance listed as hazardous be encountered, stop work, take preventative measures, and notify Departmental Representative immediately.
 - .1 Do not proceed until written instructions have been received from Departmental Representative.
- .3 Notify Departmental Representative before disrupting building access or services.

PART 2 PRODUCTS**2.1 NOT USED**

- .1 Not used.

PART 3 EXECUTION**3.1 EXAMINATION**

- .1 Inspect building with Departmental Representative and verify extent and location of items designated for removal, disposal, alternative disposal, recycling, salvage and items to remain.
- .2 Locate and protect utilities. Preserve active utilities traversing site in operating condition.
- .3 Notify and obtain approval of utility companies before starting demolition.
- .4 Disconnect, cap, plug or divert, as required, existing public utilities within the property where they interfere with the execution of the work, in conformity with the requirements of the authorities having jurisdiction. Mark the location of these and previously capped or plugged services on the site and indicate location (horizontal and vertical) on the record drawings. Support, shore up and maintain pipes and conduits encountered.
 - .1 Immediately notify Departmental Representative and utility company concerned in case of damage to any utility or service, designated to remain in place.

- .2 Immediately notify the Departmental Representative should uncharted utility or service be encountered, and await instruction in writing regarding remedial action.

3.2 PREPARATION

- .1 Temporary Erosion and Sedimentation Control:
 - .1 Provide temporary erosion and sedimentation control measures to prevent soil erosion and discharge of soil-bearing water runoff or airborne dust to adjacent properties and walkways, according to: requirements of authorities having jurisdiction & sediment and erosion control plan, specific to site, that complies with EPA 832/R-92-005 or requirements of authorities having jurisdiction, whichever is more stringent.
 - .2 Inspect, repair, and maintain erosion and sedimentation control measures during demolition.
 - .3 Remove erosion and sedimentation controls and restore and stabilize areas disturbed during removal after completion of demolition work.
- .2 Protection of In-Place Conditions:
 - .1 Prevent movement, settlement, or damage to adjacent structures and elements. Provide bracing and shoring required.
 - .2 Keep noise, dust, and inconvenience to occupants to minimum.
 - .3 Protect building systems, services and equipment.
 - .4 Provide temporary dust screens, covers, railings, supports and other protection as required.
 - .5 Do Work in accordance with Section 01 35 29 - Health and Safety Requirements.
- .3 Demolition/Removal:
 - .1 Remove items as indicated.
 - .2 Removal of Pavements, Curbs and Gutters:
 - .1 Square up adjacent surfaces to remain in place by saw cutting or other method approved by Departmental Representative.
 - .2 Protect adjacent joints and load transfer devices.
 - .3 Protect underlying and adjacent granular materials.
 - .3 Remove parts of existing building to permit new construction.
 - .4 Trim edges of partially demolished building elements to tolerances as defined by Departmental Representative to suit future use.

3.3 CLEANING

- .1 Progress Cleaning: clean in accordance with Section 01 74 11 - Cleaning.
 - .1 Leave Work area clean at end of each day.
- .2 Final Cleaning: upon completion remove surplus materials, rubbish, tools and equipment in accordance with Section 01 74 11 - Cleaning.
- .3 Refer to demolition drawings and specifications for items to be salvaged for reuse.
- .4 Waste Management: separate waste materials for reuse and recycling in accordance with Section 01 74 21 - Construction/Demolition Waste Management and Disposal.

END OF SECTION

PART 1 GENERAL**1.1 REFERENCES**

- .1 Definitions:
 - .1 Dangerous Goods: product, substance, or organism specifically listed or meets hazard criteria established in Transportation of Dangerous Goods Regulations.
 - .2 Hazardous Material: product, substance, or organism used for its original purpose; and is either dangerous goods or material that will cause adverse impact to environment or adversely affect health of persons, animals, or plant life when released into the environment.
 - .3 Hazardous Waste: hazardous material no longer used for its original purpose and that is intended for recycling, treatment or disposal.
- .2 Reference Standards:
 - .1 Canadian Environmental Protection Act, 1999 (CEPA 1999)
 - .1 Export and Import of Hazardous Waste and Hazardous Recyclable Material Regulations (SOR/2005-149).
 - .2 Department of Justice Canada (Jus)
 - .1 Transportation of Dangerous Goods Act, 1992 (TDG Act) 1992, (c. 34).
 - .2 Transportation of Dangerous Goods Regulations (T-19.01-SOR/2001-286).
 - .3 Green Seal Environmental Standards (GS)
 - .1 GS-11-2008, 2nd Edition, Paints and Coatings.
 - .2 GS-36-00, Commercial Adhesives.
 - .4 National Research Council Canada Institute for Research in Construction (NRC-IRC)
 - .1 National Fire Code of Canada-2005.

1.2 ACTION AND INFORMATIONAL SUBMITTALS

- .1 Submit in accordance with Section 01 33 00 - Submittal Procedures.
- .2 Product Data:
 - .1 Submit manufacturer's instructions, printed product literature and data sheets for hazardous materials and include product characteristics, performance criteria, physical size, finish and limitations.
 - .2 Submit WHMIS MSDS in accordance with Section 01 35 29 - Health and Safety Requirements and Section 01 35 43 - Environmental Procedures to Departmental Representative for each hazardous material required prior to bringing hazardous material on site.
 - .3 Submit hazardous materials management plan to Departmental Representative that identifies hazardous materials, usage, location, personal protective equipment requirements, and disposal arrangements.

1.3 DELIVERY, STORAGE AND HANDLING

- .1 Deliver, store and handle materials in accordance with Section 01 61 00 - Common Product Requirements and with manufacturer's written instructions.
- .2 Delivery and Acceptance Requirements: deliver materials to site in original factory packaging, labelled with manufacturer's name and address.
- .3 Transport hazardous materials and wastes in accordance with Transportation of Dangerous Goods Act, Transportation of Dangerous Goods Regulations, and applicable provincial regulations.
 - .1 When exporting hazardous waste to another country, ensure compliance with Export and Import of Hazardous Waste and Hazardous Recyclable Materials Regulations.
- .4 Storage and Handling Requirements:
 - .1 Co-ordinate storage of hazardous materials with Departmental Representative and abide by internal requirements for labelling and storage of materials and wastes.

- .2 Store and handle hazardous materials and wastes in accordance with applicable federal and provincial laws, regulations, codes, and guidelines.
- .3 Store and handle flammable and combustible materials in accordance with National Fire Code of Canada requirements.
- .4 Keep no more than 45 litres of flammable and combustible liquids such as gasoline, kerosene and naphtha for ready use.
 - .1 Store flammable and combustible liquids in approved safety cans bearing the Underwriters' Laboratory of Canada or Factory Mutual seal of approval.
 - .2 Storage of quantities of flammable and combustible liquids exceeding 45 litres for work purposes requires the written approval of the Departmental Representative.
- .5 Transfer of flammable and combustible liquids is prohibited within buildings.
- .6 Transfer flammable and combustible liquids away from open flames or heat-producing devices.
- .7 Solvents or cleaning agents must be non-flammable or have flash point above 38 degrees Celsius.
- .8 Store flammable and combustible waste liquids for disposal in approved containers located in safe, ventilated area. Keep quantities to minimum.
- .9 Observe smoking regulations, smoking is prohibited in areas where hazardous materials are stored, used, or handled.
- .10 Storage requirements for quantities of hazardous materials and wastes in excess of 5 kg for solids, and 5 litres for liquids:
 - .1 Store hazardous materials and wastes in closed and sealed containers.
 - .2 Label containers of hazardous materials and wastes in accordance with WHMIS.
 - .3 Store hazardous materials and wastes in containers compatible with that material or waste.
 - .4 Segregate incompatible materials and wastes.
 - .5 Ensure that different hazardous materials or hazardous wastes are stored in separate containers.
 - .6 Store hazardous materials and wastes in secure storage area with controlled access.
 - .7 Maintain clear egress from storage area.
 - .8 Store hazardous materials and wastes in location that will prevent them from spilling into environment.
 - .9 Have appropriate emergency spill response equipment available near storage area, including personal protective equipment.
 - .10 Maintain inventory of hazardous materials and wastes, including product name, quantity, and date when storage began.
 - .11 When hazardous waste is generated on site:
 - .1 Co-ordinate transportation and disposal with Departmental Representative.
 - .2 Comply with applicable federal, provincial and municipal laws and regulations for generators of hazardous waste.
 - .3 Use licensed carrier authorized by provincial authorities to accept subject material.
 - .4 Before shipping material obtain written notice from intended hazardous waste treatment or disposal facility it will accept material and it is licensed to accept this material.
 - .5 Label containers with legible, visible safety marks as prescribed by federal and provincial regulations.
 - .6 Only trained personnel handle, offer for transport, or transport dangerous goods.
 - .7 Provide photocopy of shipping documents and waste manifests to Departmental Representative.
 - .8 Track receipt of completed manifest from consignee after shipping dangerous goods. Provide photocopy of completed manifest to Departmental Representative.

- .9 Report discharge, emission, or escape of hazardous materials immediately to Departmental Representative and appropriate provincial authority. Take reasonable measures to control release.
 - .12 Ensure personnel have been trained in accordance with Workplace Hazardous Materials Information System (WHMIS) requirements.
 - .13 Report spills or accidents immediately to Departmental Representative. Submit a written spill report to Departmental Representative within 24 hours of incident.
- .5 Packaging Waste Management: remove for reuse by manufacturer of pallets, crates, padding, and packaging materials as specified in accordance with Section 01 74 21 - Construction/Demolition Waste Management and Disposal.

PART 2 PRODUCTS

2.1 MATERIALS

- .1 Description:
 - .1 Bring on site only quantities hazardous material required to perform Work.
 - .2 Maintain MSDS in proximity to where materials are being used. Communicate this location to personnel who may have contact with hazardous materials.
 - .3 Sustainability Characteristics:
 - .1 Adhesives and Sealants in accordance with Section 07 92 00 - Joint Sealant.
 - .2 Primers, Paints and Coatings in accordance with manufacturer's recommendations for surface conditions and Section 09 91 23 - Interior Painting.

PART 3 EXECUTION

3.1 CLEANING

- .1 Progress Cleaning: clean in accordance with Section 01 74 11 - Cleaning.
 - .1 Leave Work area clean at end of each day.
- .2 Final Cleaning: upon completion remove surplus materials, rubbish, tools and equipment in accordance with Section 01 74 11 - Cleaning.
- .3 Waste Management: separate waste materials for reuse and recycling in accordance with Section 01 74 21 - Construction/Demolition Waste Management and Disposal.
 - .1 Dispose of hazardous waste materials in accordance with applicable federal and provincial acts, regulations, and guidelines.
 - .2 Recycle hazardous wastes for which there is approved, cost effective recycling process available.
 - .3 Send hazardous wastes to authorized hazardous waste disposal or treatment facilities.
 - .4 Burning, diluting, or mixing hazardous wastes for purpose of disposal is prohibited.
 - .5 Disposal of hazardous materials in waterways, storm or sanitary sewers, or in municipal solid waste landfills is prohibited.
 - .6 Dispose of hazardous wastes in timely fashion in accordance with applicable provincial regulations.
 - .7 Minimize generation of hazardous waste to maximum extent practicable. Take necessary precautions to avoid mixing clean and contaminated wastes.
 - .8 Identify and evaluate recycling and reclamation options as alternatives to land disposal, such as:
 - .1 Hazardous wastes recycled in manner constituting disposal.
 - .2 Hazardous waste burned for energy recovery.
 - .3 Lead-acid battery recycling.
 - .4 Hazardous wastes with economically recoverable precious metals.

END OF SECTION

PART 1 GENERAL**1.1 RELATED SECTIONS**

- .1 Section 01 33 00 - Submittal Procedures.
- .2 Section 01 61 00 - Common Product Requirements.

1.2 REFERENCES

- .1 American Society for Testing and Materials International, (ASTM)
 - .1 ASTM A 53/A 53M-[02], Specification for Pipe, Steel, Black and Hot-Dipped, Zinc-Coated Welded and Seamless.
 - .2 ASTM A 269-02, Specification for Seamless and Welded Austenitic Stainless Steel Tubing for General Service.
 - .3 ASTM A 307-02, Specification for Carbon Steel Bolts and Studs, 60,000 PSI Tensile Strength.
- .2 Canadian General Standards Board (CGSB)
 - .1 CAN/CGSB-1.40-97, Anti-corrosive Structural Steel Alkyd Primer.
 - .2 CAN/CGSB-1.181-92, Ready-Mixed, Organic Zinc-Rich Coating.
- .3 Canadian Standards Association (CSA International)
 - .1 CAN/CSA-G40.20/G40.21-98, General Requirements for Rolled or Welded Structural Quality Steel.
 - .2 CAN/CSA-G164-M92(R1998), Hot Dip Galvanizing of Irregularly Shaped Articles.
 - .3 CAN/CSA-S16.1-01, Limit States Design of Steel Structures.
 - .4 CSA W48-01, Filler Metals and Allied Materials for Metal Arc Welding (Developed in co-operation with the Canadian Welding Bureau).
 - .5 CSA W59-1989(R2001), Welded Steel Construction (Metal Arc Welding) (Imperial Version).
- .4 The Environmental Choice Program
 - .1 CCD-047a-98, Paints, Surface Coatings.
 - .2 CCD-048-98, Surface Coatings - Recycled Water-borne.

1.3 SUBMITTALS

- .1 Product Data:
 - .1 Submit manufacturer's printed product literature, specifications and data sheet in accordance with Section 01 33 00 - Submittal Procedures.
 - .2 Submit WHMIS MSDS - Material Safety Data Sheets in accordance with Section 01 33 00 - Submittal Procedures. Indicate VOC's:
 - .1 For finishes, coatings, primers and paints.
- .2 Shop Drawings
 - .1 Submit shop drawings in accordance with Section 01 33 00 - Submittal Procedures.
 - .2 Indicate materials, core thicknesses, finishes, connections, joints, method of anchorage, number of anchors, supports, reinforcement, details, and accessories.
 - .3 Shop drawings to be reviewed, stamped and sealed by Structural Engineer licensed in the province of Ontario.

1.4 QUALITY ASSURANCE

- .1 Test Reports: Certified test reports showing compliance with specified performance characteristics and physical properties.
- .2 Certificates: Product certificates signed by manufacturer certifying materials comply with specified performance characteristics and criteria and physical requirements.

- .3 Pre-installation Meetings: Conduct pre-installation meeting to verify project requirements, manufacturer's installation instructions and manufacturer's warranty requirements.

1.5 DELIVERY, STORAGE, AND HANDLING

- .1 Packing, Shipping, Handling and Unloading:
 - .1 Deliver, store, handle and protect materials in accordance with Section 01 61 00 - Common Product Requirements.
- .2 Storage and Protection:
 - .1 Cover exposed stainless steel surfaces with pressure sensitive heavy protection paper or apply strippable plastic coating, before shipping to job site.
 - .2 Leave protective covering in place until final cleaning of building. Provide instructions for removal of protective covering.

1.6 WASTE MANAGEMENT AND DISPOSAL

- .1 Separate and recycle waste materials in accordance with Section 01 74 19 - Construction/Demolition Waste Management And Disposal.
- .2 Remove from site and dispose of packaging materials at appropriate recycling facilities.
- .3 Collect and separate for disposal paper, plastic, polystyrene, and corrugated cardboard packaging material [in appropriate on-site] for recycling in accordance with Waste Management Plan.
- .4 Divert unused metal materials from landfill to metal recycling facility approved by Architect.

PART 2 PRODUCTS

2.1 MATERIALS

- .1 Steel sections and plates: to CAN/CSA-G40.20/G40.21, Grade 300W.
- .2 Steel pipe: to ASTM A 53/A 53M extra strong, galvanized finish.
- .3 Welding materials: to CSA W59.
- .4 Welding electrodes: to CSA W48 Series.
- .5 Bolts and anchor bolts: to ASTM A 307.
- .6 Stainless steel tubing: to ASTM A 269, Type 302 Commercial grade Seamless welded with AISI No. 4 finish.
- .7 Grout: non-shrink, non-metallic, flowable, 15 MPa at 24 hours.

2.2 FABRICATION

- .1 Fabricate work square, true, straight and accurate to required size, with joints closely fitted and properly secured.
- .2 Use self-tapping shake-proof flat headed screws on items requiring assembly by screws or as indicated.
- .3 Where possible, fit and shop assemble work, ready for erection.
- .4 Ensure exposed welds are continuous for length of each joint. File or grind exposed welds smooth and flush.

2.3 FINISHES

- .1 Galvanizing: hot dipped galvanizing with zinc coating 600 g/m² to CAN/CSA-G164.

- .2 Chromium plating: chrome on steel with plating sequence of 0.009 mm thickness of copper 0.010 mm thickness of nickel and 0.0025 mm thickness of chromium.
- .3 Shop coat primer: to CAN/CGSB-1.40.
- .4 Zinc primer: zinc rich, ready mix to CAN/CGSB-1.181.

2.4 ISOLATION COATING

- .1 Isolate aluminum from following components, by means of bituminous paint:
 - .1 Dissimilar metals except stainless steel, zinc, or white bronze of small area.
 - .2 Concrete, mortar and masonry.
 - .3 Wood.

2.5 SHOP PAINTING

- .1 Apply one shop coat of primer to metal items, with exception of galvanized or concrete encased items.
- .2 Use primer unadulterated, as prepared by manufacturer. Paint on dry surfaces, free from rust, scale, grease. Do not paint when temperature is lower than 7 degrees C.
- .3 Clean surfaces to be field welded; do not paint.

2.6 ANGLE LINTELS

- .1 Steel angles: galvanized, sizes indicated for openings. Provide 150 mm minimum bearing at ends.
- .2 Weld or bolt back-to-back angles to profiles as indicated.

2.7 FRAMES

- .1 Fabricate frames from steel, sizes of channel and opening as indicated.
- .2 Weld channels together to form continuous frame for jambs and head of openings, sizes as indicated.
- .3 Finish: as indicated.

PART 3 EXECUTION

3.1 ERECTION

- .1 Do welding work in accordance with CSA W59 unless specified otherwise.
- .2 Erect metalwork square, plumb, straight, and true, accurately fitted, with tight joints and intersections.
- .3 Provide suitable means of anchorage acceptable to Architect such as dowels, anchor clips, bar anchors, expansion bolts and shields, and toggles.
- .4 Exposed fastening devices to match finish and be compatible with material through which they pass.
- .5 Provide components for building by other sections in accordance with shop drawings and schedule.
- .6 Make field connections with bolts to CAN/CSA-S16.1, or weld.
- .7 Hand items over for casting into concrete or building into masonry to appropriate trades together with setting templates.
- .8 Touch-up rivets, field welds, bolts and burnt or scratched surfaces after completion of erection with primer.

- .9 Touch-up galvanized surfaces with zinc rich primer where burned by field welding.

3.2 **CHANNEL FRAMES**

- .1 Install steel channel frames to openings as indicated.

3.3 **CLEANING**

- .1 Perform cleaning after installation to remove construction and accumulated environmental dirt.
- .2 Upon completion of installation, remove surplus materials, rubbish, tools and equipment barriers.

END OF SECTION

PART 1 GENERAL**1.1 RELATED SECTIONS**

- .1 Section 01 33 00 - Submittal Procedures.
- .2 Section 01 35 29 - Health and Safety Requirements.

1.2 REFERENCES

- .1 American Society for Testing and Materials International (ASTM)
 - .1 ASTM C 553-02, Specification for Mineral Fibre Blanket Thermal Insulation for Commercial and Industrial Applications.
 - .2 ASTM C 665-01e1, Specification for Mineral-Fiber Blanket Thermal Insulation for Light Frame Construction and Manufactured Housing.
 - .3 ASTM C 1320-05, Standard Practice for Installation of Mineral Fiber Batt and Blanket Thermal Insulation for Light Frame Construction.
- .2 Canadian Gas Association (CGA)
 - .1 CAN/CGA-B149.1-05, Natural Gas and Propane Installation Code Handbook.
 - .2 CAN/CGA-B149.2-05, Propane Storage and Handling Code.
 - .3 Canadian Standards Association (CSA International)
 - .1 CSA B111-1974(R2003), Wire Nails, Spikes and Staples.
 - .4 Underwriters Laboratories of Canada (ULC)
 - .1 CAN/ULC-S604-M1991, Type A Chimneys.
 - .2 CAN/ULC-S702-1997, Standard for Mineral Fibre Insulation.

1.3 SUBMITTALS

- .1 Product Data:
 - .1 Submit manufacturer's printed product literature, specifications and data sheet in accordance with Section 01 33 00 - Submittal Procedures.
 - .2 Manufacturer's Instructions:
 - .1 Submit manufacturer's installation instructions.

1.4 QUALITY ASSURANCE

- .1 Test Reports: certified test reports showing compliance with specified performance characteristics and physical properties.
- .2 Certificates: product certificates signed by manufacturer certifying materials comply with specified performance characteristics and criteria and physical requirements.
- .3 Convene pre-installation meeting one week prior to beginning on-site installations.
 - .1 Verify project requirements.
 - .2 Review installation and substrate conditions.
 - .3 Co-ordinate with other building subtrades.
 - .4 Review manufacturer's installation instructions and warranty requirements.
- .4 Health and Safety Requirements: do construction occupational health and safety in accordance with Section 01 35 29 - Health and Safety Requirements.

1.5 WASTE MANAGEMENT AND DISPOSAL

- .1 Separate waste materials for reuse and recycling in accordance with Section 01 74 21 - Construction/Demolition Waste Management and Disposal.
- .2 Remove from site and dispose of packaging materials at appropriate recycling facilities.
- .3 Collect and separate for disposal paper, plastic, polystyrene and corrugated cardboard packaging material for recycling in accordance with Waste Management Plan.

PART 2 PRODUCTS**2.1 INSULATION**

- .1 Batt and blanket mineral fibre: to ASTM C 553, ASTM C 665 & CAN/ULC S702-09.
 - .1 Type: 1.
 - .2 Thickness: 152 mm as indicated.

2.2 ACCESSORIES

- .1 Insulation clips:
 - .1 Impale type, perforated 50 x 50 mm cold rolled carbon steel 0.8 mm thick, adhesive back, spindle of 2.5 mm diameter annealed steel, length to suit insulation, 25 mm diameter washers of self-locking type.
- .2 Nails: galvanized steel, length to suit insulation plus 25 mm, to CSA B111.
- .3 Staples: 12 mm minimum leg.
- .4 Tape: as recommended by manufacturer.

PART 3 EXECUTION**3.1 MANUFACTURER'S INSTRUCTIONS**

- .1 Compliance: comply with manufacturer's written data, including product technical bulletins, product catalogue installation instructions, product carton installation instructions, and data sheets.

3.2 INSULATION INSTALLATION

- .1 Install insulation to maintain continuity of thermal protection to building elements and spaces and to ASTM C 1320.
- .2 Install insulation with factory applied vapour barrier facing warm side of building spaces [and vapour permeable membrane facing cold side]. Lap ends and side flanges of membrane over framing members. Retain in position with [nails] [staples] [insulation clips] [wire ties] installed as recommended by manufacturer. Tape seal butt ends [and lapped side flanges]. Do not tear or cut vapour barrier.
- .3 Fit insulation closely around electrical boxes, pipes, ducts, frames and other objects in or passing through insulation.
- .4 Do not compress insulation to fit into spaces.
- .5 Keep insulation minimum 75 mm from heat emitting devices such as recessed light fixtures, and minimum 50 mm from sidewalls of CAN/ULC-S604 Type A chimneys and CAN/CGA-B149.1 and CAN/CGA-B149.2 Type B and L vents.
- .6 Do not enclose insulation until it has been inspected and approved by Architect.

3.3 CLEANING

- .1 Upon completion of installation, remove surplus materials, rubbish, tools and equipment barriers.

END OF SECTION

PART 1 GENERAL**1.1 SECTION INCLUDES**

- .1 Fireproofing material

1.2 RELATED SECTIONS

- .1 Section 01 33 00 - Submittal Procedures.
- .2 Section 01 45 00 - Quality Control.
- .3 Section 01 61 00 - Common Product Requirements.
- .4 Section 01 74 11 - Cleaning.
- .5 Section 02 81 01 - Hazardous Materials.
- .6 Section 05 50 00 – Metal Fabrications

1.3 1.3 REFERENCES

- .1 CAN4 -S101 M - Standard Methods of Fire Endurance Tests of Building Construction and Materials
- .2 ANSI/UL 263 – 13TH Edition, ASTM E119-2000 Edition
- .3 CAN4-S102 M - Standard Method of Test for Surface Burning Characteristics of Building Materials and Assemblies
- .4 ULC - List of Equipment and Materials

1.4 SUBMITTALS

- .1 Submit Product data to requirements of Section 01 33 00 - Submittal Procedures.
- .2 Submit manufacturer's product data for materials and samples, providing descriptions are sufficient for identification at job site. Include manufacturer's printed instructions for installation and listing design references.

1.5 QUALITY ASSURANCE

- .1 Manufacturer: Company specializing in manufacturing products of this Section is certified by Underwriters Laboratories of Canada.
- .2 Applicator: Approved or supervised by the manufacturer of fireproofing materials.
- .3 Product: Manufactured under appropriate test agency Follow-up Program. Each container or package shall bear the listing company's label or listing mark.

1.6 REGULATORY REQUIREMENTS

- .1 Conform to latest edition of the National Building Code of Canada or the applicable Provincial Building Code for fire resistance ratings.

1.7 DELIVERY, STORAGE AND HANDLING

- .1 Units of 5 gallons per pail.
- .2 Deliver and store materials in a dry, protected area, off ground in original, undamaged, sealed containers with manufacturer's labels and seals intact at temperatures between 10C and 30C.
- .3 Product shelf life is 6 months from purchase.

- .4 Protect from frost during storage and use.

1.8 PROJECT/SITE CONDITIONS

- .1 Existing Conditions:
 - .1 Verify existing conditions and substrates before starting work. Correct unsatisfactory conditions before proceeding.
 - .2 Proceed with installation only after steel components are primed with compatible recommended primer.
- .2 Environmental requirements:
 - .1 Provide masking and drop cloths to prevent contamination of adjacent surfaces by fireproofing material.
 - .2 Comply with manufacturing recommendations for temperature and humidity conditions before, during and after installation of fireproofing.

1.9 SEQUENCING AND SCHEDULING

- .1 Sequence work to permit installation of fireproofing materials to be installed after adjacent work is complete.

PART 2 PRODUCTS

2.1 MATERIALS

- .1 Designs or Assemblies listed in the ULC Guide. Tested in accordance with the Standard Method of Fire Tests of Building Construction and Materials, CAN/ULC-S101-07 Edition (ANSI/UL 263 – 13th Edition, ASTM E 119-2000 Edition).
- .2 Acceptable manufacturers and products: 3M™ Fire Protection Products - 3M™ FireDam™ Intumescent Coating WB 1000

PART 3 EXECUTION

3.1 EXAMINATION

- .1 Examine surfaces to receive work of this Section and report any defects which may affect the work of this section.
- .2 Confirm compatibility of surfaces (primers) to receive fireproofing material.
- .3 Beginning of installation means acceptance substrate.

3.2 PREPARATION

- .1 Examine sizes and conditions of steel to be fireproofed to establish correct thickness and installation of materials. Ensure that substrates and surfaces are clean, dry and frost free.
- .2 Prepare surfaces to received fireproofing material to manufacturer's instructions.
- .3 Mask where necessary to avoid spillage and over coating onto adjoining surfaces; remove stains on adjacent surfaces.

3.3 APPLICATION

- .1 The applicator must be trained and qualified and should apply the 3M FireDam Intumescent Coating WB 1000 in accordance with the Testing Agency listing and the following instructions.

- .2 The 3M FireDam Intumescent Coating WB 1000 should not be applied when relative humidity exceeds 80% or the surface to be coated is less than 3C above the dewpoint. The product is recommended to be applied only when temperatures are above 10C or 50F.
- .3 To ensure an even coating thickness, the desired thickness should be achieved by the application of successive coats of no more than 300 microns dft (460 microns wft) per coat
- .4 Apply in sufficient thickness to achieve rating to uniform density and texture.
- .5 The completed dry film thickness should be checked to ensure the required thickness has been applied.
- .6 When multiple coats of 3M FireDam Intumescent Coating WB 1000 are required to achieve the prescribed dry film thickness, adequate drying time between the coats should be allowed. At 20C the minimum overcoating time is typically 4-6 hours. (The time will vary depending upon the prevailing temperature, relative humidity, air movement and thickness of material applied.

3.4 **CLEANING**

- .1 Clean adjacent surfaces of fireproofing material.

3.5 **3.5 FIELD QUALITY CONTROL**

- .1 Notify Consultant when ready for inspection.

END OF SECTION

PAGE INTENTIONALLY LEFT BLANK

PART 1 GENERAL**1.1 RELATED SECTIONS**

- .1 Section 01 33 00 - Submittal Procedures.
- .2 Section 01 45 00 - Quality Control.
- .3 Section 01 61 00 - Common Product Requirements.
- .4 Section 02 81 01 - Hazardous Materials.

1.2 REFERENCES

- .1 Health Canada/Workplace Hazardous Materials Information System (WHMIS)
 - .1 Material Safety Data Sheets (MSDS).
- .2 Underwriter's Laboratories of Canada (ULC)
 - .1 ULC-S115-1995, Fire Tests of Fire stop Systems.

1.3 DEFINITIONS

- .1 Fire Stop Material: device intended to close off opening or penetration during fire or materials that fill openings in wall or floor assembly where penetration is by cables, cable trays, conduits, ducts and pipes and poke-through termination devices, including electrical outlet boxes along with their means of support through wall or floor openings.
- .2 Single Component Fire Stop System: fire stop material that has Listed Systems Design and is used individually without use of high temperature insulation or other materials to create fire stop system.
- .3 Multiple Component Fire Stop System: exact group of fire stop materials that are identified within Listed Systems Design to create on site fire stop system.
- .4 Tightly Fitted; (ref: NBC Part 3.1.9.1.1 and 9.10.9.6.1): penetrating items that are cast in place in buildings of non-combustible construction or have "0" annular space in buildings of combustible construction.
 - .1 Words "tightly fitted" should ensure that integrity of fire separation is such that it prevents passage of smoke and hot gases to unexposed side of fire separation.

1.4 SUBMITTALS

- .1 Provide submittals in accordance with Section 01 33 00 - Submittal Procedures.
- .2 Product Data:
 - .1 Submit manufacturer's printed product literature, specifications and datasheet and include product characteristics, performance criteria, physical size, finish and limitations.
 - .2 Submit WHMIS MSDS - Material Safety Data Sheets in accordance with Section 02 81 01 - Hazardous Materials.
- .3 Shop Drawings:
 - .1 Submit shop drawings to show [location,] proposed material, reinforcement, anchorage, fastenings and method of installation.
 - .2 Construction details should accurately reflect actual job conditions.
- .4 Samples:
 - .1 Submit duplicate 300 x 300 mm samples showing actual fire stop material proposed for project.
- .5 Quality assurance submittals: submit following in accordance with Section 01 45 00 - Quality Control.

- .1 Test reports: in accordance with CAN-ULC-S101 for fire endurance and CAN-ULC-S102 for surface burning characteristics.
 - .1 Submit certified test reports from approved independent testing laboratories, indicating compliance of applied fire stopping with specifications for specified performance characteristics and physical properties.
 - .2 Certificates: submit certificates signed by manufacturer certifying that materials comply with specified performance characteristics and physical properties.
 - .3 Manufacturer's Instructions: submit manufacturer's installation instructions and special handling criteria, installation sequence, and cleaning procedures.
 - .4 Manufacturer's Field Reports: submit to manufacturer's written reports within 3 days of review, verifying compliance of Work, as described in PART 3 - FIELD QUALITY CONTROL.

1.5 QUALITY ASSURANCE

- .1 Qualifications:
 - .1 Installer: company specializing in fire stopping installations with 5 years documented experience and approved by manufacturer.
- .2 Pre-Installation Meetings: convene pre-installation meeting one week prior to beginning work of this Section with contractor's representative:
 - .1 Verify project requirements.
 - .2 Review installation and substrate conditions.
 - .3 Co-ordination with other building subtrades.
 - .4 Review manufacturer's installation instructions and warranty requirements.
- .3 Site Meetings: as part of Manufacturer's Services described in PART 3 - FIELD QUALITY CONTROL, schedule site visits, to review Work, at stages listed.
 - .1 After delivery and storage of products, and when preparatory Work is complete, but before installation begins.
 - .2 During progress of Work at 60% complete.
 - .3 Upon completion of Work, after cleaning is carried out.

1.6 DELIVERY, STORAGE AND HANDLING

- .1 Packing, shipping, handling and unloading:
 - .1 Deliver, store and handle materials in accordance with Section 01 61 00 - Common Product Requirements.
 - .2 Deliver, store and handle materials in accordance with manufacturer's written instructions.
 - .3 Deliver materials to the site in undamaged condition and in original unopened containers, marked to indicate brand name, manufacturer, ULC markings.
- .2 Storage and Protection:
 - .1 Store materials indoors, in dry location and in accordance with manufacturer's recommendations in clean, dry, well-ventilated area.
 - .2 Replace defective or damaged materials with new.
- .3 Waste Management and Disposal:
 - .1 Separate waste materials for reuse and recycling in accordance with Section 01 74 21 - Construction/Demolition Waste Management and Disposal.

PART 2 PRODUCTS

2.1 MATERIALS

- .1 Fire stopping and smoke seal systems: in accordance with CAN-ULC-S115.
 - .1 Asbestos-free materials and systems capable of maintaining effective barrier against flame, smoke and gases in compliance with requirements of CAN- ULC-S115 and not

- to exceed opening sizes for which they are intended and conforming to specified special requirements described in PART 3.
- .2 Fire stop system rating: as indicated; Fire resistance rating of installed fire stopping assembly shall not be less than the fire resistance rating of the surrounding floor and wall assembly.
 - .2 Service penetration assemblies: systems tested to CAN-ULC-S115.
 - .3 Service penetration fire stop components: certified by test laboratory to CAN-ULC-S115.
 - .4 Fire-resistance rating of installed fire stopping assembly in accordance with NBC.
 - .5 Fire stopping and smoke seals at openings intended for ease of re-entry such as cables: elastomeric seal.
 - .6 Fire stopping and smoke seals at openings around penetrations for pipes, ductwork and other mechanical items requiring sound and vibration control: elastomeric seal.
 - .7 Primers: to manufacturer's recommendation for specific material, substrate, and end use.
 - .8 Water (if applicable): potable, clean and free from injurious amounts of deleterious substances.
 - .9 Damming and backup materials, supports and anchoring devices: to manufacturer's recommendations, and in accordance with tested assembly being installed as acceptable to authorities having jurisdiction.
 - .10 Sealants for vertical joints: non-sagging.

PART 3 EXECUTION

3.1 MANUFACTURER'S INSTRUCTIONS

- .1 Compliance: comply with manufacturer's written recommendations or specifications, including product technical bulletins, handling, storage and installation instructions, and datasheets.

3.2 PREPARATION

- .1 Examine sizes and conditions of voids to be filled to establish correct thicknesses and installation of materials.
 - .1 Ensure that substrates and surfaces are clean, dry and frost free.
- .2 Prepare surfaces in contact with fire stopping materials and smoke seals to manufacturer's instructions.
- .3 Maintain insulation around pipes and ducts penetrating fire separation without interruption to vapour barrier.
- .4 Mask where necessary to avoid spillage and over coating onto adjoining surfaces; remove stains on adjacent surfaces.

3.3 INSTALLATION

- .1 Install fire stopping and smoke seal material and components in accordance with manufacturer's certified tested system listing.
- .2 Seal holes or voids made by through penetrations, poke-through termination devices, and unpenetrated openings or joints to ensure continuity and integrity of fire separation are maintained.
- .3 Provide temporary forming as required and remove forming only after materials have gained sufficient strength and after initial curing.
- .4 Tool or trowel exposed surfaces to neat finish.

- .5 Remove excess compound promptly as work progresses and upon completion.

3.4 SEQUENCES OF OPERATION

- .1 Proceed with installation only when submittals have been reviewed by Architect.
- .2 Install floor fire stopping before interior partition erections.
- .3 Metal deck bonding: fire stopping to precede spray applied fireproofing to ensure required bonding.
- .4 Mechanical pipe insulation: [certified] fire stop system component.
 - .1 Ensure pipe insulation installation precedes fire stopping.

3.5 FIELD QUALITY CONTROL

- .1 Inspections: notify Architect when ready for inspection and prior to concealing or enclosing fire stopping materials and service penetration assemblies.
- .2 Manufacturer's Field Services:
 - .1 Obtain written report from manufacturer verifying compliance of Work, in handling, installing, applying, protecting and cleaning of product and submit Manufacturer's Field Reports as described in PART 1 - SUBMITTALS.
 - .2 Provide manufacturer's field services consisting of product use recommendations and periodic site visits for inspection of product installation in accordance with manufacturer's instructions.
 - .3 Schedule site visits, to review Work, as directed in PART 1 - QUALITY ASSURANCE.

3.6 CLEANING

- .1 Proceed in accordance with Section 01 74 11 - Cleaning.
- .2 On completion and verification of performance of installation, remove surplus materials, excess materials, rubbish, tools and equipment.
- .3 Remove temporary dams after initial set of fire stopping and smoke seal materials.

3.7 SCHEDULE

- .1 Fire stop and smoke seal at:
 - .1 Penetrations through fire-resistance rated masonry, concrete, and gypsum board partitions and walls.
- .2 Edge of floor slabs at curtain wall and precast concrete panels.
- .3 Top of fire-resistance rated masonry and gypsum board partitions.
- .4 Intersection of fire-resistance rated masonry and gypsum board partitions.
- .5 Control and sway joints in fire-resistance rated masonry and gypsum board partitions and walls.
- .6 Penetrations through fire-resistance rated floor slabs, ceilings and roofs.
- .7 Openings and sleeves installed for future use through fire separations.
- .8 Around mechanical and electrical assemblies penetrating fire separations.
- .9 Rigid ducts: greater than 129 cm²: fire stopping to consist of bead of fire stopping material between retaining angle and fire separation and between retaining angle and duct, on each side of fire separation.

END OF SECTION

PART 1 GENERAL**1.1 RELATED SECTIONS**

- .1 Section 01 33 00 - Submittal Procedures.
- .2 Section 01 45 00 - Quality Control.
- .3 Section 01 61 00 - Common Product Requirements.
- .4 Section 01 74 21 - Construction/Demolition Waste Management And Disposal.

1.2 REFERENCES

- .1 American Society for Testing and Materials International, (ASTM)
 - .1 ASTM C 919-02, Standard Practice for Use of Sealants in Acoustical Applications.
- .2 Canadian General Standards Board (CGSB)
 - .1 CGSB 19-GP-5M-1984, Sealing Compound, One Component, Acrylic Base, Solvent Curing (Issue of 1976 reaffirmed, incorporating Amendment No. 1).
 - .2 CAN/CGSB-19.13-M87, Sealing Compound, One-component, Elastomeric, Chemical Curing.
 - .3 CGSB 19-GP-14M-1984, Sealing Compound, One Component, Butyl-Polyisobutylene Polymer Base, Solvent Curing (Reaffirmation of April 1976).
 - .4 CAN/CGSB-19.17-M90, One-Component Acrylic Emulsion Base Sealing Compound.
 - .5 CAN/CGSB-19.24-M90, Multi-component, Chemical Curing Sealing Compound.
- .3 Department of Justice Canada (Jus)
 - .1 Canadian Environmental Protection Act, 1999 (CEPA).
- .4 General Services Administration (GSA) - Federal Specifications (FS)
 - .1 FS-SS-S-200-E(2)1993, Sealants, Joint, Two-Component, Jet-Blast-Resistant, Cold Applied, for Portland Cement Concrete Pavement.
- .5 Health Canada/Workplace Hazardous Materials Information System (WHMIS)
 - .1 Material Safety Data Sheets (MSDS).
- .6 Transport Canada (TC)
 - .1 Transportation of Dangerous Goods Act, 1992 (TDGA).

1.3 SUBMITTALS

- .1 Submit product data in accordance with Section 01 33 00 - Submittal Procedures.
- .2 Manufacturer's product to describe.
 - .1 Caulking compound.
 - .2 Primers.
 - .3 Sealing compound, each type, including compatibility when different sealants are in contact with each other.
- .3 Submit samples in accordance with Section 01 33 00 - Submittal Procedures.
- .4 Submit duplicate samples of each type of material and colour.
- .5 Cured samples of exposed sealants for each color where required to match adjacent material.
- .6 Submit manufacturer's instructions in accordance with Section 01 33 00 - Submittal Procedures.
 - .1 Instructions to include installation instructions for each product used.

1.4 QUALITY ASSURANCE/MOCK-UP

- .1 Construct mock-up to show location, size, shape and depth of joint(s) complete with back-up material, primer, caulking and sealant.
- .2 Mock-up will be used:
 - .1 To judge workmanship, substrate preparation, operation of equipment and material application.
- .3 Locate where directed by Architect.
- .4 Allow 24 hours for inspection of mock-up by Architect before proceeding with sealant work.
- .5 When accepted, mock-up will demonstrate minimum standard of quality required for this Work. [Approved mock-up may [not] remain as part of finished Work] [Remove mock-up and dispose of materials when no longer required and when directed by Architect].

1.5 DELIVERY, STORAGE, AND HANDLING

- .1 Deliver, handle, store and protect materials in accordance with Section 01 61 00 - Common Product Requirements.
- .2 Deliver and store materials in original wrappings and containers with manufacturer's seals and labels, intact. Protect from freezing, moisture, water and contact with ground or floor.

1.6 WASTE MANAGEMENT AND DISPOSAL

- .1 Separate waste materials for reuse and recycling in accordance with Section 01 74 21 - Construction/Demolition Waste Management And Disposal.
- .2 Remove from site and dispose of packaging materials at appropriate recycling facilities.
- .3 Collect and separate for disposal paper, plastic, polystyrene, and corrugated cardboard packaging material [in appropriate on-site bins] for recycling in accordance with Waste Management Plan.
- .4 Place materials defined as hazardous or toxic in designated containers.
- .5 Handle and dispose of hazardous materials in accordance with the CEPA, TDGA, Regional and Municipal regulations.
- .6 Unused sealant material must not be disposed of into sewer system, into streams, lakes, onto ground or in other location where it will pose health or environmental hazard.
- .7 Divert unused joint sealing material from landfill to official hazardous material collections site approved by Architect.
- .8 Empty plastic joint sealer containers are not recyclable. Do not dispose of empty containers with plastic materials destined for recycling.
- .9 Fold up metal banding, flatten, and place in designated area for recycling.

1.7 PROJECT CONDITIONS

- .1 Environmental Limitations:
 - .1 Do not proceed with installation of joint sealants under following conditions:
 - .1 When ambient and substrate temperature conditions are outside limits permitted by joint sealant manufacturer or are below 4.4 degrees C.
 - .2 When joint substrates are wet.
- .2 Joint-Width Conditions:
 - .1 Do not proceed with installation of joint sealants where joint widths are less than those allowed by joint sealant manufacturer for applications indicated.

- .3 Joint-Substrate Conditions:
 - .1 Do not proceed with installation of joint sealants until contaminants capable of interfering with adhesion are removed from joint substrates.

1.8 ENVIRONMENTAL REQUIREMENTS

- .1 Comply with requirements of Workplace Hazardous Materials Information System (WHMIS) regarding use, handling, storage, and disposal of hazardous materials; and regarding labelling and provision of Material Safety Data Sheets (MSDS) acceptable to Labour Canada.
- .2 Conform to manufacturer's recommended temperatures, relative humidity, and substrate moisture content for application and curing of sealants including special conditions governing use.

PART 2 PRODUCTS

2.1 SEALANT MATERIALS

- .1 Do not use caulking that emits strong odours, contains toxic chemicals or is not certified as mould resistant in air handling units.
- .2 When low toxicity caulks are not possible, confine usage to areas which off gas to exterior, are contained behind air barriers, or are applied several months before occupancy to maximize off gas time.
- .3 Where sealants are qualified with primers use only these primers.

2.2 SEALANT MATERIAL DESIGNATIONS

- .1 Acoustical Sealant to CAN/CGSB 19.21: Type D, One-Part, Non-Skinning, Sound Dampering Sealant.
 - .1 Resistance to Sag to CGSB 7.1: Passes.
 - .2 Extrusion Rate to CGSB 3.1: Passes
 - .3 Viscosity Brookfield: 1,000,000 cps
 - .4 Shear Modulus using GR component: 45,000 N/m².
 - .5 Density: 1720 Kg/m³.
 - .6 Colour: Dark grey.

2.3 SEALANT SELECTION

- .1 Sealant Type D:
 - .1 Acoustical sealing of drywall partitions, corridors and party walls.
 - .2 Lap joint and perimeter sealant for polyethylene vapour barriers over fibre glass batt or other insulations.

2.4 JOINT CLEANER

- .1 Non-corrosive and non-staining type, compatible with joint forming materials and sealant recommended by sealant manufacturer.
- .2 Primer: as recommended by manufacturer.

PART 3 EXECUTION

3.1 PROTECTION

- .1 Protect installed Work of other trades from staining or contamination.

3.2 SURFACE PREPARATION

- .1 Examine joint sizes and conditions to establish correct depth to width relationship for installation of backup materials and sealants.
- .2 Clean bonding joint surfaces of harmful matter substances including dust, rust, oil grease, and other matter which may impair Work.
- .3 Do not apply sealants to joint surfaces treated with sealer, curing compound, water repellent, or other coatings unless tests have been performed to ensure compatibility of materials. Remove coatings as required.
- .4 Ensure joint surfaces are dry and frost free.
- .5 Prepare surfaces in accordance with manufacturer's directions.

3.3 PRIMING

- .1 Where necessary to prevent staining, mask adjacent surfaces prior to priming and caulking.
- .2 Prime sides of joints in accordance with sealant manufacturer's instructions immediately prior to caulking.

3.4 BACKUP MATERIAL

- .1 Apply bond breaker tape where required to manufacturer's instructions.
- .2 Install joint filler to achieve correct joint depth and shape, with approximately 30% compression.

3.5 MIXING

- .1 Mix materials in strict accordance with sealant manufacturer's instructions.

3.6 APPLICATION

- .1 Sealant.
 - .1 Apply sealant in accordance with manufacturer's written instructions.
 - .2 Mask edges of joint where irregular surface or sensitive joint border exists to provide neat joint.
 - .3 Apply sealant in continuous beads.
 - .4 Apply sealant using gun with proper size nozzle.
 - .5 Use sufficient pressure to fill voids and joints solid.
 - .6 Form surface of sealant with full bead, smooth, free from ridges, wrinkles, sags, air pockets, embedded impurities.
 - .7 Tool exposed surfaces before skinning begins to give slightly concave shape.
 - .8 Remove excess compound promptly as work progresses and upon completion.
- .2 Curing.
 - .1 Cure sealants in accordance with sealant manufacturer's instructions.
 - .2 Do not cover up sealants until proper curing has taken place.
- .3 Cleanup.
 - .1 Clean adjacent surfaces immediately and leave Work neat and clean.
 - .2 Remove excess and droppings, using recommended cleaners as work progresses.
 - .3 Remove masking tape after initial set of sealant.

END OF SECTION

PART 1 GENERAL**1.1 REFERENCES**

- .1 American Society for Testing and Materials International (ASTM)
 - .1 ASTM A 653 / A 653M-10, Standard Specification for Steel Sheet, Zinc-Coated (Galvanized) or Zinc-Iron Alloy-Coated (Galvannealed) by the Hot-Dip Process.
- .2 Canadian General Standards Board (CGSB)
 - .1 CAN/CGSB-1.181-99, Ready-Mixed Organic Zinc-Rich Coating.
 - .2 CGSB 41-GP-19Ma-84, Rigid Vinyl Extrusions for Windows and Doors.
- .3 Canadian Standards Association (CSA International)
 - .1 CSA-G40.20-04/G40.21-04 (R2009), General Requirements for Rolled or Welded Structural Quality Steel/Structural Quality Steel.
 - .2 CSA W59-03(R2008), Welded Steel Construction (Metal Arc Welding).
- .4 Canadian Steel Door Manufacturers' Association (CSDMA)
 - .1 CSDMA, Recommended Specifications for Commercial Steel Doors and Frames, 2000.
 - .2 CSDMA, Selection and Usage Guide for Commercial Steel Doors, 1990.
- .5 National Fire Protection Association (NFPA)
 - .1 NFPA 80-10, Standard for Fire Doors and Fire Windows.
 - .2 NFPA 252-08, Standard Methods of Fire Tests of Door Assemblies.
- .6 Underwriters' Laboratories of Canada (ULC)
 - .1 CAN/ULC-S704-11, Standard for Thermal Insulation, Polyurethane and Polyisocyanurate Boards, Faced.
 - .2 CAN4-S104-M80 (R1985), Standard Method for Fire Tests of Door Assemblies.
 - .3 CAN4-S105-M85(R1992), Standard Specification for Fire Door Frames Meeting the Performance Required by CAN4-S104.

1.2 SYSTEM DESCRIPTION

- .1 Design Requirements:
 - .1 Steel fire rated frames: labelled and listed by an organization accredited by Standards Council of Canada in conformance with CAN4-S104 or NFPA 252 for ratings specified or indicated.
 - .2 Provide fire labelled frames for openings requiring fire protection ratings. Test products in conformance with CAN4-S104, or NFPA 252 and listed by nationally recognized agency having factory inspection services.

1.3 SUBMITTALS

- .1 Provide submittals in accordance with Section 01 33 00 - Submittal Procedures.
- .2 Provide product data: in accordance with Section 01 33 00 - Submittal Procedures.
- .3 Provide shop drawings: in accordance with Section 01 33 00 - Submittal Procedures.
 - .1 Indicate each type of door, material, steel core thicknesses, mortises, reinforcements, location of exposed fasteners, openings, glazed and louvred, arrangement of hardware, fire rating and finishes.
 - .2 Indicate each type frame material, core thickness, reinforcements, glazing stops, location of anchors and exposed fastenings and reinforcing, fire rating and finishes.
 - .3 Include schedule identifying each unit, with door marks and numbers relating to numbering on drawings and door schedule.
 - .4 Submit test and engineering data, and installation instructions.
- .4 Provide samples in accordance with Section 01 33 00 - Submittal Procedures.

1.4 DELIVERY, STORAGE AND HANDLING

- .1 Deliver, store and handle materials in accordance with Section 01 61 00 - Common Product Requirements.
- .2 Waste Management and Disposal:
 - .1 Separate waste materials for reuse and recycling in accordance with Section 01 74 21 - Construction/Demolition Waste Management and Disposal.

PART 2 PRODUCTS**2.1 MATERIALS**

- .1 Hot dipped galvanized steel sheet: to ASTM A 653M, ZF75, minimum base steel thickness in accordance with CSDMA Table 1 - Thickness for Component Parts.
- .2 Reinforcement channel: to CSA G40.20/G40.21, Type 44W, coating designation to ASTM A 653M, ZF75.

2.2 ADHESIVES

- .1 Honeycomb cores and steel components: heat resistant, spray grade, resin reinforced neoprene/rubber (polychloroprene) based, low viscosity, contact cement.
 - .1 Adhesive: maximum VOC content 50 g/L.
- .2 Polystyrene and polyurethane cores: heat resistant, epoxy resin based, low viscosity, contact cement.

2.3 PRIMER

- .1 Touch-up prime CAN/CGSB-1.181.

2.4 PAINT

- .1 Field paint steel frames in accordance with Section 09 91 23 - Interior Painting.

2.5 ACCESSORIES

- .1 Door silencers: single stud rubber/neoprene type.
- .2 Exterior and interior top and bottom caps: steel.
- .3 Fabricate glazing stops as formed channel, minimum 16 mm height, accurately fitted, butted at corners and fastened to frame sections with counter-sunk oval head sheet metal screws.
- .4 Door bottom seal: In accordance with Section 08 71 00 - Door Hardware.
- .5 Metallic paste filler: to manufacturer's standard.
- .6 Fire labels: metal riveted.
- .7 Make provisions for glazing as indicated and provide necessary glazing stops.
 - .1 Provide removable stainless steel glazing beads for use with glazing tapes and compounds and secured with countersunk stainless steel screws and dry glazing of snap-on type.
 - .2 Design exterior glazing stops to be tamperproof.

2.6 FRAMES FABRICATION GENERAL

- .1 Metal Frame Types:
 - .1 Interior frames (**MF-01**): 1.6 mm knocked-down type construction.
- .2 Fabricate frames in accordance with CSDMA specifications.
- .3 Fabricate frames to profiles and maximum face sizes as indicated.

- .4 Blank, reinforce, drill and tap frames for mortised, templated hardware, and electronic hardware using templates provided by finish hardware supplier. Reinforce frames for surface mounted hardware.
- .5 Protect mortised cutouts with steel guard boxes.
- .6 Prepare frame for door silencers, 1 for single door, 2 at head for double door.
- .7 Manufacturer's nameplates on frames and screens are not permitted.
- .8 Conceal fastenings except where exposed fastenings are indicated.
- .9 Provide factory-applied touch up primer at areas where zinc coating has been removed during fabrication.

2.7 **FRAME ANCHORAGE**

- .1 Provide appropriate anchorage to floor and wall construction.
- .2 Locate each wall anchor immediately above or below each hinge reinforcement on hinge jamb and directly opposite on strike jamb.
- .3 Provide 2 anchors for rebate opening heights up to 1520 mm and 1 additional anchor for each additional 760 mm of height or fraction thereof.
- .4 Locate anchors for frames in existing openings not more than 150 mm from top and bottom of each jambs and intermediate at 660 mm on centre maximum.

2.8 **FRAMES: WELDED TYPE**

- .1 Welding in accordance with CSA W59.
- .2 Accurately mitre or mechanically joint frame product and securely weld on inside of profile.
- .3 Cope accurately and securely weld butt joints of mullions, transom bars, centre rails and sills.
- .4 Grind welded joints and corners to a flat plane, fill with metallic paste and sand to uniform smooth finish.
- .5 Securely attach floor anchors to inside of each jamb profile.
- .6 Weld in 2 temporary jamb spreaders per frame to maintain proper alignment during shipment.
- .7 Securely attach lead to inside of frame profile from return to jamb soffit (inclusive) on door side of frame only.

2.9 **FRAMES: KNOCKED-DOWN TYPE**

- .1 Ship knocked-down type frames unassembled.
- .2 Provide frames with mechanical joints which inter-lock securely and provide functionally satisfactory performance when assembled and installed in accordance with CSDMA Recommended Installation Guide for Steel Doors and Frames.
- .3 Securely attach floor anchors to inside of each jamb profile.

2.10 **HOLLOW STEEL CONSTRUCTION (MD-01)**

- .1 Form face sheets for interior doors from 1.6 mm sheet steel.
- .2 Reinforce doors with vertical stiffeners, securely welded to face sheets at 150 mm on centre maximum.
- .3 Fill voids between stiffeners of exterior doors with honeycomb core.
- .4 Fill voids between stiffeners of interior doors with honeycomb core.

2.11 **HONEYCOMB CORE CONSTRUCTION**

- .1 Form face sheets from 1.6 mm sheet steel with honeycomb or polyurethane core laminated under pressure to face sheets.

PART 3 EXECUTION

3.1 MANUFACTURER'S INSTRUCTIONS

- .1 Compliance: comply with manufacturer's written recommendations or specifications, including product technical bulletins, handling, storage and installation instructions, and datasheets.

3.2 INSTALLATION GENERAL

- .1 Install labelled steel fire rated doors and frames to NFPA 80 except where specified otherwise.
- .2 Install doors and frames to CSDMA Installation Guide.

3.3 FRAME INSTALLATION

- .1 Set frames plumb, square, level and at correct elevation.
- .2 Secure anchorages and connections to adjacent construction.
- .3 Brace frames rigidly in position while building-in. Install temporary horizontal wood spreader at third points of door opening to maintain frame width. Provide vertical support at centre of head for openings over 1200 mm wide. Remove temporary spreaders after frames are built-in.
- .4 Make allowances for deflection of structure to ensure structural loads are not transmitted to frames.
- .5 Caulk perimeter of frames between frame and adjacent material.

3.4 DOOR INSTALLATION

- .1 Install doors and hardware in accordance with hardware templates and manufacturer's instructions and coordinate with Section 08 71 00 - Door Hardware.
- .2 Provide even margins between doors and jambs and doors, and finished floor and thresholds as follows.
 - .1 Hinge side: 1.0 mm.
 - .2 Latchside and head: 1.5 mm.
 - .3 Finished floor, and thresholds: 13 mm.
 - .4 Adjust operable parts for correct function.
 - .5 Install louvres.

3.5 FINISH REPAIRS

- .1 Touch up with primer finishes damaged during installation.
- .2 Fill exposed frame anchors and surfaces with imperfections with metallic paste filler and sand to a uniform smooth finish.

3.6 GLAZING

- .1 Install glazing for doors and frames in accordance with Section 08 80 50 - Glazing.

END OF SECTION

PART 1 GENERAL**1.1 RELATED SECTIONS**

- .1 Section 01 31 19 - Project Meetings.
- .2 Section 01 33 00 - Submittal Procedures.
- .3 Section 01 61 00 - Common Product Requirements.
- .4 Section 01 74 11 - Cleaning.
- .5 Section 01 74 21 - Construction/Demolition Waste Management and Disposal.
- .6 Section 01 78 00 - Closeout Submittals.
- .7 Section 08 71 10 - Door Hardware.

1.2 REFERENCES

- .1 Aluminum Association (AA)
 - .1 AA DAF 45-03(R2009), Designation System for Aluminum Finishes.
- .2 American Architectural Manufacturers Association (AAMA)
 - .1 AAMA 609/610-09, Cleaning and Maintenance Guide for Architecturally Finished Aluminum.
- .3 American National Standards Institute (ANSI) / National Fire Protection Agency (NFPA)
 - .1 ANSI/NFPA 80-2010, Standard for Fire Doors and Other Opening Protectives.
- .4 ASTM International
 - .1 ASTM A 167-99(2009), Specification for Stainless and Heat-Resisting Chromium-Nickel Steel Plate, Sheet, and Strip.
 - .2 ASTM A 276-08a, Standard Specification for Stainless Steel Bars and Shapes.
 - .3 ASTM A 480/A 480M-10, Standard Specification for General Requirements for Flat Rolled Stainless Steel and Heat-Resisting Steel Plate, Sheet and Strip.
 - .4 ASTM A 653/A 653M-09a, Standard Specification for Steel Sheet, Zinc-Coated (Galvanized) or Zinc-Iron Alloy-Coated (Galvanealed) by the Hot-Dip Process.
- .5 Architectural Woodwork Manufacturers' Association of Canada (AWMAC)
 - .1 Architectural Woodwork Standards 2009.
- .6 Canadian General Standards Board (CGSB)
 - .1 CAN/CGSB-1.105-M91, Quick-Drying Primer.
 - .2 CAN/CGSB-12.1-M90, Tempered or Laminated Safety Glass.
 - .3 CAN/CGSB-12.12-M90, Plastic Safety Glazing.
- .7 CSA International
 - .1 CSA O141-05, Softwood Lumber.
 - .2 CSA Z809-08, Sustainable Forest Management.
- .8 Environmental Choice Program (ECP)
 - .1 CCD-047-98(R2005), Architectural Surface Coatings.
 - .2 CCD-048-98(R2006), Surface Coatings - Recycled Water-borne.
- .9 Electrical and Electronic Manufacturers' Association of Canada (EEMAC)
- .10 Green Seal Environmental Standards (GS)
 - .1 GS-11-2008, 2nd Edition, Paints and Coatings.
 - .2 GS-36-00, Commercial Adhesives.

- .11 South Coast Air Quality Management District (SCAQMD), California State, Regulation XI. Source Specific Standards
 - .1 SCAQMD Rule 1113-A2007, Architectural Coatings.
 - .2 SCAQMD Rule 1168-A2005, Adhesives and Sealants Applications.
- .12 Underwriters Laboratories of Canada (ULC)
 - .1 CAN4-S104-80(R1985), Standard Method for Fire Tests of Door Assemblies.
 - .2 CAN/ULC-S105-09, Standard Specification for Fire Door Frames.

1.3 ADMINISTRATIVE REQUIREMENTS

- .1 Pre-Installation Meetings:
 - .1 Convene pre-installation meeting 1 week prior to beginning on-site installation, with Contractor's Representative and Architect to:
 - .1 Verify project requirements.
 - .2 Review installation and substrate conditions.
 - .3 Co-ordination with other construction sub-trades.
 - .4 Review manufacturer's written installation instructions and warranty requirements.
 - .2 Arrange for site visit with Architect prior to start of Work to examine existing site conditions adjacent to demolition Work.
 - .3 Ensure key personnel, site supervisor, project manager and subcontractor representatives attend.
 - .4 Architect will submit written notification of change to meeting schedule established upon contract award 24 hours prior to scheduled meeting.

1.4 ACTION AND INFORMATIONAL SUBMITTALS

- .1 Submit in accordance with Section 01 33 00 - Submittal Procedures.
- .2 Product Data:
 - .1 Submit manufacturer's instructions, printed product literature and data sheets for door components and grilles and include product characteristics, performance criteria, physical size, finish and limitations.
- .3 Shop Drawings:
 - .1 Submit drawings stamped and signed by professional engineer registered or licensed in Province of Ontario, Canada.
 - .2 Indicate each type of door and grille, arrangement of hardware, required clearances, and electrical characteristics including voltage, size of motors, auxiliary controls and wiring diagrams.
 - .3 Indicate assembly details and dimensions of fabrication, required clearances [and electrical connections].
- .4 Test Reports: certified test reports showing compliance with specified performance characteristics and physical properties.
- .5 Manufacturers Reports:
 - .1 Manufacturer's Field Reports: submit manufacturer's written reports within 3 days of review, verifying compliance of Work, as described in PART 3 - FIELD QUALITY CONTROL.

1.5 CLOSEOUT SUBMITTALS

- .1 Submit in accordance with Section 01 78 00 - Closeout Submittals.

- .2 Operation and Maintenance Data: submit operation and maintenance data for overhead coiling doors and grilles, and hardware for incorporation into manual.

1.6 QUALITY ASSURANCE

- .1 Regulatory Requirements:
 - .1 Overhead coiling doors: labeled and listed by an organization accredited by Standards Council of Canada to CAN4-S104 and CAN/ULC-S105 for ratings specified or indicated.
 - .2 Fabricate and install overhead coiling doors to ANSI/NFPA 80 to suit fire protection rating required.
- .2 Certifications: product certificates signed by manufacturer certifying materials comply with specified performance characteristics and criteria and physical requirements.

1.7 DELIVERY, STORAGE AND HANDLING

- .1 Deliver, store and handle materials in accordance with Section 01 61 00 - Common Product Requirements and with manufacturer's written instructions.
- .2 Delivery and Acceptance Requirements: deliver materials to site in original factory packaging, labeled with manufacturer's name and address.
- .3 Storage and Handling Requirements:
 - .1 Store materials off ground, indoors, in dry location and in accordance with manufacturer's recommendations in clean, dry, well-ventilated area.
 - .2 Store and protect overhead coiling doors and grilles from nicks, scratches, and blemishes.
 - .3 Replace defective or damaged materials with new.

PART 2 PRODUCTS

2.1 DESIGN CRITERIA

- .1 Design rolling door curtain and assembly to withstand wind load of 960 Pa within door opening area.

2.2 MATERIALS

- .1 Rolling doors.
- .2 Galvanized steel sheet: lock-forming quality to ASTM A-653.
- .3 Galvanized steel sheet: commercial quality with Coating Designation Z180 or Z275.
- .4 Doors:
 - .1 Door face sheets to interior doors 16 minimum mm base thickness.
- .5 Primer: to CAN/CGSB-1.105 and CGSB 1.213.
 - .1 VOC limit 250 g/L maximum to GS-11 & SCAQMD Rule 1113.
- .6 Adhesives and Sealants: VOC limit 250 g/L maximum to SCAQMD Rule 1168 & GS-36.

2.3 DOOR FABRICATION

- .1 Fabricate rolling metal fire doors to ANSI/NFPA 80 with 1-1/2 hour fire rating bearing label.
- .2 Coiling door curtain interlocking slat sections:
 - .1 Roll formed steel, 16 mm base metal thickness x 58 mm wide, prime painted.
 - .2 Profile: flat.

- .3 Ensure bottom bar of double equal weight steel angles is equipped with tubular neoprene weatherstrip.
- .4 Form guides of metal angles of sections of 4.8 mm minimum thickness for face of wall installation. Equip guides with weatherstrip.
- .5 Construct counterbalance assembly of heat treated torsion spring with 25% overload factor.
 - .1 Enclose spring in steel pipe to support door curtain and counterbalance mechanism with maximum deflection of 1/360th of opening width.
 - .2 Include ball bearings at rotating points and spring tension adjusting wheel, accessible for setting.
- .6 Support counterbalance assembly on 5 mm minimum thickness steel plate brackets, forming end enclosures.
- .7 Enclose counterbalance assembly with galvanized steel sheet formed hood.
- .8 Attach to hood sheet metal flame and smoke baffle to drop in place automatically when activated by temperature rise and melting of fusible link.
- .9 Equip door for locking from both sides with lockset.

2.4 OPERATION

- .1 Equip door for operation by:
 - .1 Electric motor operator.
- .2 Install fusible link activated automatic closing device to close door at controlled slow even speed in case of fire.
- .3 Arrange automatic closing device to permit manual lifting of curtain for emergency exit after automatic closing with curtain returning to closed position when released.

2.5 ELECTRICAL OPERATOR

- .1 Electrical motors, controller units, remote pushbutton stations, relays and other electrical components: to CSA and ULC approval.
- .2 Power supply: as recommended by the door manufacturer for size and type of door.
- .3 Motor: high starting torque, instant reversing, capacity to operate grille at 200 mm per second, removable without affecting emergency chain device or setting of limit switches. Equip motor with overload protection, centrifugal clutch and electric brake.
- .4 Motor size matching gear reducer with gears running in oil bath.
- .5 Controller units with integral motor reversing starter, 3 heater elements for overload protection, including pushbuttons and control relays as applicable.
- .6 Operation:
 - .1 Remote push button stations: surface mounted, in 2 locations, with OPEN-STOP-CLOSE push buttons.
 - .2 Cable control: pendant hung control to open and electric eyes to close.
- .7 Design brake to stop and hold doors in any position.
- .8 Include hand crank interlocked auxiliary operator to disconnect motor mechanically and electrically when engaged and allow manual operation of door.
- .9 Safety switch: electro mechanical or electro pneumatic device full length of bottom rail of bottom section of door, to reverse door to open position when coming in contact with object on closing cycle.

- .10 Door speed: 152 mm/s.
- .11 Mounting brackets: galvanized steel, size and thickness to suit conditions.
- .12 Control circuit: 24 VAC.

PART 3 EXECUTION

3.1 EXAMINATION

- .1 Verification of Conditions: verify conditions of substrates previously installed under other Sections or Contracts are acceptable for overhead coiling doors and grilles installation in accordance with manufacturer's written instructions.
 - .1 Visually inspect substrate in presence of Architect.
 - .2 Inform Architect of unacceptable conditions immediately upon discovery.
 - .3 Proceed with installation only after unacceptable conditions have been remedied and after receipt of written approval to proceed from Architect.

3.2 INSTALLATION

- .1 Manufacturer's Instructions: comply with manufacturer's written recommendations, including product technical bulletins, product catalogue installation instructions, product carton installation instructions, and data sheets.
- .2 Install doors in accordance with manufacturer's printed instructions.
- .3 Install electrical motors, controller units, pushbutton stations, relays and other electrical equipment required for door operation.
- .4 Install electric wiring from power supply located near door.
- .5 Install master keyed cylinder specified in Section 08 71 00 - Door Hardware.
- .6 Adjust door operating components to ensure smooth opening and closing of doors and grilles.

3.3 FIELD QUALITY CONTROL

- .1 Test labeled coiling doors for proper operation by activating fusible link. Test coiling door in presence of Architect.
- .2 Have manufacturer of products supplied under this Section review Work involved in handling, installation, protection and cleaning of its product[s], and submit written reports in acceptable format to verify compliance of Work with Contract.
- .3 Manufacturer's Field Services:
 - .1 Obtain written reports from manufacturer verifying compliance of Work, in handling, installing, applying, protecting and cleaning of product within 3 days.
- .4 Submit manufacturer's field services consisting of product use recommendations and periodic site visits for inspection of product installation in accordance with manufacturer's instructions.
- .5 Ensure manufacturer's representative is present before and during critical periods of installation and testing.
- .6 Schedule site visits to review Work at stages listed:
 - .1 Upon completion of Work, after cleaning is carried out.

3.4 CLEANING

- .1 Perform cleaning of aluminum components in accordance with: AAMA 609.
- .2 Progress Cleaning: clean in accordance with Section 01 74 11 - Cleaning.
 - .1 Leave Work area clean at end of each day.
- .3 Final Cleaning: upon completion remove surplus materials, rubbish, tools and equipment in accordance with Section 01 74 11 - Cleaning.
 - .1 Clean aluminum and stainless steel with damp rag and approved non-abrasive cleaner in accordance with manufacturer's instructions.
 - .2 Remove traces of primer, caulking; clean doors and frames.
 - .3 Clean glass and glazing materials with approved non-abrasive cleaner.

3.5 PROTECTION

- .1 Protect installed products and components from damage during construction.
- .2 Repair damage to adjacent materials caused by overhead coiling door and grille installation.

END OF SECTION

PART 1 GENERAL**1.1 REFERENCES**

- .1 American National Standards Institute (ANSI) / Builders Hardware Manufacturers Association (BHMA)
 - .1 ANSI/BHMA A156.1-2000, American National Standard for Butts and Hinges.
 - .2 ANSI/BHMA A156.2-2003, Bored and Preassembled Locks and Latches.
 - .3 ANSI/BHMA A156.5-2001, Auxiliary Locks and Associated Products.
 - .4 ANSI/BHMA A156.8-2005, Door Controls - Overhead Stops and Holders.
 - .5 ANSI/BHMA A156.13-2002, Mortise Locks and Latches Series 1000.
 - .6 ANSI/BHMA A156.16-2002, Auxiliary Hardware.
 - .7 ANSI/BHMA A156.18-2006, Materials and Finishes.
- .2 Canadian Steel Door and Frame Manufacturers' Association (CSDMA)
 - .1 CSDMA Recommended Dimensional Standards for Commercial Steel Doors and Frames - 2009.

1.2 ACTION AND INFORMATIONAL SUBMITTALS

- .1 Submit in accordance with Section 01 33 00 - Submittal Procedures.
- .2 Product Data:
 - .1 Submit manufacturer's instructions, printed product literature and data sheets for door hardware and include product characteristics, performance criteria, physical size, finish and limitations.
- .3 Samples:
 - .1 Submit for review and acceptance of each unit.
 - .2 Samples will be returned for inclusion into work.
 - .3 Identify each sample by label indicating applicable specification paragraph number, brand name and number, finish and hardware package number.
 - .4 After approval samples will be returned for incorporation in Work.
- .4 Hardware List:
 - .1 Submit contract hardware list.
 - .2 Indicate specified hardware, including make, model, material, function, size, finish and other pertinent information.
- .5 Test Reports: certified test reports showing compliance with specified performance characteristics and physical properties.
- .6 Manufacturer's Instructions: submit manufacturer's installation instructions.

1.3 CLOSEOUT SUBMITTALS

- .1 Submit in accordance with Section 01 78 00 - Closeout Submittals.
- .2 Operation and Maintenance Data: submit operation and maintenance data for door hardware for incorporation into manual.

1.4 MAINTENANCE MATERIALS SUBMITTALS

- .1 Extra Stock Materials:
 - .1 Supply maintenance materials in accordance with Section 01 78 00 - Closeout Submittals.
 - .2 Tools:
 - .1 Supply 2 sets of wrenches for each type of door closers, locksets and fire exit hardware.

1.5 QUALITY ASSURANCE

- .1 Regulatory Requirements:
 - .1 Hardware for doors in fire separations and exit doors certified by a Canadian Certification Organization accredited by Standards Council of Canada.
- .2 Certificates: product certificates signed by manufacturer certifying materials comply with specified performance characteristics and criteria and physical requirements.

1.6 DELIVERY, STORAGE AND HANDLING

- .1 Deliver, store and handle materials in accordance with Section 01 61 00 - Common Product Requirements and with manufacturer's written instructions.
- .2 Delivery and Acceptance Requirements: deliver materials to site in original factory packaging, labelled with manufacturer's name and address.
- .3 Package items of hardware including fastenings, separately or in like groups of hardware, label each package as to item definition and location.
- .4 Storage and Handling Requirements:
 - .1 Store materials indoors in dry location and in accordance with manufacturer's recommendations in clean, dry, well-ventilated area.
 - .2 Store and protect door hardware from nicks, scratches, and blemishes.
 - .3 Protect prefinished surfaces with wrapping.
 - .4 Replace defective or damaged materials with new.
- .5 Packaging Waste Management: remove for reuse by manufacturer of pallets, crates, padding, and packaging materials.

PART 2 PRODUCTS

2.1 HARDWARE ITEMS

- .1 Use one manufacturer's products only for similar items.

2.2 DOOR HARDWARE

- .1 Locks and latches:
 - .1 Mortise locks and latches: to ANSI/BHMA A156.13, series 1000 mortise lock, grade 1, cylinders and keys supplied by owner, cylinders installed by contractor.
 - .1 Acceptable Product or Equivalent: Corbin Russwin, ML2000 Series.
- .2 Butts and hinges:
 - .1 Butts and hinges: to ANSI/BHMA A5112, standard weight, full mortise, five knuckle, non-removable pin, size and finish as stated in Hardware Schedule.
 - .1 Acceptable Product or Equivalent: Hager BB1279.
- .3 Door Closers and Accessories:
 - .1 Door closers: to ANSI/BHMA A156.4, cast-iron cylinder, heavy duty forged arm, adjustable speed, function and finish as stated in Hardware Schedule.
 - .1 Acceptable Product or Equivalent: Ingersoll-Rand, LCN 4041 Series.
- .4 Floor stops: 44.5 mm diameter, 28.6 mm high domed floor mounted door stop, grey rubber bumper.
- .5 Auxiliary locks and associated products: to ANSI/BHMA A156.31, listed in Hardware Schedule.
 - .1 Cylinders: cylinders and keys supplied by owner, cylinders installed by owner.
- .6 Architectural door trim: to ANSI/BHMA A156.6, size and finish as stated in Hardware Schedule.
 - .1 Kick plate: 1.27 mm thick, 305 mm high, brushed stainless steel, countersunk screw mounting.
- .7 Automatic Door Bottom:

- .1 Door seal of extruded aluminum frame and closed cell neoprene seal, surface mounted, closed ends, adjustable automatic retract mechanism when door is open, clear anodized finish.
 - .1 Acceptable Products or Equivalent: K.N. Crowder Manufacturing, CT-50.
- .8 Threshold:
 - .1 Extruded Aluminum.
 - .1 Acceptable Products or Equivalent: K.N. Crowder Manufacturing, CT-9SS
- .9 Door seal/silencer:
 - .1 Door seal of Santoprene self-adhesive gasket, black finish.
 - .1 Acceptable Products or Equivalent: K.N. Crowder Manufacturing, W-66.

2.3 FASTENINGS

- .1 Use only fasteners provided by manufacturer. Failure to comply may void warranties and applicable licensed labels.
- .2 Supply screws, bolts, expansion shields and other fastening devices required for satisfactory installation and operation of hardware.
- .3 Exposed fastening devices to match finish of hardware.
- .4 Where pull is scheduled on one side of door and push plate on other side, supply fastening devices, and install so pull can be secured through door from reverse side. Install push plate to cover fasteners.
- .5 Use fasteners compatible with material through which they pass.

2.4 KEYING

- .1 Doors, padlocks and cabinet locks to be as noted in Hardware Schedule.
- .2 Supply keys in duplicate for every lock in this Contract.
- .3 Supply 3 master keys for each master key or grand master key group.
- .4 Stamp keying code numbers on keys and cylinders.
- .5 Supply construction cores.
- .6 Hand over permanent cores and keys to Departmental Representative.

PART 3 EXECUTION

3.1 INSTALLATION

- .1 Manufacturer's Instructions: comply with manufacturer's written recommendations, including product technical bulletins, product catalogue installation instructions, product carton installation instructions, and data sheets.
- .2 Supply metal door and frame manufacturers with complete instructions and templates for preparation of their work to receive hardware.
- .3 Supply manufacturers' instructions for proper installation of each hardware component.
- .4 Install hardware to standard hardware location dimensions in accordance with CSDFMA Canadian Metric Guide for Steel Doors and Frames (Modular Construction).
- .5 Where door stop contacts door pulls, mount stop to strike bottom of pull.
- .6 Install key control cabinet.
- .7 Use only manufacturer's supplied fasteners.
 - .1 Use of "quick" type fasteners, unless specifically supplied by manufacturer, is unacceptable.

- .8 Remove construction cores & locks when directed by Departmental Representative.
 - .1 Install permanent cores and ensure locks operate correctly.

3.2 ADJUSTING

- .1 Adjust door hardware, operators, closures and controls for optimum, smooth operating condition, safety and for weather tight closure.
- .2 Lubricate hardware, operating equipment and other moving parts.
- .3 Adjust door hardware to ensure tight fit at contact points with frames.

3.3 CLEANING

- .1 Progress Cleaning: clean in accordance with Section 01 74 11 - Cleaning.
 - .1 Leave Work area clean at end of each day.
 - .2 Clean hardware with damp rag and approved non-abrasive cleaner, and polish hardware in accordance with manufacturer's instructions.
 - .3 Remove protective material from hardware items where present.
 - .4 Final Cleaning: upon completion remove surplus materials, rubbish, tools and equipment in accordance with Section 01 74 11 - Cleaning.
- .2 Waste Management: separate waste materials for reuse and recycling.
 - .1 Remove recycling containers and bins from site and dispose of materials at appropriate facility.

3.4 DEMONSTRATION

- .1 Keying System Setup and Cabinet:
 - .1 Set up key control system with file key tags, duplicate key tags, numerical index, alphabetical index and key change index, label shields, control book and key receipt cards.
 - .2 Place file keys and duplicate keys in key cabinet on their respective hooks.
 - .3 Lock key cabinet and turn over key to Departmental Representative.
- .2 Maintenance Staff Briefing:
 - .1 Brief maintenance staff regarding:
 - .1 Proper care, cleaning, and general maintenance of projects complete hardware.
 - .2 Description, use, handling, and storage of keys.
 - .3 Use, application and storage of wrenches for door closers, locksets and fire exit hardware.
- .3 Demonstrate operation, operating components, adjustment features, and lubrication requirements.

3.5 PROTECTION

- .1 Protect installed products and components from damage during construction.
- .2 Repair damage to adjacent materials caused by door hardware installation.

END OF SECTION

PART 1 GENERAL**1.1 RELATED SECTIONS**

- .1 Section 01 33 00 - Submittal Procedures.
- .2 Section 01 74 19 - Construction/Demolition Waste Management And Disposal.
- .3 Section 07 92 00 - Joint Sealing.

1.2 REFERENCES

- .1 Aluminum Association
 - .1 Designation for Aluminum Finishes-1997.
- .2 American Society for Testing and Materials International, (ASTM)
 - .1 ASTM C 36/C 36M-01, Specification for Gypsum Wallboard.
 - .2 ASTM C 79/C 79M-01, Standard Specification for Treated Core and Non-treated Core Gypsum Sheathing Board.
 - .3 ASTM C 442/C 442M-01, Specification for Gypsum Backing Board, Gypsum Coreboard, and Gypsum Shaftliner Board.
 - .4 ASTM C 475-01, Specification for Joint Compound and Joint Tape for Finishing Gypsum Board.
 - .5 ASTM C 514-01, Specification for Nails for the Application of Gypsum Board.
 - .6 ASTM C 557-99, Specification for Adhesives for Fastening Gypsum Wallboard to Wood Framing.
 - .7 ASTM C 840-01, Specification for Application and Finishing of Gypsum Board.
 - .8 ASTM C 954-00, Specification for Steel Drill Screws for the Application of Gypsum Panel Products or Metal Plaster Bases to Steel Studs From 0.033 in. (0.84 mm) to 0.112 in. (2.84 mm) in Thickness.
 - .9 ASTM C 1002-01, Specification for Steel Self-Piercing Tapping Screws for the Application of Gypsum Panel Products or Metal Plaster Bases to Wood Studs or Steel Studs.
 - .10 ASTM C 1047-99, Specification for Accessories for Gypsum Wallboard and Gypsum Veneer Base.
- .3 Association of the Wall and Ceilings Industries International (AWEI)
- .4 Canadian General Standards Board (CGSB)
 - .1 CAN/CGSB-71.25-M88, Adhesive, for Bonding Drywall to Wood Framing and Metal Studs.
- .5 Underwriters' Laboratories of Canada (ULC)
 - .1 CAN/ULC-S102-1988(R2000), Surface Burning Characteristics of Building Materials and Assemblies.

1.3 DELIVERY, STORAGE AND HANDLING

- .1 Deliver materials in original packages, containers or bundles bearing manufacturers brand name and identification.
- .2 Store materials inside, level, under cover. Keep dry. Protect from weather, other elements and damage from construction operations and other causes.
- .3 Handle gypsum boards to prevent damage to edges, ends or surfaces. Protect metal accessories and trim from being bent or damaged.

1.4 SITE ENVIRONMENTAL REQUIREMENTS

- .1 Maintain temperature minimum 10 degrees C, maximum 21 degrees C for 48 hours prior to and during application of gypsum boards and joint treatment, and for at least 48 hours after completion of joint treatment.
- .2 Apply board and joint treatment to dry, frost free surfaces.
- .3 Ventilation: Ventilate building spaces as required to remove excess moisture that would prevent drying of joint treatment material immediately after its application.

1.5 SAMPLES

- .1 Submit samples in accordance with Section 01 33 00 - Submittal Procedures.

1.6 WASTE MANAGEMENT AND DISPOSAL

- .1 Separate and recycle waste materials in accordance with Section 01 74 19 - Construction/Demolition Waste Management and Disposal.
- .2 Remove from site and dispose of packaging materials at appropriate recycling facilities.
- .3 Collect and separate for disposal paper, plastic, polystyrene, and corrugated cardboard packaging material in appropriate on-site for recycling in accordance with Waste Management Plan.
- .4 Divert unused gypsum from landfill to gypsum recycling facility for disposal approved by Architect.
- .5 Divert unused metal materials from landfill to metal recycling facility approved by Architect.
- .6 Divert unused wood materials from landfill to recycling facility approved by Architect.
- .7 Divert unused paint and caulking material from landfill to official hazardous material collections site approved by Architect.
- .8 Do not dispose of unused paint and caulking materials into sewer systems, into lakes, streams, onto ground or in other locations where it will pose health or environmental hazard.

PART 2 PRODUCTS

2.1 MATERIALS

- .1 Standard Board: to ASTM C 36/C 36M Type X, 16 mm thick, 1200 mm wide x maximum practical length, ends square cut, edges squared.
- .2 Steel drill screws: to ASTM C 1002.
- .3 Stud adhesive: to CAN/CGSB-71.25.
- .4 Laminating compound: as recommended by manufacturer, asbestos-free.
- .5 Casing beads, corner beads, control joints and edge trim: to ASTM C 1047, 0.5 mm base thickness, perforated flanges one piece length per location.
- .6 Sealants: In accordance with Section 07 92 00 - Joint Sealing.
- .7 Polyethylene: to CAN/CGSB-51.34, Type 2.
- .8 Insulating strip: rubberized, moisture resistant, 3 mm thick closed cell neoprene strip, 12 mm wide, with self sticking permanent adhesive on one face, lengths as required.
- .9 Joint compound: to ASTM C 475, asbestos-free.

2.2 FINISHES

- .1 Texture finish: asbestos-free [standard white] texture coating and primer-sealer, recommended by gypsum board manufacturer.

PART 3 EXECUTION**3.1 ERECTION**

- .1 Do application and finishing of gypsum board in accordance with ASTM C 840 except where specified otherwise.
- .2 Do application of gypsum sheathing in accordance with ASTM C 1280.
- .3 Erect hangers and runner channels for suspended gypsum board ceilings in accordance with ASTM C 840 except where specified otherwise.
- .4 Support light fixtures by providing additional ceiling suspension hangers within 150 mm of each corner and at maximum 600 mm around perimeter of fixture.
- .5 Install work level to tolerance of 1:1200.
- .6 Do not apply gypsum board until bucks, anchors, blocking, sound attenuation, electrical and mechanical works are approved.
- .7 Apply double layer gypsum board to metal framing using screw fasteners for first layer, laminating adhesive and screw fasteners for second layer. Maximum spacing of screws 300 mm on centre.
 - .1 Double-Layer Application:
 - .1 Install gypsum board for base layer and exposed gypsum board for face layer.
 - .2 Apply base layer to ceilings prior to base layer application on walls; apply face layers in same sequence. Offset joints between layers at least 250 mm.
 - .3 Apply base layers at right angles to supports unless otherwise indicated.
 - .4 Apply base layer on walls and face layers vertically with joints of base layer over supports and face layer joints offset at least 250 mm with base layer joints.
 - .2 Apply 12 mm diameter bead of acoustic sealant continuously around periphery of each face of partitioning to seal gypsum board/structure junction where partitions abut fixed building components. Seal full perimeter of cut-outs around electrical boxes, ducts, in partitions where perimeter sealed with acoustic sealant.
 - .3 Apply board using stud adhesive on furring or framing.
 - .4 Install gypsum board with face side out.
 - .5 Do not install damaged or damp boards.
 - .6 Locate edge or end joints over supports. Stagger vertical joints over different studs on opposite sides of wall.

3.2 INSTALLATION

- .1 Erect accessories straight, plumb or level, rigid and at proper plane. Use full length pieces where practical. Make joints tight, accurately aligned and rigidly secured. Mitre and fit corners accurately, free from rough edges. Secure at 150 mm on centre.
- .2 Install casing beads around perimeter of suspended ceilings.
- .3 Install casing beads where gypsum board butts against surfaces having no trim concealing junction and where indicated. Seal joints with sealant.
- .4 Install insulating strips continuously at edges of gypsum board and casing beads abutting metal window and exterior door frames, to provide thermal break.
- .5 Install shadow mould at gypsum board/ceiling juncture. Minimize joints; use corner pieces and splicers.
- .6 Construct control joints of preformed units set in gypsum board facing and supported independently on both sides of joint.
- .7 Provide continuous polyethylene dust barrier behind and across control joints.
- .8 Locate control joints at approximate 10 m spacing on long corridor runs.

- .9 Install control joints straight and true.
- .10 Construct expansion joints, at building expansion and construction joints. Provide continuous dust barrier.
- .11 Install expansion joint straight and true.
- .12 Install cornice cap where gypsum board partitions do not extend to ceiling.
- .13 Fit cornice cap over partition, secure to partition track with two rows of sheet metal screws staggered at 300 mm on centre.
- .14 Splice corners and intersections together and secure to each member with 3 screws.
- .15 Install access doors to electrical and mechanical fixtures specified in respective sections.
 - .1 Rigidly secure frames to furring or framing systems.
- .16 Finish face panel joints and internal angles with joint system consisting of joint compound, joint tape and taping compound installed according to manufacturer's directions and feathered out onto panel faces.
- .17 Gypsum Board Finish: finish gypsum board walls and ceilings to following levels in accordance with Association of the Wall and Ceiling Industries (AWCI) International Recommended Specification on Levels of Gypsum Board Finish:
 - .1 Levels of finish:
 - .1 Level 1: Embed tape for joints and interior angles in joint compound. Surfaces to be free of excess joint compound; tool marks and ridges are acceptable.
- .18 Finish corner beads, control joints and trim as required with two coats of joint compound and one coat of taping compound, feathered out onto panel faces.
- .19 Fill screw head depressions with joint and taping compounds to bring flush with adjacent surface of gypsum board so as to be invisible after surface finish is completed.
- .20 Sand lightly to remove burred edges and other imperfections. Avoid sanding adjacent surface of board.
- .21 Completed installation to be smooth, level or plumb, free from waves and other defects and ready for surface finish.
- .22 Apply one coat of white primer sealer over surface to be textured. When dry apply textured finish in accordance with manufacturer's instructions.
- .23 Mix joint compound slightly thinner than for joint taping.
- .24 Apply thin coat to entire surface using trowel or drywall broadknife to fill surface texture differences, variations or tool marks.
- .25 Allow skim coat to dry completely.
- .26 Remove ridges by light sanding or wiping with damp cloth.
- .27 Provide protection that ensures gypsum drywall work will remain without damage or deterioration at time of substantial completion.

END OF SECTION

PART 1 GENERAL**1.1 RELATED SECTIONS**

- .1 Section 01 31 19 - Project Meetings.
- .2 Section 01 74 19 - Construction/Demolition Waste Management And Disposal.
- .3 Section 07 92 00 - Joint Sealants.

1.2 REFERENCES

- .1 American Society for Testing and Materials International, (ASTM).
 - .1 ASTM C 645-00, Specification for Nonstructural Steel Framing Members.
 - .2 ASTM C 754-00, Specification for Installation of Steel Framing Members to Receive Screw-Attached Gypsum Panel Products.
- .2 Canadian General Standards Board (CGSB).
 - .1 CAN/CGSB-1.40-97, Primer, Structural Steel, Oil Alkyd Type.
- .3 Environmental Choice Program (ECP).
 - .1 CCD-047a-98, Paints - Surface Coatings.
 - .2 CCD-048-98, Surface Coatings - Recycled Water-borne.

1.3 QUALITY ASSURANCE

- .1 Test Reports: certified test reports showing compliance with specified performance characteristics and physical properties.
- .2 Certificates: product certificates signed by manufacturer certifying materials comply with specified performance characteristics and criteria and physical requirements.
- .3 Pre-Installation Meetings: conduct pre-installation meeting to verify project requirements, manufacturer's installation instructions and manufacturer's warranty requirements. Comply with Section 01 31 19 - Project Meetings.

1.4 WASTE MANAGEMENT AND DISPOSAL

- .1 Separate and recycle waste materials in accordance with Section 01 74 19 - Construction/Demolition Waste Management and Disposal.
- .2 Remove from site and dispose of packaging materials at appropriate recycling facilities.
- .3 Collect and separate for disposal paper, plastic, polystyrene, and corrugated cardboard packaging material in appropriate on-site for recycling in accordance with Waste Management Plan.
- .4 Divert unused metal materials from landfill to metal recycling facility approved by Architect.
- .5 Divert unused gypsum materials from landfill to recycling facility approved by Architect.

PART 2 PRODUCTS**2.1 MATERIALS**

- .1 Non-load bearing channel stud framing: to ASTM C 645, 152 mm stud size, roll formed from 0.91 mm thickness hot dipped galvanized steel sheet, for screw attachment of gypsum board. Knock-out service holes at 460 mm centres.
- .2 Floor and ceiling tracks: to ASTM C 645, in widths to suit stud sizes:
 - .1 Bottom channel: 32 mm flange height.

- .2 Deflection channel (fixed to u/s of structure): 65 mm flange height.
- .3 Non-load bearing truss stud framing system: to consist of:
 - .1 Studs: 152 mm size; truss-type bent rod web with 12 x 6 mm x 1.2 mm channel chords; welded together at contact points. Make rod of minimum 4.5 mm diameter cold drawn steel wire having tensile strength of 620 MPa. Design studs for clip attachment of gypsum lath or wire tying of metal lath.
 - .2 Floor track: snap-in type formed to hold studs securely in place at 50 mm intervals; fabricated from 0.5 mm thick steel sheet; size to suit studs.
 - .3 Ceiling track: channel shaped track for use with stud shoes and 1.2 mm diameter double wire ties; size to suit studs.
 - .4 After fabrication apply one shop coat of CAN/CGSB-1.40 primer to steel surfaces. Descale and clean surfaces before painting.
- .4 Metal channel stiffener: 1.4 mm thick cold rolled steel, coated with rust inhibitive coating.
- .5 Acoustical sealant: In accordance with Section 07 92 00 - Joint Sealants.
- .6 Insulating strip: rubberized, moisture resistant 3 mm thick foam strip, 12 mm wide, with self sticking adhesive on one face, lengths as required.

PART 3 EXECUTION

3.1 ERECTION

- .1 Align partition tracks at floor and ceiling and secure at 600 mm on centre maximum.
- .2 Install damp proof course under stud shoe tracks of partitions on slabs on grade.
- .3 Place studs vertically at 400 mm on centre and not more than 50 mm from abutting walls, and at each side of openings and corners. Position studs in tracks at floor and ceiling. Cross brace steel studs as required to provide rigid installation to manufacturer's instructions.
- .4 Erect metal studding to tolerance of 1:1000.
- .5 Attach studs to bottom track using screws.
- .6 Co-ordinate simultaneous erection of studs with installation of service lines. When erecting studs ensure web openings are aligned.
- .7 Co-ordinate erection of studs with installation of door/window frames and special supports or anchorage for work specified in other Sections.
- .8 Provide two studs extending from floor to ceiling at each side of openings wider than stud centres specified. Secure studs together, 50 mm apart using column clips or other approved means of fastening placed alongside frame anchor clips.
- .9 Install heavy gauge single jamb studs at openings.
- .10 Erect track at head of door/window openings and sills of sidelight/window openings to accommodate intermediate studs. Secure track to studs at each end, in accordance with manufacturer's instructions. Install intermediate studs above and below openings in same manner and spacing as wall studs.
- .11 Frame openings and around built-in equipment, cabinets, access panels, on four sides. Extend framing into reveals. Check clearances with equipment suppliers.
- .12 Provide [40] mm stud or furring channel secured between studs for attachment of fixtures behind lavatory basins, toilet and bathroom accessories, and other fixtures including grab bars and towel rails, attached to steel stud partitions.
- .13 Install steel studs or furring channel between studs for attaching electrical and other boxes.
- .14 Extend partitions to ceiling height except where noted otherwise on drawings.

- .15 Maintain clearance under beams and structural slabs to avoid transmission of structural loads to studs. Use double track slip joint.
- .16 Install continuous insulating strips to isolate studs from uninsulated surfaces.
- .17 Install two continuous beads of acoustical sealant under studs and tracks around perimeter of sound control partitions.

3.2 **CLEANING**

- .1 Upon completion of installation, remove surplus materials, rubbish, tools and equipment barriers.

END OF SECTION

PAGE INTENTIONALLY LEFT BLANK

PART 1 GENERAL**1.1 Related Sections:**

- .1 Section 01 33 00 - Submittal Procedures.
- .2 Section 01 45 00 - Quality Control.
- .3 Section 01 51 00 - Temporary Utilities.
- .4 Section 01 61 00 - Common Product Requirements.
- .5 Section 01 74 21 - Construction/Demolition Waste Management and Disposal.
- .6 Section 01 78 00 - Closeout Submittals.
- .7 Section 07 81 20 - Intumescent Fire Resistive Material.

1.2 REFERENCES

- .1 Department of Justice Canada (Jus)
 - .1 Canadian Environmental Protection Act (CEPA), 1999, c. 33
- .2 Environmental Protection Agency (EPA)
 - .1 EPA Test Method for Measuring Total Volatile Organic Compound Content of Consumer Products, Method 24 - 1995, (for Surface Coatings).
- .3 Health Canada / Workplace Hazardous Materials Information System (WHMIS)
 - .1 Material Safety Data Sheets (MSDS).
- .4 Master Painters Institute (MPI)
 - .1 MPI Architectural Painting Specifications Manual, 2004.
- .5 National Fire Code of Canada - 1995.
- .6 Society for Protective Coatings (SSPC)
 - .1 SSPC Painting Manual, Volume Two, 8th Edition, Systems and Specifications Manual.
- .7 Transport Canada (TC)
 - .1 Transportation of Dangerous Goods Act (TDGA), 1992, c. 34 .

1.3 QUALITY ASSURANCE

- .1 Qualifications:
 - .1 Contractor: minimum of five years proven satisfactory experience. Provide list of last three comparable jobs including, job name and location, specifying authority, and project manager.
 - .2 Journeymen: qualified journeymen who have "Tradesman Qualification Certificate of Proficiency" engaged in painting work.
 - .3 Apprentices: working under direct supervision of qualified trades person in accordance with trade regulations.
- .2 Mock-Ups:
 - .1 Construct mock-ups in accordance with Section 01 45 00 - Quality Control.
 - .1 Provide 300 mm x 300 mm mock-up. Prepare and paint designated surface, area, room or item (in each colour scheme) to specified requirements, with specified paint or coating showing selected colours, gloss/sheen and textures.
 - .2 Mock-up will be used:
 - .1 To judge workmanship, substrate preparation, operation of equipment and material application and workmanship to MPI Architectural Painting Specification Manual standards.

- .3 Locate where directed by Architect.
- .4 Allow 24 hours for inspection of mock-up before proceeding with work.
- .5 When accepted, mock-up will demonstrate minimum standard of quality required for this work.

.3 Health and Safety:

- .1 Do construction occupational health and safety in accordance with Section 01 35 29 - Health and Safety Requirements.

1.4 SCHEDULING

- .1 Submit work schedule for various stages of painting to Architect for review. Submit schedule minimum of 48 hours in advance of proposed operations.
- .2 Obtain written authorization from Architect for changes in work schedule.
- .3 Schedule painting operations to prevent disruption of occupants.

1.5 SUBMITTALS

- .1 Submittals in accordance with Section 01 33 00 - Submittal Procedures.
- .2 Product Data:
 - .1 Submit product data and instructions for each paint and coating product to be used.
 - .2 Submit product data for the use and application of paint thinner.
 - .3 Submit Workplace Hazardous Materials Information System (WHMIS) Material Safety Data Sheets (MSDS) in accordance with Section 01 33 00 - Submittal Procedures. Indicate VOCs during application and curing.
- .3 Samples:
 - .1 Submit full range colour sample chips to indicate where colour availability is restricted.
 - .2 Submit duplicate sample panels of each paint and special finish with specified paint or coating in colours, gloss/sheen and textures required to MPI Architectural Painting Specification Manual standards submitted on following substrate materials:
 - .1 3 mm for finishes over metal surfaces.
 - .2 13 mm for finishes over gypsum board and other smooth surfaces.
 - .3 Retain reviewed samples on-site to demonstrate acceptable standard of quality for appropriate on-site surface.
 - .4 Test reports: submit certified test reports for paint from approved independent testing laboratories, indicating compliance with specifications for specified performance characteristics and physical properties.
 - .1 Lead, cadmium and chromium: presence of and amounts.
 - .2 Mercury: presence of and amounts.
 - .3 Organochlorines and PCBs: presence of and amounts.
 - .5 Certificates: submit certificates signed by manufacturer certifying that materials comply with specified performance characteristics and physical properties.
 - .6 Manufacturer's Instructions:
 - .1 Submit manufacturer's installation and application instructions.
 - .7 Closeout Submittals: submit maintenance data for incorporation into manual specified in Section 01 78 00 - Closeout Submittals include following:
 - .1 Product name, type and use.
 - .2 Manufacturer's product number.
 - .3 Colour numbers.
 - .4 MPI Environmentally Friendly classification system rating.

1.6 MAINTENANCE

- .1 Extra Materials:
 - .1 Deliver to extra materials from same production run as products installed. Package products with protective covering and identify with descriptive labels. Comply with Section 01 78 00 - Closeout Submittals.
 - .2 Quantity: provide one - four litre can of each type and colour of finish coating. Identify colour and paint type in relation to established colour schedule and finish system.
 - .3 Delivery, storage and protection: comply with Architect requirements for delivery and storage of extra materials.

1.7 DELIVERY, STORAGE AND HANDLING

- .1 Packing, Shipping, Handling and Unloading:
 - .1 Pack, ship, handle and unload materials in accordance with Section 01 61 00 - Common Product Requirements and manufacturer's written instructions.
- .2 Acceptance at Site:
 - .1 Identify products and materials with labels indicating:
 - .1 Manufacturer's name and address.
 - .2 Type of paint or coating.
 - .3 Compliance with applicable standard.
 - .4 Colour number in accordance with established colour schedule.
- .3 Remove damaged, opened and rejected materials from site.
- .4 Storage and Protection:
 - .1 Provide and maintain dry, temperature controlled, secure storage.
 - .2 Store materials and supplies away from heat generating devices.
 - .3 Store materials and equipment in well ventilated area with temperature range 7 degrees C to 30 degrees C.
- .5 Store temperature sensitive products above minimum temperature as recommended by manufacturer.
- .6 Keep areas used for storage, cleaning and preparation clean and orderly. After completion of operations, return areas to clean condition.
- .7 Remove paint materials from storage only in quantities required for same day use.
- .8 Fire Safety Requirements:
 - .1 Provide one Type ABC fire extinguisher adjacent to storage area.
 - .2 Store oily rags, waste products, empty containers and materials subject to spontaneous combustion in ULC approved, sealed containers and remove from site on a daily basis.
 - .3 Handle, store, use and dispose of flammable and combustible materials in accordance with National Fire Code of Canada requirements.
- .9 Waste Management and Disposal:
 - .1 Separate waste materials for reuse and recycling in accordance with Section 01 74 21 - Construction/Demolition Waste Management and Disposal.
 - .2 Remove from site and dispose of packaging materials at appropriate recycling facilities.
 - .3 Collect and separate for disposal paper, plastic, polystyrene, and corrugated cardboard packaging material for recycling in accordance with Waste Management Plan (WMP).
 - .4 Separate for reuse and recycling and place in designated containers [Steel] [Metal] Plastic waste in accordance with Waste Management Plan (WMP).
 - .5 Place materials defined as hazardous or toxic in designated containers.

- .6 Handle and dispose of hazardous materials in accordance with Regional and Municipal regulations.
- .7 Ensure emptied containers are sealed and stored safely.
- .8 Unused paint and coating materials must be disposed of at official hazardous material collections site as approved by Architect.
- .9 Paint, stain and wood preservative finishes and related materials (thinners, and solvents) are regarded as hazardous products and are subject to regulations for disposal. Information on these controls can be obtained from Provincial Ministries of Environment and Regional levels of Government.
- .10 Material which cannot be reused must be treated as hazardous waste and disposed of in an appropriate manner.
- .11 Place materials defined as hazardous or toxic waste, including used sealant and adhesive tubes and containers, in containers or areas designated for hazardous waste.
- .12 To reduce the amount of contaminants entering waterways, sanitary/storm drain systems or into ground follow these procedures:
 - .1 Retain cleaning water for water-based materials to allow sediments to be filtered out.
 - .2 Retain cleaners, thinners, solvents and excess paint and place in designated containers and ensure proper disposal.
 - .3 Return solvent and oil soaked rags used during painting operations for contaminant recovery, proper disposal, or appropriate cleaning and laundering.
 - .4 Dispose of contaminants in approved legal manner in accordance with hazardous waste regulations.
 - .5 Empty paint cans are to be dry prior to disposal or recycling (where available).
- .13 Where paint recycling is available, collect waste paint by type and provide for delivery to recycling or collection facility.
- .14 Set aside and protect surplus and uncontaminated finish materials. Deliver to or arrange collection by employees, or organizations for verifiable re-use or re-manufacturing.

1.8 SITE CONDITIONS

- .1 Heating, Ventilation and Lighting:
 - .1 Ventilate enclosed spaces in accordance with Section 01 51 00 - Temporary Utilities.
 - .2 Provide heating facilities to maintain ambient air and substrate temperatures above 10 degrees C for 24 hours before, during and after paint application until paint has cured sufficiently.
 - .3 Provide continuous ventilation for seven days after completion of application of paint.
 - .4 Coordinate use of existing ventilation system with Architect and ensure its operation during and after application of paint as required.
 - .5 Provide temporary ventilating and heating equipment where permanent facilities are not available or supplemental ventilating and heating equipment if ventilation and heating from existing system is inadequate to meet minimum requirements.
 - .6 Provide minimum lighting level of 323 Lux on surfaces to be painted.
- .2 Temperature, Humidity and Substrate Moisture Content Levels:
 - .1 Unless pre-approved written approval by Paint Inspection Agency Authority and product manufacturer, perform no painting when:
 - .1 Ambient air and substrate temperatures are below 10 degrees C.
 - .2 Substrate temperature is above 32 degrees C unless paint is specifically formulated for application at high temperatures.
 - .3 Substrate and ambient air temperatures are not expected to fall within MPI or paint manufacturer's prescribed limits.

- .4 The relative humidity is under 85 % or when the dew point is more than [3] degrees C variance between the air/surface temperature. Paint should not be applied if the dew point is less than 3 degrees C below the ambient or surface temperature. Use sling psychrometer to establish the relative humidity before beginning paint work.
- .5 Rain or snow are forecast to occur before paint has thoroughly cured or when it is foggy, misty, raining or snowing at site.
- .6 Ensure that conditions are within specified limits during drying or curing process, until newly applied coating can itself withstand 'normal' adverse environmental factors.
- .2 Perform painting work when maximum moisture content of the substrate is below:
 - .1 Allow new concrete and masonry to cure minimum of 28 days.
 - .2 15 % for wood.
 - .3 12 % for plaster and gypsum board.
- .3 Test for moisture using calibrated electronic Moisture Meter. Test concrete floors for moisture using "cover patch test".
- .4 Test concrete, masonry and plaster surfaces for alkalinity as required.
- .3 Surface and Environmental Conditions:
 - .1 Apply paint finish in areas where dust is no longer being generated by related construction operations or when wind or ventilation conditions are such that airborne particles will not affect quality of finished surface.
 - .2 Apply paint to adequately prepared surfaces and to surfaces within moisture limits.
 - .3 Apply paint when previous coat of paint is dry or adequately cured.
- .4 Additional interior application requirements:
 - .1 Apply paint finishes when temperature at location of installation can be satisfactorily maintained within manufacturer's recommendations.
 - .2 Apply paint in occupied facilities during silent hours only. Schedule operations to approval of Architect such that painted surfaces will have dried and cured sufficiently before occupants are affected.

PART 2 PRODUCTS

2.1 MATERIALS

- .1 Paint materials listed in the MPI Approved Products List (APL) are acceptable for use on this project.
- .2 Provide paint materials for paint systems from single manufacturer.
- .3 Only qualified products with E2 "Environmentally Friendly" rating are acceptable for use on this project.
- .4 Conform to latest MPI requirements for interior painting work including preparation and priming.
- .5 Materials (primers, paints, coatings, varnishes, stains, lacquers, fillers, thinners, solvents, etc.) in accordance with MPI Architectural Painting Specification Manual "Approved Product" listing.
- .6 Linseed oil, shellac, and turpentine: highest quality product from approved manufacturer listed in MPI Architectural Painting Specification Manual, compatible with other coating materials as required.
- .7 Provide paint products meeting MPI "Environmentally Friendly" E2 ratings based on VOC (EPA Method 24) content levels.

- .8 Use MPI listed materials having minimum E2 rating where indoor air quality (odour) requirements exist.
- .9 Paints, coatings, adhesives, solvents, cleaners, lubricants, and other fluids:
 - .1 Water-based.
 - .2 Biodegradable.
 - .3 Manufactured without compounds which contribute to ozone depletion in the upper atmosphere.
 - .4 Manufactured without compounds which contribute to smog in the lower atmosphere.
 - .5 Do not contain methylene chloride, chlorinated hydrocarbons, toxic metal pigments.
- .10 Formulate and manufacture water-borne surface coatings with no aromatic solvents, formaldehyde, halogenated solvents, mercury, lead, cadmium, hexavalent chromium or their compounds.
- .11 Flash point: 61.0 degrees C or greater for water-borne surface coatings and recycled water-borne surface coatings.
- .12 Ensure manufacture and process of both water-borne surface coatings and recycled water-borne surface coatings does not release:
 - .1 Matter in undiluted production plant effluent generating 'Biochemical Oxygen Demand' (BOD) in excess of 15 mg/L to natural watercourse or sewage treatment facility lacking secondary treatment.
 - .2 Total Suspended Solids (TSS) in undiluted production plant effluent in excess of 15 mg/L to natural watercourse or a sewage treatment facility lacking secondary treatment.
- .13 Water-borne paints and stains, recycled water-borne surface coatings and water borne varnishes to meet minimum "Environmentally Friendly" E2 rating.
- .14 Recycled water-borne surface coatings to contain 50 % post-consumer material by volume.
- .15 Recycled water-borne surface coatings must not contain:
 - .1 Lead in excess of 600.0 ppm weight/weight total solids.
 - .2 Mercury in excess of 50.0 ppm weight/weight total product.
 - .3 Cadmium in excess of 1.0 ppm weight/weight total product.
 - .4 Hexavalent chromium in excess of 3.0 ppm weight/weight total product.
 - .5 Organochlorines or polychlorinated biphenyls (PCBS) in excess of 1.0 ppm weight/weight total product.

2.2 COLOURS

- .1 Submit proposed Colour Schedule to Architect for review.
- .2 Selection of colours from manufacturer's full range of colours.
- .3 Where specific products are available in restricted range of colours, selection based on limited range.
- .4 Second coat in three coat system to be tinted slightly lighter colour than top coat to show visible difference between coats.

2.3 MIXING AND TINTING

- .1 Perform colour tinting operations prior to delivery of paint to site. Obtain written approval from Architect for tinting of painting materials.
- .2 Mix paste, powder or catalyzed paint mixes in accordance with manufacturer's written instructions.

- .3 Use and add thinner in accordance with paint manufacturer's recommendations. Do not use kerosene or similar organic solvents to thin water-based paints.
- .4 Thin paint for spraying in accordance with paint manufacturer's instructions.
- .5 Re-mix paint in containers prior to and during application to ensure break-up of lumps, complete dispersion of settled pigment, and colour and gloss uniformity.

2.4 GLOSS/SHEEN RATINGS

- .1 Paint gloss is defined as sheen rating of applied paint, in accordance with following values:

Gloss Level Category:	Units @ 60 Degrees:	Units 85 Degrees:
G1 – Matte finish (Flat)	0 to 5	Max. 10
G2 – Velvet finish	0 to 10	10 to 35
G3 – Eggshell finish	10 to 25	10 to 35
G4 – Satin finish	20 to 35	Min. 35
G5 – Semi-gloss finish	35 to 70	
G6 – Gloss finish	70 to 85	
G7 – High gloss finish	More than 85	

- .2 Gloss level ratings of painted surfaces as indicated and as noted on Finish Schedule.

2.5 INTERIOR PAINTING SYSTEMS

- .1 Concrete horizontal surfaces: floors and stairs:
 - .1 INT 3.2C - Epoxy G5 finish.
- .2 Structural steel and metal fabrications: columns, beams, joists:
 - .1 Section 07 81 20 - Intumescent Fire Resistant Material:
 - .1 Apply colour approved by manufacturer and applied in full accordance with the primer manufacturer's written instructions. Colour to match adjacent.
- .3 Galvanized metal: doors, frames, railings, misc. steel, pipes, overhead decking, and ducts.
 - .1 INT 5.3M - High performance architectural latex G5 finish.
- .4 Plaster and gypsum board: gypsum wallboard, drywall, "sheet rock type material", and textured finishes:
 - .1 INT 9.2B - High performance architectural latex G3 finish.

2.6 SOURCE QUALITY CONTROL

- .1 Perform following tests on each batch of consolidated post-consumer material before surface coating is reformulated and canned. Testing by laboratory or facility which has been accredited by Standards Council of Canada.
 - .1 Lead, cadmium and chromium are to be determined using ICP-AES (Inductively Coupled Plasma - Atomic Emission Spectroscopy) technique no. 6010 as defined in EPA SW-846.
 - .2 Mercury is to be determined by Cold Vapour Atomic Absorption Spectroscopy using Technique no. 7471 as defined in EPA SW-846.
 - .3 Organochlorines and PCBs are to be determined by Gas Chromatography using Technique no. 8081 as defined in EPA SW-846.

PART 3 EXECUTION

3.1 MANUFACTURER'S INSTRUCTIONS

- .1 Compliance: comply with manufacturer's written recommendations or specifications, including product technical bulletins, handling, storage and installation instructions, and data sheet.

3.2 GENERAL

- .1 Perform preparation and operations for interior painting in accordance with MPI Architectural Painting Specifications Manual except where specified otherwise.
- .2 Apply paint materials in accordance with paint manufacturer's written application instructions.

3.3 EXAMINATION

- .1 Investigate existing substrates for problems related to proper and complete preparation of surfaces to be painted. Report to Architect damages, defects, unsatisfactory or unfavourable conditions before proceeding with work.
- .2 Conduct moisture testing of surfaces to be painted using properly calibrated electronic moisture meter, except test concrete floors for moisture using simple "cover patch test". Do not proceed with work until conditions fall within acceptable range as recommended by manufacturer.
- .3 Maximum moisture content as follows:
 - .1 Stucco, plaster and gypsum board: 12 %.
 - .2 Concrete: 12 %.
 - .3 Clay and Concrete Block/Brick: 12 %.
 - .4 Wood: 15 %.

3.4 PREPARATION

- .1 Protection:
 - .1 Protect existing building surfaces and adjacent structures from paint spatters, markings and other damage by suitable non-staining covers or masking. If damaged, clean and restore surfaces as directed by Architect.
 - .2 Protect items that are permanently attached such as Fire Labels on doors and frames.
 - .3 Protect factory finished products and equipment.
 - .4 Protect building occupants and general public in and about the building.
- .2 Surface Preparation:
 - .1 Remove electrical cover plates, light fixtures, surface hardware on doors, bath accessories and other surface mounted equipment, fittings and fastenings prior to undertaking painting operations. Identify and store items in secure location and re-installed after painting is completed.
 - .2 Move and cover furniture and portable equipment as necessary to carry out painting operations. Replace as painting operations progress.
 - .3 Place "WET PAINT" signs in occupied areas as painting operations progress. Signs to approval of Architect.
- .3 Clean and prepare surfaces in accordance with MPI Architectural Painting Specification Manual requirements. Refer to MPI Manual in regard to specific requirements and as follows:
 - .1 Remove dust, dirt, and other surface debris by vacuuming, wiping with dry, clean cloths or compressed air.
 - .2 Wash surfaces with a biodegradable detergent [and bleach where applicable] and clean warm water using a stiff bristle brush to remove dirt, oil and other surface contaminants.
 - .3 Rinse scrubbed surfaces with clean water until foreign matter is flushed from surface.

- .4 Allow surfaces to drain completely and allow to dry thoroughly.
 - .5 Prepare surfaces for water-based painting, water-based cleaners should be used in place of organic solvents.
 - .6 Use trigger operated spray nozzles for water hoses.
 - .7 Many water-based paints cannot be removed with water once dried. Minimize use of mineral spirits or organic solvents to clean up water-based paints.
- .4 Prevent contamination of cleaned surfaces by salts, acids, alkalis, other corrosive chemicals, grease, oil and solvents before prime coat is applied and between applications of remaining coats. Apply primer, paint, or pretreatment as soon as possible after cleaning and before deterioration occurs.
 - .5 Where possible, prime non-exposed surfaces of new wood surfaces before installation. Use same primers as specified for exposed surfaces.
 - .1 Apply vinyl sealer to MPI #36 over knots, pitch, sap and resinous areas.
 - .2 Apply wood filler to nail holes and cracks.
 - .3 Tint filler to match stains for stained woodwork.
 - .6 Sand and dust between coats as required to provide adequate adhesion for next coat and to remove defects visible from a distance up to 1000 mm.
 - .7 Clean metal surfaces to be painted by removing rust, loose mill scale, welding slag, dirt, oil, grease and other foreign substances in accordance with MPI requirements. Remove traces of blast products from surfaces, pockets and corners to be painted by brushing with clean brushes or vacuum cleaning.
 - .8 Touch up of shop primers with primer as specified.
 - .9 Do not apply paint until prepared surfaces have been accepted by Architect.

3.5 APPLICATION

- .1 Method of application to be as approved by Architect. Apply paint by brush, roller and air sprayer. Conform to manufacturer's application instructions unless specified otherwise.
- .2 Brush and Roller Application:
 - .1 Apply paint in uniform layer using brush and/or roller type suitable for application.
 - .2 Work paint into cracks, crevices and corners.
 - .3 Paint surfaces and corners not accessible to brush using spray, daubers and/or sheepskins. Paint surfaces and corners not accessible to roller using brush, daubers or sheepskins.
 - .4 Brush and/or roll out runs and sags, and over-lap marks. Rolled surfaces free of roller tracking and heavy stipple.
 - .5 Remove runs, sags and brush marks from finished work and repaint.
- .3 Spray application:
 - .1 Provide and maintain equipment that is suitable for intended purpose, capable of atomizing paint to be applied, and equipped with suitable pressure regulators and gauges.
 - .2 Keep paint ingredients properly mixed in containers during paint application either by continuous mechanical agitation or by intermittent agitation as frequently as necessary.
 - .3 Apply paint in uniform layer, with overlapping at edges of spray pattern. Back roll first coat application.
 - .4 Brush out immediately all runs and sags.
 - .5 Use brushes and rollers to work paint into cracks, crevices and places which are not adequately painted by spray.

- .4 Use dipping, sheepskins or daubers only when no other method is practical in places of difficult access.
- .5 Apply coats of paint continuous film of uniform thickness. Repaint thin spots or bare areas before next coat of paint is applied.
- .6 Allow surfaces to dry and properly cure after cleaning and between subsequent coats for minimum time period as recommended by manufacturer.
- .7 Sand and dust between coats to remove visible defects.
- .8 Finish surfaces both above and below sight lines as specified for surrounding surfaces, including such surfaces as tops of interior cupboards and cabinets and projecting ledges.
- .9 Finish inside of cupboards and cabinets as specified for outside surfaces.
- .10 Finish closets and alcoves as specified for adjoining rooms.
- .11 Finish top, bottom, edges and cutouts of doors after fitting as specified for door surfaces.

3.6 MECHANICAL/ELECTRICAL EQUIPMENT

- .1 Paint finished area exposed conduits, piping, hangers, ductwork and other mechanical and electrical equipment with colour and finish to match adjacent surfaces, except as indicated.
- .2 Boiler room, mechanical and electrical rooms: paint exposed conduits, piping, hangers, ductwork and other mechanical and electrical equipment.
- .3 Other unfinished areas: leave exposed conduits, piping, hangers, ductwork and other mechanical and electrical equipment in original finish and touch up scratches and marks.
- .4 Touch up scratches and marks on factory painted finishes and equipment with paint as supplied by manufacturer of equipment.
- .5 Do not paint over nameplates.
- .6 Keep sprinkler heads free of paint.
- .7 Paint inside of ductwork where visible behind grilles, registers and diffusers with primer and one coat of matt black paint.
- .8 Paint fire protection piping red.
- .9 Paint disconnect switches for fire alarm system and exit light systems in red enamel.
- .10 Paint natural gas piping yellow.
- .11 Paint both sides and edges of backboards for telephone and electrical equipment before installation. Leave equipment in original finish except for touch-up as required, and paint conduits, mounting accessories and other unfinished items.
- .12 Do not paint interior transformers and substation equipment.

3.7 SITE TOLERANCES

- .1 Walls: no defects visible from a distance of 1000 mm at 90 degrees to surface.
- .2 Ceilings: no defects visible from floor at 45 degrees to surface when viewed using final lighting source.
- .3 Final coat to exhibit uniformity of colour and uniformity of sheen across full surface area.

3.8 FIELD QUALITY CONTROL

- .1 Interior painting and decorating work shall be inspected by a Paint Inspection Agency (inspector) acceptable to the specifying authority and local Painting Contractor's Association. Painting contractor shall notify Paint Inspection Agency a minimum of one week prior to commencement of work and provide a copy of project painting specification, plans and elevation drawings (including pertinent details) as well as a Finish Schedule.
- .2 Interior surfaces requiring painting shall be inspected by Paint Inspection Agency who shall notify Architect and General Contractor in writing of defects or problems, prior to commencing painting work, or after prime coat shows defects in substrate.
- .3 Where "special" painting, coating or decorating system applications (i.e. elastomeric coatings) or non-MPI listed products or systems are to be used, paint or coating manufacturer shall provide as part of this work, certification of surfaces and conditions for specific paint or coating system application as well as on site supervision, inspection and approval of their paint or coating system application as required at no additional cost to Architect.
Standard of Acceptance:
 - .1 Walls: no defects visible from a distance of 1000 mm at 90 degrees to surface.
 - .2 Ceilings: no defects visible from floor at 45 degrees degrees to surface when viewed using final lighting source.
 - .3 Final coat to exhibit uniformity of colour and uniformity of sheen across full surface area.
- .4 Field inspection of painting operations to be carried out by independent inspection firm as designated by Architect.
- .5 Advise Architect when surfaces and applied coating is ready for inspection. Do not proceed with subsequent coats until previous coat has been approved.
- .6 Cooperate with inspection firm and provide access to areas of work.
- .7 Retain purchase orders, invoices and other documents to prove conformance with noted MPI requirements when requested by Architect.

3.9 RESTORATION

- .1 Clean and re-install hardware items removed before undertaken painting operations.
- .2 Remove protective coverings and warning signs as soon as practical after operations cease.
- .3 Remove paint splashings on exposed surfaces that were not painted. Remove smears and spatter immediately as operations progress, using compatible solvent.
- .4 Protect freshly completed surfaces from paint droppings and dust to approval of Architect. Avoid scuffing newly applied paint.
- .5 Restore areas used for storage, cleaning, mixing and handling of paint to clean condition as approved by Architect.

END OF SECTION

PAGE INTENTIONALLY LEFT BLANK