



National Research Council
Canada

Conseil national de recherches
Canada

Administrative Services
and Property Management
Branch

Direction des services
administratifs et
gestion de l'immobilier



Addendum / Addenda

No./N^o

1

Project Description / Description de projet		
M14 Re-Roofing		
Solicitation No./ No de sollicitation	Project No./N ^o de projet	W.O. No./N ^o d'ordre de travail
14-22001	3941	C746-CORR
Departmental Representative / représentant ministériel		Date
Mark O'Connor		APRIL 29, 2014
Notice: This addendum shall form part of the tender documents and all conditions shall apply and be read in conjunction with the original plans and specifications.		Nota: Cet addenda fait partie intégrale des dossiers d'appel d'offres; toutes les conditions énoncées doivent être lues et appliquées en conjonction avec les plans et les devis originaux.

General/Drawing revisions

General:

- A. Set-up areas will be on the north and south sides of the building.
- B. Existing roof assembly is as follows:

<u>Roofs 2-3-5-6 & 7:</u>	<u>Roof 9:</u>
-Gravel	-cap sheet/base sheet
-4-ply membrane	-asphalt board
-Fiberglass insulation	-Rigid insulation
-Vapour barrier	-Vapour barrier
-Drywall	-Drywall
-Steel Deck	-Steel Deck
- C. Supply and install new ceiling access hatch at drain located below roof 6.

Drawing R1:

1. Roof 2:
 - Revised drains (2 drains instead of 3)
 - Revised sloped insulation
 - Added 1 soil vent
2. Roof 3:
 - Revised drains (1 drain instead of 2)
 - Revised sloped insulation
3. Roof 5:
 - Revised drain locations (closer to center of roof)
 - Revised back slope (from 1.2m to 3.6m)
 - Revised crickets
 - Added 1 soil vent

-Added 2 capped curbs.

4. Roof 9:

-This section is no longer part of the contract. (N.I.C.)

Drawing R2:

1. Detail 1/R2:

-Revised the typical roof assembly to add new 12mm Densdeck sheathing.
(existing deck is steel deck not concrete)

End of Addendum #1