



Addendum / Addenda

No./N^o
1

Project Description / Description de projet M1 M2A M15 Re-Roofing		
Solicitation No./ No de sollicitation 14-22002	Project No./N ^o de projet 3940	W.O. No./N ^o d'ordre de travail C736-CORR
Departmental Representative / représentant ministériel Mark O'Connor		Date APRIL 29, 2014
<p>Notice: This addendum shall form part of the tender documents and all conditions shall apply and be read in conjunction with the original plans and specifications.</p>		<p>Nota: Cet addenda fait partie intégrale des dossiers d'appel d'offres; toutes les conditions énoncées doivent être lues et appliquées en conjonction avec les plans et les devis originaux.</p>

General/Drawing revisions

General:

- A. Set-up area will be on the north side of building M1.
- B. O/H protection to be provided at man doors of building 1 during canopy work.
- C. Set-up area will be on the south side of building M2A.
- D. Set-up area will be on the east side of building M15.

M1 Drawing R1:

- 1. Canopy has been added to the contract; refer to the drawing for assembly.

M15 Drawing R1:

- 1. New 4.8x2.4m sloped insulation sump has been added to roof 2. Base insulation in this area shall drop to 38mm.
- 2. New 150x150mm Eaves through and downspout to be supplied and installed on east end of roof 2 (Downspout to be on south side with base extending 1.5m away from the building).

End of Addendum #1