

ADDENDUM ITEMS

Date:	30 APRIL 2014
Project File Number:	13-12
Project Title:	PROPOSED ROOF REPAIRS MTC/POB BUILDINGS GOVERNMENT OF CANADA REGINA, SASKATCHEWAN

THIS ADDENDUM SUPERCEDES ALL PREVIOUSLY ISSUED DOCUMENTATION AND WILL FORM AN INTEGRAL PART OF THE CONTRACT DOCUMENTS.

THIS ADDENDUM IS COMPRISED OF ONE (1) WRITTEN PAGE only.

ARCHITECTURAL

SPECIFICATIONS

Section 07521 – Torch Grade Roofing Materials

Article 1.7 – Warranty and Guarentees

Revise Clause #2 to read:

The contractor will provide a written warranty for workmanship related to installation and integration of new products with existing for a period of no less than two (2) years. Warranty shall certify the installation as weathertight without requiring additional modifications or remediation within the warranty period.

Article 2.0 – Products

Products approved as Equal to those specified are:

- 2.1.1 Primer: Mod-Bit Primer by IKO Industries Ltd.
- 2.1.2 Primer: SAM Adhesive by IKO Industries Ltd.
- 2.2.2 Adhesives: Millennium Adhesive by IKO Industries Ltd.
- 2.3.1 Roofing Membranes: Base Sheet: Roofcraft 180 base FR
- 2.3.2 base sheet flashing: Armourbond 180 Flash by IKO Industries Ltd
- 2.3.3 Cap sheet : Prevent TP 250 cap sheet by IKO Industries Ltd.
- 2.3.4 Cap sheet Flashing : Prevent TP 250 cap sheet by IKO Industries Ltd
- 2.3.5 End lap tap Tape: Modiflex Tape by IKO Industries Ltd.
- 2.3.6 Waterproofing Mastics: Aquabarrier Mastic

Drawing A-3: Details

Detail 5 – Eaves Detail POB;

Delete supply and installation of new vent grilles within the POB soffit area. Existing ventilation soffit is to remain in place. Contractor shall conduct a full review and complete any necessary remediation of products or insulation overflow within the soffit area of the POB building to ensure full ventilation area is provided without restriction.

{ END OF WRITTEN PAGES }