



Addendum / Addenda

No./N^o
1

Project Description / Description de projet U62 Re-Roofing		
Solicitation No./ No de sollicitation 14-22011	Project No./N ^o de projet 3942	W.O. No./N ^o d'ordre de travail C766-CORR
Departmental Representative / représentant ministériel MARK O'CONNOR		Date MAY 6, 2014
<p>Notice: This addendum shall form part of the tender documents and all conditions shall apply and be read in conjunction with the original plans and specifications.</p>		<p>Nota: Cet addenda fait partie intégrale des dossiers d'appel d'offres; toutes les conditions énoncées doivent être lues et appliquées en conjonction avec les plans et les devis originaux.</p>

Addendum 1 – General/Drawing revisions

General:

- A. Set-up areas will be on south side of the building.
- B. Access to interior washroom facilities will be made available.

Plumbing:

- A. Existing rain water leader on central and west drain is also to be replaced with new line down to 2nd floor level. Refer to spec Section 15 40 00 - 3.2 PIPE INSTALLATION.

Scope of Work:

- A. Building U-70 Canopy is to be added to the contract. Existing roofing is to be removed and new assembly will be as follows:

Canopy Roof Assembly:

- New 12mm cement board
- 2-ply MBM membrane
- B. Existing canopy drain is to be removed, capped and discarded.
- C. Existing rain water leader is to be removed down to main storm collector line in basement.
- D. New pre-painted galvanized metal flashing as required. Flashing to terminate up behind line of siding on west elevation.
- E. New 150x150mm eaves through and downspout is to be provided for canopy on the East side.
(Downspout to be on East side with base extending 400mm away from the building.)

End of Addendum #1