

CASCADE GARDENS BANFF, ALBERTA

CAMBRIAN POOL REHABILITATION ISSUED FOR TENDER APRIL 2014

DRAWING LIST

ARCHITECTURAL

SIMPSON ROBERTS ARCHITECTURE INTERIOR DESIGN INC.

> 1409 6th Street N.W. Calgary, Alberta T2M 3E7 Tel: (403) 265-1313 lornegsimpson@simpsonroberts.com

- **A0.0 COVER SHEET & LIST OF DRAWINGS**
- **A0.1 GENERAL NOTES**
- **A1.1 OVERALL SITE PLAN**
- A2.1 AS-FOUND PLAN
- A2.2 AS-FOUND DETAIL PLAN
- **A2.3 REHABILITATED PLAN**
- A2.4 AS-FOUND PLAN / REHABILITATED PLAN
- A3.1 ORIGINAL SEQUENCE OF CONSTRUCTION
- A3.2 ANALYSIS OF EXISTING CONSTRUCTION
- A3.3 REHABILITATION SCOPE OF WORK & DETAIL
- A3.4 AS-FOUND SECTION & REHABILITATED SECTION
- A3.5 AS-FOUND SECTION
- A4.1 THRU A4.14 AS-FOUND PHOTO REFERENCE
 - HISTORIC CONSTRUCTION PHOTO REFERENCE
- A5.2 THRU A5.9 HISTORIC PHOTO REFERENCE (2004 REPAIRS)

STRUCTURAL:

QUINN SARETSKY STRUCTURAL ENGINEERING INC.

> 89 Hounslow Dr. N.W. Calgary, Alberta T2K 2E6 Tel: (403) 543-2257 choc@quinnsaretsky.com

STRUCTURAL NOTES

ALL CONSERVATION WORK IS TO BE PERFORMED IN ACCORDANCE WITH THE STANDARDS & GUIDELINES FOR THE CONSERVATION OF HISTORIC PLACES IN CANADA



2014 APRIL

DRAWINGS

CAMBRIAN POOL

OF ASCAL EHABI ANFF,

INTENT

THE INTENT OF THIS PROJECT IS TO COMPLETE A REHABILITATION OF THE LOWER WATER BASIN & (3) ADJACENT CASCADE PONDS. IT IS INTENDED TO BE THE FIRST PHASE OF REHABILITATION OF ALL THE POOLS AND AS SUCH WILL ACT TO CONFIRM THE EXACT NATURE OF THE CONSTRUCTION OF THE EXISTING POOL STRUCTURES, AND ESTABLISH THE REPAIR PROCEDURE FOR THE FUTURE WORK. THE PROJECT GENERALLY CONSISTS OF THE FOLLOWING ELEMENTS:

- 1.) CLEANING OF STONE IN SITU.
- 2.) CAREFUL DISMANTLING OF THE STONE WALLS WITH WORK COMPLETED IN A SEQUENTIAL FASHION. STONES ARE TO BE STORED ON INDIVIDUAL PALLETS SUCH THAT THEY CAN BE RE-INSTALLED IN THE SAME LOCATION AND IN THE SAME ORDER. WORK INCLUDES ACCURATE RE-INSTALLATION OF RANDOM FLOOR STONES. NOTE: THE WALL STONES ARE TO BE RE-INSTALLED BASED ON THE ORIGINAL STONE PATTERNS REFER TO HISTORIC PHOTOS ON DRAWING A5.1
- 3.) REMOVAL OF THE POOL BASIN FLOOR
- 4.) INSTALLATION OF FREE DRAINING GRANULAR BACK FILL AND WEEPING TILE SYSTEM WITH SUMPS
- 5.) INSTALLATION OF NEW BASIN FLOOR SLAB
- 6.) REPAIR OF EXISTING CONCRETE WALLS
- 7.) INSTALLATION OF SEAMLESS WATERPROOFING MEMBRANE AND WATER TESTING
- 8.) RE-INSTALLATION OF THE STONE WALLS
- 9.) RE-INSTALLATION OF THE FLOOR STONES
- 10.) RE-FILLING THE POOL AND MONITORING OF WATER LEVELS TO VERIFY INTEGRITY OF INSTALLATION

CASH ALLOWANCES

REFER TO SPECIFICATION SECTION: 01 21 00 - ALLOWANCES

SALVAGE & ARCHAEOLOGICAL CONSIDERATIONS

SALVAGED MATERIAL WILL BE TURNED OVER TO THE OWNER FOR STORAGE AND FUTURE REUSE. MATERIALS TO BE SALVAGED AND/OR REUSED WILL BE ESTABLISHED AT THE INITIATION OF THE PROJECT WITH THE ARCHITECT. DURING EXCAVATION ANY MATERIALS UNCOVERED DURING SUCH WORK ARE TO BE RETAINED AND REVIEWED WITH THE ARCHITECT PRIOR TO DISPOSAL.

SITE SAFETY. CLEANLINESS & PERMITS

OBTAIN ALL DEMOLITION PERMITS, BUILDING PERMITS, OCCUPANCY PERMITS AND OTHER APPLICATIONS REQUIRED TO COMPLETELY EXECUTE THE WORK AT THE CONTRACTOR'S EXPENSE.

ABIDE BY ALL APPLICABLE CODES TO ENSURE THE SAFETY OF THE WORKERS, THE PUBLIC AND ADJACENT TENANTS. COMPLETE JOB HAZARDS ASSESSMENT AND REVIEW ALL CONSTRUCTION PROCEDURES AND SAFE WORK PRACTICES WITH AUTHORITIES HAVING JURISDICTION PRIOR TO PROCEEDING WITH THE WORK.

MAINTAIN THE SITE IN A TIDY CONDITION AT ALL TIMES. REMOVE WASTE MATERIAL AND DEBRIS FROM SITE AT THE END OF EACH WORK DAY. DISPOSE OF ALL WASTE AT AN APPROVED DISPOSAL SITE AND IN AN APPROVED MANNER.

HANDLE AND STORE ALL MATERIALS AND PRODUCTS IN A MANNER TO PREVENT DAMAGE, ADULTERATION, DETERIORATION AND SOILING IN ACCORDANCE WITH MANUFACTURERS INSTRUCTIONS. STORE PACKAGED MATERIALS AND PRODUCTS IN THE ORIGINAL MANUFACTURER'S PACKING WITH SEALS AND LABELS INTACT.

CONTRACTOR SHALL ASSUME RESPONSIBILITY FOR THE CARE, CUSTODY AND CONTROL OF PROPERTY WHICH IS ASSIGNED TO HIM FOR THE PERFORMANCE OF THE WORK.

CONTRACTOR SHALL ASSUME RESPONSIBILITY FOR AND SHALL MAKE GOOD DAMAGE TO EXISTING PROPERTY ATTRIBUTABLE TO PERFORMANCE OF WORK IN THIS CONTRACT.

MAINTAIN WORK IN A TIDY CONDITION, FREE FROM THE ACCUMULATION OF WASTE PRODUCTS AND DEBRIS. REMOVE WASTE MATERIAL AND DEBRIS FROM THE SITE AT THE END OF EACH WORKING DAY. CLEAN INTERIOR AREAS PRIOR TO START OF FINISHING WORK. MAINTAIN AREAS FREE OF DUST AND OTHER CONTAMINENTS DURING FINISHING OPERATIONS.

BUILDING MOVEMENT

THE TRADE SECTIONS OF THE SPECIFICATIONS HAVE REQUIREMENTS TO PROVIDE EXPANSION AND CONTROL JOINTS WITHIN RIGID MATERIALS AND AT JUNCTIONS TO ADJACENT MATERIALS. THE CONTRACTOR IS TO ENSURE THAT THE STRUCTURAL COMPONENTS ARE ABLE TO MOVE WITHIN THEIR DESIGN LIMITS WITHOUT DETRIMENTAL EFFECTS TO THE EXPOSED FINISH MATERIALS. PROVIDE EXPANSION JOINT COVERS WHERE NOTED AND SEALANT TO ALL OTHER JOINTS EXCEPT WHERE NOTED OTHERWISE.

THE CONTRACTOR IS TO REVIEW IN DETAIL THE WALL, FLOOR AND CEILING REQUIREMENTS TO ACCOMODATE MOVEMENT. ADVISE THE ARCHITECT OF ANY OMISSIONS OR DISCREPANCIES PRIOR TO PROCEEDING WITH THE WORK.

DRAWINGS. DIMENSIONS & CO-ORDINATION

THESE DRAWINGS ARE NOT TO BE SCALED.

ALL DIMENSIONS ARE TO BE VERIFIED ON SITE PRIOR TO COMMENCEMENT OF CONSTRUCTION.

ALL WORK SHALL COMPLY WITH THE 2006 ALBERTA BUILDING CODE.

THE CONTRACTOR IS TO INSPECT AND VERIFY EXISTING SITE CONDITIONS AND ADVISE THE CONSULTANT OF ANY DISCREPANCIES, OMISSIONS OR INACCURACIES PRIOR TO COMMENCEMENT OF CONSTRUCTION.

WHERE A PRODUCT OR TYPE OF CONSTRUCTION OCCURS IN THE EXISTING BUILDING AND IT IS NOT SPECIFIED AS PART OF THE NEW WORK, PROVIDE SUCH PRODUCTS OR TYPES OF CONSTRUCTION AS NEEDED TO PATCH, EXTEND OR MATCH THE EXISTING WORK.

FULLY CO-ORDINATE ALL ADDITIONAL SUPPORT REQUIRED FOR ANCHORAGE OF MECHANICAL EQUIPMENT, ACCESS PANELS, OR DUCTS AND ELECTRICAL FIXTURES.

MANUFACTURERS INSTRUCTIONS

UNLESS OTHERWISE INDICATED IN THE SPECIFICATIONS, INSTALL AND/OR ERECT PRODUCTS IN ACCORDANCE WITH THE MANUFACTURER'S INSTRUCTIONS. DO NOT RELY ON LABELS OR ENCLOSURES PROVIDED WITH THE PRODUCTS. COMMUNICATE DIRECTLY WITH THE MANUFACTURER'S REPRESENTATIVE AND CONDUCT THE WORK IN ACCORDANCE WITH HIS WRITTEN INSTRUCTION. NOTIFY THE ENGINEER OF ANY CONFLICT BETWEEN THE SPECIFICATIONS AND THE MANUFACTURER'S INSTRUCTION PRIOR TO PROCEEDING WITH THE WORK. IMPROPER INSTALLATION OR ERECTION OF PRODUCTS, DUE TO FAILURE TO COMPLY WITH THESE REQUIREMENTS, SHALL CAUSE THE REMOVAL AND RE-INSTALLATION AT NO INCREASE IN CONTRACT PRICE.

WORKMANSHIP SHALL BE BEST QUALITY, EXECUTED BY WORKERS EXPERIENCED AND SKILLED IN THEIR RESPECTIVE DUTIES FOR WHICH THEY ARE EMPLOYED. IMMEDIATELY NOTIFY THE ARCHITECT IF REQUIRED WORK IS SUCH AS TO MAKE IT IMPRACTICAL TO PRODUCE REQUIRED RESULTS.

PROJECT COMPLETION & CLOSEOUT

WHEN WORK IS COMPLETE REMOVE SURPLUS MATERIALS, TOOLS AND EQUIPMENT — REMOVE ALL WASTE AND DEBRIS FROM SITE.

INSPECT ALL WORK WITH THE CONSULTANT AND OWNER — CARRY OUT CORRECTIVE WORK FOR ALL DEFICIENCIES AS DIRECTED.

FINAL CLEANING:

- 1. LEAVE THE WORK CLEAN BEFORE INSPECTION PROCESS COMMENCES.
- 2. CLEAN AND POLISH GLASS AND METAL FINISHES.
 3. REMOVE STAINS, SPOTS, MARKS AND DIRT FROM INTERIOR GYPSUM BOARD SURFACES, ELECTRICAL AND MECHANICAL FIXTURES, EXTERIOR METALS AND EXTERIOR MASONRY.

SIMPSON ROBERTS

Date: APRIL 2014
Project No. Drawing No. A0.1

DE GARDENS - CAMBRIAN POOL ILITATION

ASCADE GARDENS EHABILITATION ANFF, ALBERTA

C R B

awing Title GENERAL I

GENERAL NOTES

- 1. THIS SET OF DRAWINGS SHOWS THE COMPLETE PROJECT. THE DRAWINGS DO NOT INCLUDE COMPONENTS THAT MAY BE NECESSARY FOR CONSTRUCTION SAFETY. THE CONTRACTOR IS RESPONSIBLE FOR SAFETY IN AND ABOUT THE JOB SITE DURING CONSTRUCTION, AND THE DESIGN AND ERECTION OF ALL TEMPORARY STRUCTURES, FORMWORK, FALSEWORK, SHORING, ETC. REQUIRED TO COMPLETE THE WORK.
- 2. THE GENERAL CONTRACTOR SHALL REVIEW THE DRAWINGS AND CHECK THE DIMENSIONS BEFORE CONSTRUCTION. REPORT DISCREPANCIES TO THE ENGINEER FOR CLARIFICATION.
- 3. STRUCTURAL DESIGN IS IN ACCORDANCE WITH THE ALBERTA BUILDING CODE 2006.

REINFORCING NOTES

- 1. REINFORCEMENT SHALL CONFORM TO THE FOLLOWING STANDARDS:
- A. C.S.A. G30.5 WELDED WIRE MESH
- B. CAN/CSA-G30.18 GRADE 400 MPa
- 2. CONCRETE COVER OVER REINFORCEMENT SHALL BE:
- A. SURFACE IN CONTACT WITH GROUND 3"
- B. FORMED SURFACES EXPOSED TO EARTH OR WEATHER 2"
- 3. DO NOT SUBSTITUTE DEFORMED WIRE FOR REINFORCING BARS WITHOUT PRIOR APPROVAL FROM THE ENGINEER.
- 4. REINFORCING BARS, STIRRUPS AND TIES SHALL BE BILLET STEEL CONFORMING TO CAN/CSA G30.18, 400 MPa.
- 5. REINFORCING STEEL SHALL BE CUT, BENT, SPLICED, PLACED AND HANDLED IN ACCORDANCE WITH THE RECOMMENDATIONS OF CODE FOR DESIGN OF CONCRETE STRUCTURES FOR BUILDINGS (A23.3) AND THE MANUAL OF STANDARD PRACTICE FOR DETAILING REINFORCEMENT OF CONCRETE STRUCTURES (ACI-315).
- 6. REINFORCING STEEL SHALL BE FREE FROM LOOSE, FLAKY RUST, MUD, OIL OR OTHER COATINGS WHICH MAY REDUCE BOND.

CONCRETE NOTES

SPECIFICATION

- 1. CEMENT SHALL BE PORTLAND CEMENT TYPE 50 U.N.O. CONCRETE SHALL BE STONE CONCRETE WITH A UNIT WEIGHT OF 150 pcf.
- 2. CONCRETE PROPERTIES:

MIN. 56 DAY SLUMP MAX. AGG. **EXPOSURE** SIZE (mm) ELEMENT STRENGTH (MPa) (mm) CLASS

SLAB 32 MPa 75mm 20mm S-2* * - CEMENTING MATERIAL: Hs OR HSb

- MAXIMUM WATER TO CEMENT RATIO: 0.45

NOTES:

- PUMP MIXES ALSO AS ABOVE
- WATER CEMENT RATIOS FOR EXPOSURE CLASSES AS TABLE 2, CAN/CSA-23.1.
- AIR CONTENT FOR EXPOSURE CLASSES AND AGGREGATE SIZE AS TABLE 4 CAN/CSA-23.1.
- SLUMP TOLERANCE 3/4" FOR SLUMPS 3" OR LESS, OTHERWISE 1-1/2".
- AGGREGATE SIZÉS SHOWN ARE MAXIMUMS. SMALLER SIZES MAY BE USED.
- LOWER SLUMPS MAY BE USED SUBJECT TO APPROVAL.
- MIX DESIGNS SHALL STATE THE ELEMENT FOR WHICH THEY ARE INTENDED.
- 3. NO CALCIUM CHLORIDE, IN ANY FORM, IS PERMITTED IN ANY CONCRETE MIX.
- 4. DO NOT USE ADMIXTURES OTHER THAN AIR ENTRAINMENT, STANDARD WATER REDUCERS. OR SUPER PLASTICIZERS WITHOUT PRIOR APPROVAL OF THE ENGINEER.
- 5. REJECT ALL CONCRETE WHEN TIME BETWEEN BATCHING AND PLACING EXCEEDS 2 HRS.
- 6. DO NOT ADD WATER TO THE CONCRETE ON SITE UNLESS AUTHORIZED BY THE ENGINEER.
- 7. CONSOLIDATE ALL CONCRETE USING MECHANICAL VIBRATORS.
- 8. INSTALL CONSTRUCTION JOINTS AS SHOWN ON THE DRAWINGS OR AS DIRECTED BY THE ENGINEER.
- 9. PROTECT CONCRETE FROM ADVERSE WEATHER CONDITIONS IN ACCORDANCE WITH CSA A23.1 OR AS DETERMINED BY THE ENGINEER.
- 10. CONSTRUCT FORMWORK IN ACCORDANCE WITH WCB REGULATIONS AND CSA S269.3. FORMWORK DESIGN IS THE RESPONSIBILITY OF THE CONTRACTOR.

FIELD REVIEW BY QUINN SARETSKY STRUCTURAL ENGINEERS INC.

QUINN SARETSKY STRUCTURAL ENGINEERS INC. PROVIDES REVIEW ONLY FOR THE WORK SHOWN ON THESE DRAWINGS. THIS REVIEW IS NOT A "FULL TIME" REVIEW, BUT RATHER A PERIODIC REVIEW TO ASCERTAIN THAT THE WORK IS IN GENERAL CONFORMANCE WITH THE PLANS AND SUPPORTING DOCUMENTS PREPARED BY QUINN SARETSKY STRUCTURAL ENGINEERS INC., FIELD REVIEW BY QUINN SARETSKY STRUCTURAL ENGINEERS INC. DOES NOT MAKE US GUARANTORS OF THE CONTRACTOR'S WORK. IT REMAINS THE CONTRACTOR'S RESPONSIBILITY TO CONSTRUCT THE WORK IN CONFORMANCE WITH THE CONTRACT DOCUMENTS.

COLD WEATHER REQUIREMENTS

IN COLD WEATHER, ALL HEATING EQUIPMENT AND PROTECTIVE ENCLOSURES SHALL BE ON THE JOB READY FOR USE WHEN CONCRETE IS PLACED. SUCH EQUIPMENT SHALL BE ADEQUATE FOR THE PURPOSE OF HEATING THE CONCRETE MATERIALS AND PROTECTING THE CONCRETE IN ACCORDANCE WITH CSA A23.1, 2, & 3 AND THE FOLLOWING REQUIREMENTS:

- 1. WHENEVER THE TEMPERATURE OF THE SURROUNDING ATMOSPHERE IS 5 DEG C OR LOWER, OR THERE IS A PROBABILITY OF IT FALLING BELOW 5 DEG C. ALL AGGREGATES AND WATER SHALL BE PRE-HEATED AND ALL FORMS, FILL AND GROUND WITH WHICH THE CONCRETE IS IN CONTACT OR IS CALCULATED TO COME IN CONTACT WITH, SHALL BE DEFROSTED. STEEL REINFORCEMENT AND AGGREGATES SHALL BE PROTECTED BY ADEQUATE MEANS TO PREVENT FORMATION OF AN ICE FILM.
- 2. ALL CONCRETE WHEN PLACED IN THE FORMS SHALL HAVE A TEMPERATURE BETWEEN 16 DEG C AND 27 DEG C AND ADEQUATE MEANS SHALL BE PROVIDED BY ENCLOSURES AND HEATING APPURTENANCES FOR MAINTAINING A TEMPERATURE OF AT LEAST 22 DEG C FOR THE FIRST SEVEN DAYS AND AT LEAST 10 DEG C FOR AS MUCH MORE TIME AS MAY BE NECESSARY TO ENSURE THE PROPER CURING OF THE CONCRETE.
- 3. ALL CANVAS OR OTHER PROTECTIVE COVERING SHALL BE KEPT CLEAR OF ALL CONCRETE IN ORDER TO PERMIT FREE CIRCULATION OF AIR AROUND ALL WALLS, COLUMNS. AND OVER THE TOPS OF ALL SLABS.



Calgary, Alberta PH: (403) 543-2257 FAX: 271-5904 Permit No. P7453


SIMPSOI


2014 n/a APRIL 670 Ň

POOL **CAMBRIAN** S GARDEN TATION BERTA Ш ۵

ASCA EHAB ANFF,

rawing Title STRU(C) AC B






SIMPSON ROBERTS APPRIENCE INTERIOR DESIGN INC.

CASCADE GARDENS - CAMBRIAN POOL REHABILITATION BANFF, ALBERTA

PLAN







E GARDENS - CAMBRIAN POOL ITATION ILBERTA

19 Title 5-FOUND DETAIL PLAN

REHABILITA
BANFF, ALB






Date: 1/8" = 1'-0"

Date: APRIL 2014

Project No. Drawing No.


2670 A2.3



APRIL 2014

S-FOUND / REHAB. PLAN POOL


CAMBRIAN POOL GARDENS -ITATION LEBERTA



2014 **APRIL**

> CONSTRUCTION **OF** EQUENCE

CASCA REHAE BANFF




2 2014 APRIL 3/4"

> CONSTRUCTION **EXISTING**

NDE GARDENS -SILITATION F, ALBERTA CASCAI REHABI BANFF,


POOL

CAMBRIAN



REHABILITATION SCOPE OF WORK

- CLEAN STONE IN SITU
- LABEL & REMOVE WALL VENEER STONES IN "COLUMNS", STORE IN NUMBERED PALLETS
- 3. REMOVE & STOCKPILE ORGANIC MATERAL FROM POOL BOTTOM; LOCATE, LABEL & STORE LARGE FEATURE STONES
- 4. REMOVE PLASTIC LINER & SAND BED FROM POOL BOTTOM. EXCAVATE FOR NEW SLAB SUB-BASE
- 5. CLEAN CONCRETE WALLS TO EXPOSE: i) DELAMINATION - CORROSION OF REINFORCING ii) HONEYCOMB IN ORIGINAL iii) CRACK
 - ORIGINAL COLD JOINTS
 - MOVEMENT: THERMAL & LOADS
 - TREE ROOTS
- 6. CORE SAMPLES AT WALLS (4) LOCATIONS TO BE DETERMINED BY STRUCTURAL ENGINEER
- 7. AS-FOUND MAPPING / CONDITION OF CONCRETE WALLS (BY CONSERVATION ARCHITECT)
- 8. PREPARE EXISTING CONCRETE FOR LOCAL REPAIRS:
 - MUST GET DOWN TO SOLID CONCRETE; REMOVE DETERIORATED MATERIAL
 - HAND GRINDERS (NO LARGE EQUIPMENT)
- REPAIR CONCRETE WITH COMPATIBLE CEMENTITIOUS MATERIAL
- 10. INSTALL NEW COMPACTED SUB-BASE AND CONCRETE SLAB
- 11 INSTALL FULLY BONDED MEMBRANE (REVERSIBLE AT WALLS)
- 12. FLOOD TEST
- 13. INSTALL PROTECTION LAYER ON SLAB
- 14. REPLACE STONES FROM NUMBERED PALLETS; REPLACE GROUND LAYER FILL & FEATURE STONES ON SLAB




2014 APRIL П 3/4"

DETAIL

POOL

CAMBRIAN


DE GARDENS -ILITATION , ALBERTA ASC/ EHAI ANFI



SIMPSON

2670

AS-FOUND SECTION & REHABILITATED SECTION



NOTE: THIS SECTION DRAWING IS ILLUSTRATIVE AND INTENDED TO CONVEY THE RELATIVE RELATIONSHIP OF WALL HEIGHTS AND WATER LEVELS ONLY

APRIL 2014 **AS NOTED**


AS-FOUND SECTION

POOLS

CASCADE GARDENS - CAMBRIAN POOL REHABILITATION BANFF, ALBERTA

Drawing Title SOUTH











PHOTO #3





0		2	4	6	8	10	12	2 feet
SCALE 3/8"	= 1'-0)"	 	 <u> </u>	 _ <u>ī</u> _	 		

2670 AS-FOUND PHOTO REFERENCE

1.0.1

3/8" =

APRIL 2014



PHOTO #5




PHOTO #7




PHOTO #6




PHOTO #8

0		2	4		6		8		10	12 feet	
ահահահահ	1			1		1		1			
SCALE 3/8" =	= 1'-0	••									

3/ 8 .	3/8" = 1'-0"±
Date: API	APRIL 2014
 Project No.	Drawing No.
2670	A4.2




PHOTO #9




PHOTO #11




PHOTO #10




PHOTO #12

0		2	4	6	8	10	12 feet	
ահանակա		1	1					
SCALE 3/8	' = 1'-0)**						

ARCHI	A4.3	2670
	Drawing No.	Project No.
	APRIL 2014	Date: API
	3/8" = 1'-0"±	SCALE: 3/8'




PHOTO #13




PHOTO #15




PHOTO #14




PHOTO #16

0		2		4		6		8	10	12 feet	
ահահահահ			1		1	1	1		1		
SCALE 3/8"	= 1'-0)''									

A4.4	2670
Drawing No.	roject No. D
APRIL 2014	Date: APR
3/8" = 1'-0"±	SCALE: 3/8"




PHOTO #17



PHOTO #19




PHOTO #18




PHOTO #20

	0		2	4	6	8	10	12 feet
بيلينا	lulul	1					1	
SCALE	3/8" =	1'-0"	,					

SCALE:	3/8"	3/8" = 1'-0"±	
Date:	APRIL	ZIL 2014	
Project No.	رة. الأه	Drawing No.	
2670	20	A4.5	
			ARCH

SIMPSON ROBERTS

AS-FOUND PHOTO REFERENCE




PHOTO #21




PHOTO #23




PHOTO #22





PHOTO #24

0		2	4		6		8	10	12 feet	
ահահահահ		1		1	1	1				
SCALE 3/8"	= 1'-0)"								

3/8" = 1'-0"±	Date: APRIL 2014 SIMPSON	Project No. Drawing No.	2670 A4.6 Manual Control Interior Design
---------------	--------------------------	-------------------------	---






PHOTO #27




PHOTO #26



PHOTO #28


0 2 4 6 8 10 12 feet

SCALE 3/8" = 1'-0"


S - CAMBRIAN POOL		
CASCADE GARDENS -	REHABILITATION	BANFF, ALBERTA

1.-0.'±

APRIL 2014



FOUND PHOTO REFERENCE









PHOTO #35



CASCADE GARDENS - CAMBRIAN POOL REHABILITATION BANFF, ALBERTA

FOUND PHOTO REFERENCE


9

2670

1.0.1


3/8" =

APRIL 2014



1.0.1 **APRIL 2014** 3/8" = 2670

FOUND PHOTO REFERENCE




2670 CASCADE POOL S3 - AS-FOUND PHOTO REF.

APRIL 2014

AS NOTED

Drawing Title SOUTH



CASCADE GARDENS - CAMBRIAN POOL REHABILITATION BANFF, ALBERTA

S3C

CASCADE POOL


S3 - AS-FOUND PHOTO REF.

2

2670

APRIL 2014
Drawing No.

AS NOTED




APRIL 2014 **AS NOTED**

2670

- AS-FOUND PHOTO REF. CASCADE POOL S4

CASCADE GARDENS - CAMBRIAN POOL REHABILITATION BANFF, ALBERTA

Drawing Title SOUTH







PHOTO #C13

PHOTO #C14



CASCADE GARDENS - CAMBRIAN POOL REHABILITATION BANFF, ALBERTA

APRIL 2014
Drawing No.

2670

AS NOTED

SCALE:

CASCADE POOL S4 - AS-FOUND PHOTO REF. Drawing Title SOUTH




PHOTO #HI - NOVEMBER 1934



PHOTO #H3 - AUGUST 1935



PHOTO #H2 - NOVEMBER 1934




PHOTO #H4 - JUNE 1936

SIMPSON ROBERTS

Date: APRIL 2014
Project No. Drawing No.

CONSTRUCTION PHOTO REFERENCE

CAMBRIAN POOL

Drawing little




PHOTO #EI
RECORDING PRIOR TO REPAIRS



PHOTO #E3
RECORDING PRIOR TO REPAIRS



PHOTO #E2
RECORDING PRIOR TO REPAIRS



PHOTO #E4
RECORDING PRIOR TO REPAIRS

SIMPSON ROBERTS

te: APRIL 2014
oject No. Drawing No.

RIC PHOTO REFERENCE (2004 REPAIRS)

CAMBRIAN POOL

GARDENS - (FATION BERTA

Drawing Titl



PHOTO #E5
REMOVAL OF STONES IN PROGRESS



PHOTO #E7
REMOVAL OF STONES IN PROGRESS



PHOTO #E6
REMOVAL OF STONES IN PROGRESS



PHOTO #E8
REMOVAL OF STONES IN PROGRESS

APRIL 201 Ë

(2004 REPAIRS)



PHOTO #E9
ORIGINAL CONCRETE WALLS AND SLAB EXPOSED



PHOTO #EII
ORIGINAL CONCRETE WALLS AND SLAB EXPOSED



PHOTO #E10
ORIGINAL CONCRETE WALLS AND SLAB EXPOSED



PHOTO #E12
ORIGINAL CONCRETE WALLS AND SLAB EXPOSED

APRIL 20 Ë

(2004 REPAIRS)




PHOTO #E13
CONC. WALLS REPAIRED & SAND BASE INSTALLED OVER SLAB



PHOTO #E15
NEW CONCRETE WALL & DRAIN PIPE AT CASCADE#I



PHOTO #E14 CONC. WALLS REPAIRED & SAND BASE INSTALLED OVER SLAB



PHOTO #E16
NEW CONCRETE WALL & DRAIN PIPE AT CASCADE #2

SIMPSON ROBERTS

Date: APRIL 2014
Project No. Drawing No.

e ORIC PHOTO REFERENCE (2004 REPAIRS)

CAMBRIAN POOL

BANFE

Drawing Title



PHOTO #E17
INSTALLATION OF ANCHORS & DRY-FIT OF PLASTIC CLAMPING CHANNEL



PHOTO #E19
INSTALLATION OF LINER MEMBRANE



PHOTO #E18
INSTALLATION OF ANCHORS & DRY-FIT OF PLASTIC CLAMPING CHANNEL



PHOTO #E20 INSTALLATION OF LINER MEMBRANE

20 APRIL ⊢ Z

2004 REPAIRS)



PHOTO #E21
INSTALLATION OF LINER MEMBRANE



PHOTO #E23
INSTALLATION OF LINER MEMBRANE



PHOTO #E22
INSTALLATION OF LINER MEMBRANE



PHOTO #E24
INSTALLATION OF LINER MEMBRANE

APRIL 201 N.T.S.

> (2004 REPAIRS) REFERENCE



PHOTO #E25
INSTALLATION OF SAND BALLAST, FILTER FABRIC & PLASTIC CLAMPING CHANNEL



PHOTO #E27
INSTALLATION OF LINER AT CASCADE #I



PHOTO #E26
INSTALLATION OF LINER AT OVERFLOW PIPE



PHOTO #E28
INSTALLATION OF LINER AT CASCADE #2

APRIL 201 N.T.S.

(2004 REPAIRS)




PHOTO #E29 STONES REPLACED IN POOL



PHOTO #E31 STONES REPLACED AT CASCADE #I



PHOTO #E30 STONES REPLACED IN POOL



PHOTO #E32 STONES REPLACED AT CASCADE #2

APRIL 201 N.T.S.

> (2004 REPAIRS) REFERENCE GARDENS - (FATION BERTA

Appendix B Design Details Cambrian Pool and 3 Cascade Feeder Pools