

PART 1 - GENERAL

- |                                       |    |   |
|---------------------------------------|----|---|
| <u>1.1 Precedence</u>                 | .1 | For Federal Government projects, Division 1 Sections take precedence over technical specification sections in other Divisions of this Project Manual. |
| <u>1.2 Related Sections</u>           | .1 | Construction Facilities: Section 01 52 00   |
| <u>1.3 References</u>                 | .1 | Canadian General Standards Board (CGSB)<br>.1 CGSB 1.189M-84, Primer, Alkyd, Wood, Exterior.<br>.2 CGSB 1.59-97, Alkyd Exterior Gloss Enamel.         |
|                                       | .2 | Canadian Standards Association (CSA International)<br>.1 CSA-O121-08(R2013), Douglas Fir Plywood.   |
| <u>1.4 Installation and Removal</u>   | .1 | Provide temporary controls in order to execute Work expeditiously.  |
|                                       | .2 | Remove from site all such work after use.   |
| <u>1.5 Guard Rails and Barricades</u> | .1 | Provide secure, rigid guard rails and barricades around deep excavations, open shafts, open stair wells, open edges of floors and roofs.              |
|                                       | .2 | Provide as required by governing authorities.   |
| <u>1.6 Access to Site</u>             | .1 | Provide and maintain access roads, as may be required for access to Work.   |
| <u>1.7 Public Traffic Flow</u>        | .1 | Provide Traffic Control in accordance with Section 01 55 26.  |
| <u>1.8 Fire Routes</u>                | .1 | Maintain access to property including overhead clearances for use by emergency response vehicles.   |
-

PWGSC	Temporary Barriers	Section 01 56 00
Gros Morne National Park	and Enclosures	Page 2
Highway 430 Realignment, Deep Cove		
Project NO. R.062334.001		2014-02-10

- |  |    |  |
|--|----|--|
| <u>1.9 Protection<br/>for Off-Site and<br/>Public Property</u> | .1 | Protect surrounding private and public property from damage during performance of Work.            |
|  | .2 | Be responsible for damage incurred.  |
| <u>1.10 Construction<br/>Site Security Fence</u>               | .1 | Provide continuous 1.8 meter high chain link fence maintain around construction site as indicated. |
|  | .2 | Install/maintain lockable gates as required.   |