

PWGSC	General Instructions	Section 01 10 10
Gros Morne National Park		Page 1
Highway 430 Realignment, Deep Cove		
Project NO. R.062334.001		2014-02-10

PART 1 - GENERAL

- | | | |
|--------------------------------|----|---|
| <u>1.1 Description of Work</u> | .1 | The work will be carried out along Highway 430, Deep Cove within the boundaries of the Gros Morne National Park. |
| | .2 | PWGSC will have a Departmental Representative, available to work collaboratively and jointly with the Contractor to determine field quantities. |
| | .3 | <p>The work of this contract includes the provision of all materials, labour, equipment, and ancillaries, all as necessary for the completion of the work as indicated on the drawings and as described in the specifications and notes. Work on this project consists generally of, but not limited to, the following:</p> <p>.1 Excavation of all materials including rock, blasting where required. Rock will be transported to Rocky Barachois for processing. Transportation of all rock will be completed seven (7) weeks after contract award.</p> <p>.2 Rock bolting as directed by the Departmental Representative.</p> <p>.3 Ditching in locations as directed by Departmental Representative.</p> <p>.4 Clearing and grubbing in locations as directed by Departmental Representative.</p> <p>.5 Removal of old culverts, supply and install new culverts as shown on the drawings.</p> <p>.6 Rock breaking and crushing of base and subbase gravels from excavated material and stockpiling at Rocky Barachois; transportation to the Site.</p> <p>.7 Supply and install all environmental protection measures required, such as silt fences, diversion ditches and check dams and removal upon completion of project.</p> <p>.8 Supply and install rip rap headwalls as shown on the Project Drawings and as directed by the Departmental Representative.</p> <p>.9 Supply and installation of energy dissipation pool.</p> <p>.10 Supply, place and compact asphalt as shown on drawings.</p> <p>.11 Supply, place and compact new granular base, sub-base and rock fill up to underside of asphalt as shown on drawings.</p> |

- .12 Supply all necessary road signs, message boards, guiderails and traffic control.
- .13 Line Painting.
- .14 Excavation and removal of old guide rail and posts, replacement with new guider rail complete with posts and all associated hardware.
- .15 All other labour, materials and work necessary to complete the project to the Departmental Representative's full satisfaction.

- .4 Carry out all work in accordance with applicable federal and provincial regulations for those agencies having jurisdiction for the work. The work is subject to the National Park Act and Regulations, Canadian Environmental Protection Act, Canada Labour Code and the NL Occupational Health and Safety Act and Regulations.
- .5 Be advised that other construction work may be being performed by others at several different locations during the time frame of this contract.
- .6 Maintain work during construction. Undertake continuous and effective maintenance work day by day, with adequate equipment and forces so that the work is continuously kept in a condition satisfactory to Departmental Representative.

1.2 Familiarization With Site

- .1 Before submitting a bid, it is recommended that bidders visit the site to review and verify the form, nature and extent of the work, materials needed, the means of access and the temporary facilities required to perform the Work.
- .2 Obtain prior permission from the Departmental Representative before carrying out such site inspection.

1.3 Codes and Standards

- .1 Perform work in accordance with the latest versions of the National Building Code of Canada and any other code of provincial or local application, including all amendments up to bid closing date, provided that in any case of conflict or discrepancy, the more stringent requirement shall apply.

PWGSC	General Instructions	Section 01 10 10
Gros Morne National Park		Page 3
Highway 430 Realignment, Deep Cove		
Project NO. R.062334.001		2014-02-10

	.2	Materials and workmanship must meet or exceed requirements of specified standards, codes and referenced documents.
<u>1.4 Interpretation of Documents</u>	.1	Supplementary to the Order of Precedence article of the General Conditions of the Contract, the Division 01 sections take precedence over the technical specification sections in other Divisions of the Specification Manual.
<u>1.5 Setting Out Work</u>	.1	Set out the Work. Execute complete layout of work to locations, lines and elevations indicated.
	.2	Supply such devices as straight edges and templates required to facilitate Departmental Representative's inspection of work.
<u>1.6 Maintenance of Work During Construction</u>	.1	Maintain work during construction. Undertake continuous and effective maintenance work day by day, with adequate equipment and forces so that the roadway or structures are continuously kept in a condition satisfactory to Departmental Representative.
<u>1.7 Codes</u>	.1	Perform work in accordance with National Parks Act, Code of Practice of the Department of Labour, as it pertains to the Temporary Workplace Traffic Control Manual (Department of Transportation & Works) and any other code of federal, provincial or local application provided that in any case of conflict or discrepancy, the more stringent requirements shall apply.
	.2	Materials and workmanship must conform to or exceed applicable standards of Canadian General Standards Board (CGSB), Canadian Standards Association (CSA), American Society for Testing and Materials (ASTM) and other standards organizations.
	.3	Conform to latest revision of any referenced standard as re-affirmed or revised to date of specification. Standards or codes not dated shall be deemed editions in force on date of tender advertisement.

- 1.8 Work Within Park Boundaries
- .1 The project is within a national park and it is essential that lands remain as undisturbed as possible. Use standards and methods beyond those for normal construction in order to protect the environment and ensure the aesthetics of the work. Strictly adhere to contract limits and take every precaution to minimize environmental damage and disruption to vegetation, wildlife habitat, and structures or existing services, both on construction and storage sites.
- .1 If any damage occurs during construction, the Contractor is responsible to bear the expense to immediately restore such damaged areas to the satisfaction of the Departmental Representative.
- .2 If Contractor fails to repair damage to the satisfaction of the Departmental Representative, the Departmental Representative may have repairs completed by others at the Contractor's expense.
- .3 Perform work that meets the standards outlined in the contract specification and drawings.
- .4 Do no damage to any existing underground telephone cables.
- .5 Submit all sources of aggregate and asphalt cement to the Departmental Representative for approval at least two weeks prior to the start of any work.
- .6 Follow the Provincial requirements regarding the following:
- .1 Pit and Quarry Guidelines
- .2 Environmental Construction Practice specifications
- .7 Make arrangements with authorities or owners of private properties for quarrying and transporting materials and machinery over their properties and be responsible for obtaining and paying of fees.
- 1.9 Documents Required
- .1 Maintain at job site, one copy each of following:
- .1 Contract drawings.
- .2 Specifications.
- .3 Addenda.
- .4 Reviewed drawings.
- .5 Change orders.
- .6 Other modifications to Contract.
- .7 Health and Safety Plan.
- .8 Environmental Protection Plan (EPP)
-

.9 Copy of approved work schedule.

- | | | |
|-------------------------------|----|--|
| <u>1.10 Site Conditions</u> | .1 | Visit the roadway and review existing site conditions. |
| <u>1.11 Work Schedule</u> | .1 | Provide to the Departmental Representative in writing and within five (5) working days after Contract award, a detailed construction schedule and traffic control plan. Schedule to show proposed work to be undertaken and anticipated completion dates for each category of work in the Unit Price Table. |
| | .2 | After receiving the Contractor's plan and prior to start of construction, a meeting involving Contractor, Departmental Representative and Parks Canada will be held at a place and time to be determined by the Departmental Representative. This meeting will review implications of the contract, design, schedule of work, methods of construction, environment protection methods and traffic control. |
| | .3 | Interim reviews of work progress based on work schedule will be conducted as decided by Departmental Representative and schedule updated by Contractor in conjunction with and to approval of Departmental Representative. |
| | .4 | No work will begin until the pre-construction meeting is held, and the environmental protection plan and health and safety hazard assessment have both been approved. |
| | .5 | Following the pre-construction meeting and approval of the schedule and traffic control plan, the work will be carried out to meet the time restraints and have the project completed on time. |
| <u>1.12 Sanitary Services</u> | .1 | Provide and maintain sanitary facilities for the use of workers at locations specified by the Departmental Representative. Provision of sanitary facilities must meet requirements of provincial government and municipal statutes and authorities. |

- | | | |
|---|----|---|
| 1.13 Contractor's
<u>Use of Site</u> | .1 | Use of site: for execution of work within roadway right of way and those areas specified by the Departmental Representative. |
| | .2 | The Departmental Representative will specify the areas for work and storage. |
| 1.14 Project
<u>Meetings</u> | .1 | Departmental Representative will arrange and set times for project meetings. |
| | .2 | The Owner shall make available, with adequate notice, meeting facilities for regular project meetings. Otherwise, project meetings will take place on site of work, in the project site office. |
| | .3 | Departmental Representative will assume responsibility for recording minutes of meetings and forwarding copies to all parties present at the meetings. |
| | .4 | The contractor will have the required responsible member(s) of firm present at all project meetings. |
| 1.15 Cutting &
<u>Patching</u> | .1 | Cut and patch as required to make work fit. |
| | .2 | Where new work connects with existing and where existing work is altered, cut, patch and make good to match existing work. |
| 1.16 Existing
<u>Services</u> | .1 | Carry out work at times directed by authorities having jurisdiction, with minimum of disturbance to pedestrian and vehicular traffic. |
| | .2 | Before commencing work, establish location and extent of service lines in area of work and notify Departmental Representative of findings. |
| | .3 | Submit schedule to and obtain approval from Departmental Representative for any shut down or closure of active service or facility. Adhere to approved schedule and provide notice to affected parties. |
-

- .4 Where unknown services are encountered, immediately advise Departmental Representative and confirm findings in writing.
- .5 Record locations of maintained, re-routed and abandoned service lines.
- .6 Maintain a two (2) lane detour for traffic at the construction sites at all times.
- .7 Ensure pedestrian and other traffic is not unduly impeded, interrupted or endangered by execution or existence of work or plant.
- .8 Maintain existing signs at all times. When it is necessary to temporarily remove a sign, dismantle it and re-establish on a temporary post or stand set back from construction area. This work is considered to be incidental and no separate payment will be made for maintaining or moving signs.
- .9 Verify locations of any underground utilities.

1.17 Additional Drawings

- .1 Departmental Representative may furnish additional drawings for clarification. These additional drawings have same meaning and intent as if they were included with plans referred to in Contract documents.

1.18 Relics, Antiques and Wildlife Habitat

- .1 Protect relics, antiquities, wildlife habitat, items of historical or scientific interest such as cornerstones and contents, animal nesting sites, commemorative plaques, inscribed tablets, and similar objects found during course of work.
- .2 Give immediate notice to Departmental Representative and await Departmental Representative's written instructions before proceeding with work in this area.
- .3 Relics, antiquities and items of historical or scientific interest remain her Majesty's property.

1.19 National Park Act

- .1 For projects within boundaries of National Park, perform work in accordance with National Parks Act.

- 1.20 Permits/
Authorities
- .1 Obtain and pay for permits from authorities as required for all operations and construction. Comply with all pertinent regulations of all authorities having jurisdiction over the work. Provide copies of all permits to the Departmental Representative prior to starting the work. Obtain all applicable permits, inspections and approvals required and pay all changes in connection therewith.