

PART 1 - GENERAL

- 1.1 DESCRIPTION
- .1 This section specifies requirements for demolishing and removing wholly or in part various items designated to be removed or partially removed.
 - .2 Demolition and removal will consist of, but not necessarily be limited to, the following:
 - .1 Demolition, removal, and disposal of treated dimension timber wheelguard, wheelguard blocking and associated hardware.
 - .2 Demolition, removal, and disposal of treated or untreated dimension hardwood timber fenders and associated hardware.
 - .3 Demolition, removal, and disposal of treated or untreated ladders, ladder handgrips, mooring rings and associated.
 - .4 Removal on the existing cleats, storage and then the reinstallation of them back in the same location.
- 1.2 GENERAL REQUIREMENTS
- .1 A Notice to Shipping is to be issued prior to commencement and upon completion of work. Notify the Marine Communications and Traffic Services' Centre, of Fisheries and Oceans Canada, at (709) 772-2083, ten (10) days prior to commencement and upon completion of the work, in order to allow for the issuance of Notices to Shipping/Mariners.
 - .2 During construction, any vessels or barges utilized must be marked in accordance with the provisions of the Canada Shipping Act Collision Regulations.
 - .3 Upon completion of the project, a written Notice to Mariners must be issued.
-

PWGSC
P/N R.069811.001
BREAKWATER REPAIRS
BLUE BEACH,NL

SITWORK, DEMOLITION
AND REMOVAL

Section 02 41 16
Page 2
MAY 2014

1.3 PROTECTION

- .1 Protect existing objects designated to remain. In event of damage, immediately replace or make repairs to approval of and at no additional cost to Canada.
- .2 Place a floating boom around entire demolition site to prevent loss of any materials.
- .3 Remove all floating debris from water on a routine and timely basis.

1.4 MEASUREMENT
FOR PAYMENT

- .1 No separate payment will be made for this item. Include costs incidental to the unit price for item in which demolition and removal is required.

PART 2 - PRODUCTS

NOT APPLICABLE

PART 3 - EXECUTION

3.1 EXECUTION

- .1 Inspect site and verify with Departmental Representative objects designated for removal.
- .2 Locate and protect utility lines. Preserve in operating condition active utilities traversing site.

3.2 REMOVAL

- .1 Remove in their entirety all materials and objects specified for removal.
 - .2 Do not disturb adjacent work designated to remain in place.
-

- 3.3 DISPOSAL OF MATERIAL
- .1 All demolished materials, except materials designated to be reused, will become property of contractor and will be removed from site and disposed of to satisfaction of Departmental Representative and in accordance with environmental guidelines. It is the sole responsibility of the contractor to dispose of all demolished materials at an approved disposal site. Ensure that disposal site is approved and willing to accommodate any materials disposed of from work site.
 - .2 Contractor shall obtain and pay for all necessary permits and disposal fees for use of an approved waste disposal site.
- 3.4 RESTORATION
- .1 Upon completion of work, remove debris, trim surfaces and leave work site in clean condition.
 - .2 Reinstate areas and existing works outside areas of demolition to conditions that existed prior to commencement of work.