

**Part 1            General**

**1.1                RELATED RE QUIREMENTS**

- .1    Section 01 33 00 Shop Drawings, Product Data and Samples
- .2    Section 01 45 00 Quality Control
- .3    Section 08 34 58.01 Vaults Doors and Frames
- .4    Section 31 23 33.01 Excavating, Trenching and Backfilling

**1.2                REFERENCES**

- .1    American Society for Testing and Materials International (ASTM)
  - .1    ASTM A82/A82M-05a, Standard Specification for Steel Wire, Plain, for Concrete Reinforcement.
  - .2    ASTM A185/A185M-05a, Standard Specification for Steel Welded Wire Reinforcement, Plain, for Concrete.
  - .3    ASTM C139-05, Standard Specification for Concrete Masonry Units for Construction of Catch Basins and Manholes.
  - .4    ASTM C 478/C478M-06, Standard Specification for Precast Reinforced Concrete Manhole Sections.
  - .5    ASTM D1056-00, Standard Specification for Flexible Cellular Materials - Sponge or Expanded Rubber.
  - .6    ASTM D3034, Standard Specification for Type PSM Poly(Vinyl Chloride) (PVC) Sewer and Pipe Fittings.
- .2    Canadian Standards Association (CSA International)
  - .1    CSA B196.3-M.983, PVC Underground Telecommunication Cable Ducting and Fittings
  - .2    CAN/CSA-A3000-03(R2005), Cementitious Materials Compendium (Consists of A3001, A3002, A3003, A3004 and A3005).
    - .1    CSA-A3001-03, Cementitious Materials for Use in Concrete.
  - .3    CSA A23.1/A23.2-04, Concrete Materials and Methods of Concrete Construction/Methods of Test and Standard Practices for Concrete.
  - .4    CSA A23.4-09, Precast Concrete – Materials and Construction
  - .5    CAN/CSA-G30.18-M92(R2002), Billet-Steel Bars for Concrete Reinforcement.
- .3    Health Canada/Workplace Hazardous Materials Information System (WHMIS)
  - .1    Material Safety Data Sheets (MSDS).

**1.3                ACTION AND INFORMATIONAL SUBMITTALS**

- .1    Provide submittals in accordance with Section 01 33 00 – Shop Drawings, Product Data and Samples.
  - .2    Product Data:
    - .1    Submit manufacturer's printed product literature, specifications and datasheet and include product characteristics, performance criteria, physical size, finish and limitations.
  - .3    Shop Drawings:
-

- .1 Submit shop drawings for precast vault.
- .4 Quality assurance submittals: submit following in accordance with Section 01 45 00 Quality Control.
  - .1 Test reports: submit certified test reports for specified materials from approved independent testing laboratories, indicating compliance with specifications for specified performance characteristics and physical properties.
  - .2 Certificates: submit certificates signed by manufacturer certifying that materials comply with specified performance characteristics and physical properties.
- .5 Manufacturer's Instructions: submit manufacturer's installation instructions and special handling criteria, installation sequence, cleaning procedures.

**1.4 DELIVERY, STORAGE AND HANDLING**

- .1 Packing, shipping, handling and unloading:
  - .1 Deliver, store and handle materials in accordance with manufacturer's written instructions.

**Part 2 Products**

**2.1 PRECAST CONCRETE VAULTS**

- .1 Precast Concrete, H20 Traffic Loading.
- .2 Precast Concrete: to CSA A23.4-09.
  - .1 Precast concrete manholes, vaults and auxiliary sections to be fabricated in steel forms.
- .3 Aggregates: to CSA A23.1/A23.2.
- .4 Cement: CAN/CSA-A3001, Type GU.
- .5 Steel welded wire fabric mesh reinforcing: to ASTM A82/A82M.ASTM A185/A185M
- .6 Neoprene gasket seals between vault sections: to ASTM D1056.
- .7 Top, walls, and bottom: reinforced concrete.
- .8 Walls and bottom: monolithic concrete construction.
- .9 Top: monolithic concrete construction

**Part 3 Execution**

**3.1 MANUFACTURER'S INSTRUCTIONS**

- .1 Compliance: comply with manufacturer's written recommendations or specifications, including product technical bulletins, handling, storage and installation instructions, and datasheets.

**3.2 EXCAVATION AND BACKFILL**

- .1 Excavate and backfill in accordance with Section 31 23 33.01 - Excavating Trenching and Backfilling and as indicated.
-

**3.3            INSTALLATION**

- .1        Construct units in accordance with details indicated, plumb and true to alignment and grade.

**3.4            FIELD QUALITY CONTROL**

- .1        N/A

**3.5            CLEANING**

- .1        See Section 01 74 11 Cleaning.

**END OF SECTION**

**APPENDIX A: Pre – Functional Check List**

**Air - Cooled Chiller:**

**PROJECT :**

**DATE :**

**Instructions:**

*Step 1: Circle Yes or No and fill in with requested information.*

*Step 2: Explain all "No" responses at the bottom of the checklist.*

Item	Task Description	Response	
		Submitted	Delivered
<b>1</b>	<b>Delivery Book</b>		
<b>A</b>	<b>Model Verification</b>	Submitted	Delivered
1	Manufacturer		
2	Model		
3	Serial Number	N/A	
4	Capacity (tons)		
7	Chilled Fluid Type		
8	Chilled Fluid Flow Rate (gpm)		
9	Refrigerant Type		
10	Compressor Motor Power (kW)		
11	Compressor Motor Voltage / Phase / Frequency (V / - / Hz)		
<b>B</b>	<b>Physical Check</b>		
1	Unit is free from physical damage	Yes	No
2	Openings are sealed with plastic	Yes	No
3	All components present (cooler, condenser, compressor, motor, etc.)	Yes	No
4	Motor bearings are double sealed and permanently lubricated	Yes	No
5	Electrical disconnect is provided	Yes	No
6	Installation and startup manual provided	Yes	No
7	Unit tags affixed	Yes	No
<b>2</b>	<b>Construction Checklist</b>		
<b>A</b>	<b>Installation of Chiller</b>		
1	Unit secured as required by manufacturer and specifications	Yes	No
2	There is a minimum of 36 inches of clearance around entire unit	Yes	No
3	There is a minimum of 48 inches of clearance in front of starter or VFD	Yes	No
4	There is a minimum clearance of one unit length for tube pull space	Yes	No
5	All components accessible for maintenance	Yes	No
6	Unit labeled and is easy to see	Yes	No
7	Chilled water piping leak tested	Yes	No