

Part 1 - GENERAL

1.1 WORK COVERED BY CONTRACT DOCUMENTS

- .1 Work of this Contract comprises:
 - .1 Pavement cracks cleaning and sealing, in accordance with their degree of stringency, on the existing runway, taxiway and traffic area;
 - .2 Pavement overlay by coverage rate on existing pavement of runway, taxiway and part of the traffic area;
 - .3 Granular reloading of shoulders to meet pavement new levels;
 - .4 Removal of existing pavement and placing of new asphalt pavement, including adjustment of granular base course on part of traffic area;
 - .5 Re-profiling of existing ditches, excavation of new ditches and building of new structures to prevent water runoff problems;
 - .6 Runway, taxiway and traffic area marking, including three new helicopter parking areas;
 - .7 Addition, displacement and lifting of lighting;
 - .8 Extension of concrete electrical duct, including removal of existing equipment, installation of new cables, conduits and pullpits.
 - .9 New lighting system for the expansion of the traffic area.

1.2 CONTRACT METHOD

- .1 Construction Works under unit price contract.

1.3 WORK BY OTHERS

- .1 Co-operate with other Contractors, if applicable, in carrying out their respective works and carry out instructions from Departmental Representative.
- .2 If applicable, co-ordinate work with that of other Contractors. If any part of work under this Contract depends for its proper execution or result upon work of another Contractor, report promptly to Departmental Representative, in writing, any defects which may interfere with proper execution of Work.

1.4 WORK SEQUENCE

- .1 Construct Work in stages, in accordance with the phasing plan, to accommodate Owner's continued use of premises during construction.
- .2 Co-ordinate Progress Schedule and co-ordinate with Owner Occupancy during construction.
- .3 Maintain fire access/control.

1.5 CONTRACTOR USE OF PREMISES

- .1 Limit use of premises to allow:
 - .1 Owner occupancy.
 - .2 Work by other contractors.
 - .3 Public usage.
- .2 Co-ordinate use of premises under direction of Departmental Representative.

- .3 Obtain and pay for use of additional storage or work areas needed for operations under this Contract.
- .4 Remove or alter existing work to prevent injury or damage to portions of existing work which remain.
- .5 Repair or replace portions of existing work which have been altered during construction operations to match existing or adjoining work, as directed by Departmental Representative.
- .6 At completion of operations condition of existing work: equal to or better than that which existed before new work started.

1.6 OWNER OCCUPANCY

- .1 Owner will occupy premises during entire construction period for execution of normal operations.
- .2 Co-operate with Owner in scheduling operations to minimize conflict and to facilitate Owner usage.

1.7 EXISTING SERVICES

- .1 Notify, Departmental Representative and utility companies of intended interruption of services and obtain required permission.
- .2 Where Work involves breaking into or connecting to existing services, give Departmental Representative 48 hour notice for necessary interruption of mechanical or electrical service throughout course of work. Minimize duration of interruptions. Carry out work at times as directed by governing authorities with minimum disturbance to tenant operations.
- .3 Provide alternative routes for personnel and vehicular traffic.
- .4 Establish location and extent of service lines in area of work before starting Work. Notify Departmental Representative of findings.
- .5 Submit schedule to and obtain approval from Departmental Representative for any shut-down or closure of active service or facility including power and communications services. Adhere to approved schedule and provide notice to affected parties.
- .6 Provide temporary services when directed by Departmental Representative to maintain critical building and tenant systems.
- .7 Provide adequate bridging over trenches which cross sidewalks or roads to permit normal traffic.
- .8 Where unknown services are encountered, immediately advise Departmental Representative and confirm findings in writing.
- .9 Protect, relocate or maintain existing active services. When inactive services are encountered, cap off in manner approved by authorities having jurisdiction.
- .10 Record locations of maintained, re-routed and abandoned service lines.

1.8 DOCUMENTS REQUIRED

- .1 Maintain at job site, one copy each document as follows:
 - .1 Contract Drawings.
 - .2 Specifications.
 - .3 Addenda.
 - .4 Reviewed Shop Drawings.
 - .5 List of Outstanding Shop Drawings.
 - .6 Change Orders.
 - .7 Other Modifications to Contract.
 - .8 Field Test Reports.
 - .9 Copy of Approved Work Schedule.
 - .10 Health and Safety Plan and Other Safety Related Documents.
 - .11 Other documents as specified.

Part 2 PRODUCTS

- .1 Not used.

Part 3 EXECUTION

3.1 TIME FRAME

- .1 During first year of Works, the time frame of the Works described on the phasing plans and in section 01 32 16.07 – Construction progress schedule – Bar (GANTT) chart, shall be 35 calendar days following contract awarding.
- .2 During second year of Works, the time frame of the Works described on the phasing plans and in section 01 32 16.07 – Construction progress schedule – Bar (GANTT) chart, shall be 70 calendar days following June 30th.

END OF SECTION

Part 1 - GENERAL

1.1 GENERAL

- .1 Include in Contract Price, fixed allowances stated herein.
- .2 Cash allowances, unless otherwise specified, cover cost to Contractor of services, products, construction machinery and equipment, handling, unloading, storage installation and other authorized expenses incurred in performing Work.
- .3 If the allowances fixed by the Ministry are considered not enough by Contractor, the excess cost will be included in the Contractor's overhead and profit distributed in the different items of the contract.
- .4 All the other costs necessary for the Contractor to complete the work that are not covered by any specific payment items or allowances shall be included in Contractor's overhead and distributed in different sections of the contract.
- .5 All down payments paid for authorized work and coming from a fixed allowance will be included in the monthly payment certificate established by Departmental Representative.

1.2 REFUNDABLE CASH ALLOWANCE

- .1 Amount of each allowance, for Work specified in different specification Sections is as follows:
 - .1 A refundable allowance of 50 000.00\$ is specified for services of escorts. The allowance covers all costs associated with escort services, except administrative charges. Contractor shall pay directly the airport administrators for these services and will be refunded at cost price by Departmental Representative.

1.3 FIXED PRICE CASH ALLOWANCE

- .1 Amount of each allowance, for Work specified in different specification Sections is as follows:
 - .1 A fixed price allowance of 1 900 000.00\$ is specified for mobilization, demobilization construction site organization and crushing of aggregates. Mobilization will include preparation, transport, loading and unloading of all materiel and construction equipment. Site organization will include setting up the construction site, transportation of all workers, setting up the Engineer laboratory and construction site camp. The fixed allowance will be paid in proportion to the work progress. Departmental Representative will pay 30% of the fixed allowance during the first year of Work (20% at first payment and 10% at last payment) and 70% during second year (50% at first payment and 20% at last payment).

Part 2 PRODUCTS

- .1 Not used.

Part 3 EXECUTION

- .1 Not used.

END OF SECTION

Part 1 - GENERAL

1.1 RELATED REQUIREMENTS

- .1 Particular requirements for inspection and testing to be carried out by testing laboratory designated by Departmental Representative are specified under sections as follows:
 - .1 Section 31 05 16 – Aggregate materials
 - .2 Section 31 23 33.01 – Excavation, trenching and backfilling
 - .3 Section 32 11 16.01 – Granular sub-base
 - .4 Section 32 11 23 – Aggregate base course
 - .5 Section 32 12 16 – Asphalt paving

1.2 APPOINTMENT AND PAYMENT

- .1 Departmental Representative will appoint and pay for services of testing laboratory except follows:
 - .1 Inspection and testing required by laws, ordinances, rules, regulations or orders of public authorities.
 - .2 Inspection and testing performed exclusively for Contractor's convenience.
 - .3 Testing, adjustment and balancing of conveying systems, mechanical and electrical equipment and systems.
 - .4 Mill tests and certificates of compliance.
 - .5 Tests specified to be carried out by Contractor under supervision of Departmental Representative.
- .2 Where tests or inspections by designated testing laboratory reveal Work not in accordance with contract requirements, pay costs for additional tests or inspections as required by Departmental Representative to verify acceptability of corrected work.

1.3 CONTRACTOR'S RESPONSABILITIES

- .1 Provide labour, equipment and facilities to:
 - .1 Provide access to Work for inspection and testing.
 - .2 Facilitate inspections and tests.
 - .3 Make good Work disturbed by inspection and test.
 - .4 Provide storage on site for laboratory's exclusive use to store equipment and cure test samples.
- .2 Notify Departmental Representative 48 hours minimum sufficiently in advance of operations to allow for assignment of laboratory personnel and scheduling of test.
- .3 Where materials are specified to be tested, deliver representative samples in required quantity to testing laboratory.
- .4 Pay costs for uncovering and making good Work that is covered before required inspection or testing is completed and approved by Departmental Representative.

Part 2 – PRODUCTS

.1 Not used

Part 3 – EXECUTION

.1 Not used

END OF SECTION

Part 1 - GENERAL

1.1 DEFINITIONS

- .1 Activity: element of Work performed during course of Project. Activity normally has expected duration, and expected cost and expected resource requirements. Activities can be subdivided into tasks.
- .2 Bar Chart (GANTT Chart): graphic display of schedule-related information. In typical bar chart, activities or other Project elements are listed down left side of chart, dates are shown across top, and activity durations are shown as date-placed horizontal bars. Generally Bar Chart should be derived from commercially available computerized project management system.
- .3 Baseline: original approved plan (for project, work package, or activity), plus or minus approved scope changes.
- .4 Construction Work Week: Monday to Friday, inclusive, will provide five day work week and define schedule calendar working days as part of Bar (GANTT) Chart submission.
- .5 Duration: number of work periods (not including holidays or other nonworking periods) required to complete activity or other project element. Usually expressed as workdays or workweeks.
- .6 Master Plan: summary-level schedule that identifies major activities and key milestones.
- .7 Milestone: significant event in project, usually completion of major deliverable.
- .8 Project Schedule: planned dates for performing activities and the planned dates for meeting milestones. Dynamic, detailed record of tasks or activities that must be accomplished to satisfy Project objectives. Monitoring and control process involves using Project Schedule in executing and controlling activities and is used as basis for decision making throughout project life cycle.
- .9 Project Planning, Monitoring and Control System: overall system operated by Departmental Representative to enable monitoring of project work in relation to established milestones.

1.2 REQUIREMENTS

- .1 Ensure Master Plan and Detail Schedules are practical and remain within specified Contract duration.
- .2 Plan to complete Work in accordance with prescribed milestones and time frame.
- .3 Limit activity durations to maximum of approximately 10 working days, to allow for progress reporting.
- .4 Ensure that it is understood that Award of Contract or time of beginning, rate of progress, Interim Certificate and Final Certificate as defined times of completion are of essence of this contract.

1.3 SUBMITTALS

- .1 Provide submittals in accordance with Section 01 33 00 - Submittal Procedures.
- .2 Submit to Departmental Representative within 10 working days of Award of Contract Bar (GANTT) Chart as Master Plan for planning, monitoring and reporting of project progress.
- .3 Submit Project Schedule to Departmental Representative within 5 working days of receipt of acceptance of Master Plan.

1.4 PROJECT MILESTONES

- .1 Project milestones form interim targets for Project Schedule. Phases must be done one after the other, and shall begin immediately after the preceding one.

Year 1	Description	Time frame (calendar days)
	Mobilization and aggregate crushing necessary for Contract's Work. Excavation of apron's expansion and placing of aggregate base course and granular sub-base.	35 days
Year 2		
	<u>Beginning of Works: June 30th 2015</u>	
Phase A	Pavement cracks repair and pavement of overlay on East side of runway.	20 days
Phase B	Pavement cracks repair and pavement of overlay on West side of runway.	20 days
Phase C	Pavement cracks repair and pavement of overlay on taxiway and on part of traffic area. Placing of new pavement on part of traffic area, including all other related Work.	30 days

1.5 MASTER PLAN

- .1 Structure schedule to allow orderly planning, organizing and execution of Work as Bar Chart (GANTT).
- .2 Departmental Representative will review and return revised schedules within 5 working days.
- .3 Revise impractical schedule and resubmit within 5 working days.
- .4 Accepted revised schedule will become Master Plan and be used as baseline for updates

1.6 PROJECT SCHEDULE

- .1 Develop detailed Project Schedule derived from Master Plan and respecting Phasing Plan.
- .2 Ensure detailed Project Schedule includes as minimum milestone and activity types as follows:
- .1 Award.
 - .2 Shop Drawings, Samples.
 - .3 Permits.
 - .4 Mobilization.
 - .5 Excavation.
 - .6 Backfill.
 - .7 Asphalt paving.
 - .8 Lighting of Runway, Apron and Parking.
 - .9 Electrical.
 - .10 Controls.

- .11 Testing and Commissioning.
- .12 Supplied equipment long delivery items.

1.7 PROJECT SCHEDULE REPORTING

- .1 Update Project Schedule on weekly basis reflecting activity changes and completions, as well as activities in progress.
- .2 Include as part of Project Schedule, narrative report identifying Work status to date, comparing current progress to baseline, presenting current forecasts, defining problem areas, anticipated delays and impact with possible mitigation

1.8 PROJECT MEETINGS

- .1 Discuss Project Schedule at regular site meetings, identify activities that are behind schedule and provide measures to regain slippage. Activities considered behind schedule are those with projected start or completion dates later than current approved dates shown on baseline schedule.
- .2 Weather related delays with their remedial measures will be discussed and negotiated.

1.9 SPECIAL REQUIREMENTS

- .1 Construction Works will be carried out during 2 summer seasons, on 2 consecutive years.
- .2 Works carried out during the first year will consist mainly of the following:
 - .1 Mobilization.
 - .2 Site preparation and construction facilities.
 - .3 Crushing of aggregates according to sections 31 05 16 – Aggregate Materials, 32 11 23 – Aggregate Base courses and 32 12 16 – Asphalt Paving.
 - .4 Expansion of the Apron only, including the granular sub-base and aggregate base course.
 - .5 Electrical Works necessary for the expansion of traffic area, including removal of cables, extension of concrete electrical duct and other related Works.
- .3 Works carried out during the second year will consist mainly of the following:
 - .1 Pavement cracks repair on runway, taxiway and part of traffic area.
 - .2 Pavement overlay on runway, taxiway and part of traffic area.
 - .3 Existing asphalt paving removal on part of traffic area.
 - .4 Levelling on base course and placing of asphalt pavement on part of traffic area expansion.
 - .5 Marking.
 - .6 Addition, displacement and lifting of lighting and other electrical works;
 - .7 New lighting system for the expansion of the traffic area.
 - .8 Crushing, cleaning and environmental interventions on the site of the quarry.
 - .9 Every other Work indicated on plans.
- .4 Every other Works, including demolition, sub-base, base course, asphalt paving and overlays and electrical, that will be achieved during the 2 years must be me done following the phasing plan.
- .5 The Contractor must note that the runway will remain operational during the entire duration of the project. The construction Works must be achieved on half of the runway and taxiway width at the time.

- .6 Every phase must be done in its whole (granular courses, crack repair, paving) before proceeding to the next one.
- .7 The projected schedule of movement areas utilisation by aircrafts is as following :
 - .1 From Monday to Friday :
5h00 @ 15h30
 - .2 This schedule can be modified at any times, subject to a 15 days' notice given by the Departmental Representative.
- .8 Work must take place in continuous, outside hours of operation of movement areas by aircrafts, i.e. between 15h30 and 5h00 the next day.
- .9 Contractor must anticipate a loss of working time of about 1 hour per week for an average of 2 MEDIVAC emergency evacuations that can occur anytime. Contractor will then have to remove all equipment and personnel out of movement areas to permit aircraft movements.

Part 2 – PRODUCTS

- .1 Not used

Part 3 – EXECUTION

- .1 Not used

END OF SECTION

Part 1 GENERAL

1.1 ADMINISTRATIVE

- .1 Submit to Departmental Representative submittals listed for review. Submit promptly and in orderly sequence to not cause delay in Work. Failure to submit in ample time is not considered sufficient reason for extension of Contract Time and no claim for extension by reason of such default will be allowed.
- .2 Do not proceed with Work affected by submittal until review is complete.
- .3 Present shop drawings, product data, samples and mock-ups in SI Metric units.
- .4 Where items or information is not produced in SI Metric units converted values are acceptable.
- .5 Review submittals prior to submission to Departmental Representative. This review represents that necessary requirements have been determined and verified, or will be, and that each submittal has been checked and co-ordinated with requirements of Work and Contract Documents. Submittals not stamped, signed, dated and identified as to specific project will be returned without being examined and considered rejected.
- .6 Notify Departmental Representative, in writing at time of submission, identifying deviations from requirements of Contract Documents stating reasons for deviations.
- .7 Verify field measurements and affected adjacent Work are co-ordinated.
- .8 Contractor's responsibility for errors and omissions in submission is not relieved by Departmental Representative's review of submittals.
- .9 Contractor's responsibility for deviations in submission from requirements of Contract Documents is not relieved by Departmental Representative review.
- .10 Keep one reviewed copy of each submission on site

1.2 SHOP DRAWINGS AND PRODUCT DATA

- .1 The term "shop drawings" means drawings, diagrams, illustrations, schedules, performance charts, brochures and other data which are to be provided by Contractor to illustrate details of a portion of Work.
- .2 Submit drawings stamped and signed by professional engineer registered or licensed in Canada.
- .3 Indicate materials, methods of construction and attachment or anchorage, erection diagrams, connections, explanatory notes and other information necessary for completion of Work. Where articles or equipment attach or connect to other articles or equipment, indicate that such items have been co-ordinated, regardless of Section under which adjacent items will be supplied and installed. Indicate cross references to design drawings and specifications.
- .4 Allow 10 days for Departmental Representative's review of each submission.

-
- .5 Adjustments made on shop drawings by Departmental Representative are not intended to change Contract Price. If adjustments affect value of Work, state such in writing to Departmental Representative prior to proceeding with Work.
 - .6 Make changes in shop drawings as Departmental Representative may require, consistent with Contract Documents. When resubmitting, notify Departmental Representative in writing of revisions other than those requested.
 - .7 Accompany submissions with transmittal letter, in duplicate, containing:
 - .1 Date.
 - .2 Project title and number.
 - .3 Contractor's name and address.
 - .4 Identification and quantity of each shop drawing, product data and sample.
 - .5 Other pertinent data.
 - .8 Submissions include:
 - .1 Date and revision dates.
 - .2 Project title and number.
 - .3 Name and address of:
 - .1 Subcontractor.
 - .2 Supplier.
 - .3 Manufacturer.
 - .4 Contractor's stamp, signed by Contractor's authorized representative certifying approval of submissions, verification of field measurements and compliance with Contract Documents.
 - .5 Details of appropriate portions of Work as applicable:
 - .1 Fabrication.
 - .2 Layout, showing dimensions, including identified field dimensions, and clearances.
 - .3 Setting or erection details.
 - .4 Capacities.
 - .5 Performance characteristics.
 - .6 Standards.
 - .7 Operating weight.
 - .8 Wiring diagrams.
 - .9 Single line and schematic diagrams.
 - .10 Relationship to adjacent work.
 - .9 After Departmental Representative's review, distribute copies
 - .10 Submit 3 copies of shop drawings for each requirement requested in specification Sections and as Departmental Representative may reasonably request.
 - .11 Submit 3 copies of product data sheets or brochures for requirements requested in specification Sections and as requested by Departmental Representative where shop drawings will not be prepared due to standardized manufacture of product.

-
- .12 Submit 2 copies of test reports for requirements requested in specification Sections and as requested by Departmental Representative.
 - .1 Report signed by authorized official of testing laboratory that material, product or system identical to material, product or system to be provided has been tested in accord with specified requirements.
 - .2 Testing must have been within 3 years of date of contract award for project.
 - .13 Submit 2 copies of certificates for requirements requested in specification Sections and as requested by Departmental Representative.
 - .1 Statements printed on manufacturer's letterhead and signed by responsible officials of manufacturer of product, system or material attesting that product, system or material meets specification requirements.
 - .2 Certificates must be dated after award of project contract complete with project name.
 - .14 Submit 2 copies of manufacturers instructions for requirements requested in specification Sections and as requested by Departmental Representative.
 - .1 Pre-printed material describing installation of product, system or material, including special notices and Material Safety Data Sheets concerning impedances, hazards and safety precautions.
 - .15 Submit 2 copies of Manufacturer's Field Reports for requirements requested in specification Sections and as requested by Departmental Representative.
 - .1 Documentation of the testing and verification actions taken by manufacturer's representative to confirm compliance with manufacturer's standards or instructions.
 - .16 Submit 2 copies of Operation and Maintenance Data for requirements requested in specification Sections and as requested by Departmental Representative.
 - .17 Delete information not applicable to project.
 - .18 Supplement standard information to provide details applicable to project.
 - .19 If upon review by Departmental Representative, no errors or omissions are discovered or if only minor corrections are made, copies will be returned and fabrication and installation of Work may proceed. If shop drawings are rejected, noted copy will be returned and resubmission of corrected shop drawings, through same procedure indicated above, must be performed before fabrication and installation of Work may proceed.
 - .20 The review of shop drawings by Public Works and Government Services Canada (PWGSC) is for sole purpose of ascertaining conformance with general concept.
 - .1 This review shall not mean that PWGSC approves detail design inherent in shop drawings, responsibility for which shall remain with Contractor submitting same, and such review shall not relieve Contractor of responsibility for errors or omissions in shop drawings or of responsibility for meeting requirements of construction and Contract Documents.

- .2 Without restricting generality of foregoing, Contractor is responsible for dimensions to be confirmed and correlated at job site, for information that pertains solely to fabrication processes or to techniques of construction and installation and for co-ordination of Work of sub-trades.

1.3 SAMPLES

- .1 Submit for review samples in duplicate as requested in respective specification Sections. Label samples with origin and intended use.
- .2 Deliver samples prepaid to Departmental Representative's business address.
- .3 Notify Departmental Representative in writing, at time of submission of deviations in samples from requirements of Contract Documents.
- .4 Where colour, pattern or texture is criterion, submit full range of samples.
- .5 Adjustments made on samples by Departmental Representative are not intended to change Contract Price. If adjustments affect value of Work, state such in writing to Departmental Representative prior to proceeding with Work.
- .6 Make changes in samples which Departmental Representative may require, consistent with Contract Documents.
- .7 Reviewed and accepted samples will become standard of workmanship and material against which installed Work will be verified

1.4 MOCK-UPS

- .1 Erect mock-ups in accordance with 01 45 00 - Quality Control.

1.5 CERTIFICATES AND TRANSCRIPTS

- .1 Immediately after award of Contract, submit Workers' Compensation Board status.
- .2 Submit transcription of insurance immediately after award of Contract.

Part 2 PRODUCTS

- .1 Not used.

Part 3 EXECUTION

- .1 Not used.

END OF SECTION

Part 1 – GENERAL

1.1 DÉFINITIONS

- .1 Restricted zone: Every zone located inside the airport where access is prohibited by a sign or by any other means is a restricted zone.
- .2 Movement Area: The part of an aerodrome to be used for the take-off, landing and taxiing of aircraft, consisting of the manoeuvring area and the apron.

1.2 RESPONSABILITY OF CONTRACTOR

- .1 Take notice of regulations concerning airport circulation and instruct staff and subcontractors.
- .2 Regulations can be found at this address: <http://www.tc.gc.ca/eng/acts-regulations/menu.htm>
- .3 Be responsible of his staff, construction vehicles and subcontractors working on this project and that will enter restricted zones.

1.3 GENERAL PROTECTION

- .1 Do not disrupt airport business except as permitted by Departmental Representative.
- .2 Provide temporary protection for safe handling of public, personnel, pedestrians and vehicular traffic.
- .3 Provide barricades and lights where directed.

1.4 MOVEMENT OF EQUIPMENT AND PERSONNEL

- .1 In areas of airport not closed to aircraft traffic:
 - .1 Obtain Departmental Representative's approval on scheduling of Work.
 - .2 Control movements of equipment and personnel as directed by Departmental Representative.
 - .3 Obey signals from airport authorities instantly.

1.5 OPERATIONNAL RESTRAINTS

- .1 Comply with safety and security operational requirements and any other applicable requirements during Work and alongside runway, taxiway and apron in operation, including, but not limited to:
 - .1 The integrity of all electronical and visual navigation aids associated to aviation activities taking place at the same time must be maintained for aircraft movements, prevailing on Work; Every shut-down period for electrical Work must be done by the Contractor.
 - .2 Underground power cables, for transmission and control and all other equipment and underground services located near construction area have to be protected and identified;
 - .3 The movement capability of emergency relief services must be maintained at all times. Service roads must be checked by Departmental Representative on a biweekly basis to ensure that access is maintained at all times. Alternate roads, to be approved, must be planned if new work is anticipated to affect the access.

1.6 CLOSED AREA TO AIRCRAFT MOVEMENT

- .1 The contractor is responsible of furniture, installation, maintenance and removal of barricades and lighting units used for closed areas delimitation to aircraft movement.

- .2 Equipment parking and material storing will only be permitted in Contractor's storing area.
- .3 Equipment must be stored in storing areas designated by Departmental Representative.
- .4 Contractor is notified that due to turbulence resulting from aircrafts, every marker must be firmly anchored and attached, and all delineators must be correctly held down using sand bags or being bolted to pavement.

1.7 MARKING AND TEMPORARY MARKERS

- .1 Contractor shall furnish, install, move or remove, in accordance to needs, temporary closed runway and taxiway markers.
 - .1 On runway, closed markers will be placed at each extremity of the runway or at each extremity of the closed part. Additional markers will be placed in such a way that the maximum spacing between two successive markers shall not exceed 300 meters.
 - .2 On taxiway, closed markers will be placed at each extremity of the taxiway or at each extremity of the closed part.
 - .3 Closed runway and taxiway markers dimensions shall be as indicated on plans, white when placed on runway and yellow when on taxiway.
 - .4 Closed runway and taxiway markers will be made of a 0,15 mm thick polyethylene geomembrane (minimum) anchored to the ground in such a way that it can resist to adverse weather conditions and aircraft engine's thrust.
 - .5 Closed taxiway markers shall be made with painted plywood, weighted with sand bags.
- .2 During day, Contractor shall furnish, install, maintain or move, in accordance to Work advancement, runway edge and threshold markers.
 - .1 Runway threshold markers prefabricated with wood, according with details shown on plans, will be installed at both runway threshold and on each side of the runway part in operation.
 - .2 Temporary runway edge markers made of orange construction cones of a 500 mm height with a 60 m spacing in between them, will be placed along the runway center line to set boundaries between phases A et B.
 - .3 Temporary markers will be anchored to the ground in such a way that they can resist to adverse weather conditions and aircraft engine's thrust.
- .3 At night, Contractor must install or move the following lights, depending on the case:
 - .1 Temporary runway and taxiway edge lights. Move existing lights at new location to delimit operational runway and taxiway edges. Temporary edge lights will have a maximum height of 300 mm, spaced of 60 m and symmetrically disposed on each side of the operational runway or taxiway.
 - .2 Temporary runway threshold light to delimit the part of runway in operation. These lights are made of 8 lights in 2 groups of 4. Only one group at the time shall be moved depending on the side of runway in operation.
 - .3 Temporary runway identification light. The lights are made of 2 lights placed on each end of the runway. Only one light at a time shall be moved to identify the side of the runway in operation.
 - .4 Temporary lighting shall be installed according to frangibility standards for objects located inside the runway strip.
 - .5 Contractor shall make all temporary electrical fittings Work necessary to ensure safe operation of temporary lighting.

- .4 Contractor shall furnish, install, maintain or move, in accordance to Work advancement, markers for Work on the Apron.
 - .1 On the apron, temporary markers with a distance of 3 m maximum between each of them must be installed to form a barricade.
 - .2 Barricades must be made of markers of type TRV7 polyethylene barrels, approved by MTQ equipped with a white strip of high density reflective tape of a 84 mm width and with an orange fluorescent strip of a 120 mm width. Barrels shall have a total height of 1 321 mm, a 4 mm thickness, a head diameter of 318 mm and a base diameter of 495 mm. The approximate weight of each barrel shall be of at least 4,5 kg. Barrels shall be weighted in place with a weight of at least 15 kg and each barrel will be anchored to the ground in such a way that they can resist to adverse weather conditions and aircraft engine's thrust.

Markers characteristics:

 - .1 Thickness of 5/32"
 - .2 Total height of 1321mm
 - .3 318mm Diameter at the head and 495mm at the base.
 - .4 Approximate weight of each marker: 4.5kg,
 - .3 During the night, barricades will be supplied of artificial red lights in continuous with the following features:
 - .1 type : omni directional
 - .2 colour : red
 - .3 Average intensity :CD x 1 000 : 0,4 CD – Candela
 - .4 Distance between lights : maximum 3,0 meters (10 feet) apart
 - .5 set up to 350mm high (14 inches).

1.8 ESCORT

- .1 Escort services will be given by Departmental Representative.
- .2 Obey promptly and as soon as possible to Departmental Representative instructions and directives. Contractor must advise Departmental Representative 12 hours before any change to the Work schedule when escorts are needed to allow them to plan ahead new schedules.
- .3 Radios necessary for communications between Departmental Representative and Escort shall be provided by Departmental Representative.
- .4 Access of Contractor's vehicles and equipment to site will be limited to secured entrances. These access points will require in all time the presence of security personnel during Work periods, that will be provided by Contractor.
- .5 No vehicle or any transport related to Work will be able to travel on paved surfaces (runway, taxiway and traffic area) located outside Work boundaries without escort from safety authorities.
- .6 Contractor will pay directly the Departmental Representative all costs necessary to the furniture of escort services. These services are part of an allowance and will be refunded at the cost price as described in section 01 21 00 - Allowances

1.9 GENERAL PROVISIONS FOR AIRPORT ACTIVITIES

- .1 Refer to Work plan and applicable plans for details related to Work to be done at airport.
- .2 Equipment and material storage shall be confined to construction areas or areas indicated by Departmental Representative.
- .3 Contractor must be able to communicate by radio to everyone on airport site at all times during Work, in a short and efficient way, instructions of movement in movement areas.
- .4 Mobilisation must be coordinated with Departmental Representative to ensure that all precautions for airport security are correctly put in place. Instructions will be provided during first reunion previous to the beginning of the project.
- .5 Every area on the runway side (runway, taxiway, traffic area, etc.) are considered non-smoking. Contractor must make sure that all construction workers are informed and respect that condition.

Part 2 – PRODUCTS

- .1 Not used.

Part 3 – EXECUTION

- .1 Not used.

FIN DE LA SECTION

Part 1 - GENERAL

1.1 RÉFÉRENCES

- .1 Canada Labour Code - Part II, Canadian Occupational Safety and Health Regulations.
- .2 Canadian Standards Association (CSA)
- .3 Workplace Hazardous Materials Information System (WHMIS)
- .4 Act Respecting Occupational Health and Safety, R.S.Q. Chapter S-2.1.
- .5 Construction Safety Code, S-2.1, r.6.

1.2 SUBMITTALS

- .1 Submit the documents required according to section 01 33 00 - (Documents and samples to be submitted).
- .2 Submit to Departmental Representative, the CSST, the Association paritaire en santé et sécurité du secteur de la construction (ASP Construction) the site-specific safety program, as outlined in 1.8 at least 10 days prior to start of work. The Contractor must review his program during the course of the project if any change occurs in work methods or site conditions. The Departmental Representative may, after receiving the program or at any time during the project, ask the Contractor to update or modify the program in order to better reflect the reality of the construction site and activities. The Contractor must make the required changes before work begins.
- .3 Submit to Departmental Representative the site inspection sheet, duly completed, at the intervals indicated in 1.12.1.
- .4 Submit to Departmental Representative within 24 hours a copy of any inspection report, correction notice or recommendation issued by federal or provincial inspectors.
- .5 Submit to Departmental Representative within 24 hours an investigation report for any accident involving injury and any incident exposing a potential hazard.
- .6 Submit to Departmental Representative all safety data sheets for hazardous material to be used at the site at least three days before they are to be used.
- .7 Submit to Departmental Representative copies of all training certificates required for application of the safety program, in particular:
 - .1 General construction site safety and health courses;
 - .2 Safety officer attestations;
 - .3 First aid in the workplace and cardiopulmonary resuscitation;
 - .4 Work likely to release asbestos dust;
 - .5 Work in confined spaces;
 - .6 Lockout procedures;
 - .7 Wearing and fitting of individual protective gear;
 - .8 forklift truck;
 - .9 positioning platform;
 - .10 Any other requirement of Regulations or the safety program.

- .8 Medical examinations : Wherever legislation, regulations, directives, specification or a safety program require medical examinations, Contractor must:
 - .1 Prior to start-up, submit to Departmental Representative certificates of medical examination for all concerned supervisory staff and employees who will be on duty when the site opens.
 - .2 Thereafter, submit without delay certificates of medical examination for any newly hired concerned personnel as and when they start work at the site.
- .9 Emergency plan : The emergency plan, as defined in 1.8.3, shall be submitted to Departmental Representative at the same time as the site-specific safety program.
- .10 Notice of site opening : Notice of site opening shall be submitted to the Commission *de la santé et de la sécurité du travail* before work begins . A copy of such notice shall be submitted to Departmental Representative at the same time and another posted in full view at the site. During demobilization, a notice of site closing shall be submitted to the CSST, with copy to Departmental Representative.
- .11 Plans and certificates of compliance : Submit to the CSST and to Departmental Representative a copy signed and sealed by engineer of all plans and certificates of compliance required pursuant to the Construction Safety Code (S-2.1, r. 6), or by any other legislation or regulation or by any other clause in the specifications or in this contract. Copies of these documents must be on hand at the site at all times.
- .12 Certificate of compliance delivered by the CSST: The certificate of compliance is a document delivered by the CSST confirming that the contractor is in rule with the CSST, i.e. that he had pay out all the benefits concerning this contract. This document must be delivered to Departmental Representative at the end of the work.

1.3 HAZARDS ASSESSMENT

- .1 The contractor must identify all hazards inherent in each task to be carried out at the site.
- .2 The contractor must plan and organize work so as to eliminate hazards at source or promote mutual protection so that reliance on individual protective gear can be kept to a minimum. Where individual protection against falling is required, workers shall use safety harness that meets standard Can - CSA- Z-259.10 - M90. Safety belts shall not be used as protection against falling.
- .3 Equipment, tools and protective gear which cannot be installed, fitted or used without compromising the health or safety of workers or the public shall be deemed inadequate for the work to be executed.
- .4 All mechanical equipment shall be inspected before delivery to the site. Before using any mechanical equipment, submit to Departmental Representative a certificate of compliance signed by a qualified mechanic. Whenever he suspects a defect or accident risk, Departmental Representative may at any time order the immediate shut-down of equipment and require a new inspection by a specialist of his own choosing.

1.4 MEETINGS

- .1 Contractor decisional representative must attend any meetings at which site safety and health issues are to be discussed
- .2 Set up a site safety committee, and convene meetings every in accordance with the Construction Safety Code (S-2.1, r.6).

1.5 LEGAL AND REGULATORY REQUIREMENTS

- .1 Comply with all legislation, regulations and standards applicable to the site and its related activities.
- .2 Comply with specified standards and regulations to ensure safe operations at site containing hazardous or toxic materials.
- .3 Regardless of the publication date shown in the construction safety code, always use the most recent version.

1.6 SITE-SPECIFIC CONDITIONS

- .1 At the site, the contractor must take account of the following specific conditions:
 - .1 Evening and night works.

1.7 SAFETY AND HEALTH MANAGEMENT

- .1 Acknowledge and assume all the tasks and obligations which customarily devolve upon a principal Contractor under the terms of the Act Respecting Occupational Health and Safety (R.S.Q., chapter S-2.1) and the Construction Safety Code (S-2.1, r.6).
- .2 Develop a site-specific safety program based on the hazards identified and apply it from the start of project work until close-out is completed. The safety program must take account of all information appearing in 1.7 and must be submitted to all parties concerned, in accordance with the provisions set forth in 1.3. At a minimum, the site-specific safety program must include :
 - .1 Company safety and health policy.
 - .2 A description of the work, total costs, schedule and projected workforce curve.
 - .3 Flow chart of safety and health responsibility.
 - .4 The physical and material layout of the site.
 - .5 First-aid and first-line treatment standards.
 - .6 Identification of site-specific hazards.
 - .7 Risk assessment for the tasks to be carried out, including preventive measures and the procedures for applying them.
 - .8 Training requirements.
 - .9 Procedures in case of accident/injury
 - .10 Written commitment from all parties to comply with the prevention program.
 - .11 A site inspection schedule based on the preventive measures.
- .3 The contractor must draw up an effective emergency plan based on the characteristics and constraints of the site and its surroundings. Submit the emergency plan to all parties concerned, pursuant to the provisions of 1.3. The emergency plan must include:
 - .1 Evacuation procedure;
 - .2 Identification of resources (police, firefighters, ambulance services, etc.);
 - .3 Identification of persons in charge at the site;
 - .4 Identification of those with first-aid training;
 - .5 Training required for those responsible for applying the plan;

- .6 Any other information needed, in the light of the site characteristics.

1.8 RESPONSIBILITIES

- .1 No matter the size of the construction site or how many workers are present at the workplace, designate a competent person to supervise and take responsibility for health and safety. Take all necessary measures to ensure the health and safety of persons and property at or in the immediate vicinity of the site and likely to be affected by any of the work.
- .2 Take all necessary measures to ensure application of and compliance with the safety and health requirements of the contract documents, applicable federal and provincial regulations and standards as well as the site-specific safety program, complying without delay with any order or correction notice issued by the Commission de la santé et de la sécurité du travail.
- .3 Take all necessary measures to keep the site clean and in good order throughout the course of the work

1.9 COMMUNICATIONS AND POSTING

- .1 Make all necessary arrangements to ensure effective communication of safety and health information at the site. As they arrive on site, all workers must be informed of their rights and obligations pertaining to the site specific safety program. The Contractor must insist on their right to refuse to perform work which they feel may threaten their own health, safety or physical integrity or that of other persons at the site. The Contractor must keep and update a written record of all information transmitted with signatures of all affected workers.
- .2 The following information and documents must be posted in a location readily accessible to all workers:
 - .1 Notice of site opening;
 - .2 Identification of principal Contractor;
 - .3 Company OSH policy;
 - .4 Site-specific safety program;
 - .5 Emergency plan;
 - .6 Data sheets for all hazardous material used at the site;
 - .7 Minutes of site committee meetings;
 - .8 Names of site committee representatives;
 - .9 Names of those with first-aid training;
 - .10 Action reports and correction notices issued by the CSST.

1.10 UNFORESEEN CIRCUMSTANCES

- .1 Whenever a source of danger not defined in the specifications or identified in the preliminary site inspection arises as a result of or in the course of the work, immediately suspend work, take appropriate temporary measures to protect the workers and the public and notify Departmental Representative, both verbally and in writing. Then the Contractor must modify or update the site specific safety program in order to resume work in safe conditions.

1.11 INSPECTION OF SITE AND CORRECTION OF HAZARDOUS SITUATIONS

- .1 Inspect the work site and complete the site inspection sheet at least once a week.

- .2 Immediately take all necessary measures to correct any lapses from legislative or regulatory requirements and any hazards identified by a government inspector, by the Departmental Representative, by the site safety and health coordinator or during routine inspections.
- .3 Submit to Departmental Representative written confirmation of all measures taken to correct lapses and hazardous situations.
- .4 Give the safety officer or, where there is no safety officer, the person assigned to safety and health responsibilities, full authority to order interruption and resuming of work as and when deemed necessary or desirable in the interests of safety and health. This person should always act so that the safety and health of the public and site workers and environmental protection take precedence over cost and scheduling considerations.
- .5 Without limiting the scope of sections 1.8 and 1.9, Departmental Representative may order cessation of work if, in his/her view, there is any hazard or threat to the safety or health of site personnel or the public or to the environment.

1.12 BLASTING

- .1 Blasting and other use of explosives are forbidden unless authorized in writing by Departmental Representative.
- .2 Any operation involving explosives must be carried out under the supervision of a qualified shot firer.
- .3 The purchase, carriage, storage and use of explosives must comply with all applicable federal and provincial legislation:
 - .1 Canada: Explosives Act (E-17)1, Explosives Regulations (C.R.C. CH. 599), Standard for Storage of Blasting Charges and Detonators, Transportation of Dangerous Goods Act and Regulations.
 - .2 Quebec: Explosives Act (E-22), Explosives Regulations (E-22, r.1), Safety Code for the Construction Industry (S-2.1, r.6), Transportation of Dangerous Goods Regulations.
- .4 Contractor shall obtain all permits required pursuant to the legislation and regulations referred to above and keep copies on hand at the site.
- .5 Contractor shall facilitate inspection of the site, stored explosives and vehicles used to transport explosives by any government representatives or police officers whose jurisdiction encompasses explosives.

1.13 POWDER ACTUATED DEVICES

- .1 Use of power hammers and other explosive-actuated devices must be authorized by Departmental Representative.
- .2 Any person using a power hammer shall hold a training certificate and meet all requirements of Section 7 of the Construction Safety Code (S-2.1, r. 6).
- .3 Any other explosive-actuated device shall be used in accordance with the manufacturer's directions and applicable standards and regulations

END OF SECTION

Part 1 - GENERAL

1.1 RÉFÉRENCES

- .1 Définitions :
 - .1 Environmental Pollution and Damage: presence of chemical, physical, biological elements or agents which adversely affect human health and welfare; unfavourably alter ecological balances of importance to human life; affect other species of importance to humankind; or degrade environment aesthetically, culturally and/or historically.
 - .2 Environmental Protection: prevention/control of pollution and habitat or environment disruption during construction. Control of environmental pollution and damage requires consideration of land, water, and air; biological and cultural resources; and includes management of visual aesthetics; noise; solid, chemical, gaseous, and liquid waste; radiant energy and radioactive material as well as other pollutants.
- .2 U.S. Environmental Protection Agency (EPA)/Office of Water
 - .1 EPA 832/R-92-005-92, Storm Water Management for Construction Activities, Chapter 3.

1.2 ACTION AND INFORMATIONAL SUBMITTALS

- .1 Provide submittals in accordance with Section 01 33 00 - Submittal Procedures.
- .2 Prior to commencing construction activities or delivery of materials to site, provide Environmental Protection Plan for review and approval by Departmental Representative.
- .3 Ensure Environmental Protection Plan includes comprehensive overview of known or potential environmental issues to be addressed during construction.
- .4 Address topics at level of detail commensurate with environmental issue and required construction tasks.
- .5 Include in Environmental Protection Plan:
 - .1 Names of persons responsible for ensuring adherence to Environmental Protection Plan.
 - .2 Names and qualifications of persons responsible for manifesting hazardous waste to be removed from site.
 - .3 Names and qualifications of persons responsible for training site personnel.
 - .4 Descriptions of environmental protection personnel training program.
 - .5 Erosion and sediment control plan identifying type and location of erosion and sediment controls to be provided including monitoring and reporting requirements to assure that control measures are in compliance with erosion and sediment control plan, Federal, Provincial, and Municipal laws and regulations, EPA 832/R-92-005, Chapter 3 requirements.
 - .6 Drawings showing locations of proposed temporary excavations or embankments for haul roads, stream crossings, material storage areas, structures, sanitary facilities, and stockpiles of excess or spoil materials including methods to control runoff and to contain materials on site.
 - .7 Traffic Control Plans including measures to reduce erosion of temporary roadbeds by construction traffic, especially during wet weather. Ensure plans include measures to minimize amount of mud transported onto paved public roads by vehicles or runoff.

- .8 Work area plan showing proposed activity in each portion of area and identifying areas of limited use or non-use. Ensure plan includes measures for marking limits of use areas and methods for protection of features to be preserved within authorized work areas.
- .9 Spill Control Plan including procedures, instructions, and reports to be used in event of unforeseen spill of regulated substance.
- .10 Non-Hazardous solid waste disposal plan identifying methods and locations for solid waste disposal including clearing debris.
- .11 Air pollution control plan detailing provisions to assure that dust, debris, materials, and trash, are contained on project site.
- .12 Contaminant Prevention Plan identifying potentially hazardous substances to be used on job site; intended actions to prevent introduction of such materials into air, water, or ground; and detailing provisions for compliance with Federal, Provincial, and Municipal laws and regulations for storage and handling of these materials.
- .13 Waste Water Management Plan identifying methods and procedures for management and/or discharge of waste waters which are directly derived from construction activities, such as concrete curing water, clean-up water, dewatering of ground water, disinfection water, hydrostatic test water, and water used in flushing of lines.
- .14 Historical, archaeological, cultural resources biological resources and wetlands plan that defines procedures for identifying and protecting historical, archaeological, cultural resources, biological resources and wetlands.
- .15 Pesticide treatment plan to be included and updated, as required.

1.3 FIRES

- .1 Fires and burning of rubbish on site not permitted.

1.4 DRAINAGE

- .1 Provide Erosion and Sediment Control Plan identifying type and location of erosion and sediment controls provided. Ensure plan includes monitoring and reporting requirements to assure that control measures are in compliance with erosion and sediment control plan, Federal, Provincial, and Municipal laws and regulations, EPA 832/R-92-005, Chapter 3 requirements.
- .2 Storm Water Pollution Prevention Plan (SWPPP) to be substituted for erosion and sediment control plan.
- .3 Provide temporary drainage and pumping required to keep excavations and site free from water.
- .4 Ensure pumped water into waterways, sewer or drainage systems is free of suspended materials.
- .5 Control disposal or runoff of water containing suspended materials or other harmful substances in accordance with local authority requirements.

1.5 SITE CLEARING AND PLANT PROTECTION

- .1 Protect trees and plants on site and adjacent properties as indicated.
- .2 Wrap in burlap, trees and shrubs adjacent to construction work, storage areas and trucking lanes, and encase with protective wood framework from grade level to height of 2m minimum.
- .3 Protect roots of designated trees to dripline during excavation and site grading to prevent disturbance or damage. Avoid unnecessary traffic, dumping and storage of materials over root zones.

- .4 Minimize stripping of topsoil and vegetation.
- .5 Restrict tree removal to areas indicated or designated by Departmental Representative.

1.6 WORK ADJACENT TO WATERWAYS

- .1 Construction equipment to be operated on land only.
- .2 Do not use waterway beds for borrow material without Departmental Representative's approval.
- .3 Waterways to be free of excavated fill, waste material and debris.
- .4 Design and construct temporary crossings to minimize erosion to waterways.
- .5 Do not skid logs or construction materials across waterways.
- .6 Avoid indicated spawning beds when constructing temporary crossings of waterways.

1.7 POLLUTION CONTROL

- .1 Maintain temporary erosion and pollution control features installed under this Contract.
- .2 Control emissions from equipment and plant to local authorities' emission requirements.
- .3 Prevent sandblasting and other extraneous materials from contaminating air and waterways beyond application area.
 - .1 Provide temporary enclosures where directed by Departmental Representative.
- .4 Cover or wet down dry materials and rubbish to prevent blowing dust and debris. Provide dust control for temporary roads.

1.8 HISTORICAL/ARCHAEOLOGICAL CONTROL

- .1 Provide historical, archaeological, cultural resources biological resources and wetlands plan that defines procedures for identifying and protecting historical, archaeological, cultural resources, biological resources and wetlands known to be on project site: and/or identifies procedures to be followed if historical archaeological, cultural resources, biological resources and wetlands not previously known to be onsite or in area are discovered during construction.
- .2 Plan: include methods to assure protection of known or discovered resources and identify lines of communication between Contractor personnel and Departmental Representative.

1.9 NOTIFICATION

- .1 Departmental Representative will notify Contractor in writing of observed noncompliance with Federal, Provincial or Municipal environmental laws or regulations, permits, and other elements of Contractor's Environmental Protection plan.
- .2 Contractor: after receipt of such notice, inform Departmental Representative of proposed corrective action and take such action for approval by Departmental Representative.
 - .1 Do not take action until after receipt of written approval by Departmental Representative.
- .3 Departmental Representative will issue stop order of work until satisfactory corrective action has been taken.
- .4 No time extensions granted or equitable adjustments allowed to Contractor for such suspensions.

Part 2 – PRODUCTS

- .1 Not used.

Part 3 – EXECUTION

3.1 CLEANING

- .1 Clean in accordance with Section 01 74 11 - Cleaning.

FIN DE LA SECTION

Part 1 GENERAL

1.1 INSPECTION

- .1 Allow Departmental Representative access to Work. If part of Work is in preparation at locations other than Place of Work, allow access to such Work whenever it is in progress.
- .2 Give timely notice requesting inspection if Work is designated for special tests, inspections or approvals by Departmental Representative instructions, or law of Place of Work.
- .3 If Contractor covers or permits to be covered Work that has been designated for special tests, inspections or approvals before such is made, uncover such Work, have inspections or tests satisfactorily completed and make good such Work.
- .4 Departmental Representative will order part of Work to be examined if Work is suspected to be not in accordance with Contract Documents. If, upon examination such work is found not in accordance with Contract Documents, correct such Work and pay cost of examination and correction. If such Work is found in accordance with Contract Documents, Departmental Representative shall pay cost of examination and replacement..

1.2 INDEPENDANT INSPECTION AGENCIES

- .1 Independent Inspection/Testing Agencies will be engaged by Departmental Representative for purpose of inspecting and/or testing portions of Work. Cost of such services will be borne by Departmental Representative.
- .2 Provide equipment required for executing inspection and testing by appointed agencies.
- .3 Employment of inspection/testing agencies does not relax responsibility to perform Work in accordance with Contract Documents.
- .4 If defects are revealed during inspection and/or testing, appointed agency will request additional inspection and/or testing to ascertain full degree of defect. Correct defect and irregularities as advised by Departmental Representative at no cost to Departmental Representative. Pay costs for retesting and reinspection.

1.3 ACCESS TO WORK

- .1 Allow inspection/testing agencies access to Work, off site manufacturing and fabrication plants.
- .2 Co-operate to provide reasonable facilities for such access.

1.4 PROCEDURE

- .1 Notify appropriate agency and Departmental Representative in advance of requirement for tests, in order that attendance arrangements can be made.
- .2 Submit samples and/or materials required for testing, as specifically requested in specifications. Submit with reasonable promptness and in orderly sequence to not cause delays in Work.
- .3 Provide labour and facilities to obtain and handle samples and materials on site. Provide sufficient space to store and cure test samples.

1.5 REJECTED WORK

- .1 Remove defective Work, whether result of poor workmanship, use of defective products or damage and whether incorporated in Work or not, which has been rejected by Departmental Representative as failing to conform to Contract Documents. Replace or re-execute in accordance with Contract Documents.
- .2 Make good other Contractor's work damaged by such removals or replacements promptly.
- .3 If in opinion of Departmental Representative it is not expedient to correct defective Work or Work not performed in accordance with Contract Documents, Owner will deduct from Contract Price difference in value between Work performed and that called for by Contract Documents, amount of which will be determined by Departmental Representative.

1.6 REPORTS

- .1 Submit 2 copies of inspection and test reports to Departmental Representative.
- .2 Provide copies to subcontractor of work being inspected or tested.

1.7 TESTS AND MIX DESIGNS

- .1 Furnish test results and mix designs as requested.
- .2 Cost of tests and mix designs beyond those called for in Contract Documents or beyond those required by law of Place of Work will be appraised by Departmental Representative and may be authorized as recoverable.

1.8 MOCK-UPS

- .1 Prepare mock-ups for Work specifically requested in specifications. Include for Work of Sections required to provide mock-ups.
- .2 Construct in locations acceptable to Departmental Representative.
- .3 Prepare mock-ups for Departmental Representative review with reasonable promptness and in orderly sequence, to not cause delays in Work.
- .4 Failure to prepare mock-ups in ample time is not considered sufficient reason for extension of Contract Time and no claim for extension by reason of such default will be allowed.
- .5 If requested, Departmental Representative will assist in preparing schedule fixing dates for preparation.
- .6 Remove mock-up at conclusion of Work or when acceptable to Departmental Representative.

1.9 MILL TEST

- .1 Submit mill test certificates as required of specification Sections.

1.10 EQUIPMENT AND SYSTEMS

- .1 Submit adjustment and balancing reports for mechanical and electrical systems.

Part 2 PRODUCTS

- .1 Not used.

Part 3 EXECUTION

- .1 Not used.

END OF SECTION

Part 1 - GENERAL

1.1 REFERENCES

- .1 Canadian General Standards Board (CGSB)
 - .1 CAN/CGSB 1.189-00, Exterior Alkyd Primer for Wood.
 - .2 CGSB 1.59-97, Alkyd Exterior Gloss Enamel Association canadienne de normalisation (CSA International)
- .2 Canadian Standards Association (CSA International)
 - .1 CSA-A23.1/A23.2-04, Concrete Materials and Methods of Concrete Construction/Methods of Test and Standard Practices for Concrete.
 - .2 CSA-0121-08, Douglas Fir Plywood.
 - .3 CAN/CSA-S269.2-M1987(R2003), Access Scaffolding for Construction Purposes.
 - .4 CAN/CSA-Z321-96(R2001), Signs and Symbols for the Occupational Environment
- .3 U.S. Environmental Protection Agency (EPA) / Office of Water
 - .1 EPA 832R92005, Storm Water Management for Construction Activities: Developing Pollution Prevention Plans and Best Management Practices.

1.2 SUBMITTALS

- .1 Provide submittals in accordance with Section 01 33 00 - Submittal Procedures.

1.3 INSTALLATION AND REMOVAL

- .1 Prepare site plan indicating proposed location and dimensions of area to be fenced and used by Contractor, number of trailers to be used, avenues of ingress/egress to fenced area and details of fence installation.
- .2 Identify areas which have to be gravelled to prevent tracking of mud.
- .3 Indicate use of supplemental or other staging area.
- .4 Provide construction facilities in order to execute work expeditiously.
- .5 Remove from site all such work after use.

1.4 HOISTING

- .1 Provide, operate and maintain hoists cranes required for moving of workers, materials and equipment. Make financial arrangements with Subcontractors for their use of hoists.
- .2 Hoists cranes to be operated by qualified operator.

1.5 SITE STORAGE/LOADING

- .1 Confine work and operations of employees by Contract Documents. Do not unreasonably encumber premises with products.
- .2 Do not load or permit to load any part of Work with weight or force that will endanger Work.

1.6 ACCESS ROADS

- .1 Provide access and temporary relocated roads as necessary to maintain traffic.
- .2 Maintain and protect traffic on affected roads during construction period except as otherwise specifically directed by Departmental Representative.
- .3 Clean dirt or mud tracked onto paved or surfaced roadways.

1.7 CONSTRUCTION PARKING

- .1 Parking will be permitted on site provided it does not disrupt performance of Work.
- .2 Clean runways and taxi areas where used by Contractor's equipment.

1.8 SECURITY

- .1 Provide and pay for responsible security personnel to guard site and contents of site after working hours and during holidays.

1.9 OFFICES

- .1 Provide office heated to 22 degrees C, lighted 750 lx and ventilated, of sufficient size to accommodate site meetings and furnished with drawing laydown table.
- .2 Provide marked and fully stocked first-aid case in a readily available location.
- .3 Subcontractors to provide their own offices as necessary. Direct location of these offices.
- .4 Departmental Representative's Site office.
 - .1 Provide temporary office for Departmental Representative.
 - .2 Inside dimensions minimum 3.6 m long x 3 m wide x 2.4 m high, with floor 0.3 m above grade, complete with 4 50% opening windows and one lockable door.
 - .3 Insulate building and provide heating system to maintain 22 degrees C inside temperature at -20 degrees C outside temperature.
 - .4 Finish inside walls and ceiling with plywood, hardboard or wallboard and paint in selected colours. Finish floor with 19 mm thick plywood.
 - .5 Install electrical lighting system to provide min 750 lx using surface mounted, shielded commercial fixtures with 10 % upward light component.
 - .6 Provide private washroom facilities adjacent to office complete with flush or chemical type toilet, lavatory and mirror and maintain supply of paper towels and toilet tissue.
 - .7 Equip office with 1 x 2 m table, 4 chairs, 6 m of shelving 300 mm wide, one 3 drawer filing cabinet, one plan rack and one coat rack and shelf.
 - .8 Maintain in clean condition.

1.10 EQUIPMENT, TOOL AND MATERIAL STORAGE

- .1 Provide and maintain, in clean and orderly condition, lockable weatherproof sheds for storage of tools, equipment and materials.
- .2 Locate materials not required to be stored in weatherproof sheds on site in manner to cause least interference with work activities.

1.11 SANITARY FACILITIES

- .1 Provide sanitary facilities for work force in accordance with governing regulations and ordinances.
- .2 Post notices and take precautions as required by local health authorities. Keep area and premises in sanitary condition.

1.12 ELECTRICAL

- .1 For all the duration of the Work, provide temporary electrical power, and cover the costs and maintenance in accordance to rules and regulations in place.

1.13 WATER SUPPLY

- .1 For all the duration of the Work, provide temporary water supply, and cover the costs and maintenance in accordance to rules and regulations in place.

1.14 DRAINAGE

- .1 See section 01 35 43 – Environmental procedures.

1.15 REMOVAL OF TEMPORARY FACILITIES

- .1 No storage in temporary facilities.
- .2 Remove from site all temporary facilities upon request from Departmental Representative.

1.16 PROTECTION AND MAINTENANCE OF TRAFFIC

- .1 Verify adequacy of existing roads and allowable load limit on these roads and follow rules and regulations in place. Contractor: responsible for repair of damage to roads caused by construction operations.
- .2 Provide measures for protection and diversion of traffic, including provision of watch-persons and flag-persons, erection of barricades, placing of lights around and in front of equipment and work, and erection and maintenance of adequate warning, danger, and direction signs.

1.17 PAYMENT

- .1 The cost for temporary facilities is a fixed price as described in section 01 21 00 - Allowances.

Part 2 – PRODUCTS

- .1 Not used

Part 3 – EXECUTION

3.1 TEMPORARY EROSION AND SEDIMENTATION CONTROL

- .1 Provide temporary erosion and sedimentation control measures to prevent soil erosion and discharge of soil-bearing water runoff or airborne dust to adjacent properties and walkways, according to requirements of authorities having jurisdiction, to sediment and erosion control drawings and to sediment and erosion control plan, specific to site, that complies with EPA 832/R-92-005 or requirements of authorities having jurisdiction, whichever is more stringent.
- .2 Inspect, repair, and maintain erosion and sedimentation control measures during construction until permanent vegetation has been established.
- .3 Remove erosion and sedimentation controls and restore and stabilize areas disturbed during removal.

END OF SECTION

Part 1 GENERAL

1.1 REFERENCES

- .1 Conform to these reference standards, in whole or in part as specifically requested in specifications.
- .2 If there is question as to whether products or systems are in conformance with applicable standards, Departmental Representative reserves right to have such products or systems tested to prove or disprove conformance.
- .3 Cost for such testing will be born by Departmental Representative in event of conformance with Contract Documents or by Contractor in event of non-conformance.

1.2 QUALITY

- .1 Products, materials, equipment and articles incorporated in Work shall be new, not damaged or defective, and of best quality for purpose intended. If requested, furnish evidence as to type, source and quality of products provided.
- .2 Defective products, whenever identified prior to completion of Work, will be rejected, regardless of previous inspections. Inspection does not relieve responsibility, but is precaution against oversight or error. Remove and replace defective products at own expense and be responsible for delays and expenses caused by rejection.
- .3 Should disputes arise as to quality or fitness of products, decision rests strictly with Departmental Representative based upon requirements of Contract Documents.
- .4 Unless otherwise indicated in specifications, maintain uniformity of manufacture for any particular or like item throughout building.
- .5 Permanent labels, trademarks and nameplates on products are not acceptable in prominent locations, except where required for operating instructions, or when located in mechanical or electrical rooms.

1.3 AVAILABILITY

- .1 Immediately upon signing Contract, review product delivery requirements and anticipate foreseeable supply delays for items. If delays in supply of products are foreseeable, notify Departmental Representative of such, in order that substitutions or other remedial action may be authorized in ample time to prevent delay in performance of Work.
- .2 In event of failure to notify Departmental Representative at commencement of Work and should it subsequently appear that Work may be delayed for such reason, Departmental Representative reserves right to substitute more readily available products of similar character, at no increase in Contract Price or Contract Time.

1.4 STORAGE, HANDLING AND PROTECTION

- .1 Handle and store products in manner to prevent damage, adulteration, deterioration and soiling and in accordance with manufacturer's instructions when applicable.
- .2 Store packaged or bundled products in original and undamaged condition with manufacturer's seal and labels intact. Do not remove from packaging or bundling until required in Work.
- .3 Store products subject to damage from weather in weatherproof enclosures.
- .4 Keep sand, when used for grout or mortar materials, clean and dry. Store sand on wooden platforms and cover with waterproof tarpaulins during inclement weather.
- .5 Store and mix paints in heated and ventilated room. Remove oily rags and other combustible debris from site daily. Take every precaution necessary to prevent spontaneous combustion.
- .6 Remove and replace damaged products at own expense and to satisfaction of Departmental Representative.
- .7 Touch-up damaged factory finished surfaces to Departmental Representative's satisfaction. Use touch-up materials to match original. Do not paint over name plates.

1.5 TRANSPORTATION

- .1 Pay costs of transportation of products required in performance of Work.
- .2 Transportation cost of products supplied by Owner will be paid for by Departmental Representative. Unload, handle and store such products.

1.6 MANUFACTURER'S INSTRUCTIONS

- .1 Unless otherwise indicated in specifications, install or erect products in accordance with manufacturer's instructions. Do not rely on labels or enclosures provided with products. Obtain written instructions directly from manufacturers.
- .2 Notify Departmental Representative in writing, of conflicts between specifications and manufacturer's instructions, so that Departmental Representative will establish course of action.
- .3 Improper installation or erection of products, due to failure in complying with these requirements, authorizes Departmental Representative to require removal and re-installation at no increase in Contract Price or Contract Time.

1.7 QUALITY OF WORK

- .1 Ensure Quality of Work is of highest standard, executed by workers experienced and skilled in respective duties for which they are employed. Immediately notify Departmental Representative if required Work is such as to make it impractical to produce required results.
- .2 Do not employ anyone unskilled in their required duties. Departmental Representative reserves right to require dismissal from site, workers deemed incompetent or careless.
- .3 Decisions as to standard or fitness of Quality of Work in cases of dispute rest solely with Departmental Representative, whose decision is final.

1.8 CO-ORDINATION

- .1 Ensure co-operation of workers in laying out Work. Maintain efficient and continuous supervision.
- .2 Be responsible for coordination and placement of openings, sleeves and accessories.

1.9 REMEDIAL WORK

- .1 Perform remedial work required to repair or replace parts or portions of Work identified as defective or unacceptable. Co-ordinate adjacent affected Work as required.
- .2 Perform remedial work by specialists familiar with materials affected. Perform in a manner to neither damage nor put at risk any portion of Work.

1.10 LOCATION OF FIXTURES

- .1 Inform Departmental Representative of conflicting installation. Install as directed.

1.11 FASTENINGS

- .1 Provide metal fastenings and accessories in same texture, colour and finish as adjacent materials, unless indicated otherwise.
- .2 Prevent electrolytic action between dissimilar metals and materials.
- .3 Use non-corrosive hot dip galvanized steel fasteners and anchors for securing exterior work, unless stainless steel or other material is specifically requested in affected specification Section.
- .4 Space anchors within individual load limit or shear capacity and ensure they provide positive permanent anchorage. Wood, or any other organic material plugs are not acceptable

1.12 FASTENINGS - EQUIPMENT

- .1 Use fastenings of standard commercial sizes and patterns with material and finish suitable for service.
- .2 Use heavy hexagon heads, semi-finished unless otherwise specified. Use No. 304 stainless steel for exterior areas.
- .3 Bolts may not project more than one diameter beyond nuts.
- .4 Use plain type washers on equipment, sheet metal and soft gasket lock type washers where vibrations occur. Use resilient washers with stainless steel.

1.13 EXISTING UTILITIES

- .1 When breaking into or connecting to existing services or utilities, execute Work at times directed by local governing authorities, with minimum of disturbance to Work, and/or building occupants and pedestrian and vehicular traffic.
- .2 Protect, relocate or maintain existing active services. When services are encountered, cap off in manner approved by authority having jurisdiction. Stake and record location of capped service.

Part 2 PRODUCTS

- .1 Not used.

Part 3 EXECUTION

- .1 Not used.

END OF SECTION

Part 1 - GENERAL

1.1 REFERENCES

- .1 Owner's identification of existing survey control points and property limits.

1.2 QUALIFICATIONS OF SURVEYOR

- .1 Qualified registered land surveyor, licensed to practice in Place of Work, acceptable to Departmental Representative.

1.3 SURVEY REFERENCE POINTS

- .1 Existing base horizontal and vertical control points are designated on drawings.
- .2 Locate, confirm and protect control points prior to starting site work. Preserve permanent reference points during construction.
- .3 The 3 reference points located on the runway will have to be replaced by new ones, adjusted and levelled with the asphalt overlay.
- .4 The Contractor must hire a registered surveyor to update the reference point record, in accordance with the requirements from the MRNQ (Ministère des Ressources naturelles du Québec).
- .5 Require surveyor to replace control points in accordance with original survey control.

1.4 SURVEY REQUIREMENTS

- .1 Establish two permanent bench marks on site, referenced to established bench marks by survey control points. Record locations, with horizontal and vertical data in Project Record Documents.
- .2 Establish lines and levels, locate and lay out, by instrumentation.
- .3 Stake for grading, fill placement.
- .4 Stake slopes.
- .5 Establish pipe invert elevations.
- .6 Stake batter boards for foundations.
- .7 Establish foundation elevations.
- .8 Establish lines and levels for mechanical and electrical work.

1.5 EXISTING UTILITIES

- .1 Before commencing work, establish location and extent of service lines in area of Work and notify Departmental Representative of findings.
- .2 Remove abandoned service lines within 2m of structures. Cap or otherwise seal lines at cut-off points as directed by Departmental Representative.

1.6 LOCATION OF EQUIPMENT AND FIXTURES

- .1 Location of equipment, fixtures and outlets indicated or specified are to be considered as approximate.
- .2 Locate equipment, fixtures and distribution systems to provide minimum interference and maximum usable space and in accordance with manufacturer's recommendations for safety, access and maintenance.
- .3 Inform Departmental Representative of impending installation and obtain approval for actual location.
- .4 Submit field drawings to indicate relative position of various services and equipment when required by Departmental Representative.

1.7 RECORDS

- .1 Maintain a complete, accurate log of control and survey work as it progresses.
- .2 On completion of foundations and major site improvements, prepare a certified survey showing dimensions, locations, angles and elevations of Work.
- .3 Record locations of maintained, re-routed and abandoned service lines.

1.8 SUBMITTALS

- .1 Submit name and address of Surveyor to Departmental Representative.
- .2 On request of Departmental Representative, submit documentation to verify accuracy of field engineering work.
- .3 Submit certificate signed by surveyor certifying and noting those elevations and locations of completed Work that conform and do not conform with Contract Documents.

1.9 SUBSURFACE CONDITIONS

- .1 Promptly notify Consultant in writing if subsurface conditions at Place of Work differ materially from those indicated in Contract Documents, or a reasonable assumption of probable conditions based thereon.
- .2 After prompt investigation, should Consultant determine that conditions do differ materially, instructions will be issued for changes in Work as provided in Changes and Change Orders.

Part 2 – PRODUCTS

- .1 Not used.

Part 3 – EXECUTION

- .1 Not used.

END OF SECTION

Part 1 GENERAL

1.1 PROJECT CLEANLINESS

- .1 Maintain Work in tidy condition, free from accumulation of waste products and debris, including that caused by Owner or other Contractors.
- .2 Remove waste materials from site at daily regularly scheduled times or dispose of as directed by Departmental Representative. Do not burn waste materials on site, unless approved by Departmental Representative.
- .3 Clear snow and ice from access to building, bank/pile snow in designated areas only.
- .4 Make arrangements with and obtain permits from authorities having jurisdiction for disposal of waste and debris.
- .5 Provide on-site containers for collection of waste materials and debris.
- .6 Provide and use marked separate bins for recycling.
- .7 Store volatile waste in covered metal containers, and remove from premises at end of each working day.
- .8 Provide adequate ventilation during use of volatile or noxious substances. Use of building ventilation systems is not permitted for this purpose.
- .9 Use only cleaning materials recommended by manufacturer of surface to be cleaned, and as recommended by cleaning material manufacturer.
- .10 Schedule cleaning operations so that resulting dust, debris and other contaminants will not fall on wet, newly painted surfaces nor contaminate building systems.

1.2 FINAL CLEANING

- .1 When Work is Substantially Performed remove surplus products, tools, construction machinery and equipment not required for performance of remaining Work.
- .2 Remove waste products and debris other than that caused by others, and leave Work clean and suitable for occupancy.
- .3 Prior to final review remove surplus products, tools, construction machinery and equipment.
- .4 Remove waste products and debris including that caused by Owner or other Contractors.
- .5 Remove waste materials from site at regularly scheduled times or dispose of as directed by Departmental Representative. Do not burn waste materials on site, unless approved by Departmental Representative.
- .6 Make arrangements with and obtain permits from authorities having jurisdiction for disposal of waste and debris.

- .7 Clean lighting reflectors, lenses, and other lighting surfaces.
- .8 Vacuum clean and dust building interiors, behind grilles, louvres and screens.
- .9 Inspect finishes, fitments and equipment and ensure specified workmanship and operation.
- .10 Remove dirt and other disfiguration from exterior surfaces..
- .11 Sweep and wash clean paved areas.

1.3 WASTE MANAGEMENT AND DISPOSAL

- .1 Separate waste materials for reuse and recycling, according to section 01 74 21 – Construction/demolition waste management and disposal.

Part 2 PRODUCTS

- .2 Not used.

Part 3 EXECUTION

- .3 Not used.

END OF SECTION

Part 1 GENERAL

1.1 WASTE MANAGEMENT GOALS

- .1 Prior to start of Work conduct meeting with Departmental Representative to review and discuss PWGSC's Waste Management Plan and Goals.
- .2 Accomplish maximum control of solid construction waste.
- .3 Preserve environment and prevent pollution and environment damage.

1.2 DEFINITIONS

- .1 Class III: non-hazardous waste - construction renovation and demolition waste.
- .2 Cost/Revenue Analysis Workplan (CRAW): based on information from WRW, and intended as financial tracking tool for determining economic status of waste management practices.
- .3 Demolition Waste Audit (DWA): relates to actual waste generated from project.
- .4 Inert Fill: inert waste - exclusively asphalt and concrete.
- .5 Materials Source Separation Program (MSSP): consists of series of ongoing activities to separate reusable and recyclable waste material into material categories from other types of waste at point of generation.
- .6 Recyclable: ability of product or material to be recovered at end of its life cycle and re-manufactured into new product for reuse.
- .7 Recycle: process by which waste and recyclable materials are transformed or collected for purpose of being transferred into new products.
- .8 Recycling: process of sorting, cleansing, treating and reconstituting solid waste and other discarded materials for purpose of using in altered form. Recycling does not include burning, incinerating, or thermally destroying waste.
- .9 Reuse: repeated use of product in same form but not necessarily for same purpose. Reuse includes:
 - .1 Salvaging reusable materials from re-modelling projects, before demolition stage, for resale, reuse on current project or for storage for use on future projects.
 - .2 Returning reusable items including pallets or unused products to vendors.
- .10 Salvage: removal of structural and non-structural materials from deconstruction/disassembly projects for purpose of reuse or recycling.
- .11 Separate Condition: refers to waste sorted into individual types.
- .12 Source Separation: acts of keeping different types of waste materials separate beginning from first time they became waste.

- .13 Waste Audit (WA): detailed inventory of materials in building. Involves quantifying by volume/weight amounts of materials and wastes generated during construction, demolition, deconstruction, or renovation project. Indicates quantities of reuse, recycling and landfill. Refer to Schedule A.
- .14 Waste Management Co-ordinator (WMC) : contractor representative responsible for supervising waste management activities as well as coordinating related, required submittal and reporting requirements.
- .15 Waste Reduction Workplan (WRW): written report which addresses opportunities for reduction, reuse, or recycling of materials. Refer to Schedule B. WRW is based on information acquired from WA (Schedule A).

1.3 DOCUMENTS

- .1 Maintain at job site, one copy of following documents:
 - .1 Waste Reduction Workplan.
 - .2 Material Source Separation Plan.

1.4 SUBMITTALS

- .1 Submittals in accordance with Section 01 33 00 - Submittal Procedures.
- .2 Prepare and submit following prior to project start-up:
 - .1 Submit 2 copies of completed Waste Reduction Workplan (WRW): Schedule B.
 - .2 Submit 2 copies of Materials Source Separation Program (MSSP) description.
- .3 Submit before final payment summary of waste materials salvaged for reuse, recycling or disposal by project using deconstruction/disassembly material audit form.
 - .1 Failure to submit could result in hold back of final payment.
 - .2 Provide receipts, scale tickets, waybills, and show quantities and types of materials reused, recycled, co-mingled and separated off-site or disposed of.
 - .3 For each material reused, sold or recycled from project, include amount in tonnes, quantities by number, type and size of items and the destination.
 - .4 For each material land filled or incinerated from project, include amount in tonnes of material and identity of landfill, incinerator or transfer station.

1.5 WASTE REDUCTION WORKPLAN (WRW)

- .1 Prepare WRW prior to project start-up.
- .2 WRW should include but not limited to:
 - .1 Destination of materials listed.
 - .2 Deconstruction/disassembly techniques and sequencing.
 - .3 Schedule for deconstruction/disassembly.
 - .4 Location.
 - .5 Security.
 - .6 Protection.

- .7 Clear labelling of storage areas.
- .8 Details on materials handling and removal procedures.
- .9 Quantities for materials to be salvaged for reuse or recycled and materials sent to landfill.
- .3 Structure WRW to prioritize actions and follow 3R's hierarchy, with Reduction as first priority, followed by Reuse, then Recycle.
- .4 Describe management of waste.
- .5 Post WRW or summary where workers at site are able to review content.
- .6 Set realistic goals for waste reduction, recognize existing barriers and develop strategies to overcome these barriers.
- .7 Monitor and report on waste reduction by documenting total volume and cost of actual waste removed from project.

1.6 MATERIALS SOURCE SEPARATION PROGRAM (MSSP)

- .1 Prepare MSSP and have ready for use prior to project start-up.
- .2 Implement MSSP for waste generated on project in compliance with approved methods and as reviewed by Departmental Representative.
- .3 Provide on-site facilities for collection, handling, and storage of anticipated quantities of reusable and recyclable materials.
- .4 Provide containers to deposit reusable and recyclable materials.
- .5 Locate containers in locations, to facilitate deposit of materials without hindering daily operations.
- .6 Locate separated materials in areas which minimize material damage.
- .7 Collect, handle, store on-site, and transport off-site, salvaged materials in separate condition.
 - .1 Transport to approved and authorized recycling facility.
- .8 Collect, handle, store on-site, and transport off-site, salvaged materials in combined condition.
 - .1 Ship materials to site operating under Certificate of Approval.
 - .2 Materials must be immediately separated into required categories for reuse or recycling.

1.7 STORAGE, HANDLING AND PROTECTION

- .1 Store, materials to be reused, recycled and salvaged in locations as directed by Departmental Representative.
- .2 Unless specified otherwise, materials for removal become Contractor's property.
- .3 Protect, stockpile, store and catalogue salvaged items.
- .4 Separate non-salvageable materials from salvaged items. Transport and deliver non-salvageable items to licensed disposal facility.
- .5 Protect structural components not removed for demolition from movement or damage.
- .6 Support affected structures. If safety of building is endangered, cease operations and immediately notify Departmental Representative.
- .7 Protect surface drainage, mechanical and electrical from damage and blockage.
- .8 Separate and store materials produced during dismantling of structures in designated areas.
- .9 Prevent contamination of materials to be salvaged and recycled and handle materials in accordance with requirements for acceptance by designated facilities.
 - .1 On-site source separation is recommended.
 - .2 Remove co-mingled materials to off-site processing facility for separation.
 - .3 Provide waybills for separated materials.

1.8 DISPOSAL OF WASTES

- .1 Do not bury rubbish or waste materials.
- .2 Do not dispose of waste, volatile materials, mineral spirits, oil or paint thinner into waterways, storm, or sanitary sewers.
- .3 Keep records of construction waste including:
 - .1 Number and size of bins.
 - .2 Waste type of each bin.
 - .3 Total tonnage generated.
 - .4 Tonnage reused or recycled.
 - .5 Reused or recycled waste destination.
- .4 Remove materials from deconstruction as deconstruction/disassembly Work progresses.
- .5 Prepare project summary to verify destination and quantities on a material-by-material basis as identified in pre-demolition material audit.

1.9 USE OF SITE AND FACILITIES

- .1 Execute work with least possible interference or disturbance to normal use of premises.
- .2 Provide temporary security measures approved by Departmental Representative.

1.10 SCHEDULING

- .1 Co-ordinate Work with other activities at site to ensure timely and orderly progress of Work.

Part 2 PRODUCTS

1.11 NOT USED

- .1 Not Used.

Part 3 EXECUTION

1.12 APPLICATION

- .1 Do Work in compliance with WRW.
- .2 Handle waste materials not reused, salvaged, or recycled in accordance with appropriate regulations and codes.

1.13 CLEANING

- .1 Remove tools and waste materials on completion of Work, and leave work area in clean and orderly condition.
- .2 Clean-up work area as work progresses.
- .3 Source separate materials to be reused/recycled into specified sort areas.

1.14 DIVERSION OF MATERIALS

- .1 From following list, separate materials from general waste stream and stockpile in separate piles or containers, as reviewed by Departmental Representative, and consistent with applicable fire regulations.
 - .1 Mark containers or stockpile areas.
 - .2 Provide instruction on disposal practices.
- .2 On-site sale of reusable/recyclable materials is not permitted.

.3 Demolition Waste:

Material Type	Recommended Diversion %	Actual Diversion %
Granular materials surplus	100%	Reuse or stockpile at location indicated by Departmental Representative.
Cut excavation material surplus	100%	Reuse or stockpile at location indicated by Departmental Representative.
Asphalt pavement removal residu	100%	Dispose off site according to Departmental Representative instructions according to regulations in effect..
Electrical Equipment	100%	Dispose to a recycling plant off site
Metals	100%	Dispose to a recycling plant off site
Other		

.4 Construction Waste:

Material Type	Recommended Diversion %	Actual Diversion %
Cardboard	100%	Dispose to a recycling plant off site
Plastic Packaging	100%	Dispose to a recycling plant off site
Rubble	100%	Dispose to a recycling plant off site
Steel	100%	Dispose to a recycling plant off site
Wood (uncontaminated)	100%	Dispose to a recycling plant off site
Other		[]

1.15 WASTE REDUCTION WORKPLAN (WRW)

.1 Schedule B:

(1) Material Category	(2) Person(s) Respon- sible	(3) Total Quantity of Waste (unit)	(4) Reused Amount (units) Projected	Actual	(5) Recycled Amount (unit) Projected	Actual	(6) Material(s)) Destina- tion
Wood and Plastics Material Descriptio n							
Chutes							
Warped							

(1) Material Category	(2) Person(s) Respon- sible	(3) Total Quantity of Waste (unit)	(4) Reused Amount (units) Projected	Actual	(5) Recycled Amount (unit) Projected	Actual	(6) Material(s)) Destina- tion
Pallet Forms							
Plastic Packag ing							
Card- board Packag ing							
Glass							
Wood							
Metal							
Other							

1.16 CANADIAN GOVERNMENTAL DEPARTMENTS CHIEF RESPONSIBILITY FOR THE ENVIRONMENT

.1 Schedule E - Government Chief Responsibility for the Environment:

Province	Address	General Inquires	Fax
Québec	Ministère de l'Environnement et de la Faune, Siège social 150, boul, René-Lévesque Est Québec QC G1R 4Y1	418-643-3127 800- 561-1616	418-646-5974
	Conseil de la conservation et de l'environnement 800, place d'Youville, 19e étage Québec QC G1R 3P4	418-643-3818	

END OF SECTION

Part 1 - GENERAL

1.1 RÉFÉRENCES

- .1 Canadian Environmental Protection Act (CEPA)
 - .1 SOR/2008-197, Storage Tank Systems for Petroleum Products and Allied Petroleum Products Regulations.

1.2 ADMINISTRATIVE REQUIREMENTS

- .1 Pre-warranty Meeting:
 - .1 Convene meeting one week prior to contract completion with contractor's representative and Departmental Representative to:
 - .1 Verify Project requirements.
 - .2 Review manufacturer's installation instructions and warranty requirements.
 - .2 Departmental Representative to establish communication procedures for:
 - .1 Notifying construction warranty defects.
 - .2 Determine priorities for type of defects.
 - .3 Determine reasonable response time.
 - .3 Contact information for bonded and licensed company for warranty work action: provide name, telephone number and address of company authorized for construction warranty work action.
 - .4 Ensure contact is located within local service area of warranted construction, is continuously available, and is responsive to inquiries for warranty work action.

1.3 ACTION AND INFORMATIONAL SUBMITTALS

- .1 Provide submittals in accordance with Section 01 33 00 - Submittal Procedures.
- .2 Two weeks prior to Substantial Performance of the Work, submit to the Departmental Representative, four final copies of operating and maintenance manuals in English and French.
- .3 Provide spare parts, maintenance materials and special tools of same quality and manufacture as products provided in Work.
- .4 Provide evidence, if requested, for type, source and quality of products supplied.

1.4 FORMAT

- .1 Organize data as instructional manual.
- .2 Binders: vinyl, hard covered, 3 'D' ring, loose leaf 219 x 279 mm with spine and face pockets.
- .3 When multiple binders are used correlate data into related consistent groupings.
 - .1 Identify contents of each binder on spine.
- .4 Cover: identify each binder with type or printed title 'Project Record Documents'; list title of project and identify subject matter of contents.

- .5 Arrange content by systems and process flow under Section numbers and sequence of Table of Contents.
- .6 Provide tabbed fly leaf for each separate product and system, with typed description of product and major component parts of equipment.
- .7 Text: manufacturer's printed data, or typewritten data.
- .8 Drawings: provide with reinforced punched binder tab.
 - .1 Bind in with text; fold larger drawings to size of text pages.
- .9 Provide 1:1 scaled CAD files in dwg format on CD.

1.5 CONTENTS – PROJECT RECORD DOCUMENTS

- .1 Table of Contents for Each Volume: provide title of project;
 - .1 Date of submission; names.
 - .2 Addresses, and telephone numbers of Consultant and Contractor with name of responsible parties.
 - .3 Schedule of products and systems, indexed to content of volume.
- .2 For each product or system:
 - .1 List names, addresses and telephone numbers of subcontractors and suppliers, including local source of supplies and replacement parts.
- .3 Product Data: mark each sheet to identify specific products and component parts, and data applicable to installation; delete inapplicable information.
- .4 Drawings: supplement product data to illustrate relations of component parts of equipment and systems, to show control and flow diagrams.
- .5 Typewritten Text: as required to supplement product data.
 - .1 Provide logical sequence of instructions for each procedure, incorporating manufacturer's instructions specified in Section 01 45 00 - Quality Control.
- .6 Training: refer to Section 01 79 00 - Demonstration and Training.

1.6 AS-BUILT DOCUMENTS AND SAMPLES

- .1 Maintain at site for Departmental Representative one record copy of:
 - .1 Contract Drawings.
 - .2 Specifications.
 - .3 Addenda.
 - .4 Change Orders and other modifications to Contract.
 - .5 Reviewed shop drawings, product data, and samples.
 - .6 Field test records.
 - .7 Inspection certificates.
 - .8 Manufacturer's certificates.
- .2 Store record documents and samples in field office apart from documents used for construction.
 - .1 Provide files, racks, and secure storage.

- .3 Label record documents and file in accordance with Section number listings in List of Contents of this Project Manual.
 - .1 Label each document "PROJECT RECORD" in neat, large, printed letters.
- .4 Maintain record documents in clean, dry and legible condition.
 - .1 Do not use record documents for construction purposes.
- .5 Keep record documents and samples available for inspection by Departmental Representative.

1.7 RECORDING INFORMATION ON PROJECT RECORD DOCUMENTS

- .1 Record information on set of black line opaque drawings, and in copy of Project Manual, provided by Departmental Representative.
- .2 Use felt tip marking pens, maintaining separate colours for each major system, for recording information.
- .3 Record information concurrently with construction progress.
 - .1 Do not conceal Work until required information is recorded.
- .4 Contract Drawings and shop drawings: mark each item to record actual construction, including:
 - .1 Measured horizontal and vertical locations of underground utilities and appurtenances, referenced to permanent surface improvements.
 - .2 Measured locations of internal utilities and appurtenances, referenced to visible and accessible features of construction.
 - .3 Field changes of dimension and detail.
 - .4 Changes made by change orders.
 - .5 Details not on original Contract Drawings.
 - .6 References to related shop drawings and modifications.
- .5 Specifications: mark each item to record actual construction, including:
 - .1 Manufacturer, trade name, and catalogue number of each product actually installed, particularly optional items and substitute items.
 - .2 Changes made by Addenda and change orders.
- .6 Other Documents: maintain manufacturer's certifications, inspection certifications, and field test records, required by individual specifications sections.
- .7 Provide digital photos, if requested, for site records.

1.8 FINAL SURVEY

- .1 Submit final site survey certificate in accordance with Section 01 71 00 - Examination and Preparation, certifying that elevations and locations of completed Work are in conformance, or non-conformance with Contract Documents.

1.9 EQUIPMENT AND SYSTEMS

- .1 For each item of equipment and each system include description of unit or system, and component parts.
 - .1 Give function, normal operation characteristics and limiting conditions.
 - .2 Include performance curves, with engineering data and tests, and complete nomenclature and commercial number of replaceable parts.
- .2 Panel board circuit directories: provide electrical service characteristics, controls, and communications.
- .3 Include installed colour coded wiring diagrams.
- .4 Operating Procedures: include start-up, break-in, and routine normal operating instructions and sequences.
 - .1 Include regulation, control, stopping, shut-down, and emergency instructions.
 - .2 Include summer, winter, and any special operating instructions.
- .5 Maintenance Requirements: include routine procedures and guide for trouble-shooting; disassembly, repair, and reassembly instructions; and alignment, adjusting, balancing, and checking instructions.
- .6 Provide servicing and lubrication schedule, and list of lubricants required.
- .7 Include manufacturer's printed operation and maintenance instructions.
- .8 Include sequence of operation by controls manufacturer.
- .9 Provide original manufacturer's parts list, illustrations, assembly drawings, and diagrams required for maintenance.
- .10 Provide installed control diagrams by controls manufacturer.
- .11 Provide list of original manufacturer's spare parts, current prices, and recommended quantities to be maintained in storage.
- .12 Include test and balancing reports as specified in Section 01 45 00 - Quality Control.
- .13 Additional requirements: as specified in individual specification sections

1.10 MATERIALS AND FINISHES

- .1 Building products, applied materials, and finishes: include product data, with catalogue number, size, composition, and colour and texture designations.
 - .1 Provide information for re-ordering custom manufactured products.
- .2 Instructions for cleaning agents and methods, precautions against detrimental agents and methods, and recommended schedule for cleaning and maintenance.
- .3 Moisture-protection and weather-exposed products: include manufacturer's recommendations for cleaning agents and methods, precautions against detrimental agents and methods, and recommended schedule for cleaning and maintenance.
- .4 Additional requirements: as specified in individual specifications sections.

1.11 MAINTENANCE MATERIALS

- .1 Spare Parts:
 - .1 Provide spare parts, in quantities specified in individual specification sections.
 - .2 Provide items of same manufacture and quality as items in Work.
 - .3 Deliver to location as directed; place and store.
 - .4 Receive and catalogue items.
 - .1 Submit inventory listing to Departmental Representative.
 - .2 Include approved listings in Maintenance Manual.
 - .5 Obtain receipt for delivered products and submit prior to final payment.
- .2 Extra Stock Materials:
 - .1 Provide maintenance and extra materials, in quantities specified in individual specification sections.
 - .2 Provide items of same manufacture and quality as items in Work.
 - .3 Deliver to location as directed; place and store.
 - .4 Receive and catalogue items.
 - .1 Submit inventory listing to Departmental Representative.
 - .2 Include approved listings in Maintenance Manual.

1.12 DELIVERY, STORAGE AND HANDLING

- .1 Store spare parts, maintenance materials, and special tools in manner to prevent damage or deterioration.
- .2 Store in original and undamaged condition with manufacturer's seal and labels intact.
- .3 Store components subject to damage from weather in weatherproof enclosures.
- .4 Store paints and freezable materials in a heated and ventilated room.
- .5 Remove and replace damaged products at own expense and for review by Departmental Representative.

1.13 WARRANTIES AND BONDS

- .1 Develop warranty management plan to contain information relevant to Warranties.
- .2 Submit warranty management plan, 30 days before planned pre-warranty conference, to Departmental Representative approval.
- .3 Warranty management plan to include required actions and documents to assure that Departmental Representative receives warranties to which it is entitled.
- .4 Provide plan in narrative form and contain sufficient detail to make it suitable for use by future maintenance and repair personnel.
- .5 Submit, warranty information made available during construction phase, to Departmental Representative for approval prior to each monthly pay estimate.
- .6 Assemble approved information in binder, submit upon acceptance of work and organize binder as follows:

- .1 Separate each warranty or bond with index tab sheets keyed to Table of Contents listing.
- .2 List subcontractor, supplier, and manufacturer, with name, address, and telephone number of responsible principal.
- .3 Obtain warranties and bonds, executed in duplicate by subcontractors, suppliers, and manufacturers, within ten days after completion of applicable item of work.
- .4 Verify that documents are in proper form, contain full information, and are notarized.
- .5 Co-execute submittals when required.
- .6 Retain warranties and bonds until time specified for submittal.
- .7 Except for items put into use with Owner's permission, leave date of beginning of time of warranty until Date of Substantial Performance is determined.
- .8 Conduct joint 4 month and 9 month warranty inspection, measured from time of acceptance, by Departmental Representative.
- .9 Include information contained in warranty management plan as follows:
 - .1 Roles and responsibilities of personnel associated with warranty process, including points of contact and telephone numbers within the organizations of Contractors, subcontractors, manufacturers or suppliers involved.
 - .2 Provide list for each warranted equipment, item, feature of construction or system indicating:
 - .1 Name of item.
 - .2 Model and serial numbers.
 - .3 Location where installed.
 - .4 Name and phone numbers of manufacturers or suppliers.
 - .5 Names, addresses and telephone numbers of sources of spare parts.
 - .6 Warranties and terms of warranty: include one-year overall warranty of construction. Indicate items that have extended warranties and show separate warranty expiration dates.
 - .7 Cross-reference to warranty certificates as applicable.
 - .8 Starting point and duration of warranty period.
 - .9 Summary of maintenance procedures required to continue warranty in force.
 - .10 Cross-Reference to specific pertinent Operation and Maintenance manuals.
 - .11 Organization, names and phone numbers of persons to call for warranty service.
 - .12 Typical response time and repair time expected for various warranted equipment.
 - .3 Contractor's plans for attendance at 4 and 9 month post-construction warranty inspections.
 - .4 Procedure and status of tagging of equipment covered by extended warranties.
 - .5 Post copies of instructions near selected pieces of equipment where operation is critical for warranty and/or safety reasons.

- .10 Respond in timely manner to oral or written notification of required construction warranty repair work.
- .11 Written verification to follow oral instructions.
 - .1 Failure to respond will be cause for the Departmental Representative to proceed with action against Contractor.

1.14 WARRANTY TAGS

- .1 Tag, at time of installation, each warranted item. Provide durable, oil and water resistant tag approved by Departmental Representative.
- .2 Attach tags with copper wire and spray with waterproof silicone coating.
- .3 Leave date of acceptance until project is accepted for occupancy.
- .4 Indicate following information on tag:
 - .1 Type of product/material.
 - .2 Model number.
 - .3 Serial number.
 - .4 Contract number.
 - .5 Warranty period.
 - .6 Inspector's signature.
 - .7 Construction Contractor.

Part 2 – PRODUCTS

- .1 Not used

Part 3 – EXECUTION

- .1 Not used

END OF SECTION

Part 1 - GENERAL

1.1 ADMINISTRATIVE REQUIREMENTS

- .1 Demonstrate scheduled operation and maintenance of equipment and systems to Owner's personnel two weeks prior to date of final inspection.
- .2 Owner: provide list of personnel to receive instructions, and co-ordinate their attendance at agreed-upon times.
- .3 Preparation:
 - .1 Verify conditions for demonstration and instructions comply with requirements.
 - .2 Verify designated personnel are present.
 - .3 Ensure equipment has been inspected and put into operation.
 - .4 Ensure testing, adjusting, and balancing has been performed and equipment and systems are fully operational.
- .4 Demonstration and Instructions:
 - .1 Demonstrate start-up, operation, control, adjustment, trouble-shooting, servicing, and maintenance of each item of equipment at scheduled times, at the equipment location.
 - .2 Instruct personnel in phases of operation and maintenance using operation and maintenance manuals as basis of instruction.
 - .3 Review contents of manual in detail to explain aspects of operation and maintenance.
 - .4 Prepare and insert additional data in operations and maintenance manuals when needed during instructions.

1.2 ACTION AND INFORMATIONAL SUBMITTALS

- .1 Provide submittals in accordance with Section 01 33 00 - Submittal Procedures.
- .2 Submit schedule of time and date for demonstration of each item of equipment and each system two weeks prior to designated dates, for Departmental Representative's approval.
- .3 Submit reports within one week after completion of demonstration, that demonstration and instructions have been satisfactorily completed.
- .4 Give time and date of each demonstration, with list of persons present.
- .5 Provide copies of completed operation and maintenance manuals for use in demonstrations and instructions.

1.3 QUALITY ASSURANCE

- .1 When specified in individual Sections requiring manufacturer to provide authorized representative to demonstrate operation of equipment and systems:
 - .1 Instruct Owner's personnel.
 - .2 Provide written report that demonstration and instructions have been completed.

Part 2 – PRODUCTS

.1 Not used.

Part 3 – EXECUTION

.1 Not used

END OF SECTION