



Existing CCTV System - Block Diagram

CCTV Notes

1. REMOVE ALL SIX MONITORS FROM ROOM 102.
2. REMOVE BOTH NVUS UNITS (NETWORK VIDEO USER STATION) FROM INSIDE THE CONSOLE IN ROOM 102 AND HAND THEM OVER TO THE DEPARTMENTAL REPRESENTATIVE.
3. MONITORS IN ROOM 100 TO REMAIN. THESE MONITORS ARE INTENDED TO DISPLAY SPECIFIC CAMERAS ON THE SYSTEM.
4. NVR UNITS (NETWORK VIDEO RECORDER) TO REMAIN.
5. PROVIDE NEW KEYBOARD AT NEW CONTROL CONSOLE IN ROOM 100. ROUTE NEW CABLING FROM CCTV CABINET IN ROOM 122 TO NEW CONTROL STATION IN ROOM 100. ROUTE CABLING THROUGH CEILING SPACE AND DOWN NEW RACEWAY AT THE NEW CONTROL CONSOLE.
6. PROVIDE AS-BUILT DRAWING OF CCTV SYSTEM ON THIS DRAWING SHOWING ADDITIONAL DETAIL.
7. REPROGRAM SYSTEM TO SUIT NEW CONFIGURATION. DISCUSS DETAILS OF REQUIRED PROGRAMMING WITH DEPARTMENTAL REPRESENTATIVE.
8. REMOVE ALL REDUNDANT CABLING.
9. TURN OVER ALL REMOVED CCTV EQUIPMENT (NOT CABLING) TO THE DEPARTMENTAL REPRESENTATIVE.

Revision/	Issue for Tender	June 2014
Revision/	Description/Description	Date/Date
Client/Client		
Correctional Service Canada Metchosin BC William Head Institution		
Project title/Titre du projet		
Principal Entrance Renovations		
Consultant Signature Only		
Designed by/Concept par G. Robertshaw		
Drawn by/Dessiné par D. Burns May 2014		
PWGSC Project Manager/Administrateur de Projets TPSGC S. Leslie		
A/Regional Manager, Architectural and Engineering Services Gestionnaire régionale, Services d'architectural et de génie, TPSGC O. Klutas		
Drawing title/Titre du dessin		
Electrical CCTV System		
Project No./No. du projet	Sheet/Fauille	Revision no./La Révision no.
R.066815.001	E12	

