
Part 1 ADDENDUM NO.2

1.1 General

- .1 This Addendum is issued prior to tender closing and shall become an integral part of the Tender, Specifications, Drawings and Contract Documents for this project.
- .2 In the event of conflicts between the various Contract Documents, the order of precedence shall be as stipulated in the General Conditions of the Contract, except that this Addendum shall take overall precedence.

Part 2 Clarifications

- 2.1 It Must be noted that not all of the electrical may be on the slab in the attic space. Some of the electrical may be in the slab and x-raying may be required.**
- 2.2 A question asked during the site visit was that were the cores filled in the existing masonry walls. Answer: In reviewing the existing drawings the walls it was un-clear if the cores were filled contractor to assume that the cores were filled.**
- 2.3 The underground parkade area is not to be used for storage of any construction materials without the consent of the Project Manager**
- 2.4 Half of the parking lot to the rear of the detachment may be used to store materials during construction. Contractor to discuss with the project manager at the start of the project to identify location.**
- 2.5 Fire Alarm: It must be noted that the fire alarm must be certified at the end of each phase.**
- 2.6 Millwork: It should be clarified that only the counter tops are to be stainless steel. The rest of the cabinets are to be conventional.**

Part 3 Drawings

3.1 A2.0 Main Floor Plan

- .1 Added approximate location of hording required for phase 1 and phase 2 to drawings
- .2 See attached drawings A2.0 Rev 02

Part 4 Equals

- 4.1 Eh Price – Backdraft Dampers and fire dampers - Approved**

END OF SECTION

