

PART 1 - GENERAL

- |   |    |   |
|---|----|---|
| <u>1.1 GENERAL</u>                      | .1 | Conduct cleaning and disposal operations to comply with local ordinances and anti-pollution laws.   |
|   | .2 | Store volatile waste in covered metal containers, and remove from premises at end of each working day.  |
|   | .3 | Prevent accumulation of wastes which create hazardous conditions.   |
|   | .4 | Provide adequate ventilation during use of volatile or noxious substances.  |
| <u>1.2 MATERIALS</u>                    | .1 | Use only cleaning materials recommended by manufacturer of surface to be cleaned, and as recommended by cleaning material manufacturer.                 |
| <u>1.3 CLEANING DURING CONSTRUCTION</u> | .1 | Maintain project grounds and public properties in a tidy condition, free from accumulations of waste material and debris. Clean areas on a daily basis. |
|   | .2 | Provide on-site garbage containers for collection of waste materials and debris.  |
|   | .3 | Remove waste materials and debris from site on a daily basis.   |
| <u>1.4 FINAL CLEANING</u>               | .1 | In preparation for acceptance of the Work perform final cleaning.   |

	CLEANING	Section 01 74 11
Launchway Construction		Page 2
Bird Cove, NL		
P/N: F6143-140007		2014-07-07

- .2 Inspect finishes, fitments and equipment.  
Ensure specified workmanship and operation.
- .3 Broom clean exterior paved and concrete  
surfaces; rake clean other surfaces of  
grounds.