

**CANADIAN MUSEUM OF IMMIGRATION
AT PIER 21 - EXPANSION**

Halifax, Nova Scotia
Project #: 13-005
Aug 11, 2014

ADDENDUM 04

Page 1

The following information supplements and / or supersedes the bid documents issue on July 14th, 2014-07-31. This addendum forms part of the contract documents and is to be read, interpreted, and coordinated with all other parts. The cost of all contained herein is to be included in the contract sum. The following revisions supersede the information contained in the original drawings and specifications issued for the above named project to the extent referenced and shall become part thereof. Acknowledge receipt of this Addendum by inserting its number and date on the Tender Form. Failure to do so may subject to disqualification.

TABLE OF CONTENTS:

Mechanical Addendum 04

Reference Drawings V101, V102:

All demolition and new ductwork shown on the Phase 2/3 side of the phase line (grids 36-16) shall be included in the phase 2 contract pricing. Phase 1 ductwork shall stop at the phase line and be temporarily capped for reconnection. The existing air handler AHU-9 must remain operational during Phase 1 construction, shut down of the unit and connection to phase 1 ductwork shall occur as part of phase 2 and be closely coordinated with CMIP.