

DRAWING E1 SYMBOL LEGEND

—	REMOVE EXISTING CONDUIT AND WIRING
—	EXISTING CONDUIT AND WIRING TO REMAIN
+ —	SUPPLY & INSTALL NEW CONDUIT AND WIRING
— +	SUPPLY & INSTALL NEW AC90 CABLE TO CONNECT LIGHT FIXTURE
○	SUPPLY & INSTALL NEW JUNCTION BOX
□	EXISTING SURFACE MOUNTED LIGHT FIXTURE REMOVED AND STORED ON SITE BY OTHERS (N.I.C.). THIS CONTRACTOR TO REMOVE ALL FIXTURES FROM SITE
○	EXISTING SURFACE MOUNTED FLUORESCENT FIXTURE TO REMAIN
□	SUPPLY & INSTALL NEW TYPE 'A' FLUORESCENT FIXTURE RECESSED IN NEW T-BAR CEILING
□	INSTALL NEW TYPE 'B' FLUORESCENT FIXTURE SUPPLIED BY PWSC.
□	SUPPLY & INSTALL TWO NEW 32W - T8, 4100K FLUORESCENT LAMPS FOR EACH FIXTURE
□	LIGHT FIXTURE CONNECTED TO UNSWITCHED NIGHT LIGHT CIRCUIT
□	REMOVE EXISTING H.L.D. WALL MOUNTED FIXTURE AND RE-INSTALL AS INDICATED ON NEW LIGHTING PLAN
RE-INSTALLED	RE-INSTALL EXISTING H.L.D. WALL MOUNTED FIXTURE IN THIS LOCATION
XX	REMOVE EXISTING D.C. EMERGENCY LIGHTING BATTERY PACK
XX	SUPPLY & INSTALL NEW D.C. EMERGENCY LIGHTING BATTERY PACK
▲	SUPPLY & INSTALL NEW D.C. EMERGENCY DUAL LIGHTING HEADS
■	SUPPLY & INSTALL NEW D.C. EMERGENCY LIGHTING RELAY CABINET - SEE D.C. EMERGENCY LIGHTING RELAY CABINET DETAIL BELOW
♦	REMOVE EXISTING LIGHT SWITCH
♦	SUPPLY & INSTALL NEW SPST LIGHT SWITCH
♦3	SUPPLY & INSTALL NEW 3-WAY LIGHT SWITCH

NOTES

1. EXISTING CONDUIT, WIRING AND CIRCUITING INDICATED ON PLANS IS IN ACCORDANCE WITH THE ORIGINAL AS-BUILT DRAWINGS FOR KENT INSTITUTION AND IS NOT TO BE CONSIDERED 100% ACCURATE. CONTRACTOR SHALL CONFIRM ALL EXISTING CONDUIT, WIRING AND CIRCUITING PRIOR TO DEMOLITION AND MODIFY ALL NEW CONDUIT, WIRING AND CIRCUIT NUMBERS AS REQUIRED AND INDICATE CHANGES ON NEW AS-BUILT DRAWINGS.

