

## **PART 1 - GENERAL**

### **1.1 RELATED SECTIONS**

- .1 Section 01 74 19 - Construction/Demolition Waste Management And Disposal.
- .2 Section 01 33 00 – Shop Drawings, Product Data and Samples.
- .3 Section 01 51 00 - Temporary Utilities.
- .4 Section 01 61 00 – Common Product Requirements.

### **1.2 REFERENCES**

- .1 Underwriters' Laboratories of Canada (ULC)
  - .1 CAN/ULC-S101-04, Standard methods of fire endurance tests of Building Construction and Materials.
  - .2 CAN-ULC-S102-03, Method of Test for Surface Burning Characteristics of Building Materials and Assemblies.
  - .3 CAN-ULC-S114 (ASTME-136) Standard method of test for determination of Non-Combustibility in Building Materials.
  - .4 CAN-ULC-S102-M88 (ASTN E-84) Standard method of test for determination of flame spread in building material.
  - .5 ASTM C-518 Standard method of test for Thermal Conductivity Test.

### **1.3 TEST REPORTS**

- .1 Submit test reports, verifying qualities of insulation meet or exceed requirements of this specification, in accordance with Section 01 33 00 – Shop Drawings, Product Data and Samples.
- .2 Submit test reports in accordance with CAN/ULC-S101 for fire endurance and CAN/ULC-S102 for surface burning characteristics.
- .3 Submit test reports in accordance with CAN/ULC-S114 for non-combustibility.

### **1.4 QUALITY ASSURANCE**

- .1 Applicators to conform to manufacturers Quality Assurance Program.

### **1.5 MOCK-UP**

- .1 Construct mock-up in accordance with Section 01 33 00 – Shop Drawings, Product Data and Samples.
- .2 Construct mock-up 10 m<sup>2</sup> minimum, of spray in place urethane foam insulation including one inside corner and one outside corner. Mock-up may be part of finished work.
- .3 Allow 24 hours for inspection of mock-up by Departmental Representative before proceeding with the work.

### **1.6 SAFETY REQUIREMENTS**

- .1 Protect workers as recommended by CAN/ULC-S705.2 and manufacturer's recommendations:
  - .1 Workplace to conform to Section 01 35 33 – Health and Safety Requirements, 01 35 43 – Environmental Procedures.

## **1.7 PROTECTION**

- .1 Ventilate area in accordance with Section 01 51 00 - Temporary Utilities.
- .2 Ventilate area to receive insulation by introducing fresh air and exhausting air continuously during and 24 hour after application to maintain non-toxic, unpolluted, safe working conditions.
- .3 Provide temporary enclosures to prevent spray and noxious vapours from contaminating air beyond application area.
- .4 Protect adjacent surfaces and equipment from damage by overspray, fall-out, and dusting of insulation materials.

## **1.8 WASTE MANAGEMENT AND DISPOSAL**

- .1 Separate and recycle waste materials in accordance with Section 01 74 21 - Construction/Demolition Waste Management And Disposal.
- .2 Remove from site and dispose of all packaging materials at appropriate recycling facilities.
- .3 Collect and separate for disposal paper, plastic, polystyrene, corrugated cardboard, packaging material in appropriate on-site bins for recycling in accordance with Waste Management Plan.
- .4 Fold up metal banding, flatten and place in designated area for recycling.
- .5 Dispose of waste foam daily in location designated by Departmental Representative and decontaminate empty drums in accordance with foam manufacturer's instructions CAN/ULC-S705.2.
- .6 Divert metal drums from landfill to metal recycling facility in accordance to CAN/ULC-S705.2.

## **1.9 ENVIRONMENTAL REQUIREMENTS**

- .1 Apply insulation only when surfaces and ambient temperatures are within manufacturers' prescribed limits.

## **PART 2 - PRODUCTS**

### **2.1 MATERIALS**

- .1 Insulation: glass fibre based spray applied thermal insulation c/w non-hazardous, water based synthetic emulsion adhesive.

## **PART 3 - EXECUTION**

### **3.1 APPLICATION**

- .1 Apply insulation to clean surfaces in accordance with CAN/ULC-S705.2 and manufacturer's printed instructions. Use primer where recommended by manufacturer.
- .2 Apply sprayed foam insulation in thickness 50 mm as indicated.

**END OF SECTION**

## **PART 1 - GENERAL**

### **1.1 RELATED SECTIONS**

- .1 Section 01 33 00 – Shop Drawings, Data Products and Samples
- .2 Section 01 74 21 – Construction/Demolition Waste management and Disposal

### **1.2 REFERENCES**

- .1 Health Canada/Workplace Hazardous Materials Information System (WHMIS)
  - .1 Material Safety Data Sheets (MSDS).
- .2 Underwriter's Laboratories of Canada (ULC)
  - .1 ULC-S115-1995, Fire Tests of Fire stop Systems.

### **1.3 DEFINITIONS**

- .1 Fire Stop Material: device intended to close off opening or penetration during fire or materials that fill openings in wall or floor assembly where penetration is by cables, cable trays, conduits, ducts and pipes and poke-through termination devices, including electrical outlet boxes along with their means of support through wall or floor openings.
- .2 Single Component Fire Stop System: fire stop material that has Listed Systems Design and is used individually without use of high temperature insulation or other materials to create fire stop system.
- .3 Multiple Component Fire Stop System: exact group of fire stop materials that are identified within Listed Systems Design to create on site fire stop system.
- .4 Tightly Fitted; (ref: NBC Part 3.1.9.1.1 and 9.10.9.6.1): penetrating items that are cast in place in buildings of non-combustible construction or have "0" annular space in buildings of combustible construction.
  - .1 Words "tightly fitted" should ensure that integrity of fire separation is such that it prevents passage of smoke and hot gases to unexposed side of fire separation.

### **1.4 SUBMITTALS**

- .1 Provide submittals in accordance with Section 01 33 00 – Shop Drawings, Data Products and Samples.
- .2 Product Data:
  - .1 Submit manufacturer's printed product literature, specifications and datasheet and include product characteristics, performance criteria, physical size, finish and limitations.
  - .2 Submit two copies of WHMIS MSDS - Material Safety Data Sheets in accordance with Section 02 81 01 - Hazardous Materials.
- .3 Shop Drawings:
  - .1 Submit shop drawings to show location, proposed material, reinforcement, anchorage, fastenings and method of installation.
  - .2 Construction details should accurately reflect actual job conditions.
- .4 Samples:
  - .1 Submit duplicate 300 x 300 mm samples showing actual fire stop material proposed for project.

- .5 Quality assurance submittals: submit following in accordance with Section 01 11 55 – General Instructions.
  - .1 Test reports: in accordance with CAN-ULC-S101 for fire endurance and CAN-ULC-S102 for surface burning characteristics.
    - .1 Submit certified test reports from approved independent testing laboratories, indicating compliance of applied fire stopping with specifications for specified performance characteristics and physical properties.
  - .2 Certificates: submit certificates signed by manufacturer certifying that materials comply with specified performance characteristics and physical properties.
  - .3 Manufacturer's Instructions: submit manufacturer's installation instructions and special handling criteria, installation sequence, cleaning procedures.
  - .4 Manufacturer's Field Reports: submit to manufacturer's written reports within 3 days of review, verifying compliance of Work, as described in PART 3 - FIELD QUALITY CONTROL.

## 1.5 QUALITY ASSURANCE

- .1 Qualifications:
  - .1 Installer: company specializing in fire stopping installations with 5 years documented experience and approved by manufacturer.
- .2 Pre-Installation Meetings: convene pre-installation meeting one week prior to beginning work of this Section, with contractor's representative and Departmental Representative in accordance with Section 01 32 16.06 - Construction Progress Schedule - Critical Path Method (CPM) to:
  - .1 Verify project requirements.
  - .2 Review installation and substrate conditions.
  - .3 Co-ordination with other building subtrades.
  - .4 Review manufacturer's installation instructions and warranty requirements.
- .3 Site Meetings: as part of Manufacturer's Services described in PART 3 - FIELD QUALITY CONTROL, schedule site visits, to review Work, at stages listed.
  - .1 After delivery and storage of products, and when preparatory Work is complete, but before installation begins.
  - .2 Twice during progress of Work at 25% and 60% complete.
  - .3 Upon completion of Work, after cleaning is carried out.

## 1.6 DELIVERY, STORAGE AND HANDLING

- .1 Packing, shipping, handling and unloading:
  - .1 Deliver, store and handle materials in accordance with Section 01 61 00 - Common Product Requirements.
  - .2 Deliver, store and handle materials in accordance with manufacturer's written instructions.
  - .3 Deliver materials to the site in undamaged condition and in original unopened containers, marked to indicate brand name, manufacturer, ULC markings.
- .2 Storage and Protection:
  - .1 Store materials indoors and in accordance with manufacturer's recommendations in clean, dry, well-ventilated area.
  - .2 Replace defective or damaged materials with new.

- .3 Waste Management and Disposal:
  - .1 Separate waste materials for reuse and recycling in accordance with Section 01 74 21 - Construction/Demolition Waste Management and Disposal.

## **PART 2 - PRODUCTS**

### **2.1 MATERIALS**

- .1 Fire stopping and smoke seal systems: in accordance with CAN-ULC-S115.
  - .1 Asbestos-free materials and systems capable of maintaining effective barrier against flame, smoke and gases in compliance with requirements of CAN-ULC-S115 and not to exceed opening sizes for which they are intended [and conforming to specified special requirements described in PART 3.
  - .2 Fire stop system rating: 2 HR.
- .2 Service penetration assemblies: systems tested to CAN-ULC-S115.
- .3 Service penetration fire stop components: certified by test laboratory to CAN-ULC-S115.
- .4 Fire-resistance rating of installed fire stopping assembly in accordance with NBC and VBBL.
- .5 Fire stopping and smoke seals at openings intended for ease of re-entry such as cables: elastomeric seal.
- .6 Fire stopping and smoke seals at openings around penetrations for pipes, ductwork and other mechanical items requiring sound and vibration control: elastomeric seal.
- .7 Primers: to manufacturer's recommendation for specific material, substrate, and end use.
- .8 Water (if applicable): potable, clean and free from injurious amounts of deleterious substances.
- .9 Damming and backup materials, supports and anchoring devices: to manufacturer's recommendations, and in accordance with tested assembly being installed as acceptable to authorities having jurisdiction.
- .10 Sealants for vertical joints: non-sagging.

## **PART 3 - EXECUTION**

### **3.1 MANUFACTURER'S INSTRUCTIONS**

- .1 Compliance: comply with manufacturer's written recommendations or specifications, including product technical bulletins, handling, storage and installation instructions, and datasheets.

### **3.2 PREPARATION**

- .1 Examine sizes and conditions of voids to be filled to establish correct thicknesses and installation of materials.
  - .1 Ensure that substrates and surfaces are clean, dry and frost free.
- .2 Prepare surfaces in contact with fire stopping materials and smoke seals to manufacturer's instructions.
- .3 Maintain insulation around pipes and ducts penetrating fire separation without interruption to vapour barrier.
- .4 Mask where necessary to avoid spillage and over coating onto adjoining surfaces; remove stains on adjacent surfaces.

### 3.3 INSTALLATION

- .1 Install fire stopping and smoke seal material and components in accordance with manufacturer's certified tested system listing.
- .2 Seal holes or voids made by through penetrations, poke-through termination devices, and unpenetrated openings or joints to ensure continuity and integrity of fire separation are maintained.
- .3 Provide temporary forming as required and remove forming only after materials have gained sufficient strength and after initial curing.
- .4 Tool or trowel exposed surfaces to neat finish.
- .5 Remove excess compound promptly as work progresses and upon completion.

### 3.4 SEQUENCES OF OPERATION

- .1 Proceed with installation only when submittals have been reviewed by Departmental Representative.
- .2 Install floor fire stopping before interior partition erections.
- .3 Metal deck bonding: fire stopping to precede spray applied fireproofing to ensure required bonding.
- .4 Mechanical pipe insulation: certified fire stop system component.
  - .1 Ensure pipe insulation installation precedes fire stopping.

### 3.5 FIELD QUALITY CONTROL

- .1 Inspections: notify Departmental Representative when ready for inspection and prior to concealing or enclosing fire stopping materials and service penetration assemblies.
- .2 Manufacturer's Field Services:
  - .1 Obtain written report from manufacturer verifying compliance of Work, in handling, installing, applying, protecting and cleaning of product and submit Manufacturer's Field Reports as described in PART 1 - SUBMITTALS.
  - .2 Provide manufacturer's field services consisting of product use recommendations and periodic site visits for inspection of product installation in accordance with manufacturer's instructions.
  - .3 Schedule site visits, to review Work, as directed in PART 1 - QUALITY ASSURANCE.

### 3.6 CLEANING

- .1 Proceed in accordance with Section 01 11 55 – General Instructions.
- .2 On completion and verification of performance of installation, remove surplus materials, excess materials, rubbish, tools and equipment.
- .3 Remove temporary dams after initial set of fire stopping and smoke seal materials.

### 3.7 SCHEDULE

- .1 Fire stop and smoke seal at:
  - .1 Penetrations through fire-resistance rated masonry, concrete, and gypsum board partitions and walls.
  - .2 Edge of floor slabs at curtain wall and precast concrete panels.

- .3 Top of fire-resistance rated masonry and gypsum board partitions.
- .4 Intersection of fire-resistance rated masonry and gypsum board partitions.
- .5 Control and sway joints in fire-resistance rated masonry and gypsum board partitions and walls.
- .6 Penetrations through fire-resistance rated floor slabs, ceilings and roofs.
- .7 Openings and sleeves installed for future use through fire separations.
- .8 Around mechanical and electrical assemblies penetrating fire separations.
- .9 Rigid ducts: greater than 129 cm<sup>2</sup>: fire stopping to consist of bead of fire stopping material between retaining angle and fire separation and between retaining angle and duct, on each side of fire separation.

**END OF SECTION**

## **PART 1- GENERAL**

### **1.1 RELATED REQUIREMENTS**

- .1 Section 01 33 00 – Shop Drawings, Data Products and Samples
- .2 Section 01 45 00 – Quality Control
- .3 Section 01 61 00 – Common Product Requirements
- .4 Section 01 74 21 – Construction/Demolition Waste Management and Disposal
- .5 Section 06 40 00 – Architectural Woodwork
- .6 Section 08 11 00 – Metal Doors and Frames

### **1.2 REFERENCES**

- .1 ASTM International
  - .1 ASTM C919-08, Standard Practice for Use of Sealants in Acoustical Applications.
- .2 Canadian General Standards Board (CGSB)
  - .1 CGSB 19-GP-5M-1984, Sealing Compound, One Component, Acrylic Base, Solvent Curing (Issue of 1976 reaffirmed, incorporating Amendment No. 1).
  - .2 CAN/CGSB-19.13-M87, Sealing Compound, One-component, Elastomeric, Chemical Curing.
  - .3 CGSB 19-GP-14M-1984, Sealing Compound, One Component, Butyl-Polyisobutylene Polymer Base, Solvent Curing (Reaffirmation of April 1976).
  - .4 CAN/CGSB-19.17-M90, One-Component Acrylic Emulsion Base Sealing Compound.
  - .5 CAN/CGSB-19.24-M90, Multi-component, Chemical Curing Sealing Compound.
- .3 General Services Administration (GSA) - Federal Specifications (FS)
  - .1 FS-SS-S-200-E(2)1993, Sealants, Joint, Two-Component, Jet-Blast-Resistant, Cold Applied, for Portland Cement Concrete Pavement.
- .4 Health Canada/Workplace Hazardous Materials Information System (WHMIS)
  - .1 Material Safety Data Sheets (MSDS).
- .5 South Coast Air Quality Management District (SCAQMD), California State, Regulation XI. Source Specific Standards
  - .1 SCAQMD Rule 1168-A2005, Adhesives and Sealants Applications.

### **1.3 ACTION AND INFORMATIONAL SUBMITTALS**

- .1 Submit in accordance with Section 01 33 00 – Shop Drawings, Data Products and Samples.
- .2 Product Data:
  - .1 Submit manufacturer's instructions, printed product literature and data sheets for [joint sealants] and include product characteristics, performance criteria, physical size, finish and limitations.



- .2 Manufacturer's product to describe:
  - .1 Caulking compound.
  - .2 Primers.
  - .3 Sealing compound, each type, including compatibility when different sealants are in contact with each other.
- .3 Submit 2 copies of WHMIS MSDS in accordance with Section 01 35 29.06 - Health and Safety Requirements, Section 01 35 43 - Environmental Procedures.
- .3 Samples:
  - .1 Submit 2 samples of each type of material and colour.
  - .2 Cured samples of exposed sealants for each colour where required to match adjacent material.
- .4 Manufacturer's Instructions:
  - .1 Submit instructions to include installation instructions for each product used.
- .5 Sustainable Design Submittals:
  - .1 Construction Waste Management:
    - .1 Submit project Waste Management Plan highlighting recycling and salvage requirements.
    - .2 Submit calculations on end-of-project recycling rates, salvage rates, and landfill rates demonstrating that 75% of construction wastes were recycled or salvaged.

#### 1.4 CLOSEOUT SUBMITTALS

- .1 Submit in accordance with Section 01 78 00 - Closeout Submittals.
- .2 Operation and Maintenance Data: submit operation and maintenance data for incorporation into manual.

#### 1.5 DELIVERY, STORAGE AND HANDLING

- .1 Deliver, store and handle materials in accordance with Section 01 61 00 - Common Product Requirements and with manufacturer's written instructions.
- .2 Delivery and Acceptance Requirements: deliver materials to site in original factory packaging, labelled with manufacturer's name and address.
- .3 Storage and Handling Requirements:
  - .1 Store materials indoors and in accordance with manufacturer's recommendations in clean, dry, well-ventilated area.
  - .2 Store and protect joint sealants from nicks, scratches, and blemishes.
  - .3 Replace defective or damaged materials with new.
- .4 Develop Construction Waste Management Plan related to Work of this Section.
- .5 Packaging Waste Management: remove for reuse of pallets, crates, padding, and packaging materials as specified in Construction Waste Management Plan in accordance with Section 01 74 21 - Construction/Demolition Waste Management and Disposal.

## 1.6 SITE CONDITIONS

- .1 Ambient Conditions:
  - .1 Proceed with installation of joint sealants only when:
    - .1 Ambient and substrate temperature conditions are within limits permitted by joint sealant manufacturer or are above 4.4 degrees C.
    - .2 Joint substrates are dry.
    - .3 Conform to manufacturer's recommended temperatures, relative humidity, and substrate moisture content for application and curing of sealants including special conditions governing use.
- .2 Joint-Width Conditions:
  - .1 Proceed with installation of joint sealants only where joint widths are more than those allowed by joint sealant manufacturer for applications indicated.
- .3 Joint-Substrate Conditions:
  - .1 Proceed with installation of joint sealants only after contaminants capable of interfering with adhesion are removed from joint substrates.

## 1.7 ENVIRONMENTAL REQUIREMENTS

- .1 Comply with requirements of Workplace Hazardous Materials Information System (WHMIS) regarding use, handling, storage, and disposal of hazardous materials; and regarding labelling and provision of Material Safety Data Sheets (MSDS) acceptable to Health Canada.
- .2 Departmental Representative will arrange for ventilation system to be operated on maximum outdoor air and exhaust during installation of caulking and sealants. Ventilate area of work as directed by Departmental Representative by use of approved portable supply and exhaust fans.

## PART 2- PRODUCTS

### 2.1 SEALANT MATERIALS

- .1 Do not use caulking that emits strong odours, contains toxic chemicals or is not certified as mould resistant in air handling units.
- .2 When low toxicity caulks are not possible, confine usage to areas which off gas to exterior, are contained behind air barriers, or are applied several months before occupancy to maximize off gas time.
- .3 Where sealants are qualified with primers use only these primers.

### 2.2 SEALANT MATERIAL DESIGNATIONS

- .1 Urethanes two part:
  - .1 Self-levelling: to CAN/CGSB-19.24, Type 1, Class B, colour from manufacturers standard colour range.
- .2 Urethanes two part:
  - .1 Non-sag: to CAN/CGSB-19.24, Type 2, Class B, colour from manufacturers standard colour range.
- .3 Silicones one part: to CAN/CGSB-19.13.
- .4 Acrylics one part: to CGSB 19-GP-5M.

- .5 Acrylic latex one part: to CAN/CGSB-19.17.
- .6 Acoustical sealant: to ASTM C919.
- .7 Butyl: to CGSB 19-GP-14M.
- .8 Preformed compressible and non-compressible back-up materials:
  - .1 Polyethylene, urethane, neoprene or vinyl foam:
    - .1 Extruded open cell foam backer rod. Size: oversize 30 to 50 %.
  - .2 Neoprene or butyl rubber:
    - .1 Round solid rod, Shore A hardness 70.
  - .3 High density foam:
    - .1 Extruded closed cell polyvinyl chloride (PVC), extruded polyethylene, closed cell, Shore A hardness 20, tensile strength 140 to 200 kPa, extruded polyolefin foam, 32 kg/m<sup>3</sup> density, or neoprene foam backer, size as recommended by manufacturer.
  - .4 Bond breaker tape:
    - .1 Polyethylene bond breaker tape which will not bond to sealant.

## 2.3 SEALANT SELECTION

- .1 Perimeters of exterior openings where frames meet exterior facade of building (i.e. brick, block, precast masonry): sealant type: urethane two part.
- .2 Expansion and control joints in exterior surfaces of poured-in-place concrete walls: sealant type: urethane two part.
- .3 Expansion and control joints in exterior surfaces of precast, architectural wall panels: sealant type: urethane two part.
- .4 Control and expansion joints in exterior surfaces of unit masonry walls: sealant type: urethane two part.
- .5 Coping joints and coping-to facade joints: sealant type: urethane two part.
- .6 Cornice and wash (or horizontal surface joints): sealant type: urethane two part.
- .7 Exterior joints in horizontal wearing surfaces (as itemized): sealant type: urethane two part.
- .8 Interior control and expansion joints in floor surfaces: sealant type: urethane two part.
- .9 Perimeters of interior frames, as detailed and itemized: sealant type: urethane two part .
- .10 Interior masonry vertical control joints (block-to-block, block-to-concrete, and intersecting masonry walls): sealant type: urethane two part.
- .11 Joints at tops of non-load bearing masonry walls at the underside of poured concrete: sealant type: urethane two part.
- .12 Perimeter of bath fixtures (e.g. sinks, tubs, urinals, stools, water closets, basins, vanities): sealant type: silicone one part.
- .13 Exposed interior control joints in drywall: sealant type: urethane two part.

## 2.4 JOINT CLEANER

- .1 Non-corrosive and non-staining type, compatible with joint forming materials and sealant in accordance with sealant manufacturer's written recommendations.
- .2 Primer: in accordance with sealant manufacturer's written recommendations.

## **PART 3 - EXECUTION**

### **3.1 EXAMINATION**

- .1 Verification of Conditions: verify that conditions of substrate previously installed under other Sections or Contracts are acceptable for joint sealants installation in accordance with manufacturer's written instructions.
  - .1 Visually inspect substrate in presence of Departmental Representative.
  - .2 Inform Departmental Representative of unacceptable conditions immediately upon discovery.
  - .3 Proceed with installation only after unacceptable conditions have been remedied and after receipt of written approval to proceed from Departmental Representative.

### **3.2 SURFACE PREPARATION**

- .1 Examine joint sizes and conditions to establish correct depth to width relationship for installation of backup materials and sealants.
- .2 Clean bonding joint surfaces of harmful matter substances including dust, rust, oil grease, and other matter which may impair Work.
- .3 Do not apply sealants to joint surfaces treated with sealer, curing compound, water repellent, or other coatings unless tests have been performed to ensure compatibility of materials. Remove coatings as required.
- .4 Ensure joint surfaces are dry and frost free.
- .5 Prepare surfaces in accordance with manufacturer's directions.

### **3.3 PRIMING**

- .1 Where necessary to prevent staining, mask adjacent surfaces prior to priming and caulking.
- .2 Prime sides of joints in accordance with sealant manufacturer's instructions immediately prior to caulking.

### **3.4 BACKUP MATERIAL**

- .1 Apply bond breaker tape where required to manufacturer's instructions.
- .2 Install joint filler to achieve correct joint depth and shape, with approximately 30% compression.

### **3.5 MIXING**

- .1 Mix materials in strict accordance with sealant manufacturer's instructions.

### **3.6 APPLICATION**

- .1 Sealant:
  - .1 Apply sealant in accordance with manufacturer's written instructions.
  - .2 Mask edges of joint where irregular surface or sensitive joint border exists to provide neat joint.
  - .3 Apply sealant in continuous beads.
  - .4 Apply sealant using gun with proper size nozzle.
  - .5 Use sufficient pressure to fill voids and joints solid.
  - .6 Form surface of sealant with full bead, smooth, free from ridges, wrinkles, sags, air pockets, embedded impurities.

- .7 Tool exposed surfaces before skinning begins to give slightly concave shape.
- .8 Remove excess compound promptly as work progresses and upon completion.
- .2 Curing:
  - .1 Cure sealants in accordance with sealant manufacturer's instructions.
  - .2 Do not cover up sealants until proper curing has taken place.

### 3.7 CLEANING

- .1 Progress Cleaning: clean in accordance with Section 01 11 55 – General Instructions.
  - .1 Leave Work area clean at end of each day. Clean adjacent surfaces immediately.
  - .2 Remove excess and droppings, using recommended cleaners as work progresses.
  - .3 Remove masking tape after initial set of sealant.
- .2 Final Cleaning: upon completion remove surplus materials, rubbish, tools and equipment in accordance with Section 01 11 55 – General Instructions.
- .3 Waste Management: separate waste materials for recycling in accordance with Section 01 74 21 - Construction/Demolition Waste Management and Disposal.
  - .1 Remove recycling containers and bins from site and dispose of materials at appropriate facility.

### 3.8 PROTECTION

- .1 Protect installed products and components from damage during construction.
- .2 Repair damage to adjacent materials caused by joint sealants installation.

**END OF SECTION**